MIL-D-46647B (MU)
31 May 1966
SUPERSEDING
MIL-D-46647A (MU)
15 May 1966

MILITARY SPECIFICATION

DETONATOR, STAB, M58
LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of detonator designated as Detonator, Stab, M58.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116 - Preservation, Methods of
MIL-A-2550 - Ammunition and Special Weapons, General Specification for.
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105).
MIL-STD-109 - Quality Assurance Terms and Definitions.
MIL-STD-1167 - Ammunition Data Cards.
MIL-STD-1168 - Lot Numbering of Ammunition.
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

FSC: 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

DRAWINGS

ORDNANCE CORPS

7548103 - Box, Set-up, Packing, Ammunition, Outer for Small Explosive Components.
7548104 - Box, Set-up, Packing, Ammunition, Outer for Small Explosive Components.
8858409 - Detonator, Stab, M58 Assembly.
8858448 - Box, Packing Ammunition for Detonators Stab M58.

PUBLICATIONS

ORDNANCE CORPS

IEL-8858409 - Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with applicable drawings and specifications.

3.2 Detonator.-The detonators shall comply with all requirements specified on Drawing (dwg.) 8858409, and with all requirements specified in applicable specifications.

3.3 Moisture content of lead azide.-The moisture content of the lead azide used in loading the detonators at the loading station at the time of loading shall not exceed 0.50 percent when tested as specified in 4.3.1.

3.4 Moisture content of primer mixture.-The moisture content of the primer mixture used in loading the detonators at the loading station at the time of loading, shall not exceed 0.30 percent, when tested as specified in 4.3.2.

3.5 Functioning.

3.5.1 Sensitivity.-The detonators shall function on the first attempt under a maximum applied energy of 47.40 inch ounces and cause perforation of the lead disc to a diameter of not less than .156 inch when tested as specified in 4.3.4.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

3.5.2 Waterproofness.-The primer shall be waterproof as evidenced by normal functioning, as specified in 3.5.1 after being immersed in water maintained at 70 degrees Fahrenheit (F.) plus or minus 10 degrees F., at a depth of 2 inches minimum for not less than 48 hours. The test shall be performed as specified in 4.3.4.2.

3.6 Workmanship.-All parts and assemblies shall be fabricated and loaded in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, rust and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined. All packing components shall be dry.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define the terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time of the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions specified within this specification.

b. Number of units of product inspected.

c. Results obtained, by defect code, for all inspections performed.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Statement of findings on the primer mixture and a certificate of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Inspection provisions

4.2.1 Lot formation.-The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, specification, or revision thereof. Changes to either the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government inspector, shall not be deemed to alter the homogeneity of the lot. Each lot shall contain:

a. Parts of one lot interfix number from one manufacturer.
b. Primer mixture from one batch or a blending of batches which results in homogeneity of all primer mixture used in loading of a lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

c. Lead azide from one batch or a blending of batches which results in homogeneity of all explosives used in loading of a lot.

Inspection lots shall comply with MIL-STD-105 and shall be numbered in accordance with MIL-STD-1168.

Unless otherwise approved by the contracting officer, the inspection lot size of major assemblies or end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more than the largest quantity contractually scheduled for delivery during any month of the contract period. Inspection lots for components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size convenient to the contractor.

4.2.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL-STD-1235 may be used for defects other than critical, if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

4.2.2.1 Assembly, prior to loading (see dwg. 88584C9).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Coating compound or lacquer on exposed surface or disc	Visual	01001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.6)	Visual	01002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

4.2.2.2 Assembly (see dwg. 6856409).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Cup cracked, split or cut	Visual	02001
Major:	AQL 0.65 percent		
101.	Disc loose or punctured (either end)	Visual-Manual	02002
102.	Not crimped full 360 degrees	Visual	02003
103.	Color of lacquer incorrect	Visual	02004
Minor:	AQL 1.50 percent		
201.	Length	Gage	02005
202.	Diameter	Gage	02006
203.	Evidence of poor workmanship (see 3.6)	Visual	02007

4.2.2.3 Inner set up, packing box, prior to closing (see dwg. 7548104).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Box damaged to extent that the contents are exposed or liable to become exposed	Visual	03001
102.	Lot No. missing, misleading or unidentifiable	Visual	03002
Minor:	AQL 1.50 percent		
201.	Any packing material missing	Visual	03003
202.	Incorrect number of detonators	Visual	03004
203.	Separator damaged to the extent that detonators touch each other	Visual	03005

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

4.2.2.4 Outer set up, packing box, prior to inserting in barrier bag (when applicable) (see dwg. 7548103).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Lot No. missing, misleading, or unidentifiable	Visual	04001
Minor:	AQL 1.00 percent		
201.	Box damaged to extent that contents are exposed or liable to become exposed	Visual	04002
202.	Sealing strip missing, unsealed or badly wrinkled	Visual	04003

4.2.2.5 Outer set up packing box in barrier bag (when applicable) (see dwg. 7548103).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Barrier bag punctured or torn	Visual	05001
102.	Marking missing, misleading or unidentifiable	Visual	05002
103.	Barrier bag seal incomplete or improperly positioned	Visual	05003
Minor: None defined			

4.2.2.6 Packing box, prior to sealing (see dwg. 7548100).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Outer set up box missing	Visual	06001
Minor:	AQL 0.65 percent		
201.	Packing component missing	Visual	06002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

4.2.2.7 Sealed packing box (see dwg. 8858449).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Box damaged to extent that contents are exposed or liable to become exposd	Visual	07001
102.	Strapping missing broken or loose	Visual-Manual	07002
Minor:	AQL 1.50 percent		
201.	Strapping improperly engaged, positioned or assembled	Visual-Manual	07003
202.	Contents loose	Manual	07004
203.	Marking misleading or unidentifiable	Visual	07005

4.2.3 Testing

4.2.3.1 Moisture content of lead azide (see 3.3) Code No. 09001 - Major defect.-The moisture content of the lead azide shall be determined for each lot at the time of loading. A sample in sufficient quantity to perform the test detailed in 4.3.1 shall be selected and tested as specified in 4.3.1. If the moisture content is in excess of the percentage specified and loading has not begun, the lot of lead azide shall be rejected. If loading has begun, action on the unloaded lead azide shall be as specified above and all detonators loaded with questionable lead azide shall be rejected.

4.2.3.2 Primer mixture

4.2.3.2.1 Moisture content (see 3.4) - Major defect - Code No. 10001.-The moisture content of the primer mixture shall be determined for each batch or blend of batches at the time of loading. A sample, in sufficient quantity to perform the test detailed in 4.3.2 shall be selected and tested as specified in 4.3.2. If the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

moisture content is in excess of the percentage specified and if loading has not begun, the batch or blend of batches of the primer mixture shall be rejected. If loading has begun, action on the unloaded primer mixture shall be as specified above and all detonators loaded with the questionable primer mixture shall be rejected.

4.2.3.2.2 Composition (see dwg. 8858409) Major defect - Code No. 11001.-The composition of the primer mixture shall be determined for each batch or blend of batches at the time of leading. A sample, in sufficient quantity to perform the test detailed in 4.3.3, shall be selected and tested as specified in 4.3.3. If the composition of the primer mixture fails to conform to the requirements specified on the applicable drawing and if loading has not begun, the batch or blend of batches of primer mixture shall be rejected. If loading has begun, detonators loaded with the questionable primer mixture shall be rejected.

4.2.3.3 Functioning

4.2.3.3.1 Functioning (see 3.5) - Major defect - Code No. 02005. A sample of 315 detonators shall be selected at random from each lot. If 3 or more detonators fail to comply with the requirement specified the lot shall be rejected. If one or two defects are found, a second sample of 315 shall be selected at random and tested. If, in the combined first and second sample, a total of 4 or more defects are found, the lot shall be rejected. The test shall be performed as specified in 4.3.4.1 using test equipment as specified in 4.2.4.

4.2.3.3.2 Waterproofness (see 3.5) - Major defect - Code No. 02010.-A sample of 25 detonators shall be selected at random from each lot. If one or more detonators fail to comply with the requirement specified the lot shall be rejected. The test shall be performed as specified in 4.3.4.2, using test equipment as specified in 4.2.4.

4.2.3.4 Weight of base charge (see dwg. 8858409) Critical defect - Code No. 12001.-Weighing shall be performed 100 percent. Any pellet that exceeds the maximum weight requirement specified on the drawing shall be classed defective and removed from the lot.

4.2.3.5 Heat seal test of sealed bag (see dwg. 7548103). Major defect - Code No. 05004.-Sampling, acceptance criteria and test procedures for this test shall be as specified in Specification MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

4.2.4 Inspection Equipment.-Index of Inspection Equipment Number IEL-8858409 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.2.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.2.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed in the IEL shall be in accordance with Specification MIL-I-45607.

4.2.4.3 Government use of contractor's inspection equipment.-The contractor shall make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.3 Test methods and procedures

4.3.1 Determination of moisture content of lead azide.-A tared dried container at least two inches in diameter, with a cover that cannot develop any pressure or friction on the sample shall be used. An accurately weighed portion of approximately two grams of the sample shall be transferred to the moisture dish and contents shall be transferred to an oven and dried at 95 degrees Centigrade (C.) plus or minus 2 degrees C. for 2 hours. The cover shall be placed in the desiccator containing sulfuric acid, calcium chloride or other suitable dessicant, during the drying period. After drying, the dish shall be quickly transferred to the desiccator and allowed to cool to room temperature. The cover shall be placed on the dish and the assembly weighed. The loss in weight shall be calculated to percentage of moisture in the lead azide to determine compliance with 3.3 as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

Percentage of moisture = 100 (A-B) divided by A.

where:
A = the weight of the sample before drying
B = the weight of the sample after drying

4.3.2 Moisture content of primer mixture.-A sample of 0.7 grams shall be accurately weighed to the nearest milligram and dried to a constant weight at 60 degrees C. plus or minus 5 degrees C., or in a desiccator containing calcium chloride or other suitable dessicant. The loss in weight shall be calculated as the percentage of moisture.

4.3.3 Composition of primer mixture.-The composition of the primer mixture shall be determined by performing the following tests in the sequence listed.

4.3.3.1 Potassium Chlorate.-Approximately 2 grams of the primer mixture shall be accurately weighed and transferred to a tared ignited filtering crucible of approximately 15 ml. capacity. Three ml. of lead azide-saturated distilled water shall be added at a temperature of 25 degrees plus or minus 2 degrees C., agitated for exactly 1 minute, and if necessary, any lumps shall be broken up with a glass rod, taking care not to disturb the asbestos mat. Suction shall be applied. This procedure shall be repeated five times, making a total of six 3 ml. extractions. The sample shall be rinsed in the filtering crucible with a few ml. of alcohol and ether, the sample must be aspirated until the odor of solvent is no longer detectable, then dried for approximately 15 minutes at 95 degrees plus or minus 2 degrees C., cooled in a desiccator, and weighed. The loss in weight shall be calculated as percentage of potassium chlorate in the sample.

4.3.3.2 Lead azide.-The residue shall be extracted from the potassium chlorate determination with 5-ml. portions of saturated ammonium acetate solution at about 25 degrees C. (hot saturated ammonium acetate solution must not be used as it dissolves antimony sulfide to some extent) each portion being agitated for about 30 seconds, until the washings no longer give a yellow precipitate with a few drops of potassium dichromate solution. The use of more than 60 ml. of ammonium acetate solution should be avoided. The residue shall be washed with distilled water, rinsed with a few ml. of

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

alcohol and ether, the sample must be aspirated until the odor of solvent is no longer detectable, then dried for approximately 15 minutes at 95 degrees plus 2 degrees C., cooled in a desiccator and weighed. The loss in weight shall be calculated as the percentage of lead azide in the sample.

4.3.3.3 Antimony sulfide.-The residue remaining from the lead azide determination shall be extracted with concentrated hydrochloric acid until free from antimony sulfide. (This extracting can be made without removing the sample from the filtering crucible. Suction shall be applied and most of the antimony sulfide extracted with cool concentrated hydrochloric acid, then rinsed thoroughly with hot concentrated acid). The crucible and residue shall be rinsed thoroughly, ignited to remove sulfur and organic matter, cooled in a desiccator and weighed. The loss in weight shall be calculated as the percentage of antimony sulfide.

4.3.3.4 Carborundum.-The original weight of the ignited filtering crucible shall be subtracted from the weight of the crucible and residue after the antimony sulfide determination and the difference calculated as the percentage of carborundum.

4.3.4 Functioning

4.3.4.1 Sensitivity.-The detonator shall be assembled to the applicable test fixture specified in 4.2.4, so that the firing pin will strike the sensitive end of the detonator. A steel ball weighing 3.95 ounces maximum shall be dropped on the firing pin to function the detonator from a height of 12 inches, maximum. The height of drop shall be measured as the height from the top of the firing pin to the bottom of the ball. A detonator that fails to fire or fails to create a hole in the lead disc of the required size shall be classed defective.

4.3.4.2 Waterproofness.-The detonator shall be immersed under water as specified for the time specified. Within one hour after removal from the water the detonator shall be subjected to the sensitivity test specified in 4.3.4.1. Any detonator which fails to fire or fails to create a hole in the lead disc of the required size shall be classed defective.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level C.-minimum military package.-The detonators shall be preserved and packaged in accordance with dwg. 7548104.

5.1.2 Intermediate packaging.-The detonators shall be packaged in accordance with dwg. 7548103.

5.2 Packing

5.2.1 Level C-minimum military pack.-The containers shall be packed in accordance with dwg. 8858449.

5.3 Marking

5.3.1 Unit, intermediate and exterior containers shall be marked in accordance with dwgs. 7548104, 7548103, and 8858449.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 Inspection equipment lists.-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (SMUPA Form 1010) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the IEL by the following codes:

CDAF - Contractor's design responsibility on Army format in accordance with MIL-D-45608.
CDCF - Contractor's design responsibility on contractor format.
AD - Army design.
ADMU - Army design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs (see 6.3.6) or commercial equipment selections (see 6.3.5) must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawing.-Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagramatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings must be described in sufficient detail to permit identification and evaluation by the Government (see 6.3.5). Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors normally are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. When commercial inspection equipment requires the use of special fixturing, the design of this fixturing shall be considered as part of the total design, and 6.3.6 shall apply. In the latter case, only those portions of the commercial equipment need be detailed in the designs as are necessary to completely fabricate, calibrate, and operate the total item of inspection equipment. Lists and fixturing designs shall be submitted for approval as specified in 6.3.7.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35mm microfilm process. Contractors shall submit one copy of the final design as a rolled set or flat set. Designs shall be submitted for approval as specified in 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.

6.3.7 Submission of contractor designs.-Unless otherwise specified on the IEL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Check test for possible deterioration.-The following test is designed to prevent the loading of detonators which have deteriorated, into a major ammunition item. The test shall be performed on detonators from each lot which has been stored under normal conditions for more than two years, or under adverse conditions for any period of time. If the specification for the ammunition item into which the detonators are loaded does not require that the check test be performed, the contracting officer should insert a provision for the performance of the check test in that contract. The contracting officer will arrange for the contractor to be reimbursed for expenses incurred in the performance of the check test for possible deterioration.

6.4.1 Functioning.-A sample of 315 detonators shall be selected at random from each lot. If 3 or more detonators fail to comply with the requirement specified, the lot shall be rejected. If more than one defect is found, a second sample of 315 shall be selected at random and tested. If in the combined first and second sample a total of 5 or more defects are found the lot shall be rejected. The test shall be performed as specified in 4.3.4.1 using test equipment as specified in 4.2.4.

6.5 Submission of test data.-In addition to the normal distributions of records, for items procured by the Department of the Army, one copy of all functioning test data shall be forwarded to:

Commanding Officer
Picatinny Arsenal
Dover, New Jersey 07801
ATTN: SMUPA-ND5

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1375-A1014

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:33Z
Check the source to verify that this is the current version before use.