MILITARY SPECIFICATION

TEST SET, ALTIMETER SET AN/APN-348

This specification has been approved by the
Naval Air System Command, Department of the Navy.

1. SCOPE

1.1 Scope - The equipment covered by this specification shall be for Flight Line Test of the AN/APN-141 (V) Electronic Altimeter Set. The equipment shall be capable of performing preflight accuracy tests of the AN/APN-141 (V) Altimeter Set and performing fault isolation to the Weapons Replaceable Assembly.

1.2 Classification - The test equipment covered by this specification shall consist of the following items:

Drawing/Model No.	Nomenclature	Ref. Para.
1528	Test Set	Para. 3.5.5
104030-3	Case	Para. 3.5.5
104030-2	Cover	Para. 3.5.5

1.3 Associated Equipment - No associated equipment shall be required since the Flight Line Test Set shall perform its function as a test set for Weapons Replaceable Assembly (WRA) fault isolation and GO/NO GO test independent of other test equipment.

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids form a part of this specification to the extent specified herein:

SPECIFICATIONS

Military

MIL-T-5422	Testing, Environmental, Aircraft Electronic Equipment
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-T-18303	Test Procedures; Preproduction, Acceptance, and Life for Aircraft Electronic Equipment, Format for

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:15Z
Check the source to verify that this is the current version before use.

MIL-N-18307	Nomenclature and Nameplates for Aeronautical Electrical and Associated Equipment
MIL-T-21200	Test Equipment for Use with Electronic and Fire Control Systems, General Specification for
AR-5	Microelectronic Devices Used in Avionic Equipment, Procedures for Selection and Approval of

STANDARDS

Military

MIL-STD-704	Electric Power, Aircraft Characteristics and Utilization of

PUBLICATIONS:

MIL-HDBK-217	Reliability Stress and Failure Rate Data for Electronic Equipment

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions shall be obtained from the procuring activity or as directed by the contracting officer.

3. REQUIREMENTS

3.1 Preproduction - This specification makes provision for preproduction testing.

3.2 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration; in so doing the following shall guide:

(a) Parts and materials requirements shall be in accordance with MIL-T-21200. Parts selected for use which are considered nonstandard per MIL-T-21200 shall be selected to meet the design requirements. Such parts shall only be used when a standard MIL equivalent part is not available or when delivery time of the standard part is beyond the time limit required to meet the contract delivery schedule.

(b) Semiconductor devices - Semiconductors shall be chosen and applied according to best engineering practice to attain high unit reliability and to meet all the design requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:15Z
Check the source to verify that this is the current version before use.

3.2.1 Nonstandard Parts and Material Approval - Approval for the use of nonstandard parts and materials shall be obtained in accordance with MIL-T-21200. Microelectronic devices shall be approved as outlined in AR-5.

3.2.2 Electron Devices - Transistors and diodes shall be in accordance with MIL-T-21200.

3.2.3 Microelectronic Modular Assemblies - When used, Microelectronic Modular Assemblies shall be in accordance with AR-5.

3.3 Design and Construction - The equipment shall conform with all the applicable requirements of MIL-T-21200 for design, construction and workmanship except as otherwise specified herein.

3.3.1 Weight - The total weight of the equipment, excluding cables, shall not exceed 50 pounds.

3.3.2 Reliability

3.3.2.1 Operational Stability - The equipment shall operate with satisfactory performance, continuously or intermittently for a period of at least 150 hours without the necessity for readjustment of any controls which are inaccessable to the operator during normal use.

3.3.2.2 Operating Life - The equipment shall have a minimum total operating life of 25,000 hours with reasonable servicing and replacement of parts. Parts requiring scheduled replacement due to wear during the life of the equipment, and the wearout life of such parts, shall be determined by the contractor and submitted to the procuring agency.

3.3.2.3 Reliability in Meantime Between Failure - The predicted mean (operating) time between failure shall be in accordance with MIL-HDBK-217 with a minimum of 10,000 hours.

3.3.3 Cables and Connectors - The equipment shall provide for the use of cables and connectors in accordance with MIL-T-21200. Insofar as is practicable, all connectors on the front panel shall be mounted along the lower edge of the panel and in no case shall their location be such that the connecting cables will interfere with the operating controls.

3.3.3.1 Cable Assemblies, Power Electrical - Applicable input power cable and connections shall conform to MIL-T-21200.

3.3.4 Control Panels - All rack mounted control panels shall conform to the applicable requirements as specified in MIL-T-21200.

3.3.5 Interchangeability - The equipment shall meet the applicable interchangeability requirements as specified in MIL-T-21200.

3.3.6 Interference Control - The generation of radio interference by the equipment and the vulnerability of the equipment to radio interference shall be controlled within the limits of MIL-T-21200.

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:15Z
Check the source to verify that this is the current version before use.

3.3.7 Maintenance Provisions and Field Testing - Provisions for maintenance shall be as specified in MIL-T-21200. Specific test points and test facilities shall be provided to the greatest extent practicable for ease of field testing and maintenance.

3.3.8 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with MIL-N-18307.

3.3.9 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

(a) Temperature	Room ambient ($25^{\circ}C \pm 5^{\circ}C$)
(b) Altitude	Normal Ground
(c) Vibration	None
(d) Humidity	Room ambient up to 90% relative humidity
(e) Input power voltage	115±1.0VAC, 400±5Hz

3.3.10 Service Conditions - The equipment shall operate satisfactorily when subjected to the environmental service conditions in accordance with MIL-T-21200 for Class 2 equipment as listed.

(a) Vibration

(b) Temperature/Altitude

(c) Explosion

(d) Shock

(e) Humidity

3.3.11 Warm-Up Time - The time required for the equipment to warm-up prior to operations shall be kept to a minimum and shall not exceed 5 minutes under standard conditions and 10 minutes at extreme service conditions.

3.3.12 Primary Input Power Requirements - The test equipment shall be capable of satisfactory operation when supplied input power having characteristics as defined in MIL-T-21200. The power required shall be of the following type (s) and shall not exceed the specified amounts:

AC Power, Single Phase, 115V, 380-420 Hz, 350 VA

3.3.12.1 Protection - The equipment shall be capable of withstanding input power variations as imposed by abnormal electric system operations as defined in MIL-STD-704.

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:15Z
Check the source to verify that this is the current version before use.

3.4 Performance - Unless otherwise specified, values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme conditions. When reduced performance under extreme conditions is acceptable, tolerances or values setting forth acceptable variations from the performance under the standard conditions will be specified.

3.4.1 Test Capabilities - To be provided as follows:

The Flight Line Test Set shall provide for test of the AN/APN-141 (V) Radar Altimeter while the altimeter is installed in the aircraft, and shall possess the following test capabilities:

(a) System Test (GO/NO-GO) - This test capability shall provide for a rapid confidence check of the overall altimeter system with no disturbance of the aircraft cable harness.

(b) Fault Isolation - The test capability shall provide for fault isolation of the altimeter Height Indicator, Coupler unit and Receiver Transmitter and RF switch units.

3.5 Detail Requirements

3.5.1 Test Set, AN/APM-348 Characteristics:

3.5.1.1 System Test Section Characteristics - This part of the test shall operate independent of the Fault Isolation section. It shall receive the transmitted 4300 MHZ signal of the AN/APN-141 (V) system via a waveguide horn (antenna). It shall process this signal and return it to the altimeter receiving antenna via another waveguide horn.

3.5.1.1.1 The signal shall be processed to accurately simulate a return signal in the high altitude mode at 1000 feet and in the low altitude mode at 100 feet.

3.5.1.1.2 The signal shall be variable to allow for sensitivity measurements in both modes.

3.5.1.1.3 Simulator accuracy shall be as shown in Table I.

TABLE I

	Condition Tolerance	
Parameter	Standard	Extreme
Delay	±3%	±4.5%
Sensitivity	±5db	±7db

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:15Z
Check the source to verify that this is the current version before use.

3.5.1.2 Fault Isolation Test Section Characteristics - This part of the test shall provide for the following tests to fault isolate the noted altimeter assemblies from each other and from other avionics system loading.

3.5.1.2.1 Height Indicator Test - The test set, when connected in series with the Indicator and its cable connector shall provide the altitude test signals, as shown in Table II.

TABLE II

Altitude	Condition Tolerance	
	Standard	Extreme
10 ft.	± 1%	± 1.5%
100 ft.	± 1%	± 1.5%
300 ft.	± 1%	± 1.5%
1000 ft.	± 1%	± 1.5%
4000 ft.	± 1%	± 1.5%
* 5000ft.	-0% ±20%	-0% ± 20%

* This signal is not used for Indicator accuracy tests, but shall be provided for energizing the Indicator FLAG circuit.

3.5.1.2.2 Coupler Unit Test Characteristics - The test set shall provide input signals to test the Coupler unit accuracy and shall be capable of comparing the signal input with the Coupler unit linearized output. A GO indication shall occur when comparison of the Coupler input and output signals are within the range of specified limits. A NO-GO indication shall occur when the signal comparison is outside the specified limits. See Table III.

TABLE III

Signal Comparison Point	GO Limits	NO-GO Conditions
100 ft. or less	± 2.5 ft.	± 4 ft.
Greater that 100 ft.	± 2.5%	± 4%

3.5.1.3 The test set shall provide for selecting either the normal avionics Coupler load or a dummy load within the Test Set.

The Dummy Load shall be:
2.7K ± 5% Standard conditions, ± 10% extreme conditions.

3.5.1.4 The test set shall also have provision for indicating the following altimeter system conditions:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:15Z
Check the source to verify that this is the current version before use.

(a) Self Test Mode
(b) Low Altitude Limit
(c) Coupler Reliability Mode

3.5.2 Form Factor - The overall maximum dimensions of the Flight Line Test Set (including the guard rail system) shall be fourteen (14) inches high, twenty (20) inches long, and thirteen and one-half inches (13 1/2)wide.

3.5.2.1 Weight - The weight of the Flight Line Test Set including accessories shall not exceed fifty-nine (59) pounds. Of this the fault isolation panel shall weigh approximately fourteen (14) pounds.

3.5.2.2 Cover and Case Assembly - The equipment shall be housed in a combination case, composed of two sections. The Cover Assembly and the Case Assembly shall have the capability of being separated.

3.5.2.3 The Cover Assembly shall have a hinged panel and will be used to store and transport the two (2) microwave horns and the six (6) cable assemblies.

3.5.2.4 The Case Assembly shall contain two (2) sections. One section (system test) will consist of all microwave components and be fixed in the case. The second section (fault isolation) will consist of electronic components and shall be removable from the case for cockpit testing (as required).

3.5.2.4.1 Handles and Latches - The Case Assembly shall contain two (2) handles, with latches provided for attaching the cover to the case.

3.5.2.4.2 Feet - The Case Assembly shall have one set of feet on the bottom.

3.5.3 Contents - The Test Set, AN/APM-348 shall contain the following assemblies/subassemblies having the indicated characteristics:

Assembly/Subassembly	Characteristics
(1) Comparator, Printed Wiring	(a) A precision ladder (accurate to one tenth percent) points, namely, zero feet, ten feet, one hundred feet, three hundred feet, one thousand feet, five thousand feet and a flag check. These signals are used for indicator and coupler tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:15Z
Check the source to verify that this is the current version before use.

(b) A comparator circuit which facilitates the GO/NO GO testing of a coupler. A second precision ladder (accurate to one tenth percent) is used as one input to the comparator while the coupler output is fed to the other input.

(c) A reliability circuit which accepts signals from the coupler and activates circuitry to display a reliable or an unreliable condition.

(d) A +4VDC regulator circuit which supplies a reliable input voltage to the coupler.

(2) 30 Volt Power Supply -

Input Voltage Range 105-125VAC
Input Frequency 50-400HZ
Regulation Accuracy +0.05%
Ripple @400 HZ 0.004% or 3 MVRMS
Output Adjustment Range 29.2 to 32.7VDC

(3) 5 Volt Power Supply -

Input Voltage Range 105-125VAC
Input Frequency 50-400HZ
Regulation Accuracy +0.5%
Ripple at 400HZ 0.04% or 10MVRMS
Outpit Adjustment Range 4.7 to 5.3V

(4) Attenuator, Coaxial -

10DB
Attenuation 10db +0.6db
Freq. Range DC to 5GHZ
Impedance 50 ohms
Max. Average Pwr. 2 to 4 watts
Max. Peak Pwr. 2.5KW

(5) Attenuator, Coaxial -

20DB
Attenuation 20db +1.0db
Freq. Range DC - 5GHZ
Impedance 50 ohms
Max. Average Pwr. 2 to 4 watts
Max. Peak Pwr. 2.5 KW

(6) Attenuator, Variable -

Attenuation Range 0 to 50db
Frequency 4300 + 10MHZ
Insertion Loss 0.5db (max.)
VSWR 1.5 max.
Average Power 10 watts

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:15Z
Check the source to verify that this is the current version before use.

(7) Directional Coupler	-	Frequency 4300 MHZ ± 10 MHZ VSWR 1.5 Primary & Secondary Coupling 20 ± 1db Impedance 50ohms nominal Insertion Loss 0.2db (max.) Directivity 15db (min.)
(8) Delay Line-Cable Assembly	-	Total Delay 178 Nanoseconds ±2% Attenuation Less than 45db VSWR 1.25: 1 or less
(9) Delay Device-Solid State	-	Frequency 4300MHZ ± 43 MHZ Insertion Loss 35 ± 1.5db Delay Time 2.02 microseconds ± 1% VSWR not to exceed 4:1
(10) Isolator (Terminated C Board)	-	Frequency 4.3 ± 0.1 GHZ Isolation 20 db (min.) Insertion Loss 0.4db (max.) VSWR 1.20 (max.)

3.5.4 Controls and Indicators - The equipment controls and indicators, their function and location shall be as follows:

System Test Controls -

CONTROL NAME	FUNCTION	LOCATION
ATTENUATOR	Sets signal level for sensitivity check.	Front Panel

Fault Isolation Controls - These shall be as follows:

CONTROL NAME	FUNCTION	LOCATION
5V Adjust*	5 Volt Power Supply Adjust	PS-1 supply
30V Adjust*	30 Volt Power Supply adjust	PS-2 supply
15V REG. ADJ.*	15 Volt regulator adjust	A1 board
OFFSET ADJ.*	Int. Ckt. offset voltage adjust	A1 board
ALTITUDE SELECTOR	Selects Indicator or Coupler for test	Front Panel
COUPLER-OFF-INDICATOR	Selects 400 Hz power source	Front Panel
IND-CPLR switch	Selects unit for test	Front Panel
REL-UNREL switch	Selects condition for Coupler test	Front Panel
COUPLER switch	Selects avionics or dummy load	Front Panel

* These controls are used for periodic calibration only.

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:15Z
Check the source to verify that this is the current version before use.

3.5.4.3 Fault Isolation Section Indicators

INDICATOR NAME	FUNCTION	LOCATION
REL SIG OUT	Indicates Reliability Output	Front Panel
115VAC	Indicates 115VAC availability	Front Panel
SELF TEST	Indicates Self Test	Front Panel
LOW ALT LIMIT	Indicates Low Altitude Limit	Front Panel
NO-GO-LOW	Indicates Coupler Output of Tolerance Condition	Front Panel
GO	Indicates Coupler Output within Tolerance	Front Panel
NO-GO-HIGH	Indicates Coupler Output Out of Tolerance Condition	Front Panel

3.5.5 Electrical Connections

Fault Isolation Connections to external circuits shall be as follows:

REFERENCE DESIGNATION	RECEPTACLE TYPE	FUNCTION
J1	MS 3114E12-10PW	from coupler, signal inlet
J2	MS 3114E12-10S	to coupler, signal outlet
J3	MS 3114E14-19S	from indicator, signal inlet
J4	MS 3114E14-19PW	to Indicator, signal outlet

3.5.5.1 System Test Connections to external circuits shall be provided as follows:

REFERENCE DESIGNATION	RECEPTACLE TYPE	FUNCTION
CP-1	CT 3000-75 (94375)	RF Signal Input (1000ft.)
CP-2	CT 3000-75 (94375)	RF Signal Input (100 ft.)
CP-3	CT 3000-75 (94375)	RF Signal Output

3.5.6 Case, Test Set AN/APM-348 - The test set shall be provided with a combination case which shall conform to specification MIL-T-21200.

3.5.6.1 Size - 19.65 inches deep, 13.15 inches wide and 14" max. inches high.

3.5.6.2 Cover

3.5.6.2.1 Size - 19.65 inches deep, 13.15 inches wide and 6.13 inches high.

3.5.6.3 Material - Aluminum Alloy 6061-0

3.5.6.4 Finish - Paint, yellow glass enamel, color no. 13538 Fed. Std. 595

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:15Z
Check the source to verify that this is the current version before use.

3.5.6.5. Stowage - Shall provide sufficient stowage volume for the accessories listed in para. 3.5.7 and instruction book.

3.5.7 Cable Assemblies and Accessories - Cable Assemblies and Accessories shall be provided as follows:

DRAWING NO.	NOMENCLATURE	QUANTITY
1528-2300	Cable Assy	1
1528-2301	Cable Assy	1
1528-2302	Cable Assy	1
1528-2303	Cable Assy	1
1528-2304	Cable Assy	1
1528-2100	Antenna	2
-----	Instruction Book	1

4. QUALITY ASSURANCE

4.1 Responsibility for Inspection - Unless otherwise specified in the contract, or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any inspections deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Classification of Tests - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements:

(a) Preproduction Tests
(b) Acceptance Tests

4.2 Preproduction Tests - Preproduction tests shall be made on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of 4.4. The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the services of a commercial testing laboratory acceptable to the Government.

4.2.1 Preproduction Test Data - The contractor shall submit all data collected in conducting these tests to the procuring agency for review and approval. On first production contracts this data shall include a list of all electrical and electronic parts giving their specified voltage, and ambient and surface temperatures. The ambient and surface temperature shall be obtained under the extreme high temperature operating condition.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:15Z
Check the source to verify that this is the current version before use.

4.2.2 Scope of Tests - Preproduction tests shall include all tests deemed necessary by the procuring activity to determine that the equipment meets all the requirements of this specification and the contract. Preproduction test shall include environmental tests in accordance with the requirements of MIL-T-5422 to the limits specified in MIL-T-21200.

4.2.3 Preproduction Approval - Approval of the preproduction sample shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction sample. Prefabrication of production equipment prior to the approval of the preproduction sample is at the contractor's own risk. The approved preproduction sample shall be retained by the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction sample shall not be considered as one of the equipments under the contract.

4.2.4 Production Equipments - Equipments supplied under the contract shall in all respects, including design, construction, workmanship, performance and quality, be equivalent to the approved preproduction sample. Each equipment shall be capable of successfully passing the same tests as imposed on the preproduction sample. Evidence of non-compliance with the above shall constitute cause for rejection and for equipment already accepted by the Government. It shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.3 Acceptance Tests - The supplier shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the Government Inspector. Suppliers not having testing facilities satisfactory to the procuring activity shall engage the services of a commercial testing laboratory acceptable to the procuring activity. The supplier shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the supplier. Acceptance tests shall consist of individual unit tests.

4.3.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability specified herein. As a minimum, each equipment accepted shall have passed the following tests:

1 Examination of Product
2 Operational Test

4.3.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.3.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:15Z
Check the source to verify that this is the current version before use.

4.4 Test Procedures - The procedures used for conducting preproduction tests and acceptance tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the Government Inspector to modify or require any additional tests deemed necessary to determine compliance with the requirements of this specification or the contract. Test specifications shall be prepared in accordance with MIL-T-18303. When test procedures are available from previous contracts, such procedures may be used when approved by the procuring activity.

4.5 Presubmission Testing - No item, part or complete equipment shall be submitted until it has been previously tested and inspected by the supplier and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.5.1 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejections and the action taken to correct the defects found in the original shall be furnished to the Government Inspector.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with MIL-E-17555.

6. NOTES

6.1 Performance Objectives - Minimum size and weight, simplicity of operation, ease of maintenance, and an improvement in the performance and reliability of the specific functions beyond the requirements of this specification are objectives which shall be considered in the production of this equipment. Where it appears a substantial reduction in size and weight or improvement in simplicity of design, performance, ease of maintenance or reliability will result from the use of materials, parts and processes other that as specified in MIL-T-21200, it is desired their use be investigated. When investigation shows advantages can be realized, a request for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

6.1.1 As a general rule, nonrepairable subassemblies should be encapsulated or hermetically-sealed. The number of connections internal to the subassembly should be held to a minimum. Detail parts tolerances and ratings should be so selected that the life of the subassembly is greater than that of a similar repairable one. With few exceptions (such as high voltage power supplies), the non-repairable subassembly should evidence a mean-time-to-failure greater than 5000 hours, and for many applications this figure must be nearer 50,000 hours.

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:15Z
Check the source to verify that this is the currentversion before use.

6.2 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(a) Contract - The contract shall have precedence over any specification.

(b) This Specification - This Specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(c) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.3 Ordering Data - Purchasers should exercise any desired options offered herein, and procurement documents should specify the following:

(1) Title, number, and date of this specification
(2) Selection of applicable levels of packaging and packing (See 5.1)

6.4 Definition - The following non-military definition shall apply throughout this specification.

6.4.1 Supplier - The facility fabricating, assembling, acceptance testing and furnishing the equipment in accordance with the contract specifications.

Project No. 6625-N502

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:15Z
Check the source to verify that this is the currenversion before use.