SS-B-755a
AMENDMENT-1
May 21, 1968

[redacted]EDERAL SPECIFICATION

BUILDING BOARD, ASBESTOS-CEMENT:

FLAT AND CORRUGATED

This amendment, which forms part of Federal Specification SS-B-755a, dated 9 March 1967, was approved by the Commissioner, Federal Supply Service, General Services Administration, for the use of all Federal agencies.

Page 1

2.1, under SPECIFICATIONS Federal: Delete

"PPP-C-650 - Crates, Wood, Open and Covered."

Before STANDARDS Military: Add

"SPECIFICATIONS

Military

MIL-W-3448 - Wallboard, Packaging of.
MIL-H-3982 - Hardware, (Fasteners, and Related Items), Packaging and Packing for Shipment and Storage of."

Page 2

2.2: Add

"2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

UNIFORM CLASSIFICATION COMMITTEE

Uniform Freight Classification Rules.

(Application for copies should be addressed to the Uniform Classification Committee, 202 Union Station, 516 West Jackson Boulevard, Chicago, Illinois 60606.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:14Z
Check the source to verify that this is the current version before use.

AMERICAN TRUCKING ASSOCIATIONS, INC.

National Motor Freight Classification Rules.

(Application for copies should be addressed to the American Trucking Associations, Inc., 1616 P Street NW, Washington, D. C. 20036.)

(Technical society and technical association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)"

After 3.8.2.2: Add

"3.8.3 Fasteners. When specified (see 6.2), fasteners for fastening the asbestos sheets and supplementary pieces to the supporting members shall be furnished. Fasteners shall be for metal or wood supporting members, as specified (see 6.2), and shall be of the type and size recommended by the supplier."

4.1, delete and substitute:

"4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

4.4.1, Major defects: Add

"112. Fasteners not as specified (when applicable)."

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:14Z
Check the source to verify that this is the current version before use.

4.5.1.3, delete and substitute:

"4.5.1.3 Examination. Samples selected in accordance with 4.5.1.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

113. Materials and containers not as specified for level A. Each incorrect material or container shall be considered one defect.
114. Strapping not zinc coated for level A.
115. Supplementary shapes and filler strips not blocked and braced within the box to prevent movement for level A.
116. Packaging of fasteners not as specified.
117. Marking missing, illegible, incorrect, or incomplete."

5., delete and substitute:

"5. PREPARATION FOR DELIVERY

5.1 Packaging. Packaging shall be level A or C as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Fasteners. The fasteners shall be packaged as specified in MIL-H-3982.

5.1.2 Level C. The fasteners, shapes, and filler strips shall be packaged to afford protection against deterioration and damage from the supplier to the initial destination.

5.2 Packing. Packing shall be level A or C as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Fasteners, supplementary shapes, and filler strips. The fasteners, packaged as specified in 5.1, and the supplementary shapes and filler strips shall be packed in boxes conforming to PPP-B-601, overseas type, style A or B. The contents shall be braced, blocked, and cushioned as applicable to prevent free movement and damage to the components. Strapping shall be zinc coated.

5.2.1.2 Building board. Building board of like size and description shall be packed in accordance with the level A requirements of MIL-W-3448.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:14Z
Check the source to verify that this is the current version before use.

Page 5 (cont'd)

5.2.2 Level C. The building board, fasteners, supplementary shapes, and filler strips shall be packed or prepared for shipment in a manner to assure carrier acceptance and safe delivery to destination at lowest rates in compliance with Uniform Freight Classification Rules or National Motor Freight Classification Rules.

5.3 Marking.

5.3.1 Civil agencies. In addition to any special marking specified in the contract or order, marking for shipment shall be in accordance with FED. STD. No. 123.

5.3.2 Military agencies. In addition to any special marking specified in the contract or order, marking for shipment shall be in accordance with MIL-STD-129."

Page 6

6.2, delete and substitute:

"(e) Level of packaging and level of packing required (see 5.1 and 5.2)."

6.2: Add

"(f) When fasteners are required, and whether the fasteners are to be used for metal or wood supporting members (see 3.8.3)."

Custodians:

Army - ME
Navy - YD
Air Force - 84

User activity:

Army - CE

Civilian agencies interest:

COM - NBS
GSA - FSS
JUS

Preparing activity:

Army - ME

Review activities:

Army - ME
Navy - YD
Air Force - 85
DSA - CS
Other - NSA

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:14Z
Check the source to verify that this is the current version before use.