INCH-POUND

MIL-C-28754/89A(NW)
23 March 1994
SUPERSEDING
MIL-C-28754/89(NAVY)
21 April 1989

MILITARY SPECIFICATION SHEET

CONNECTORS, ELECTRICAL, MODULAR, CONNECTOR FRAME, TYPE IV, OFFSET, (0.071 THICKNESS)

This specification sheet is approved for use by the Crane Division, Naval Surface Warfare Center, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

The requirements for acquiring the product described herein shall consist of this specification sheet and the issue of the following specification listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation: MIL-C-28754.

AMSC N/A FSC 5935
DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202640-20T14:54Z
Check the source to verify that this is the current version before use.




FIGURE 1. Dimensions and configurations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T14:54Z
Check the source to verify that this is the current version before use.




FIGURE 1. Dimensions and configurations - Continued.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T14:54Z
Check the source to verify that this is the current version before use.

Inches	MM	Inches	MM	Inches	MM	Inches	MM
0.000024	0.0006	0.060	1.52	0.500	12.70	4.820	122.43
0.001	0.03	0.062	1.58	0.600	15.24	4.840	122.94
0.002	0.05	0.071	1.80	3.263	82.88	4.890	124.21
0.003	0.08	0.073	1.85	3.820	97.03	5.100	129.54
0.004	0.10	0.092	2.34	4.028	102.31	5.110	129.79
0.005	0.13	0.106	2.69	4.068	103.33	5.275	133.99
0.006	0.15	0.128	3.25	4.080	103.63	5.445	138.30
0.010	0.25	0.155	3.94	4.218	107.14	5.880	149.35
0.015	0.38	0.170	4.32	4.315	109.60		
0.020	0.51	0.172	4.37	4.350	110.49		
0.030	0.76	0.300	7.62	4.388	111.46		
0.050	1.27	0.375	9.53	4.630	117.60		

NOTES:

1. Dimensions are in inches.
2. Metric equivalents are given for general information only and are based upon 1.00 inch = 25.4 mm.
3. Unless otherwise specified, tolerances are plus or minus .005 inch (.13 mm) on three place decimals, plus or minus .01 inch (.3 mm) on two place decimals and plus or minus 5° on angles.
4. Unless otherwise specified, all corner radii shall be .02 inch (.51 mm) radius maximum.
5. Dimensional limits apply after plating.

FIGURE 1. Dimensions and configurations - Continued.

Source: https://assist.dla.mil -- Downloaded: 202610-20T14:54Z
Check the source to verify that this is the current version before use.

NOTES: - Continued.

6. Mark part number, revision letter, manufacturer's code identification and date code in .12 inch (3.0 mm) plus or minus .02 inch (.51 mm) high gothic characters at approximate location shown. Use black epoxy ink per MIL-I-43553. Mark in accordance with MIL-STD-130.

7. The frame must be straight and flat to meet the requirements of the drawing prior to plating. No straightening or bending is permitted after plating.

8. Break sharp edges .005 inch (.13 mm) maximum and remove all burrs.

9. When fabricating all holes, slots and other cutouts in the frame material, care must be taken to produce features that are not prone to fracture propagation. For example, all slots are to end in a smooth radius feature, and hole surfaces are to be smooth. Break all sharp edges and polish all edges, corners, and hole circumferences.

10. These holes are to be used as racking points for plating. The use of any other racking point is not permitted.

11. Thickness is that of the finished part including all platings and coatings.

12. Surfaces shall include the shaded areas (2 places).

FIGURE 1. Dimensions and configurations - Continued.

Source: https://assist.dla.mil -- Downloaded: 202640-20T14:54Z
Check the source to verify that this is the currentversion before use.

REQUIREMENTS:

Dimensions and configurations: See figure 1.

*Material: Copper in accordance with ASTM B152, alloy UNS No. C11000, temper H03.

*Finish: Surface roughness per ANSI B46.1. Plating shall be electroless nickel per MIL-C-26074, five percent phosphorous minimum, class 1, grade A, .0015 inch (.04 mm) plus or minus .0005 inch (.013 mm). Within four hours after plating, oven bake at 275, plus or minus 10°F (135, plus or minus 6°C) for two hours for hydrogen relief and adhesion.

Examination: One frame from each plating lot shall be exposed to salt fog per MIL-STD-1344, Method 1001, test condition B, and one frame shall be exposed to oven bake at 190, plus or minus 6°C for 60 to 90 minutes. Examine each frame, using 6 to 10 power magnification, for loose or blistered coating. Examination results shall be delivered with each order. The examined frames shall be retained by the plater for a period of 6 months.

*Stress relief: Frame shall receive the following bake cycle: 190, plus or minus 6°C for 90, plus or minus 10 minutes, prior to plating and after all fabrication steps (bending, machining, or deburring).

Military part number: M28754/89

Qualification information: The frame shall meet the following qualification tests of MIL-C-28754, table IV, type IV: Subgroup I, Visual and Mechanical examination; Subgroup II, Vibration, Visual and Mechanical examination; Subgroup III, Salt spray, Visual and Mechanical examination; Subgroup IV, Shock, Fin/Header torque, Fin cantilever load, Rib strength, Visual and Mechanical examination.

Number of units to be inspected: 12 units of each dash number to be qualified shall be inspected.

Supersession data: Supersedes Naval Sea Systems Command Drawing Number 5516570, Code Identification Number 53711.

Source: https://assist.dla.mil -- Downloaded: 20260-20T14:54Z
Check the source to verify that this is the current version before use.

*Changes from previous issue: The margins of this specification sheet are marked with asterisks to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

*Custodian:
Navy - NW

Preparing activity:
Navy - NW

(Project 5935-N453)

User activity:
Navy - AS

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T14:54Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-C-28754/89A(NW)	1994 March 23

3. DOCUMENT TITLE
Connectors, Electrical, Modular, Connector Frame, Type IV, Offset, (0.071 Thickness)

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
Technical Point of Contact (TPOC): Mr. Joseph P. Toy (Code 603) PLEASE ADDRESS ALL CORRESPONDENCE AS FOLLOWS:	TPOC: 812-854-5993	88-482-5993
c. ADDRESS (Include Zip Code) Commander ATTN: Joseph P. Toy, Code 603A, Bldg. 2917 NAVSURFWARCENDIV, 300 Highway 361 Crane, IN 47522-5001	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil - Downloaded: 2026-02-20T14:54Z
Check the source to verify that this is the current version before use.