MILITARY SPECIFICATION

CONTAINER, AMMUNITION, PLASTIC, FOR 60MM MORTAR AMMUNITION

1. SCOPE

1.1 Scope. This specification covers molded, high density polyethylene plastic containers, for shipment and storage of ammunition for Mortars, 60MM, HE, M49A2 or TP, M50A2.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

FEDERAL

FED-STD-595 - Colors

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105).
MIL-STD-109 - Quality Assurance Terms and Definitions.
MIL-STD-1168 - Lot Numbering of Ammunition.
MIL-STD-1169 - Packaging, Packing and Marking for Interplant Shipment of Inert Ammunition Components, General Specification for
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

FSC: 8140

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

DRAWINGS

ARMY

8837375 - Picatinny Arsenal Environmental Testing Criteria for Shipping Containers
9223925 - Container, Ammo, Plastic for Cartridge, 60MM, HE, M49A2E2 or TP, M50A2E1.

PUBLICATIONS

ARMY

ET-9223925 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications.-The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

American Society for Testing and Materials Publications.

D1238-57T - Measuring Flow Rate of Thermoplastics by Extrusion Plastometer
D1505-57T - Measurement of Density of Plastics by the Density Gradient Technique

(Application for copies should be addressed to the American Society for Testing Materials, 1916 Race Street, Philadelphia 3, Pa.)

3. REQUIREMENTS

3.1 Material.-The resin used in the manufacture of the container shall be high density polyethylene or copolymer thereof, which contains 0.3 percent, plus or minus 0.05 percent carbon black, an anti-oxident and an ultraviolet stabilizer uniformly dispersed. In addition, the containers shall be in accordance with the applicable drawings and specifications.

3.2 Mold release agent.-No release agent used in the molding process shall have silicone components, or other components, that may adversely affect the printability of the exterior surfaces of the container.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

3.3 Physical properties.-The high density polyethylene container shall conform to the physical properties listed in Table I when tested as specified in 4.3.

3.4 Reworked material.-No reworked material or reground scrap (including runners and sprues) shall be utilized in molding containers under this specification. However, initial pelletizing of the molding compositions used shall not be construed as reworking.

3.5 Waterproofness.-The container shall be waterproof as evidenced by absence of air leakage when tested as specified in 4.4.8.

3.6 Workmanship.-All parts shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of cracks, burrs, surface defects, flash, air bubbles, holes, blisters, amides, dirt, twists, and scrap. The cleaning method shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agents. (see 4.4.7).

TABLE I
Physical Properties

Test	Requirements
Melt Index, grams/10 minutes with 2160g load	3.0 max.
Density, gms/ml	0.955 min.
Color Number	All sections of the container shall closely approximate composition colors Numbers 14036, 14052, 14056, 14062, 14064 or 14077. Although specified colors are listed as gloss, the surface finish on the container will be as produced from good molding practices.
Thermal stress cracking resistance	The containers shall not crack, split, warp, or break when exposed for 100 hours at 71 degrees C. and tested as specified in 4.4.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

Torque Test	The closure shall be completely removed without exceeding the maximum torque specified on the applicable drawing when tested as specified in 4.4.4.
Free fall drop test 23 degrees Centigrade (°C.) 71 degrees C. -40 degrees C.	The container shall withstand the free fall drop test without evidence of cracking, splitting, breaking or damage to item packed therein. Closures shall remain intact and closure gaskets unbroken when tested as specified in 4.4.5.
Wettability of container	The prepared exterior surface of the container shall hold water as a continuous film for a minimum of two seconds, when tested as specified in 4.4.6.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified within this specification.

b. Number of units of product inspected.

c. Results obtained, by defect code, for all inspections performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 Government verification.-Using the contractor's written quality assurance procedure, this detailed specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals, all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial production inspection (see 6.1).

4.2.1 Submission.-Prior to the initiation of regular production the contractor shall submit an initial production sample consisting of fifty components from each die or mold, which shall be selected proportionally from each cavity, which have been produced by the production process which the contractor will use in fulfilling the contract, to a Government-approved facility designated by the Contracting Officer. The component shall be identified by die or mold number, and the cavity number in the die or mold, as applicable. All parts and materials shall be obtained from the same source of supply as will be used in regular production. The initial production sample shall be accompanied by certificates of conformance for all materials. In addition, the contractor shall furnish a statement of his process variables such as temperatures, pressures and cycles. A sample shall also be submitted whenever a change occurs in manufacturing process, material used, drawing, specification, or source of supply such as to significantly affect product uniformity as determined by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

4.2.2 Inspections to be performed.-Assemblies and components shall be subjected by the Government to any or all of the inspections and tests specified in this specification. In addition, one component from each cavity of each die or mold, as applicable, shall be inspected for compliance with any or all of the requirements specified on the applicable drawing.

4.2.3 Rejection.-If any assembly or component fails to comply with any or all of the applicable requirements, the initial production sample shall be rejected. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit new or supplemental quantities until such time as an acceptable sample is submitted, or until otherwise directed by the Contracting Officer.

4.3 Inspection provisions.

4.3.1 Lot formation.-A lot shall consist of high density polyethylene plastic molded containers produced by one manufacturer in one unchanged continuous process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance, interchangeability or storage, as determined by the Government shall not necessitiate changing the lot interfix number. The examinations and tests listed herein shall be performed on inspection lot submitted in accordance with Standard MIL-STD-105 or MIL-STD-1235, as applicable. The criteria and procedures for the assignment of lot numbers shall be in accordance with Standard MIL-STD-1168. Each lot shall contain:

a. Material from one lot from the same manufacturer.
b. Material of one color designation.
c. Components from the same manufacturer.

4.3.2 Examination.-Inspection for Critical defects (and Major defects, when so specified,) shall be 100 percent. Sampling plans and procedures for Major and Minor defects shall be in accordance with Standard MIL-STD-105 except that continuous sampling plans in accordance with Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to individual characteristics listed using an AQL of 0.65 percent for each Minor defect and an AQL of 0.40 percent for each Major defect, except where 100 percent inspection is specified. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

4.3.2.1 Closure (see 4.3.3.2 and dwg. 9223926 covering a detail of dwg. 9223925).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Location of threads from face of open end	Gage	01001
Minor:	AQL 4.0 percent		
201.	Width of slot	Gage	01002
202.	Wall thickness, min.	Gage	01003
203.	Small outside diameter	Gage	01004
204.	Total length	Gage	01005
205.	Thickness of base from rearward face	Gage	01006
206.	Sprue projection, max.	Gage	01007
207.	Internal radius missing	Visual	01008
208.	Color incorrect	Visual	01009
209.	Manufacturer's identification missing	Visual	01010
210.	Evidence of poor workmanship (see 3.6)	Visual	01011

4.3.2.2 Body (see dwg. 9223927 covering a detail of dwg. 9223925).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Depth of thread, min.	Gage	02001
102.	Width of thread	Gage	02002
103.	Location of thread from open end face	Gage	02003
104.	Straightness	Gage	02004
105.	Inside diameter (large)	Gage	02005
106.	Inside diameter of fuze cavity	Gage	02006
107.	Location of "O" ring seat from open end face	Gage	02007

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

Minor:	AQL 4.0 percent		
201.	Depth of fuze cavity	Gage	02008
202.	Total length	Gage	02009
203.	Outside diameter (large)	Gage	02010
204.	Wall thickness, min.	Gage	02011
205.	Thickness of base from rearward face	Gage	02012
206.	Incorrect color	Visual	02013
207.	Manufacturer's identification missing	Visual	02014
208.	Evidence of poor workmanship (see 3.6)	Visual	02015

4.3.2.3 Container, Ammo, Plastic, Assembly (see dwg. 9223925).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Total length, max.	Gage	03001
Minor:	AQL 0.65 percent		
201.	Outside diameter, max.	Gage	03002

4.3.3 Tests

4.3.3.1 Classification of tests.-The examination and testing of the container assemblies shall be classified as follows: (see 6.6)

(a) Initial production tests.
(b) Regular production tests.

4.3.3.1.1 Initial production tests.-The initial production tests shall consist of all inspections tests and quantities as specified in 4.3 except that a quantity of ten container assemblies will be subjected to the tests specified in 4.3.3.8.

4.3.3.1.2 Regular production tests.-The regular production test for acceptance of individual lots shall consist of inspections and tests as specified in 4.3.

4.3.3.2 Delay time in dimensioning examinations.-No attempt shall be made to determine compliance with dimension and tolerance requirements of the sections for a minimum period of 48 hours after molding.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

4.3.3.3 Melt index (see Table 1) Major Defect, Code No. 10001. Three determinations shall be made and averaged from each lot for this test. Failure of average to meet the values when tested as specified in 4.4.1 shall be cause for the lot to be rejected.

4.3.3.4 Density (see Table 1) Major Defect, Code No. 10002. Three determinations shall be made and averaged from each lot for this test. Failure of average to meet the values when tested as specified in 4.4.2, shall be cause for the lot to be rejected.

4.3.3.5 Thermal stress cracking resistance (see Table 1) Major defect, Code No. 10003.-A sample of five container assemblies shall be selected at random from each lot for this test. If one or more assembly fails to comply with the requirements when tested as specified in 4.4.3, the lot shall be rejected.

4.3.3.6 Torque test (see Table 1) - Major defect, Code No. 10004.-Determination of compliance with this requirement shall be made on the samples required by 4.3.3.5. Torque values of five containers shall be averaged. If the average exceeds the maximum torque requirement when tested as specified in 4.4.4, the lot shall be rejected.

4.3.3.7 Free fall drop test (see Table 1) - Major Defect Code No. 10005.-A sample of five container assemblies shall be selected at random from each lot for this test. If one or more assembly fails to comply with the requirement when tested as specified in 4.4.5, the lot shall be rejected.

4.3.3.8 Wettability of container (see Table 1) - Major defect, Code No. 10006.-A sample of twenty-five container assemblies shall be selected at random from each eight hours production and tested as specified in 4.4.6. If one or more container fails to comply with the requirement specified, the entire quantity produced on initial production or since the last acceptance test shall be tested and the defective containers shall be rejected and removed from the lot. The reject containers shall be reprocessed and retested 100 percent. Any container failing to meet the specified requirement on retest shall be removed from the lot and shall not be eligible for further acceptance.

4.3.3.9 Void determination.-Major defect, Code No. 10007.-A sample of five of each component, representative of each shipment shall be selected at random for this inspection. If one or more components fails to comply with the requirement when tested as specified in 4.4.7, the lot shall be rejected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

4.3.3.10 Waterproofness (see 3.5) - Major defect - Code No. 10008.-The sampling plan for this test shall be in accordance with Standard MIL-STD-105, Code letter H, and an AQL 1.0 percent. The test shall be performed as specified in 4.4.8 using test equipment in accordance with 4.3.4.

4.3.3.11 Engagement of thread, Major defect, Code No. 10009.- A sample of three of each components from each cavity, representative of each shipment shall be selected at random for this inspection. If one or more components fail to comply with the requirement when tested as specified in 4.4.9, the lot shall be rejected. (See 6.7)

4.3.4 Inspection Equipment.-Equipment Tabulation Number ET-9223925 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed in the ET shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection and test equipment.-The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test methods and procedures.

4.4.1 Melt Index.-Melt Index shall be determined in accordance with ASTM D1238-57T, Condition E. The test specimens shall be cut from a container.

4.4.2 Density.-The density of the specimens shall be determined in accordance with ASTM D1505-57T. The test specimen shall be cut from a container. Specimens shall not be annealed or otherwise treated so as to change the crystallinity. (See 6.5)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

4.4.3 Thermal stress cracking resistance.-The closure shall be assembled to the tube or body, without closure sealing gasket, to within approximately 1/8 inch of the O ring seat. The assemblies shall then be subjected to 100 hours at 71 degrees Centigrade, plus or minus 1 degree C. Immediately following the 100 hour time period each container shall be removed individually and without disturbing the closure position, shall be visually examined while warm (see 3.4). The container assemblies shall then be subjected to the procedure of 4.4.4. Following that procedure the containers shall each be cut open longitudinally and the interior surfaces examined visually for evidence of cracks, splits, warping or other deformation.

4.4.4 Torque Test.-Following the initial visual examination of 4.4.3 the containers shall be allowed to come to temperature equilibrium at 23 degrees Centigrade, plus or minus 1 degree C. While at that temperature the amount of torque required to completely remove each closure shall be determined using inspection equipment in accordance with 4.3.4.

4.4.5 Free Fall Drop Test

4.4.5.1 Individual containers without over pack shall be prepared in accordance with the loading, assembly and packing specification for the ammunition item being packed, except that the rounds shall be completely inert.

Using inspection equipment in accordance with 4.3.4, the assemblies shall be subjected to the free fall drop test sequence for cylindrical containers indicated in Picatinny Arsenal Environmental Testing Criteria for Shipping Containers, Drawing 8837375, except that for the edge drops a free fall angle of 10.5 plus or minus 1 degree shall be maintained between the axis of the container and the vertical.

Following the falls the containers shall be opened and examined for evidence of cracking, splitting or breaking of tube or closure. The closures shall have remained intact prior to opening for examination and the gaskets remained unbroken. The containers shall be cut open longitudinally and the interior surfaces similarly examined for such damage.

Additionally, the ammunition item being packed shall be examined for dented or ruptured cartridge case, loosening of the crimp of the Cartridge to the projectile (as applicable), broken propelling charge bag, damaged rotating band or fuze, or any other damage which would impair the functionality of the ammunition. In case of dispute, the ammunition shall be chamber gaged or fitted into the appropriate weapon to determine its functionality. Failure in this latter examination shall be cause for rejection of the container.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

4.4.5.2 Additional containers shall be prepared as in 4.4.5.1 and then conditioned at 71 degrees Centigrade plus or minus 1 degree C. for 24 hours. The 13 falls shall be completed within 5 minutes after removal from the conditioning chamber in order to maintain as much as possible of the high temperature in the test assemblies. Following the free falls the containers shall be examined as in 4.4.5.1.

4.4.5.3 Additional containers shall be prepared as in 4.4.5.1 and then conditioned at -54.3 degrees Centigrade plus or minus 1 degree C. for 8 hours. The containers shall then be conditioned for 16 hours (overnight) at -40 degrees C. plus or minus 1 degree C. and then drop tested as specified in 4.4.5.1. The 13 falls shall be completed within 5 minutes after removal from the conditioning chamber in order to maintain as much as possible of the low temperature in the test assemblies. Following the free falls the containers shall be examined as in 4.4.5.1.

4.4.6 Wettability of container.-The exterior surface of the container, treated by any standard commercial method (such as flame treatment or chromic acid treatment) for promoting printability of polyethylene surfaces, (and free from subsequent contamination through handling) shall be fully submerged in a water bath. With container held in a horizontal position as it is removed from the water, the tendency of the surface water film to coalesce shall be observed and timed in seconds.

4.4.7 Void determination.-The components selected for this inspection shall be cut into four 90 degree segments. Observation shall be made for indications of voids beyond the drawing requirements.

4.4.8 Waterproofness.-The sample container shall be tested for leakage by submerging in a vacuum vessel and drawing a vacuum. A vacuum differential of 216MM (8-1/2 inches) of mercury shall be held for 30 seconds (minimum). Observation for evolution of air bubbles from any joint area shall be cause for rejection.

4.4.9 Engagement of threads.-The components selected for this inspection shall be measured utilizing standard inspection equipment. Determinations shall be made for indications of the 80 percent thread engagement beyond the drawing requirement.

5. PREPARATION FOR DELIVERY

5.1 Packing - Level C.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

5.1.1 Packing shall be in accordance with Standard MIL-STD-1169. Precaution shall be taken to prevent treated exterior surfaces from becoming contaminated by dirt, dust, light oin film deposits from the air or by handling during shipment and storage. Certain types of paper such as chipboard have an affinity for treated polyethylene surfaces and may destroy the effectiveness of the surface treatment. Therefore suitable means shall be provided to prevent direct contact of the containers with such packing materials.

5.2 Marking

5.2.1 Level C.-Level C shipments shall be marked in accordance with Standard MIL-STD-1169.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Packing required (see 5.1).
c. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
d. Provisions for submission of First Article Samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 Inspection equipment lists.-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242-3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the IEL by the following codes:

CDAF - Contractor's design responsibility on Army format in accordance with MIL-C-45608.
CDCF - Contractor's design responsibility on contractor format.
AD - Army design.
ADMU - Army design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs (see 6.3.6) or commercial equipment selections (see 6.3.5) must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawing.-Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings must be described in sufficient detail to permit identification and evaluation by the Government (see 6.3.5). Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors normally are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. When commercial inspection

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

equipment requires the use of special fixturing, the design of this fixturing shall be considered as part of the total design, and 6.3.6 shall apply. In the latter case, only those portions of the commercial equipment need be detailed in the designs as are necessary to completely fabricate, calibrate, and operate the total item of inspection equipment. Lists and fixturing designs shall be submitted for approval as specified in 6.3.7.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, clibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further caluculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-C-45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35mm microfilm process. Contractors shall submit one copy of the final design as a rolled set or flat set. Designs shall be submitted for approval as specified in 6.3.7.

6.3.7 Submission of contractor designs.-Unless otherwise specified on the IEL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the Contracting Officer. Partial submission os inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

6.4 Molding instructions.-The particular material selected as to density and melt index should be injection molded so as to meet all the requirements of this specification. It must be noted that selection of a material complying with the density and melt index requirements does not necessarily insure compliance with the performance requirements of the specification nor relieve the molder of his responsibility for molding in such a fashion that the containers will meet the requirement.

6.5 Density specimens.-Saw speed in excess of 500 to 600 lineal feet per minute have been found to be unsatisfactory as excess speed can essentially melt the material and greatly change the density.

6.6 Classification of tests.-The term classification of tests as used in text of this specification are intended to be used as follows:

6.6.1 Initial production tests will be the examination and tests performed prior to the start of regular production to assure the Government that the methods and processes being used for regular production will produce an end product by the container supplier which will be acceptable under this specification.

6.6.2 Regular production tests will be the examination and tests performed on a lot to lot basis during regular production to assure the Government that the methods and processes being used for production will produce an end product which will be acceptable under this specification.

6.7 Evaluation test samples.-During the course of regular production, three of each component from each shipment (representative of each cavity) shall be selected and furnished Commanding Officer, Picatinny Arsenal, Dover, N.J. ATTN: SMUPA-NI-5 for further evaluation. The samples shall be identified as to the shipment number from which selected.

Custodian:
Army-MU

Preparing Activity:
Army-MU

Project Number: 8140-A144

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.