MIL-A-46655B (AR)
Amendment 2
21 September 1981
SUPERSEDING
Amendment 1
25 July 1966

MILITARY SPECIFICATION

ATTACHMENTS, TOW AND PUSH FOR
DEMOLITION KIT, PROJECTED CHARGE, M157
PARTS FOR AND PACKING

This amendment forms a part of Military Specification MIL-A-46655B (MU), dated 30 April 1965, and is approved by the US Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 1

* Add the following preamble underneath the title:

"This specification is approved by the U.S. Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense."

PAGE 2

2.1, Drawings:

Delete: "Ordnance Corps" and substitute "U.S. Army Munitions Command".

Delete: "8799689 - Wrench, Structural."

* 3.4: Delete in its entirety and substitute the following:

"3.4 Functioning of gear box assembly. The gear box worm shall rotate the center spool assembly a minimum of 360 degrees in either direction under no load, and rotate the spool 1 inch minimum, in both directions, under a load of 500 pounds, minimum."

FSC: 1375



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.

Add new paragraph 3.7 as follows:

"3.7 First article inspection. This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract."

PAGE 3

4.1.1 (e): Delete in its entirety and substitute the following:

"e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents."

Delete the first paragraphs 4.2, 4.2.1, 4.2.2 and 4.2.3 and substitute the following:

"4.2 First Article Inspection.

4.2.1 Submission. The contractor shall submit a first article sample as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of 2 each of boxes 1 and 2 with contents and 2 complete sets of parts (i.e., 2 each of every individual component and every subassembly) which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including statements of findings and certificates of conformance for material, (see 4.1.1e). A sample containing known defects will not be submitted unless specifically authorized, by the contracting officer. A first article sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.

period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed. Assemblies and components will be subjected by the Government to any or all the examinations or tests specified in 4.3 or 4.4 of this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection. If any assembly or component fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component to comply with any of the stated requirements."

4.3.1: Delete in its entirety and substitute the following:

"4.3.1 Lot formation. The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, specification, or revision thereof. Changes to either the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government inspector, shall not be deemed to alter the homogeneity of the lot. Inspection lots shall comply with MIL-STD-105 and shall be numbered in accordance with MIL-STD-1168.

Unless otherwise approved by the contracting officer, the inspection lot size of major assemblies or end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.

scheduled for production during the contract period nor more than the largest quantity contractually scheduled for delivery during any month of the contract period. Inspection lots for components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size convenient to the contractor."

4.3.2.1: Delete in its entirety.

PAGE 10

4.3.2.24: Delete "(see 5.1)" and substitute "(see 5)".

4.3.2.25: Delete "(see 5.1)" and substitute "(see 5)".

4.3.2.26: Delete "(see 5.1)" and substitute "(see 5)".

4.3.2.27: Delete "(see 5.2)" and substitute "(see 5)".

PAGE 12

4.4.1: Delete in its entirety and substitute the following:

"4.4.1 Functioning of gear box assembly under load. The gear box assembly shall be mounted in the applicable test equipment. A mark shall be placed on the center spool assembly to facilitate determination of 360 degree rotation. The free wrench assembly shall be activated back and forth. If the main shaft does not rotate, the knurled handle of the stationary wrench assembly shall be rotated 180 degrees. Activation of the free wrench assembly shall then be continued until the mark on the spool assembly rotates to the starting point. The knurled handle of the free wrench shall be rotated 180 degrees and activation of the wrench attempted. If effected, the stationary wrench is defective. If no action occurs, a 500 pound load shall be applied, the setting of the stationary wrench shall be reversed, the free wrench activated and the spool assembly shall be moved for the required distance".

PAGE 13

Delete paragraphs 5.1.4, 5.2, 5.3 and 5.4 and substitute the following:



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.

"5.1.4 Packaging

5.1.4.1 Level A. The following accessory kit items shall be packaged in accordance with drawing C9209562:

| Quantity | Nomenclature | Part No. |
|---|---|---|
| 1 | Gear Box Assembly | 9799833 |
| 6 | Pin, Cotter | MS-24665-134 |
| 6 | Pin, Cotter | MS-24665-208 |
| 6 | Pin, Cotter | MS-24665-495 |
| 6 | Pin, Cotter | MS-24665-623 |
| 1 | Cable No. 1 w/attachments | 8799706 |
| 1 | Cable No. 2 w/attachments | 8799703 |
| 2 | Bolt Stripper | 8799701 |

5.2 Packing

5.2.1 Level A. Accessory kit shall be packed in accordance with drawing C9209563.

5.2.1.1 The remaining attachments shall be packed in two wooden boxes conforming to specification PPP-B-621, Class 2, Style 2, 2 1/2 or 4 for a type 3 load. Blocking or bracing required shall conform to the box requirements for lumber or MIL-F-26862 for fiberous material. Blocking in the boxes shall conform to that meeting the drop test requirements of the initial production lot. Boxes shall be closed and strapped in accordance with the appendix of the box specification.

5.2.1.1.1 The following items shall be packed in Box No. 1:

| Qunatity | Nomenclature | Drawing No. |
|---|---|---|
| 2 | Extension Bar | 8799635 |
| 1 | Chain Assembly No. 1 | 8799665 |
| 1 | Chain Assembly No. 2 | 8799667 |

5.2.1.1.2 The following items shall be packed in Box No. 2:



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.

| Quantity | Nomenclature | Drawing No. |
|---|---|---|
| 1 | Drag Plate Assembly | 8799639 |
| 1 | Pulley Support Post Assembly | 8799657 |
| 1 | Multiple Sheave Assembly | 8799642 |
| 2 | Clevis Pin Assembly | 8799690 |
| 1 | Spring Assembly | 8799673 |
| 1 | Single Sheave Assembly | 8799651 |
| 1 | Component Parts Package | Various |

5.2 Marking. Items not requiring packaging shall have tags attached showing drawing number or part number and nomenclature. Each unit and shipping container shall be marked in accordance with requirements of MIL-STD-129."

Delete paragraphs 6 through 6.4 and substitute the following:

"6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced inspection Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 Inspection equipment lists. Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (SMUPA Form 1010) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.

6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection equipment list codes. The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the EL by the following codes:

CDAF -Contractor's design responsibility on Army format in accordance with MIL-D-45608.
CDCF -Contractor's design responsibility on contractor format.
AD -Army design.
ADMU -Army design, mandatory for use.
CE -Commercial equipment.
SCD -Specification control drawing.

6.3.3 Army designs. Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs (see 6.3.6) or commercial equipment selections (see 6.3.5) must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawing. Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.

6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings must be described in sufficient detail to permit identification and evaluation by the Government (see 6.3.5). Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment. Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors normally are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. When commercial inspection equipment requires the use of special fixturing, the design of this fixturing shall be considered as part of the total design, and 6.3.6 shall apply. In the latter case, only those portions of the commercial equipment need be detailed in the designs as are necessary to completely fabricate, calibrate, and operate the total item of inspection equipment. Lists and fixturing designs shall be submitted for approval as specified in 6.3.7.

6.3.6 Contractor designs. Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.

electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35mm microfilm process. Contractors shall submit one copy of the final design as a rolled set or flat set. Designs shall be submitted for approval as specified in 6.3.7.

6.3.7 Submission of contractor designs. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commander, USA ARRADCOM, Dover, New Jersey, ATTN: DRDAR-QAR-I. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the Contracting Officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Submission of test data and ammunition data cards. In addition to the normal distribution of records, for loaded items procured by the Department of the Army, one copy of all ballistic test data and ammunition data cards shall be forwarded to the following: Commander, USA ARRADCOM, Dover, New Jersey, ATTN: QAT-M.

"The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment."

Custodian:
Army-AR

Preparing Activity:
Army-AR

Project No: 1375-A213



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:35Z
Check the source to verify that this is the current version before use.