MIL-D-46673A (MU)
1 SEPTEMBER 1964

SUPERSEDING
MIL-D-46673 (ORD)
20 SEPTEMBER 1962

MILITARY SPECIFICATION

DELAY ASSEMBLY, T47
PARTS FOR

1. SCOPE

1.1 This specification covers the parts for one type of delay assembly designated as Delay Assembly, T47.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 — Ammunition and Special Weapons, General Specification for.

MIL-P-10025 — Packaging, Packing and Marking for Interplant Shipment of Inert Ammunition Components: General Specification for.

MIL-I-45208 — Inspection Requirements, General Specification for.

MIL-I-45607 — Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIL-STD-105 — Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105).

MIL-STD-109 — Quality Assurance Terms and Definitions.

MIL-STD-1235 — Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8858663 — Housing, Delay Element.
8858664 — Body, Delay.
8858666 — Ring, Seal.
8858667 — Cup, Relay.

PUBLICATIONS

ORDNANCE CORPS

IEL-8872623 — Index of Inspection Equipment Lists.

(Copies of specifications, standard, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:38Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Material. Materials shall be in accordance with applicable drawings and specifications.

3.2 Parts. The parts shall comply with all requirements specified on drawings (dwgs) 8858663, 8858664, 8858666 and 8858667, as applicable, and with all requirements specified in applicable specifications.

3.3 Workmanship. All parts shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, cuts, tears, unblended radii, surface defects, dirt, grease, rust, corrosion and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. The supplier's responsibilities will be as specified in the contract or purchase order. Reference shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1 *Contractor quality assurance system.* The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL–I–45208. The contractor's quality assurance system shall contain a procedure for the reporting of critical defectives found during the course of his inspection and during inspection by the Government. Any critical defect encountered, unless annotated by an asterisk (*) to the right of the characteristic code number (see 6.2), will be reported within 48 hours. A monthly summary report covering those critical defects annotated by an asterisk will be furnished. The agencies to whom the reports will be furnished are identified in paragraph 6.5. The reports shall contain, as a minimum, the following information:

(a) Contractor and contract number.

(b) Number and revision date of specification.

(c) Characteristic code number.

(d) Lot or serial number.

(e) Number of defectives found.

(f) Assignable cause or analysis of occurrence.

(g) Corrective action taken or recommended. When the corrective action is beyond the control of the contractor or the scope of the contract, the report shall contain the contractor's recommendation to the Government.

4.1.2 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

(b) Number of units of product inspected.

(c) Results obtained for all inspection performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of compliance on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:38Z
Check the source to verify that this is the current version before use.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL–I–45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 **Initial production inspection.** The contractor, prior to initiation of regular production, shall submit an initial production sample consisting of inert parts (see 4.2.1) in the quantities specified herein, which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by required certificates of compliance for all materials (see 4.1.2(e)). An initial production sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply, such as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the contracting officer.

4.2.1 *Inert Parts.*

4.2.1.1 *Submission.* Fifty complete sets of inert parts (i.e., 50 each of every inert component) shall be submitted for inspection to a Government-approved laboratory designated by the contracting officer (see 6.4).

4.2.1.2 *Inspection to be performed.* The components shall be inspected for conformance with any or all of the requirements of this specification and any or all of the requirements of the applicable drawings.

4.2.1.3 *Rejection.* If any inert component fails to comply with any or all of the applicable requirements, the inert parts initial production sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of a component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit an additional sample or portion thereof of inert components for initial production inspection.

4.3 **Inspection provisions.**

4.3.1 *Lot formation.* A lot shall consist of delay assembly parts produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance or fit, as determined by the Gov-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:38Z
Check the source to verify that this is the current version before use.

ernment shall not necessitate changing the lot number.

Lots shall be submitted for inspection in accordance with Standard MIL–STD–105, or Standard MIL–STD–1235 when applicable.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defect shall be in accordance with Standard MIL–STD–105 except that inspection for critical defects when listed shall be 100 percent. Continuous sampling plans in accordance with Standard MIL–STD–1235 for defects other than critical may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be supplied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 *Ring, seal* (see dwg. 8858666).

Categories	*Defects*	*Method of inspection*	*Code No. (see 6.2)*
Critical: None defined			
Major: None defined			
Minor:	AQL 1.00 percent		
201.	Deterioration	Visual	01001
202.	Evidence of poor workmanship (see 3.3)	Visual	01002

4.3.2.2 *Cup, relay* (see dwg. 8858667).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Inside diameter	Gage	02001
102.	Thickness through bottom (min.)	Gage	02002
103.	Crack or split	Visual	02003
Minor:	AQL 1.00 percent		
201.	Total length	Gage	02004
202.	Evidence of poor workmanship (see 3.3)	Visual	02005

4.3.2.3 *Body, delay* (see dwg. 8858664).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined			
Major:	AQL 1.00 percent		
101.	Major diameter of thread	Gage	03001
102.	Pitch diameter of thread	Gage	03002
103.	Outside diameter	Gage	03003
104.	Inside diameter	Gage	03004
105.	Total length (max)	Gage	03005
106.	Depth of cavity	Gage	03006
107.	Crack or split	Visual	03007
Minor:	AQL 4.00 percent		
201.	Concentricity of thread with small outside diameter	Gage	03008
202.	Small outside diameter	Gage	03009
203.	Diameter of flash hole	Gage	03010
204.	Length of thread	Gage	03011
205.	Width of slots	Gage	03012
206.	Thread damaged	Visual	03013
207.	Slot missing	Visual	03014
208.	Improper finish	Visual	03015
209.	Evidence of poor workmanship (see 3.3)	Visual	03016

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:38Z
Check the source to verify that this is the current version before use.

4.3.2.4 *Housing, delay element* (see dwg. 8858663).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 1.50 percent		
101.	Major diameter of small exterior thread	Gage	04001
102.	Pitch diameter of small exterior thread	Gage	04002
103.	Major diameter of large exterior thread	Gage	04003
104.	Pitch diameter of large exterior thread	Gage	04004
105.	Length to (hexagon) flange from small end	Gage	04005
106.	Length to (hexagon) flange from large end	Gage	04006
107.	Diameter between (hexagon) flange and large external thread	Gage	04007
108.	Minor diameter of internal thread, max	Gage	04008
109.	Pitch diameter of internal thread	Gage	04009
110.	Concentricity of inside thread with cavity	Gage	04010
111.	Diameter of large cavity below internal thread	Gage	04011
112.	Depth of cavity below internal thread	Gage	04012
113.	Depth of cavity, small end	Gage	04013
114.	Diameter of cavity, small end	Gage	04014
115.	Diameter of flash hole	Gage	04015
116.	Length of internal thread	Gage	04016
117.	Thread damaged	Visual	04017
Minor:	AQL 2.50 percent		
201.	Diameter of small cavity below internal thread	Gage	04018
202.	Length of large external thread	Gage	04019
203.	Depth of internal thread cavity	Gage	04020
204.	Concentricity of cavity (small end) with cavity (below internal thread)	Gage	04021
205.	Finish improper (small end)	Visual	04022
206.	Protective finish inadequate	Visual	04023
207.	Evidence of poor workmanship (see 3.3)	Visual	04024

4.3.3 *Production testing.* There are no tests applicable to this specification.

4.3.4 *Inspection Equipment.* Index of Inspection Equipment Number IEL–8872623 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement of parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and wherever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4.3.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 *Level C.* The parts for delay assembly, T47, shall be packaged as specified in Specification MIL–P–10025.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:38Z
Check the source to verify that this is the current version before use.

5.2 Packing.

5.2.1 *Level C.* The parts for delay assembly, T47, shall be packed as specified in Specification MIL–P–10025.

5.3 Data cards. Data cards shall be prepared for each lot in accordance with the information specified in Specification MIL–A–2550.

5.4 Marking. Marking shall be as specified in Specification MIL–P–10025.

6. NOTES

6.1 Ordering data. Procurement documents shall specify title, number and date of this specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designed in the IEL by the following codes:

CDAF — Contractor's design responsibility on Army format in accordance with MIL–D–45608.

CDCF — Contractor's design responsibility on contractor format.

AD — Army design.

ADMU — Army design, mandatory for use.

CE — Commercial equipment.

SCD — Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and nonmandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagramatic or pictorial form only and

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:38Z
Check the source to verify that this is the current version before use.

specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL–D–45608, and in addition, contain the detail and information specified above.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Submission of Initial Production, Preproduction or Qualification Samples. Instructions, as to the location for the evaluation of Initial Production, Pre-production, or product qualification shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries should be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–NI.

6.5 Submission of critical defect reports. For U.S. Army Munitions Command procurements, one copy of each critical defect report will be furnished the cognizant Government inspection agency; the Army Ammunition Procurement and Supply Agency, ATTN: SMUAP–RO; Picatinny Arsenal, ATTN: SMUPA–ND.

6.5.1 *Reporting to other services.* For other than U.S. Army Munitions Command procurements, critical defect reporting shall be as prescribed by the contracting officer.

Custodian:
Army—MU
Project No. 1375–A778

Preparing activity:
Army—MU

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:38Z
Check the source to verify that this is the current version before use.