MIL-T-46682A(MU)
26 FEBRUARY 1965
SUPERSEDING
MIL-T-46682 (Ord)
20 JULY 1962

MILITARY SPECIFICATION

THRUSTER, PROPELLANT ACTUATED, XM24 PARTS FOR AND LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers quality assurance provisions, and special requirements not covered by the drawings, for the modification of M28A2 or M29A2 3.5-inch rocket motors for use in and the loading, assembling and packing of one type of cover remover designated as the Thruster, Propellant Actuated, XM24.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIIL-A-2550 — Ammunition and Special Weapons; General Specification for.

MIL-I-45607 — Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIIL-STD-105 — Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105).

MIL-STD-109 — Quality Assurance Terms and Definitions.

MIL-STD-129 — Marking for Shipment and Storage.

MIIL-STD-171 — Finishing of Metal and Wood Surfaces.

MIL-STD-1167 — Ammunition Data Cards.

MIL-STD-1235 — Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8830801 — Thruster, Propellant Actuated, XM24.

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

PUBLICATIONS

ORDNANCE CORPS

IEL-8830801 — Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 **Other publications.** The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

CODE OF FEDERAL REGULATIONS

49 CFR 71-90 — Interstate Commerce Commission Rules and Regulations for the Transportation of Explosives and Other Dangerous Articles.

(The Interstate Commerce Commission Regulations are now a part of the Code of Federal Regulations (1949 Edition and revisions) available from the Superintendent of Documents, Government Printig Office, Washington 25, D.C. Orders for the above publication should cite "49 CFR 71-90 (latest revision)".

3. REQUIREMENTS

3.1 **Material.** Materials shall be in accordance with applicable drawings and specifications.

3.2 **Assemblies.** The assemblies shall comply with all requirements specified on Drawing (dwg.) 8830801 and with all requirements specified in applicable specifications.

3.3 **Embrittlement of plunger spring.** The plunger spring shall not fracture when being pulled to the point of minimum permanent deformation.

3.3.1 Plunger spring load at compressed length shall conform to 3.9 plus .4 pounds. (see dwg. 8827671).

3.4 **Leakage in plunger assembly.** The assembly shall withstand an 80 pound, minimum, air pressure applied through the igniter cavity without evidence of leakage around the O ring.

3.5 **Electrical continuity of plug assembly.** The electrical resistance of the plug assembly, indicative of acceptable continuity, shall be not more than 0.5 ohm when measured between the post terminals, with the lead wires shorted.

3.6 **Electrical resistance of igniter circuit.** The resistance of the igniter circuit in the complete assembly shall be not less than 0.75 ohm nor more than 1.75 ohms when a current limited to 10 milliamperes is applied between the post terminals of the plug assembly.

3.7 **Functioning.** The thruster, when a potential of 12 volts direct current, maximum, is applied between the leads, shall function and shift the cover of a launching skid, M3, far enough to clear the center compartment.

3.8 **Workmanship.** All parts and subassemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Surface coatings shall be continuous except for a few slight scratchts not exposing base material. All required marking shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 **General quality assurance provisions.** Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1 **Submission of product.** At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions specified within this specification.

b. Number of units of product inspected.

c. Results obtained, by defect code, for all inspection performed.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Statement of findings on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agen's authority will not be required with subsequent certificate unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 **Government verification.** Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL–I–45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 **Initial production inspection.**

4.2.1 Prior to the start of regular production, the contractor shall submit an initial production sample to a Government approved facility as designated by the Contracting officer (see 6.4) for evaluation in accordance with the provisions of 4.2.2. The initial production sample shall consist of 5 complete assemblies and 10 complete sets of parts (i.e. 10 each of every individual component and every subassembly, except modified rocket motors) which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by statement of findings for materials. An initial production sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 **Inspections to be performed.** Assemblies and components will be subjected by the Government to any or all of the examinations or tests specified in 4.3.2 and 4.3.3.1 of this specification and any or all requirements of the applicable drawings.

4.2.3 *Rejection.* If any assembly or components fails to comply with any of the applicable requirements, the initial production sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample, or portion thereof. Until an initial production sample is accepted, the contractor is in no way authorized by the Government to initiate regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions.

4.3.1 *Lot formation.* A lot shall consist of thruster assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification revision. Drawing, specification, and process changes not affecting safety, performance or fit, as determined by the Government shall not necessitate changing the lot interfix number. Each lot shall contain motors from Rocket, HE, AT, 3.5 inch, M28A2, Practice or M29A2 from not more than one lot.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105 (ABC-STD-105) except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspection listed shall be in accordance with 4.3.4.

4.3.2.1 Spring, plunger (see dwg. 8827671 covering a detail of dwg. 8847420).

Categories		*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined			
Major:		AQL 1.0 percent		
	101.	Inside diameter of spring (min.)	Gage	01001
	102.	Outside diameter of spring (max.)	Gage	01002
	103.	Solid length (max.)	Gage	01003
	104.	Load at compressed height (see 4.4.2)	Test	01004
	105.	Ends squared and ground	Visual	01005
Minor:		AQL 0 65 percent		
	201.	Evidence of poor workmanship (see 3.8)	Visual	01006

4.3.2.2 Closure, motor (see dwg. 8827669 covering a detail of dwg. 8847420).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of inspection	Code No.
Major:	AQL 1.00 percent		
101.	Pitch diameter of buttress thread	Gage	02001
102.	Major diameter of buttress thread	Gage	02002
103.	Diameter of corner hole, minimum (min.)	Gage	02003
104.	Width of slot across corner hole, min.	Gage	02004
105.	Contour and location of both guide slots	Gage	02005
106.	Diameter of igniter cavity, min.	Gage	02006
107.	Depth of igniter cavity, min.	Gage	02007
108.	Gas passage hole missing	Visual	02008
109.	Plunger cavity surface finish improper	Visual	02009
110.	Operation missing	Visual	02010
111.	Protective finish improper or missing	Visual	02011
Minor:	AQL 1.50 percent		
201.	Location of slot across corner hole	Gage	02012
202.	Firing instruction not legible	Visual	02013
203.	Evidence of poor workmanship (see 3.8)	Visual	02014

4.3.2.3 Thruster plunger assembly (see dwg. 8847420 covering a detail of dwg. 8830801).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Plunger action not free	Manual	03001
102.	Component missing	Visual	03002
103.	Gas passage hole obstructed	Visual	03003
Minor:	AQL 1.0 percent		
201.	Silicone grease missing or inadequate	Visual	03004
202.	Evidence of poor workmanship (see 3.8)	Visual	03005

4.3.2.4 Plug assembly (see dwg. 8827673 covering a detail of dwg. 8830801.

Categories	Defects	Method of inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Improper tapped hole	Gage	04001
102.	Width of plug head	Gage	04002
103.	Potting compund insufficient, improper or improperly applied	Visual	04003
104.	Spacer missing or improper	Visual	04004
Minor:	AQL 1.50 percent		
201.	Length of lead	Gage	04005
202.	Lead wires improperly assembled or separately excessively	Visual	04006
203.	Evidence of poor workmaship (see 3.8)	Visual	04007

4.3.2.5 Holder, forward thruster (see dwg. 8827672 covering a detail of dwg. 8830801).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined		
Major:	AQL 1.0 percent		
101.	Location of hole	Gage	05001
102.	Inside diameter, min.	Gage	05002
103.	Width across guides, maximum (max.)	Gage	05003
104.	Thickness of either guide, max.	Gage	05004
105.	Width of guide, min.	Gage	05005
106.	Location of both guides to center hole	Gage	05006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of inspection	Code No.
Minor:	AQL 1.50 percent		
201.	Pitch diameter of thread, min.	Gage	05007
202.	Protective finish missing or inadequate	Visual	05008
203.	Evidence of poor workmanship (see 3.8)	Visual	05009

4.3.2.6 Assembly, prior to assembly of the plunger assembly and forward holder (see dwg. 8830801).

Categories	Defects	Method of inspection	Code No.
Critical:			
1.	Igniter cracked or damaged	Visual	06001
Major:	AQL 0 65 percent		
101.	Thread sealant missing (either thread)	Visual	06002
102.	End of propellant grain cracked	Visual	06003
103.	Igniter lead wires not as specified	Visual	06004
104.	Nozzle closure not sealed	Visual	06005
Minor:	AQL 0.65 percent		
201	Evidence of poor workmanship (see 3.8)	Visual	06006

4.3.2.7 Assembly (see dwg. 8830801).

Categories	Defects	Method of inspection	Code No.
Critical:			
1.	Cotter pin not inserted and not spread	Visual	07001
Major:	AQL 1.0 percent		
101.	Thruster holder guide improperly assembled or not parallel with plunger assembly groove	Gage	07002
102.	360 degrees space between plug and plunger assembly	Gage	07003
103.	Location of tape on body from plunger assembly	Gage	07004
104.	Igniter leads improperly secured or insufficient slack	Visual	07005
105.	Nozzle closure disturbed or not resealed	Visual	07006
106.	Component missing or improperly assembled	Visual	07007
107.	Plunger movement restricted	Manual-Visual	07008
Minor:	AQL 1.50 percent		
201	Threads not properly coated	Visual	07009
202.	Marking: omitted, improper or illegible	Visual	07010
203.	Evidence of poor workmanship (see 3.8)	Visual	07011

4.3.3 *Testing.*

4.3.3.1 Initial production sample (see 4.2.1). The samples submitted as the initial production quantity shall be tested as specified below after having been examined for all other drawing requirements. Rejection and resubmission shall be in accordance with 4.2.3.

4.3.3.1.1 Spring embrittlement (see 3.3 and 4.4.1) Code No. 01005.

4.3.3.1.1.1 Spring load at compressed length (see 3.3.1 and 4.4.2) Code No. 01004.

4.3.3.1.2 Leakage of plunger assembly (see 3.4 and 4.4.3) Code No. 03007.

4.3.3.1.3 Electrical continuity of plug assembly (see 3.5 and 4.4.4) Code No. 04006.

4.3.3.1.4 Electrical resistance of igniter circuit (see 3.6 and 4.4.5) Code No. 07012.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

4.3.3.1.5 Functioning (see 3.7, 4.3.3.2.5 and 4.4.6) Code No. 08001 (see 6.4).

4.3.3.1.6 Cotter pin withdrawal (see dwg. 8830801 and 4.4.7) Code No. 07013.

4.3.3.2 *Production testing.*

4.3.3.2.1 Spring embrittlement (see 3.3) — major defect — Code No. 01005. A sample of 5 springs shall be selected from each embrittlement relief batch for this test. Testing shall be as specified in 4.4.1. Failure of one or more units of the sample in meeting the requirement shall reject the batch.

4.3.3.2.2 Leakage in plunger assembly (see 3.4) — major defect — Code No. 03007. This test shall be performed 100 percent as specified in 4.4.3 using the applicable equipment of 4.3.4. Any assembly exhibiting leakage shall be classed defective and removed from the lot.

4.3.3.2.3 Electrical continuity of plug assembly (see 3.5) — major defect — Code No. 04006. This test shall be performed 100 percent using the applicable equipment of 4.3.4 as specified in 4.4.4. Any assembly failing to meet the requirement shall be classed defective and removed from the lot.

4.3.3.2.4 Electrical resistance of igniter circuit (see 3.6) — major defect — Code No. 07012. This test shall be performed 100 percent using the applicable test equipment of 4.3.4. Any unit exhibiting a resistance outside the permitted range shall be classed defective and removed from the lot. Testing shall be as specified in 4.4.5.

4.3.3.2.5 Function (see 3.7) — major defect — Code No. 08001. A sample of 3 thruster assemblies shall be selected from each lot for this test. Testing shall be as specified in 4.4.6. Failure of one or more units in meeting the requirement shall reject the lot (see 6.4).

4.3.3.2.6 Plunger spring load (see 3.3.1) — major defect — Code No. 01004. A sample of 5 springs shall be selected from each embrittlement relief batch for this test. Testing shall be as specified in 4.4.2. Failure of one or more units of the sample in meeting the requirements shall reject the batch.

4.3.3.2.7 Cotter pin withdrawal (see dwg. 8830801 and 4.4.7) — major defect — Code No. 07013. Testing shall be as specified in 4.4.7. Test equipment shall be in accordance with 4.3.4. The sampling plan for this test shall be in accordance with Standard MIL-STD-105 using table II-A, Code letter D and an AQL of 1.5 percent.

4.3.4 *Inspection equipment.* Index of Inspection Equipment Number IEL-8830801 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL-I-45607.

4.3.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of it's accuracy,

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test methods and procedures.

4.4.1 *Spring embrittlement.* The last coil at each end of the spring shall be grasped by a suitable tool and sufficient pull applied at each end to extend the spring to the point where initial permanent deformation occurs. Any spring fracturing prior to that point shall be classed defective. Springs so tested shall not be returned to the batch.

4.4.2 *Spring load at compressed height.* The spring shall be assembled into the applicable equipment of 4.3.4 and just enough force applied to effect complete compression of all coils. The required force shall be observed and recorded. Any spring failing to meet the requirement shall be classed defective.

4.4.3 *Leakage in plunger assembly.* The assembly shall be connected to the applicable equipment and shall be submerged in water to a depth of 2 inches, minimum. The required air pressure shall be applied and the plunger fully depressed several times. Observation shall be made for the escape of air around the O ring on the plunger. Any assembly exhibiting leakage shall be classed defective. After completion of the test, the plunger and spring shall be disassembled and all parts shall be thoroughly dried using a dry air stream and shall then be reassembled.

4.4.4 *Electrical continuity of plug assembly.* The assembly leads shall be shorted and the resistance between the post terminals observed. Any assembly exhibiting excessive resistance shall be classed defective.

4.4.5 *Electrical resistance of igniter circuit.* The thruster assembly shall be positioned vertically with the nozzle up and shall be connected to the specified equipment at the required terminals and the resistance of the circuit observed. Any assembly exhibiting a resistance not in compliance with the requirement shall be classed defective. Immediately after test, the plug assembly shall be secured in the motor plunger assembly.

Note: This determination may be hazardous and should be performed behind a suitable barricade.

4.4.6 *Functioning.* The cover of the launching skid shall be fully engaged in the skid and the thruster assembly mounted on the guide. Observation shall be made for engagement of the plunger of the thruster assembly with the skid. The skid shall be anchored by two lines diverging from the forward eyebolt. The leads of the thruster shall be assembled to the power source and the unit functioned. Failure of the cover to clear the center compartment shall class the unit defective.

4.4.7 *Cotter pin withdrawal.* A pull force shall be applied to the cotter pin in the direction of withdrawal from the thruster plunger assembly to determine compliance with the applicable requirement.

5. PREPARATION FOR DELIVERY

5.1 Packing.

5.1.1 *Level C.* The assemblies shall be packed in accordance with paragraph 73.90 of Code of Federal Regulations (see 2.2).

5.2.1 *Marking.* Marking shall be in accordance with 2.2 and Standard MIL-STD-129.

5.2 Shipping. When component parts from more than one lot are shipped as a carload, each lot shall be kept separate and the division between lots clearly indicated.

5.2. Data cards. Data cards shall be prepared for each lot in accordance with information specified in Specification MIL-STD-1167.

6.NOTES

6.1 Ordering data. Procurement docu-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

ments shall specify title, number and date of this specification.

6.2 **Inspection code numbers.** The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 **Inspection equipment.** The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designed in the IEL by the following codes:

CDAF — Contractor's design responsibility on Army format in accordance with MIL–D–45608.

CDCF — Contractor's design responsibility on contractor format.

AD — Army design.

ADMU — Army designs, mandatory for use.

CE — Commercial equipment.

SCD — Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classification, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.

equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administrating the contract.

6.3.6 *Contractor design.* Contractor design are design of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawing which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL–D–45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be nonreproducible diazo or electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35MM microfilm process. The contractor shall submit one rolled or flat set copy of the final approved design.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Submission of Initial Production Sample. Instructions, as to the location for the evaluation of initial production sample, shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries should be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–NI.

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1375–A847

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:40Z
Check the source to verify that this is the current version before use.