NOT MEASUREMENT SENSITIVE

MIL-M-80209B
INTERIM AMENDMENT 1(USAF)
6 SEPTEMBER 1989

MILITARY SPECIFICATION

MILLING MACHINE, VERTICAL KNEE TYPE, 3 AXIS, NUMERICALLY CONTROLLED, 1.5 TO 7.5 HORSEPOWER SPINDLE DRIVE

This interim amendment is approved for use within the Air Force, with MIL-M-80209B dated 20 September 1985.

PAGE 5

Paragraph 3.2, line 8, add the following:

"Modifications to manufacturer's standard designs to achieve requirements specified herein are not permissible, if they result in deviations from good design practice. An example of such impermissible modifications is placing a 20 hp motor in a power train designed and normally used for 10 hp."

PAGE 8

Paragraph 3.4.3, delete the first sentence and substitute the following:

"All way surfaces shall be finished by either scraping or grinding, and shall be lined with Turcite."

Paragraph 3.4.4, line 9, add the following:

"The X and Y axes ballscrew shall be a minimum of 1.25 inches in diameter."

Paragraph 3.4.5, line 7, add the following:

"The Z axis ballscrew shall be a minimum of 1.5 inches in diameter."

PAGE 14

Paragraph 3.4.11.5.1, delete the first sentence and substitute the following:

"A high resolution 9 inch cathode ray tube (CRT) capable of displaying at least 250 characters simultaneously, shall be provided."

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:46Z
Check the source to verify that this is the current version before use.

PAGE 18

Paragraph 3.8, delete the entire paragraph and substitute the following:

"3.8 Standard equipment. The contractor shall furnish all equipment normally considered by him to be standard for his machines, whether specifically called for in this military specification or not. The equipment specified (see 6.2.1) shall be furnished, in addition to equipment specified in other sections, which may or may not be standard. The inclusion of standard equipment in this paragraph which is also specified in other sections of this military specification is inadvertent and should not be construed to allow duplication."

PAGE 20

Paragraph 3.14, change to read "3.17" and add the following as paragraph 3.14, 3.15, and 3.16.

"3.14 Installation. The contractor shall be responsible for all rigging, site preparation and machine installation with the exception that the Government shall provide utilities to within ten feet of the location for installation. The cost of this service shall be included in the contract. All tooling equipment, materials, oils, lubricants, etc., required shall be contractor provided. The contractor shall inform the carrier that the machine shall only be unloaded under the supervision of the contractor and a government representative from the procuring activity."

"3.15 Training. The contractor shall provide a training program to acquaint the customers personnel with the machine and control system. The cost of all training less travel and expenses of government personnel shall be included in the contract and be contractor provided."

a. Complete electrical and electronic maintenance training for two technicians.

b. Complete mechanical maintenance training for two technicians.

c. Complete programming and operational training for four technicians.

The training shall be scheduled and conducted to coincide, as near as possible, with completion of the machine installation."

"3.16 Templates. Unless otherwise specified (see 6.2.1), the contractor shall supply two templates made to match precisely the dimensions, contours, location of access panels, limits of travel of moving members, and identity of the individual equipment it represents. The templates shall be two dimensional and be made to a scale of 1/4 inch to equal one foot. The templates shall be made of matte translucent Mylar, and have a mark receptive surface. The templates shall be imprinted with appropriate nomenclature, and mounted on Mylar storage sheets. Nomenclature shall include equipment name, the manufacturer's name, the model number and the horsepower rating. Ninety days prior to delivery of the equipment, the templates shall be submitted to the requesting activity."

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:46Z
Check the source to verify that this is the current version before use.

Paragraph 4.2, add subparagraph c as follows:

"c. Inspection and acceptance (see 4.5)."

Paragraph 4.3, line four change 4.5 and 4.6 to read "4.6" and "4.7".

PAGE 21

Paragraph 4.4, line four change 4.5 to read "4.6", line five change 4.6.2 to read "4.7".

Add new paragraph 4.5 as follows:

"4.5 Inspection and acceptance. Final inspection and acceptance shall be at the installation site by authorized representatives from the requesting activity. The acceptance test shall be performed on the machine to ensure conformance with the specification. Unless otherwise specified (see 6.2.1), the acceptance test shall be performed only after the machine is installed at its final location. The acceptance test shall consist of the examination in 4.6 and all tests in 4.7. The machine shall pass the examination and all test to be accepted."

Paragraph 4.5, change 4.5 to read 4.6 and align all other paragraphs accordingly.

PAGE 25

Paragraph 6.2.1, change subparagraph mm. to read "nn." and add new subparagraph "mm." to read as follows:

"mm. Templates, if different (see 3.16)."

Change subparagraph nn. to read "oo.", and add new subparagraph "pp." to read as follows:

"pp. Inspection and acceptance, if different (see 4.5)."

Change subparagraph oo. to read "qq."

Review Activity:
Air Force - 84

Preparing Activity:
Air Force - 82

Agent Activity:
Air Force - 99

(Project No. 3417-F184)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:46Z
Check the source to verify that this is the current version before use.