INCH-POUND

MIL-C-52298D
26 July 1991
SUPERSEDING
MIL-C-52298C
13 October 1983

MILITARY SPECIFICATION

COLUMN ASSEMBLY: TRESTLE

This specification is approved for use within the USA Belvoir Research Development and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a column assembly to be used with a trestle assembly (MIL-T-52150).

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:14Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-T-704	-	Treatment and Painting of Materiel.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-889	-	Dissimilar Metals.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Government drawings. The following Government drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13207E9712	-	Column Assembly.

(Copies of drawings, publications, and other Government documents required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-JB, Fort Belvoir, VA 22060-5606.)

2.2 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The column assembly shall be as shown on Top Assembly TA13207E9712 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the column assembly. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

3.2 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Material. Material shall be as specified herein and on the drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Material shall be new and unused.

3.3.1 Material deterioration prevention and control. The column assembly shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environment to which the item may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals, as defined in MIL-STD-889, shall be electrically insulated from one another to minimize or prevent galvanic corrosion.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.4 Identification marking. The column assembly shall be metal die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.5 Treatment and painting. The inside and outside surfaces of the column assembly shall be cleaned, treated, and painted in accordance with MIL-T-704, type B. The contact surfaces of all dissimilar metals shall be painted prior to assembly.

3.6 Stenciling. The nomenclature, National Stock Number, weight, and cube shall be stenciled on each column assembly. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. Markings shall be Gothic-type capitals and Arabic numerals 3/4-inch high. Stenciling shall conform to MIL-T-704.

3.7 Workmanship. All burrs, rough edges, and edges of holes shall be ground smooth.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:14Z
Check the source to verify that this is the current version before use.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications, standards, and drawings as applicable.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Quality Assurance Provisions (QAP) shown on the drawings. The drawings specify the characteristic's requiring inspection, the sampling plan, and the basis for acceptance and rejection (see 6.4 and 6.5).

4.2 Classification of inspections. Inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article column assembly shall be examined for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.4.2 Examination. Samples selected in accordance with 4.4.1 shall be examined for the major and minor defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The column assembly shall be examined as specified herein for the following defects:

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:14Z
Check the source to verify that this is the current version before use.

Major

101. Components missing or not as specified (see 3.1).
102. Any part or component not in accordance with the QAP requirements as shown on the drawings (see 3.1.1).
103. Materials not as specified (see 3.3).
104. Castings containing blowholes, porosity, hard spots, shrinkage defects, cracks, or not smooth and well cleaned. (Minor imperfections not affecting strength may be corrected by welding (see 3.3).
105. Materials are not resistant to corrosion and deterioration or treated to be resistant to corrosion and deterioration for the applicable storage and operating environment (see 3.3.1).
106. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.1.1).
107. Contractor does not have documentation available for identification of material, material finishes or treatments (see 3.3.1.2).
108. Workmanship not as specified (see 3.7).

Minor

201. Dimensions other than those identified by QAP data not as specified (see 3.1.1).
202. Identification marking incorrect, missing, or illegible (see 3.4).
203. Treatment and painting not as specified (see 3.5).
204. Stenciling not as specified (see 3.6).

4.6 Inspection of packaging. Examine the marking to determine compliance with MIL-STD-129. Any marking that is missing, illegible, incorrect, or incomplete shall be cause for rejection.

5. PACKAGING

5.1 Packing (see 6.6). The column assemblies shall be shipped loose (unboxed).

5.2 Marking (see 6.6). In addition to any special marking specified in the contract (see 6.2), the column assemblies shall be marked in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The column assembly is intended for use in floating and fixed bridges as a support for the transom of a trestle assembly. This item is a component of the following Supply Catalogs (SC) SC 5420-97-CL-E03, E35, E36 and E46.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1).
c. When a first article is required for inspection and approval and the number of units required (see 3.2).
d. Any special marking (see 5.2).

6.3 First article. When a first article inspection is required the item shall be examined and should be a first produced column assembly. The contracting officer should include specific instructions in the acquisition documents regarding arrangements for examinations and approval of the documents first article.

6.4 Quality assurance provisions (QAP). The contracting officer should require the contractor to maintain records of all QAP inspections. A suggested paragraph is as follows:

> "The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include, as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, and corrective action taken when applicable".

6.5 Definitions.

6.5.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP's indicate the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.6 Levels of preservation and packing. Levels of preservation and packing have not been included as the protection specified is acceptable for any level of protection. For the purposes of preservation/packing level marking, the marking shall be A/A.

6.7 Changes from previous issue. Marginal notations are not used in this revision to identify changes which respect to the previous issue due to the extensiveness of the changes.

6.8 Subject term (key word) listings.

Bridge
Column Assembly
Trestle

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:14Z
Check the source to verify that this is the current version before use.

Custodian:
Army - ME

Review activities:
Navy - MC
DLA - CS

Preparing activity:
Army - ME

Project 5420-0180

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-C-52298D	910726

3. DOCUMENT TITLE
Column Assembly: Trestle

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	c. DATE SUBMITTED (YYMMDD)
	(1) Commercial (2) AUTOVON (If applicable)	

7. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
	(703) 664-5717	354-5717

c. ADDRESS (Include Zip Code)	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT:
US Army Belvoir RDE Center ATTN: STRBE-TSE Ft. Belvoir, VA 22060-5606	Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.