MILITARY SPECIFICATION

GENERATOR SET, DIESEL ENGINE, TRAILER MOUNTED

5KW, 60 HERTZ, PU-751/M

This amendment forms a part of Military Specification MIL-G-52902A(ME), dated 17 February 1982, and is approved for use by the USA Belvoir Research and Development Center, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 2

2.1, under SPECIFICATIONS, FEDERAL, delete:

"PPP-P-40 - Packaging and Packing of Hand Tools."

2.1, under SPECIFICATIONS, MILITARY, delete:

"MIL-P-116 - Preservation Packaging, Methods of."

and substitute:

"MIL-P-116 - Preservation, Methods of."

2.1, under STANDARDS, MILITARY, delete:

"MIL-STD-1188 - Commercial Packaging of Supplies and Equipment."

and add:

"MIL-STD-889 - Dissimilar Metals."

Under 2.1.2, add the following:

"US DEPARTMENT OF COMMERCE

Product Standard PS-1 - Softwood Plywood; Construction and Industrial.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)"

AMSC N/A FSC 6115
DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

After 2.1.2, add the following:

"2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted shall be those listed in the issue of the DoDISS specified in the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS shall be the issue of the nongovernment documents which is current on the date of the solicitation.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI/HPMA-HP 1983 American National Standard for Hardwood and Decorative Plywood.

(Application for copies should be addressed to American National Standards Institute, 1430 Broadway, New York, NY 10018.)

(Nongovernment standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)"

Change 2.1.3 to 2.3:

"2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, (except for associated detail specifications, specifications sheets or MS standards), the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained."

PAGE 3

3.2, delete in its entirety and substitute:

"3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 4.3 and 6.3). Any changes or deviations of generators from the approved first article during production will be subject to the approval of the contracting officer. Approval of the first article will not relieve the contractor of his obligation to furnish generators conforming to this specification."

3.3, delete in its entirety and substitute:

"3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions in 3.3.1, 3.3.2, 3.3.3, and 3.3.4 of this specification."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

"3.3.1 Material deterioration and control. The item(s) shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operation and storage environment to which the item may be exposed.

3.3.2 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.3 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.3.4 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the generator sets may be newly fabricated from recovered materials to the maximum extent practicable, provided the generator sets produced meet all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the generator sets."

3.4, under "Item No. 1, Description and Identification":
change to read: "M116A1 MIL-C-45150
M116A2 NSN 2330-01-101-8434"

3.5, after last sentence add: "External surfaces shall be free from burrs, sharp edges and corners except when sharp edges and corners are specified on the applicable drawings."

Add:

"3.6 Safety. All changes, deviations, and waivers to TA13221E7323 shall be in accordance with the following requirements. All rotating or reciprocating parts and other parts subject to high operational temperatures that are of such a nature or are so located as to be a hazard to operating personnel, shall be guarded or insulated to the extent necessary to eliminate the hazard. Electrical equipment shall be effectively guarded and grounded to protect all persons and objects from electrical shock hazard."

4.1, line 6, after "perform" add "or repeat".

4.1.1, line 1 and 3, delete "preproduction" and substitute "first article".

4.2, line 3, delete "preproduction" and substitute "first article (see 4.3)".

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:39Z
Check the source to verify that this is the current version before use.

4.3, line 1, delete "Preproduction inspection" and substitute "First article inspection".

4.3.1, line 1, delete "preproduction" and substitute "first article".

PAGE 5

4.5.1, under defects, delete "101 through 106" in their entirety and substitute:

"101. Material not as specified.
102. Materials are not resistant to corrosion or deterioration or treated to be made resistant to corrosion or deterioration for the applicable storage and operating environment.
103. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other.
104. Contractor does not have documentation available for identification of material, material finishes or treatments.
105. Used, rebuilt, or remanufactured components, pieces or parts incorporated in the generator sets.
106. Treatment and painting not as specified.
107. Dimensions not as shown on drawings.
108. Components missing or not as specified.
109. Assembly not as shown on the drawings.
110. Workmanship not as specified.
111. Safety not as specified."

4.6.1, line 1, delete "preproduction" and substitute "first article".

Add "Any defect(s) shall be corrected and the first article re-examined."

4.6.2.3, under defects delete "107 thru 119" in their entirety and substitute:

"112. Generator sets not preserved as specified for levels A and B.
113. Fire extinguisher not removed from bracket and preserved as specified for levels A and B.
114. Power and ground cable not disconnected and secured as specified for levels A and B. Cable and terminals not matchmarked as specified.
115. Bows not secured together as specified.
116 Hammer, fuel can adapters, oil drain line and ground rods not secured as specified.
117. Technical publications not preserved as specified for all levels.
118. Tarpaulin not preserved as specified.
119. Trailer chassis components not preserved as specified for levels A and B.
120. Packing not as specified by the applicable figures for levels A and B.
121. Tarpaulin roof supports not secured to unit as specified for levels A and B.
122. Marking illegible, incomplete, incorrect, or missing.
123. Depreservation guides not prepared and attached to the power unit as specified."

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:39Z
Check the source to verify that this is the currenversion before use.

5. PACKAGING, "5.1, 5.2, 5.2.1, 5.2.1.1, 5.2.1.2, 5.2.1.3, 5.2.1.4," delete in their entirety and substitute the following:

"5. PACKAGING

5.1 First article pack. The contractor shall furnish a first article pack for examination within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied preservation, packing, and marking comply with the packaging requirements of this specification. Examination shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.5). The first article pack may be accomplished utilizing either the first article power unit or a production power unit. If the first article power unit is utilized, any preservation, and packing shall be removed by the contractor at no expense to the Government, when requested by the Government to facilitate comparison between the first article power unit and production power unit.

5.2 Preservation. Preservation shall be level A, B, or C, as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Generator sets. The generator set shall be preserved in accordance with MIL-P-116, method IIa. The generator set shall be secured directly through the barrier material to the trailer chassis, using the required mounting bolts. Before positioning the barrier material over the generator, the generator shall be covered with a half slotted container constructed in accordance with PPP-B-636, without cover, type CF, class-domestic, variety SW, grade-200 minimum. The container shall be sealed in accordance with method I of the appendix thereto. All sharp edges of the container that can damage the barrier material shall be covered with non abrasive pressure sensitive tape. The top corners of the container shall be rounded to prevent them from puncturing the barrier material. Additionally, the bottom corners and the bottom portion of the forward and aft panels shall be trimmed to receive the wood wedges. The barrier shall be protected by a box-type cover consisting of ends, sides, and top constructed in accordance with PPP-B-601, for an overseas type, style I box. Sides and ends shall be 1/4-inch-thick plywood. The top shall be one piece 1/2-inch-thick plywood and shall completely cover all edges. The humidity indicator and inspection port shall be installed on an end or side in a location convenient for inspection of the humidity indicator. The cover shall be secured using wood wedges and lag screws. The wedges shall be cut to fit the angle of the ends of the generator skids and shall be of sufficient length and width to provide a snug fit to the inside of the cover. The angle surface of the wedge shall be cushioned with fiberboard where contact with the barrier is required. Lag screws shall be the minimum length required to secure the cover to prevent puncture of the barrier. Before enclosing the generator set in the method IIa barrier, the following preservation shall be accomplished.

5.2.1.1.1 Engine. The engine and engine accessories shall be preserved in accordance with MIL-E-10062, level A, type II, method II. Drivebelts shall be relieved from tension and tagged and battery cables shall be disconnected and secured as specified herein."

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:39Z
Check the source to verify that this is the currentversion before use.

"5.2.1.2 Fire extinguisher. The fire extinguisher shall be removed from the bracket and preserved in a box conforming to PPP-B-636, type CF, class domestic, variety SW, grade 125, style optional and shall be secured to the generator set with tape conforming to PPP-T-97, type IV.

5.2.1.3 Cable. The ground cable shall be disconnected and the terminals on the generator set and cable ends shall be matchmarked with tags conforming to UU-T-81, type A. The cable shall be coiled, the coil secured. The coiled cable shall be secured to the generator set with tape conforming to PPP-T-97, type IV.

5.2.1.4 Hammer, fuel can adapters, oil drain line, and ground rods. The hammer, fuel can adapters, oil drain line, and ground rods shall be secured in the accessory box with tape conforming to PPP-T-97, type IV."

PAGE 7

Delete page 7 in its entirety and substitute the following:

"5.2.1.5.2 Bows. The bows shall be removed from the trailer pockets and secured together with strapping at six equally spaced positions. Wood blocking shall be used under the strapping to prevent damage to the bows. Strapping shall conform to QQ-S-781, class 1, type I or IV, size .020 x 3/4. Unless otherwise specified (see 6.2), strapping shall be finish B. When specified (see 6.2), strapping shall be finish A.

5.2.1.5.2.1 Tarpaulin roof support. The tarpaulin roof support shall be removed and secured in any available space within the confines of the trailer.

5.2.1.5.3 Tarpaulin. The tarpaulin shall be wrapped in film conforming to L-P-378, type I, class I, grade A, 4 to 8 mil and shall be preserved in a close-fitting box conforming to PPP-B-601, overseas type, style I. Strapping shall not be required.

5.2.1.6 Technical publications. Technical publications shall be preserved in accordance with MIL-P-116, method IC-I and shall be secured to the generator set outside the method II barrier.

5.2.2 Level B. The generator set shall be preserved as specified for level A except for the following.

5.2.2.1 Box-type cover. The box-type cover specified in 5.2.1.1 shall be domestic type.

5.2.2.2 Engine. The engine and engine accessories shall be preserved in accordance with MIL-E-10062, level A, type II, method I.

5.2.2.3 Strapping. The strapping specified in 5.2.1.2.2 shall be finish A.

5.2.2.4 Tarpaulin. The box specified in 5.2.1.2.3 shall be domestic type.

5.2.2.5 Trailer chassis. The trailer chassis components shall be preserved in accordance with MIL-STD-281, level B, as specified for mobile units.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

5.2.3 Level C. Power units including all components and surfaces requiring it, shall be preserved to provide protection against deterioration and damage during shipment and handling from the contractor to the initial destination. Cables, fuel, and oil drain lines shall not be disconnected. Technical publications shall be placed in a waterproof bag and secured to the generator set.

5.3 Packing. Packing shall be level A, B, or C as specified (see 6.2).

5.3.1 Level A. The bows shall be placed and secured on the power unit with the solid area of the bows facing the front panel of the trailer. The tarpaulin box shall be secured to the forward end of the generator box cover with two horizontal metal straps, each encompassing both boxes. Blocking shall be provided to support and aid in securing the bows in position and to prevent the tarpaulin box from raising up. Strapping for securing the bows and tarpaulin shall conform to QQ-S-781, class I, type I or IV, size .020 x 3/4. Unless otherwise specified (see 6.2), strapping shall be finish B.

PAGE 8

5.3.2, delete in its entirety and substitute the following:

"5.3.2 Level B. Packing shall be as specified for level A, except that strapping specified in 5.3.1 securing the bows, tarpaulin, and parts shall be finish A."

Add:

"5.3.3 Level C. Power units shall be completely mobile. Any components not placed in secure brackets shall be removed from them and placed in an out of the way area and secured to prevent movement. The tarpaulin cover shall be in place upon its bows."

5.4, 5.4.1, and 5.4.2, delete in their entirety and substitute:

"5.4 Marking. Marking shall be in accordance with MIL-STD-129."

6.2, (c) and (d), delete "preproduction" and substitute "first article".

6.2, (e), delete in its entirety and substitute:

"(e) Level of preservation and of packing required (see 5.2 and 5.3)."

6.3, delete in its entirety and substitute the following:

"6.3 First article. When a first article inspection is required, the items should be a preproduction model. The first article should consist of 1 or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, tests, and approval of the first article test results and disposition of the document's first article."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

6.5, line 1, title, line 2 and 3, delete "preproduction" and substitute "first article".

PAGE 9

Delete 6.8 Recycled material.

PAGES 10, 11, and 12

Delete in their entirety figures X-3742B, X-3743B, and X-3771.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 6115-A506

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:39Z
Check the source to verify that this is the current version before use.