MIL-W-52312A(ME)
7 January 1975
SUPERSEDING
MIL-W-52312(MO)
6 November 1963

MILITARY SPECIFICATION

WIRE-ROPE ASSEMBLIES, SINGLE LEG:

FOR

MEDIUM CABLEWAY

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers 750-foot-long, wire rope assemblies for a medium cableway.

1.2 Classification. The wire rope assemblies shall be of the following types, as specified (see 6.2):

Type I - With left-hand coupling.
Type II - With right-hand coupling.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on the date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

STANDARDS

Military

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-163	- Steel Mill Products, Preparation for Shipment and Storage.

FSC 5420

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

DRAWINGS

ME

TA13208E5016	- Wire Rope Assembly: Single Leg, W/Right-Hand Coupling.
TA13208E5082	- Wire Rope Assembly: Single Leg, W/Left-Hand Coupling.

(Copies of standards and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Description. Wire rope assemblies shall be as shown on the following Top Assemblies and as specified herein:

Type I	TA13208E5082
Type II	TA13208E5016

The wire rope assemblies shall withstand a load of 40,000 pounds without failure or slippage of the coupling on the wire rope. The coupling shall be socketed to wire rope as specified herein. When specified (see 6.2), coupling components may be procured separately.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the supplier shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the wire rope assembly. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the supplier or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article (preproduction model). The supplier shall furnish one wire rope assembly for examination and testing within the time frame specified (see 6.2), to prove prior to starting production that his production methods will produce wire rope assemblies that comply with the requirements of this specification. Examination and tests shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

Source: https://assist.dla.mil -- Downloaded: 20260-22T21:14Z
Check the source to verify that this is the current version before use.

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings.

3.4 Socketing. Socketing of wire rope for scissoring cables shall be accomplished as follows:

(a) The wire shall be securely seized from several inches before cutting and securely wrapped with a seizing iron to prevent untwisting of the rope and insure equal tension in the strands when load is applied.
(b) The end seizing on the wire rope shall be taken off, leaving the additional seizing at a distance from the end equal to the length of the socket basket. When present, the fiber core shall be cut back to this seizing, and the wires shall be untwisted and "broomed out", although they need not be straightened.
(c) The wires, for the distance that they are to be inserted in the socket, shall be carefully cleaned with benzine, naphtha, or gasoline. The wires, for a distance not more than three-fourths of the cleaned length, shall then be dipped in commercial muriatic acid for not less than 30 seconds and not more than 1 minute or until the acid has thoroughly cleaned each wire. Care should be taken that the acid does not come in contact with any other portion of the rope.
(d) The wires shall then be dipped in boiling water.
(e) The wires shall next be inserted in the basket of the socket. Care shall be taken to insure that the socket is in line with the axis of the wire rope.
(f) The base of the socket shall be sealed with putty, clay, or any similar substance.
(g) The basket shall be filled with molten zinc. The temperature of the molten zinc shall not exceed 830° F to avoid annealing the wires.
(h) Cable lubricant shall be applied to the cable near the sockets after cooling.

3.5 Wire rope marking. Each wire rope assembly shall be marked with paint as specified in Table I. The center of the single bands and the center of the bands nearest the coupling shall indicate the point marked. The spacing between the multiple-band markings shall be 1/2-inch. Sections of the wire rope to be painted shall be cleaned before painting and then relubricated after painting with a clear lubricant.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

Table I. Wire Rope Assembly-Marking.

Distance from coupling splice (feet)	Number of bands	Width of bands (inch)
First 50 feet and all intermediate 50-foot points	1	1/2
100	1	2
200	2	2
300	3	2
400	4	2
500	5	2
600	6	2
700	7	2

3.6 Identification marking. The wire rope assemblies shall be identified as shown on the drawings. When procured separately (see 3.1), coupling components shall be identified in accordance with MIL-STD-130.

3.7 Workmanship. Steel may be sawed, sheared, or flame-cut. Burned surfaces of flame-cut material shall be ground or machined to remove ash and cooling checks. Castings shall be free of defects such as cracks, blowholes, porosity, fins, or shrinkage defects. Wire rope assemblies shall be free from kinks, loose wires, loose strands, broken wires, crushed sections of wire, or other defects which may affect the strength of the rope. All threads shall be free of spelter.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

4.1.1 Component and material inspection. The supplier is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications, standards, and drawings, as applicable.

4.1.2 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Supplementary Quality Assurance Provisions (SQAP) shown on the drawings. The drawings specify the characteristics requiring SQAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.4 and 6.5).

4.2 Classification of inspections. Inspections shall be classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).
(c) Inspection of preparation for delivery (see 4.6).

4.3 Preproduction inspection.

4.3.1 Examination. The wire rope assembly shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Test. The wire rope assembly shall be tested as specified in 4.5.2. Failure of the test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling.

4.4.1.1 For examination. Sampling for examination shall be in accordance with MIL-STD-105, Inspection Level II.

4.4.1.2 For test. Sampling for tests shall be in accordance with MIL-STD-105, Inspection Level S-4.

4.4.2 Examination. Samples selected in accordance with 4.4.1.1 shall be examined as specified in 4.5.1. AQL shall be 4.0 percent defective.

4.4.3 Test. Samples selected in accordance with 4.4.1.2 shall be tested as specified in 4.5.2. AQL shall be 4.0 percent defective for all defects.

4.5 Inspection procedure.

4.5.1 Examination. The wire rope assemblies shall be examined as specified herein for the following defects:

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:14Z
Check the source to verify that this is the current version before use.

101. Dimensions not as specified or as shown on drawings.
102. Materials not as specified.
103. Components missing or not as specified.
104. Wire rope marking not as specified.
105. Identification marking incorrect, illegible or missing.
106. Threads not free of spelter.
107. Cracks or shrinkage defects in the spelter.
108. Coupling not in line with the axis of the wire rope.
109. Broken strands or wire or crushed sections of the wire rope.
110. Workmanship not as specified.

4.5.2 Test. Apply a 40,000-pound tensile load to the wire rope assembly through the coupling for 5 minutes to check the socketing of the coupling to the wire rope. It shall not be necessary to subject the complete length of wire rope to this load test. The wire rope may be tied off at any convenient length. Failure or slippage of the coupling on the rope or failure of strands of wire within 4 inches of the coupling shall constitute failure of this test. If the wire rope is tied off or if grips are used to secure the wire rope, the section of the wire rope which is tied or to which the grips are applied shall be examined for broken strands of wire or crushed sections. If the wire rope is crushed or strands of wire are broken due to the tying off of the rope, the wire rope assembly shall be unacceptable under this specification; however, this will not be considered a defect affecting the acceptance of the lot which the wire rope assembly represents.

4.6 Inspection of preparation for delivery. The preservation, packaging, packing, and marking shall be examined to determine compliance with MIL-STD-163. Any defects or omission in the preservation, packaging, or packing; or any marking that is missing, illegible, incorrect, or incomplete shall be cause for rejection.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging, packing, and marking. Wire rope assemblies shall be preserved, packaged, packed, and marked in accordance with MIL-STD-163. The level of preservation and packaging shall be Level A or C and the level of packing shall be Level A or C as specified (see 6.2).

6. NOTES

6.1 Intended use. The wire rope assemblies are intended to be used as track cables for the medium cableway.

6.2 Ordering data. Procurement documents should specify the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

(a) Title, number, and date of this specification.
(b) Type of wire rope assembly required (see 1.2).
(c) When coupling components only are required (see 3.1).
(d) Time frame required for submission of preproduction model (see 3.2).
(e) Level of preservation and packaging and level of packing required (see 5.1).

6.3 Preproduction model. Any changes or deviations of production wire rope assemblies from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the supplier of his obligation to furnish wire rope assemblies conforming to this specification.

6.4 Supplementary quality assurance provisions (SQAP). The contracting officer should require the supplier to maintain records of all SQAP inspections. A suggested paragraph is as follows:

"The supplier shall maintain complete records of all examinations and tests performed to verify the requirements of classified SQAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, corrective action taken when applicable."

6.5 Definitions.

6.5.1 Supplementary quality assurance provisions (SQAP). A SQAP is a contractual requirement that supplements Section 4 of the specification. SQAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

Custodian:

Army - ME

Preparing activity:

Army - ME

Project No. 5420-A180

Source: https://assist.dla.mil -- Downloaded: 20261O-22T21:14Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE: MIL-S-52347A(ME) - SUSPENSION KIT, HOSELINE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:14Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314



OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research and
Development Center
ATTN: STSFB-DS
Fort Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:14Z
Check the source to verify that this is the current version before use.