MILITARY SPECIFICATION

BOMB, INCENDIARY. TH3, 4-POUND, M126

This specification is mandatory for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the filling and assembly of the M126 incendiary bomb.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-1168 - Lot Numbering of Ammunition.

DRAWINGS

US ARMY MUNITIONS COMMAND

EDGEWOOD ARSENAL

DL14-5-3018 - Bomb, Incendiary, 4 Pound, TH3, M126.
IDL14-5-3018 - Bomb Incendairy, 4 Pound, TH3, M126, Inspection Data List.

FSC 1325

Source: https://assist.dla.mil -- Downloaded: 202610-19T16:30Z
Check the source to verify that this is the currentversion before use.

(Copies of specifications, standards, drawings, and publications required y suppliers in connection with specific procurement functions should be btained from the procuring activity or as directed by the contracting fficer.)

3. REQUIREMENTS

3.1 Materials and components.

3.1.1 Materials. All materials cited on Drawing DL14-5-3018 or on the ubsidiary drawings shall conform to the specifications thereon, or to the pecific characteristics set forth on the drawings.

3.1.2 Components. All components shall conform to the specifications and rawings listed on Drawing DL14-5-3018 and subsidiary drawings.

3.2 Filling and assembly.

3.2.1 Filling. (see 6.2).

(a) Main charge. The bomb shall be filled with thermate TH3 as pecified on Drawing D14-5-3018. The thermate shall be consolidated in no ess than 3 approximately equal increments under a minimum dead load of 500 pounds and a maximun of 7500 pounds dead load. The dead load shall e maintained for a minimum of 3 seconds for each increment. The ram used or the consolidation of all increments shall be shaped to give the depres- ion as shown on Drawing D14-5-3018. (See 6.3).

(b) First fire mixture. The bomb shall contain 42 to 62 grams of irst fire mixture. The mixture shall be consoldiated at a dead load of 500 to 7500 pounds, using a ram shaped to form the depression shown on rawing D14-5-3018. The dead load shall be maintained for 3 to 5 seconds.

3.2.2 Assembly. The bomb shall be assembled in accordance with Drawing 14-5-3018.

3.3 Functioning. The bomb shall function as follows:

(a) Primer detonation.
(b) Ignition of first-fire mixture.
(c) Ignition of thermate (TH3).
(d) Complete burning of the magnesium body to full depth of the thermate.

3.3.1 Five-foot drop. The bomb shall not function when dropped from a eight of 5 feet + 1-inches and tested as specified in 4.4.4 and 4.4.5.

3.3.2 Forty-foot drop. The bomb shall function when dropped from a eight of 40 feet ± 3 inches and tested as specified in 4.4.4 and 4.4.5.

Source: https://assist.dla.mil -- Downloaded: 202610-19T16:30Z
Check the source to verify that this is the currentversion before use.

3.4 Preproduction. Prior to the start of regular production, a preproduction lot of bombs shall be produced in accordance with this specification for examination and test (see 4.3).

3.5 Workmanship. The bomb shall be free of all foreign matter and damage such as cracks, and deformation which could affect its intended use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.

4.1.1 Supplier's responsibility. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspection are deemed necessary to assure supplies and services conform to specified requirements.

4.1.2 Objective evidence. The supplier shall provided objective evidence acceptable to the contracting officer that the requirements of 3.1 and section 5 for which specific inspection has not been provided in this specification have been satisfied.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).

4.3 Preproduction inspection.

4.3.1 Lot. A preproduction lot of 2000 bombs shall be manufactured using the same methods, materials, equipment, and processes as will be used during regular production.

4.3.2 Sampling.

4.3.2.1 For examination. Sampling shall be conducted in accordance with MIL-STD-105, general inspection level III.

4.3.2.2 For destructive tests. Eighty bombs shall be taken at random, 40 for the 5-foot drop test and 40 for the 40-foot drop test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:30Z
Check the source to verify that this is the current version before use.

4.3.3 Inspection procedures.

4.3.3.1 For examination. Sample bombs shall be examined in accordance with the classification of defects and MIL-STD-105.

4.3.3.2 For destructive tests. Sample bombs shall be tested in accordance with 4.4.4 and 4.4.5.

4.3.3.3 Acceptance/rejection criteria. The preproduction lot shall meet the examinations and tests specified herein to be acceptable. The supplier shall obtain written approval from the contracting officer prior to proceeding with regular production.

4.4 Quality conformance inspection.

4.4.1 Lotting. Each lot shall be identified and controlled in accordance with MIL-STD-1168. Contained in any one interfix number of bombs, no more than one interfix number from one manufacturer produced in one week of the following components is permitted:

(a) M126 bomb hardware
(b) Fin assemblies
(c) First fire mixture
(d) Thermate

4.4.2 Sampling.

4.4.2.1 For examination. Sampling shall be conducted in accordance with MIL-STD-105.

4.4.2.2 For destructive tests.

(a) Five-foot drop. Forty bombs, 20 for first sample and 20 for second sample, shall be taken at random from each production lot for test.

(b) Forty-foot drop. Forty bombs, 20 for first sample and 20 for second sample, shall be taken at random from each production lot for test.

4.4.3 Inspection procedure.

4.4.3.1 For examination. Sample bombs shall be examined in accordance with the classification of defects and MIL-STD-105.

4.4.3.2 For destructive tests. Sample bombs shall be tested in accordance with 4.4.4 and 4.4.5.

Source: https://assist.dla.mil -- Downloaded: 20260-19T16:30Z
Check the source to verify that this is the current version before use.

4.4.3.3 For critical defects. Each bomb shall be inspected for its critical characteristic listed in the classification of defects.

4.4.3.4 Classification of defects. (See Inspection Data List IDL14-5-3018 for inspection equipment required to perform the examinations prescribed in this section).

(a) Bomb, incendiary, 4-lb, TH3, - assembly (Dwg D14-5-3018)

Categories		Defects
Critical:		
1		Safety plunger missing
Major:	AQL	1.0 percent defective
*101		Filling damaged or incorrect
102		Component missing or incorrectly assembled
103		Depth to first fire mixture incorrect
104		Drive screw loose or not flush
105		Marking illegible or incorrect
106		Waterproofing missing
107		Overall length incorrect
**108		Sealing compound missing or inadequate. Add if applicable.
109		Safety plunger nonfunctional
110		Workmanship (3.5)
111		Loose first fire mixture on top of consolidated first fire mixture, exceeds 5 grams
*112		First fire mixture, and quantity is incorrect

*Check prior to completing assembly.
**Sealing compound is applied to one bomb per cluster.

(b) Holder, primer - assembly (Dwg A14-5-115)

Categories		Defects
Critical:		None defined
Major:	AQL	0.65 percent defective
101		Primer missing
102		Primer loose
103		Workmanship (3.5)

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:30Z
Check the source to verify that this is the current version before use.

4.4.4 Tests. The bomb shall be dropped, nose-down, from the specified height, as applicable, onto a level 1/2-inch-thick, nominal, steel plate, 4- to 6-inches square, imbedded in a concrete block at least 12 by 12 by 12 inches and placed on a level concrete surface.

4.4.5 Acceptance/rejection criteria. Each regular production lot shall be accepted in accordance with table I.

Table I. Acceptance/rejection criteria

Test	1st sample	Failures	Action	1st sample plus 2nd sample	Failures	Action
5-foot drop test	20	0	Accept	40	1	Accept
		1	Test 2nd sample		2 or more	Reject
		2 or more	Reject			
40-foot drop test	20	0	Accept	40	1	Accept
		1	Test 2nd sample		2 or more	Reject
		2 or more	Reject			

5. PREPARATION FOR DELIVERY

5.1 Packaging, and packing information is not applicable to this specification.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) If special packaging and packing is required for training purposes, this information will be made available upon request to the preparing activity.

6.2 Caution. Due to the hazardous nature of filling munitions with incendiary material, filling installations are advised to take all necessary precautions to protect personnel from injury when filling bombs.

Source: https://assist.dla.mil -- Downloaded: 20261O-19T16:30Z
Check the source to verify that this is the current version before use.

6.3 Filling. The approximate weight of the thermate TH3 charge for each bomb is 9.35 ounces. This information is furnished as an aid to procurement and not as a criterion for filling.

Custodians:

Army - MU
Air Force - 70

Review activity:

Air Force - 70

Preparing activity:

Army - MU(EA)

Project No. 1325-0146

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:30Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in use of the specification in procurement of products for ultimate use by the Department of Defense. This sh is provided for obtaining information on the use of this specification which will insure that suitable produ can be procured with a minimum amount of delay and at the least cost. Comments and the return of this fo will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comm and suggestions submitted on this form do not constitute or imply authorization to waive any portion of tl referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUF MENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional pap attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 202640-19T16:30Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding Officer
Edgewood Arsenal
ATTN: SMUEA–QAES
Edgewood Arsenal, Maryland 21010

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:30Z
Check the source to verify that this is the current version before use.