MIL-C-60985A (MU)
20 March 1969
SUPERSEDING
MIL-C-60985 (MU)
11 January 1968

MILITARY SPECIFICATION

CASE, CARTRIDGE, 40MM, M118

METAL PARTS FOR

1. SCOPE

1.1 This specification covers the metal parts for one type of cartridge case designated as Cartridge Case Assembly, 40MM, M118.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

PPP-T-45	-	Tape, Paper, Gummed, Sealing and Securing
PPP-B-636	-	Boxes, Fiber

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-A-8625	-	Anodic Coatings, for Aluminum and Aluminum Alloys
MIL-I-45607	-	Inspection Equipment, Supply and Maintenance of

FSC: 1310

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.

STANDARDS

FEDERAL

FED-STD-151	-	Metals, Test Methods

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes(ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-1168	-	Lot Numbering of Ammunition
MIL-STD-1169	-	Packaging, Packing and Harking for Inert Ammunition Components
MIL-STD-1235	-	Single and Multilevel Continuous sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. Army Munitions Command

8844610	-	Case, Cartridge, 40MM, M118
8844611	-	Plug, Base
8844612	-	Cup, Powder Charge

PUBLICATIONS

U. S. Army Munitions Command

ET-8801427	Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.

2

3. REQUIREMENTS

3.1 Material. -Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts. -The metal parts shall comply with all requirements specified on Drawings (Dwg.) 8844610, 8844611 and with all requirements specified in applicable specifications.

3.3 Hydrostatic pressure. -The cartridge case, less vent holes, shall be capable of withstanding a hydrostatic pressure of 48,000 pounds per square inch (psi), minimum (min), without evidence of a rupture Of the bottom Of the charge cup cavity when tested as specified in 4.4.1. Cases especially prepared for this test shall be identified from regular cases by painting a red stripe around the open end, or any positive identification approved by the procuring activity.

3.4 Hardness. -The hardness of the area near the mouth and on the base of the cartridge cage shall be 67 ± 7 on the Rockwell 30 T Scale when tested as specified in 4.4.2.

3.5 Workmanship. -All parts shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks,-unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agents.

3.6 Submission of results of contractor-conducted examinations and tests.- The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (See 6.4)

3.7 First article testing.- This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. -Unless otherwise specified in the contract or Purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 202640-23T01:07Z
Check the source to verify that this is the currentversion before use.

Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product. -At the time the completed lot of items deliverable under the contract is submitted to the. Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this" specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Subustantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection.-

4.2.1 Submission. -The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2 (See 6.1). The first article sample shall consist of the following:

a. One hundred thirty-five (135) cartridge cases
b. One hundred (100) cartridge cases less vent holes
c. Fifty (50) base plugs
d. Fifty (50) powder charge cups

All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes; procedures and equipment as will be used in fulfilling the contract. All parts

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.

and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in prodction for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Components will be subjected by the Government to any or all the examinations or tests specified in this specification and any or all requirements of the applicable drawings. In addition, any or all of the following examinations and tests will be performed:

4.2.2.1 Quantities for first article inspection. -After classification of defects and other inspections have been performed as specified in 4.2.2, the following quantities shall be subjected to the indicated tests:

4.2.2.1.1 Hydrostatic test of cartridge case. -Each of the one hundred (100) cartridge cases less vent holes shall be subjected to this test. This test shall be performed as specified in Paragraph 4.4.1 Code No. 05001.

4.2.2.1.2 Hardness. -One hundred (100) cartridge cases shall be subjected to this test.

4.2.2.1.3 Salt spray .-Ten (10) of each applicable part shall be subjected to the test.

4.2.2.1.4 Diameter of vent holes. -Twenty-five (25) cartridge cases shall be sectioned and the diameter of each vent hole measured by any method satisfactory to the Contracting Officer.

4.2.3 Rejection. -If any component fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 202610-23T01:07Z
Check the source to verify that this is the current version before use.

In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions.

4-3.1 Lot formation. -The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination. -The examinations listed in the following sub-paragraphs shall be performed on Inspection lots (See 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for Critical Defects (and Major Defects, when so specified) shall be 100 percent. Sampling plans for Major and Minor Defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of Major and Minor Defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each Major Defect and an AQL of 0.65 percent for each Minor Defect. When this method is elected, it shall be applied to all of the Major and Minor Defects listed in the applicable sub-paragraph of this section, except where 100 percent inspection is specified, and be documented a as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 202640-23T01:07Z
Check the source to verify that this is the current version before use.

4.3.2.1 Base plug (See Dwg. 8844611).-

Categories	Defects	Method of Inspection	Defect Code (See 6.2)
Critical:			
	1. Depth of primer cavity	Automatic Gage	01001
Major:	AQL 1.00 Percent		
	101. Largest outside diameter	Gage	01002
	102. Concentricity of smallest outside diameter with largest outside diameter	Gage	01003
	103. Concentricity of primer cavity diameter with largest outside diameter	Gage	01004
	104. Smallest outside diameter	Gage	01005
	105. Diameter of primer cavity	Gage	01006
	106. Length of primer end to shoulder including angle	Gage	01007
	107.. Total length	Gage	01008
	108. Diameter of flash hole	Gage	01009
	109. Radius of intersection of primer cavity missing	Visual	01010
Minor:	AQL 2.50 Percent		
	201. Second largest outside diameter	Gage	01011
	202. Length from primer end to far side of shoulder	Gage	01012
	203. Protective coating with bare spot except anode rack marks	Visual	01013
	204. Finish improper	Visual	01014
	205. Evidence of poor workmanship (See 3.5)	Visual	01015
	206. Color incorrect	Visual	01016

4.3.2.2 Powder charge cup (See Dwg. 8844612).-

Categories	Defects	Method of Inspection (See 4.3.3.1)	Defect Code
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 202610-23T01:07Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 Percent		
101.	Length to datum	Gage	02001
102.	Inside diameter	Gage	02002
103.	Diameter of flange, max.	Gage	02003
Minor:	AQL 1.00 Percent		
201.	Wall thickness	Gage	02004
202.	Evidence of poor workmanship (See 3.5)	Visual	02005

4.3.2.3 Case, cartridge (See Dug. 8844610).-

Categories	Defects	Method of Inspection	Defect Code
Critical:			
1.	Vent hole blocked or missing (See 6.8)	Visual	03001
Major:	AQL 2.50 Percent		
101.	Hardness	Test	03002
102.	Concentricity of largest outside diameter with second largest outside diaemter	Gage	03003
103.	Concentricity of largest inside diameter with second largest outside diameter	Gage	03004
104.	Concentricity of base plug cavity with second largest outside diameter	Gage	01005
105.	Concentricity of powder charge cup cavity with base plug cavity	Gage	03006
106.	Diameter of powder charge cup cavity, min.	Gage	03007
107.	Diameter of base plug cavity	Gage	03008
108.	Depth of base plug cavity	Gage	03009
109.	Depth from base to bottom of powder charge cup cavity	Gage	03010
110.	Second largest outside diameter (See 6.5)	Gage	03011
111.	Diameter of node	Gage	03012
112.	Perpendicularity of open end to second largest outside diameter	Gage	03013
113.	Perpendicularity of base to second largest outside diameter	Gage	03014
114.	Diameter of vent hole(See 4.3.3.2)	Gage	03015
115.	Largest inside diameter (See 6.6)	Gage	03016
116.	Distance to flat of inside projection	Gage	03017
117.	Diameter of flange, max.	Gage	03018
118.	Total length		03019

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.

119.	Burr in vent hole	Visual-Equipment	03020
120.	Diameter at datum length, min.	Gage	03021
121.	Unconfined second largest outside diameter	Gage	03022
122.	Metal defective (See 3.5 and 6.7)	Visual	03030
Minor:	AQL 2.50 Percent		
201.	Thickness of flange	Gage	03023
202.	Length of base plug seating projection from bottom of base	Gage	03024
203.	Wall thickness, min.	Gage	03025
204.	Stamping misleading or unidentifiable	Visual	03026
205.	Protective coating with bare spot except anode rack marks	Visual	03027
206.	Color incorrect	Visual	03028
207.	Evidence of poor workmanship (See 3.5)	Visual	03029

4.3.3 Testing.-

4.3.3.1 Dimensional control of stamped parts, Defect Code 04001). - In place of the normal sampling associated with the Classification of Defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last toll control check shall be returned to the contractor for corrective action.

All tools removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting officer to substantiate the request.

4.3.3.2 Total vent hole area (alternate method), (See Dwg. 8844610), Major defect, Code No. 06001.- Each cartridge case shall be inspected for total vent hole area. If any cartridge case fails to comply with the requirement specified on the applicable drawing, it shall be classified defective and removed from the lot.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 202640-23T01:07Z
Check the source to verify that this is the current version before use.

NOTE: If, upon calibration, the equipment setting has changed so as to permit acceptance of cartridge case having total vent hole areas that deviate from the requirement specified on the applicable drawing, then the cases accepted since the last calibration must be re-inspected and the defective parts removed from the lot.

This test shall be conduced in accordance with 4.4.4, using equipment in accordance with 4.3.4.

4.3.3.3 Salt spray (See Dwg. 8844610 and 8844611), Major Defect, Code No. 07001.-Samples shall be selected in accordance with MIL-A-8625. Rejection shall be as specified in MIL-A-8625.

4.3.3.4 Process control inspection of bath temperature for anodic coating (See Dwg. 8844610 and 8844611), Major Defect, Code No.08001.-Continuous monitoring inspection shall be conducted for bath temperature requirement specified on the applicable drawings. If the bath temperature for a batch of parts does not comply with the applicable drawing requirement, the batch shall be suitably identified, classified defective and removed from the lot.

4.3.4 Inspection equipment. -Equipment Tabulation (ET) number 8801427 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation. -Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures

4.4.1 Hydrostatic test of cartridge case. -The sample cartridge case, less vent holes, shall be placed in a fixture as shown on the Equipment List. The protrusion inside of the case shall not be supported. The fixture shall be placed in a press and a load applied until the required pressure is reached. The ram shall be applied at a rate not exceeding 0.25 inch per minute. This test is a destructive test. Parts so tested shall not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.

4.4.2 Hardness. -The test shall be conducted in accordance with Method 243 of Federal Standard No. 151. This is a nondestructive test. Parts so tested may be returned to the lot.

4.4.3 Salt spray. -The applicable parts shall be tested in accordance with FED-STD-151, Method 811.1. This test shall be conducted for 240 hours. Parts so tested shall not be returned to the lot. Salt solution shall be 5 per cent.

4.4.4 Total vent hole area (alternate method). -The cartridge case shall be inspected for total vent hole area, using the equipment specified on the Equipment List. This test is a non-destructive test. Parts so tested may be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.-

5.1.1 Level C. -The metal parts for Case, Cartridge, M118, shall be packaged for shipment as described below:

5.1.1,1 Case, Cartridge, M118. -Five hundred (500) cases shall be packed base down in five (5) layers in Type 1, Class 1, "B" Flute, 175 pound minimum, domestic Class, RSC Style, Specification PPP-B-636 fiberboard box. Inside dimensions of fiber box shall be 18 3/4 X 18 3/4 X 9 3/4 high (± 1/16 tol). Each layer shall be composed of an egg crate type separator in a 10 X 10 pattern. Separators shall fit snug in fiber box, length and width. Height of separator to 1 1/2 inches. A filler 18 X 18 shall be used between layers and on top as required for tight packing. Material used for separators and fillers shall be the same as that used for the fiber box.

5.1.1.2 Base plug and powder charge cup. -The base bluff and powder charge cup shall be packed as specified in MIL-STD-1169

5.1.1.3 Alternate pack for Case, Cartridge, M118. -Three hundred (300) cases shall be packed in six (6) layers in Type 1, Class 1, "B" flute, 175 pound minimum, domestic class, RSC Style, Specification PPP-B-636 fiberboard box. Inside dimensions of fiber box shall be 17 1/2 X 8 3/4 X 11 5/8 high. Each layer shall be composed of an egg crate type separator in a 10 X 5 pattern. Separators shall fit snug in fiber box, length and width. Height of separator to be 1 1/2 inches. A filler 17 X 8 shall be used between layers, and on top as required for tight packing. A spacer 8 5/8 X 8 5/8 shall be placed between flaps on bottom and on top of fiber box. Material used for separator, fillers and spacers shall be the same as that used for fiber box.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.

5.2 Packing.-

5.2.1 Level C. -The metal parts for Case, Cartridge, M118, preserved and packaged as specified in 5.1.1, shall be packed for shipment as described below:

5.2.1.1 Case, Cartridge, M118. -See 5.1.1.1 or 5.1.1.3.

5.2.1.2 Base plug and powder charge cup. -See 5.1.1.2.

5.3 The construction of the fiber box and the material requirements of the fiber box shall comply with PPP-B-636. When assembled, the corrugations of the fiber box shall parallel the fiber box depth. The manufacturer's joint on the fiber box shall be reinforced with paper tape or metal stapled or stitched.

Spacing of staples or stitches shall not average over 1 1/2 inches apart, center to center. A manufacturing tolerance of plus or minus 1/8 inch is permissible. The parts manufacturer shall be furnished pre-production samples of all packing materials so that proper fit of packing material dimensions provide a proper fit of all parts, as determined to be necessary by examination of sample packs, are permissible.

5.4 Sealing. -The fiber box flaps shall be secured with gummed Kraft paper not less than 3 inches wide, complying with PPP-T-45, Grade B. Tape. The tape shall be centered the full length of the outer flap seams and extend over each end of the fiber box at least 3 inches. The flap edge seams shall be similarly sealed with the tape extending at least 3 inches along the corners of the fiber box. Tape shall be properly moistened and sufficiently compressed to insure tight adhesion to the fiber box.

5.5 Marking. -Marking of the fiber box shall comply with MIL-STD-1169

5.6 Shipping. -When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data. -Procurement documents shall specify the following:

a. Title, number and date of this specification,
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.

6.2 Inspection code numbers. -The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (See 6.3.5).

6.3 Inspection equipment. -The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of Paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists. -Equipment lists indicate the availability of inspection equipment designs by showing in the "part Number" column of the list of inspection equipment (Form SMUPA-1010) the numbers of drawings of Federal Stock numbers of existing equipment designs, or codes as indicated in Paragraph 6.3.2. Design action required of the contractor is described in Paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes. -The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs. -Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army design fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (See 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.

6.3.4 Contractor designs. -Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculationor clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor design. -All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as Critical and Major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed to the Contracting Officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of results of contractor-conducted examinations and tests.- Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

6.5 If the requirement cannot be met in the free state, the "go" inside diameter plug gage may be inserted in the cartridge case while inspecting the "go" and "no go" second largest outside diameter. If the "go" inside diameter plug is utilized, the data cards shall be annotated accordingly.

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026l0-23T01:07Z
Check the source to verify that this is the currenversion before use.

6.6 If the requirement cannot be met in the free state, a confining fixture may be utilized while inspecting the "go" and "no go" largest inside diameter. If the confining fixture is utilized, the data cards shall be annotated accordingly.

6.7 Metal defective. -Nick, crack, dent or sharp edge which might interfere with the proper assembly or end item performance of the item.

6.8 Any case which fails this requirement shall be discarded at the source of inspection and rendered unusable. Every case which passes this requirement shall be marked 1/4 inch in from the mouth with a 1/2 inch letter H.

Custodian:
Army -MU

Preparing Activity:
Army-MU

Project Number: 1310-A-103

Source: https://assist.dla.mil -- Downloaded: 2014-07-25T18:37Z
Check the source to verify that this is the current version before use.
Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:07Z
Check the source to verify that this is the current version before use.