MILITARY SPECIFICATION

GRENADE, GP: M36

LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of grenade designated as Grenade, GP: M36.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-D-50584	-	Delay Detonator Assembly (Dwg. C-9207798)
MIL-I-45607	-	Inspection Equipment, Acquisition, Maintenance and Disposition of

FSC: 1330

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-286	-	Propellants, Solid: Sampling, Examination and Testing
MIL-STD-1168	-	Lot Numbering of Ammunition
MIL-STD-1235	-	Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

US ARMY MUNITIONS COMMAND

C-9211946	-	Grenade, GP, M36

PUBLICATIONS

ARMY

ET-9211946	-	Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

3. REQUIREMENTS

3.1 Materials and parts.-Materials and parts shall be in accordance with the applicable drawings and specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

3.2 Grenades.-The grenades shall comply with all requirements specified on Drawing (Dwg) C-9211946, all associated drawings, and with all requirements specified in the applicable specifications.

3.3 Grenade functioning.-The grenade shall function satisfactorily (See 6.10) and shall exhibit an average impact velocity of one-hundred twenty-five (125) plus or minus (±) ten (10) feet per second (fps) when tested as specified in 4.3.2. (NOTE: In-housing bursts shall be included as grenade failures.)

3.4 Workmanship.-All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, surface defects, dirt, grease, rust, salt deposits, and other foreign matter. The cleaning method shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches,not exposing base material. All required markings shall be neat and sharply defined.

3.5 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (See 6.5)

3.6 Grenade storage.-The elapsed time between the loading and assembling of the grenades and their assembly into the projectile shall be kept to a minimum. Grenades shall be stored in an approved, heated (100° F. to 120° F.), ventilated area.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 Inspection provisions

4.2.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot shall contain:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

a. Individual components and sub-assemblies of one lot interfix from one manufacturer. However, the grenade lot may contain components or sub-assemblies made by one or more manufacturers, i.e. housing assemblies from manufacturer "A" can be used with washers from manufacturer "B", with components for tube adapters from manufacturer "C", with shell tube assemblies and lower shells from manufacturer "D", etc.)

b. M5 propellant from one lot only from one manufacturer.

c. Delay detonator assemblies from one lot only from one manufacturer. (See 4.2.3.7)

d. Explosive composition A5 from one lot only from one manufacturer.

e. RDX from one lot only from one manufacturer.

4.2.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (See 4.2.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. In addition, at the option of the procuring activity, defect characteristics of the same classification which have been separated into two (2) groups to specifically allow the optional method of inspection in accordance with 4.2.3.1 and 4.2.3.2, may be combined into one (1) group when the option of 4.2.3.1 and 4.2.3.2 is not exercised. The AQL for the combined grouping will be as indicated in the applicable classification of defects paragraph. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

4.2.2.1 Cover (See Dwg C-9211969 covering a detail of Dwg C-9211946).

Categories	Defects	Method of Inspection	Code No. (See 6.2)
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

Major	AQL 0.40 Percent (See 4.2.3.1)		
101.	Outside diameter minimum (min)	Gage	01001
102.	Thickness through center	Gage	01002
Minor	*AQL 0.65 Percent (See 4.2.3.1)		
201.	Thickness around edge	Gage	01003
Minor	AQL 1.50 Percent		
202.	Dimple missing	Visual	01004
203.	Evidence of poor workmanship (See 3.4)	Visual	01005
204.	Part damaged (puncture, crack or dent)	Visual	01006

*Combined AQL for Minor defects 201-204 inclusive, is as follows: AQL 1.50 Percent (See 4.2.2)

4.2.2.2 Tube adapter charge assembly (prior to assembly of propellant and cover) (See Dwg C-9211967)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.65 Percent		
101.	Disc missing or assembled improperly (flash hole not covered or adhesive side not facing bottom)	Visual	02001
102.	Disc damaged (cut, punctured, torn or dented)	Visual	02002
103.	Foreign matter in propellant cavity (See 3.4)	Visual	02003
Minor:	None defined		

4.2.2.3 Tube adapter charge assembly (prior to assembly of cover) (See Dwg. C-9211967).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Weight of propellant	Balance	03001
Minor	AQL 0.65 Percent		
201.	Foreign matter (See 3.4)	Visual	03002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

4.2.2.4 Tube adapter charge assembly (See Dwg. C-9211967)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Width of shoulder	Gage	04001
102.	Cover not crimped tight or crimp less than 360°	Visual-Manual	04002
103.	Disc missing	Visual	04003
104.	Crack at crimp	Visual	04004
105.	Cover damaged (dented, cut or punctured)	Visual	04005
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	04006

4.2.2.5 Lower shell assembly (See Dwg D-8865602 covering a detail of Dwg C-9211946).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Depth to charge	Gage	05001
102.	Outside diameter, max	Gage	05002
103.	Diameter of shell hole, min	Gage	05003
104.	Inside diameter of charge	Gage	05004
105.	Charge chipped, cracked or pitted	Visual	05005
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	05006

4.2.2.6 Upper shell assembly (See Dwg. D-8865601 covering a detail of Dwg C-9211946).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.65 Percent		
101.	Depth to charge	Gage	06001
102.	Outside diameter, max	Gage	06002
103.	Diameter of detonator tube sleeve, min	Gage	06003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

104.	Charge chipped, cracked or pitted	Visual	06004
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	06005

4.2.2.7 Housing assembly (See Dwg. D-9211947 covering a detail of Dwg. C-9211946).

Categories	Defects	Method of Inspection	Code No.
Critical			
1.	Depth to end of slider, max	Gage	07001
2.	Depth to tip of firing pin, max	Gage	07002
3.	Hinge pin loose	Manual	07003
4.	Hinge pin missing	Visual	07004
5.	Bend in safety wire missing	Visual	07005
Major: None defined			
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	07006

4.2.2.8 Grenade body assembly (See Dwg. D-9211966 covering a detail of Dwg. C-9211946).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major	*AQL 0.40 Percent		
101.	Adapter tube charge assembly fails to withstand disassembly torque (See 4.2.3.2)	Test	08001
Major	AQL 0.65 Percent		
102.	Outside diameter, max	Gage	08002
103.	Total height, max	Gage	08003
104.	Adapter tube not fully seated against shell assembly	Visual	08004
105.	Cover on adapter tube charge assembly missing or damaged (punctures or cracks)	Visual	08005
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	08006

*Combined AQL for Major defects 101-105, inclusive, is as follows: AQL 1.00 Percent. (See 4.2.2)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

4.2.2.9 Grenade (See Dwg. C-9211946).

Categories	Defects	Method of Inspection	Code No.
Critical			
1.	Safety wire assembly missing	Visual	09001
2.	Safety wire not completely engaged	Visual	09002
Major	AQL 1.00 Percent		
101.	Retainer cap above flush	Gage	09003
102.	Grenade body loose	Manual	09004
103.	Retainer cap incompletely engaged	Visual	09005
104.	Component damaged	Visual	09006
105.	Any component missing	Visual	09007
106.	Red mark missing from housing or improperly located (not on same side as cover spring)	Visual	09008
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	09009

4.2.3 Testing.

4.2.3.1 Dimensional control of stamped parts.-In place of the normal sampling associated with the classification of defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check shall be returned to the contractor for corrective action.

All tools removed from production because of some fault, may, after reworking, be returned to production, providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

4.2.3.2 Disassembly torque of adapter (See Dwg. D-9211966) Major Defect, Code No. 08001.-In place of the normal sampling procedure associated with the classifications of defects, and with the approval of the Contracting Officer, the following inspection procedure may be used: at the start of each day, and whenever a new piece of equipment is put into operation, five (5) body assemblies shall be selected from each piece of equipment for determination of disassembly torque of the adapter for qualifying the equipment. In addition, five (5) assemblies per machine shall be selected from each hour's production, or fraction thereof, for the determination of the adapter disassembly torque as a control of the equipment. If any defective assemblies are found during qualification of the equipment, the equipment producing the defective assemblies shall not be used in production. If any defective assembly is found when inspection is performed for control of the equipment, the equipment having produced the defective assembly shall be removed from production. Further, that portion of production since the last equipment check shall be returned to the contractor for corrective action. All equipment removed from production because of some fault, may, after corrective action, be returned to production providing they pass the qualification test above.

4.2.3.3 Density of upper and lower shell assemblies (See Dwgs D-8865601 and D-8865602, resp) Major Defect, Code No. 10001.-A minimum of two (2) samples each, representative of the shell tube assembly and the lower shell being processed, shall be loaded and the densities determined to qualify each press prior to its use in the loading process in production. In addition, a sample of two (2) assemblies shall be randomly selected from the last portion of each four (4) hour's production from each press and the density determined as a control of each press during production.

If any defective assemblies are found when inspection is performed for control of a press, the press producing the defective assembly shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for corrective action.

All presses removed from production because of some fault, may, after reworking, be returned to production, providing they pass the qualification test above.

4.2.3.4 Moisture and total volatiles content of charge assembly propellant (See Dwg. C-9211967) Major Defect, Code No. 11001.-The contractor shall provide adequate controls to insure compliance with the applicable requirements. The moisture and total volatiles content of each lot of propellant shall be determined at the loading station at the time of loading the charge assemblies. This determination shall be made at least once for

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

each eight (8) hours of production. Sampling of the propellant shall be in accordance with MIL-STD-286, Method 101.2.2. In addition, if the moisture and total volatiles content fails to comply with the requirement specified on the applicable drawing and loading has not begun, the lot shall be rejected until corrective action has been taken as verified by repeating the moisture and total volatiles content determination. If loading has begun, charge assemblies loaded with non-conforming propellant shall be rejected. This determination shall be performed as specified in 4.3.1.

4.2.3.5 Grenade functioning, (See 3.4) Major Defect, first article inspection (See 6.4) Code No. 12001.-Beginning with the first lot produced and continuing until three (3) consecutive lots have been accepted under the acceptance criteria specified, one hundred twenty-five (125) grenades shall be selected by the Government inspector from each lot for this test. If eight (8) or more grenades fail to comply with the specified requirements, the lot shall be rejected. The test shall be performed as specified in 4.3.2, using equipment in accordance with 4.2.4. First article inspection shall also apply whenever a lapse in production exceeds ninety (90) days.

4.2.3.6 Grenade functioning (See 3.4) Major Defect, Regular production, Code No. 12001.-After three (3) consecutive lots have met the criteria of 4.2.3.5 for first article inspection, the Government inspector shall select fifty (50) grenades from each lot for this test. If four (4) or more grenades fail to comply with the specified requirements, the lot shall be rejected. The test shall be performed as specified in 4.3.2, using equipment in accordance with 4.2.4.

4.2.3.7 Check test for deterioration of delay detonator assemblies (See MIL-D-50584) Major Defect, Code No. 13001).-If the total time between the original acceptance of any delay detonator assembly lot into the grenade exceeds two years, or if the delay detonator assemblies have been subjected to adverse conditions, however brief, at any time since previous tests, the delay detonator assembly lot shall be subjected to and must satisfactorily pass, the check test for deterioration specified in the applicable detonator specification immediately before the delay detonator assembly lot is assemblied into the grenade. This test shall be performed by the contractor on delay detonator assemblies selected by the Government Inspector at the facility assembling the detonator assemblies into the grenade (See 6.8) All data shall be recorded. If any delay detonator assembly lot fails this check test, the data shall be forwarded as specified in 6.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

4.2.4 Inspection equipment.-Equipment Tabulation (ET) number 9211946 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.2.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.3 Test methods and procedures.

4.3.1 Moisture and total volatiles content of charge assembly propellant.-The total moisture and total volatiles content of the propellant shall be determined in accordance with MIL-STD-286, Method 101.2.2.

4.3.2 Grenade functioning.-Grenades, prepared as specified in 6.6, shall be fired using equipment specified on the applicable Equipment List. The average impact velocity shall be computed and recorded for each grenade subjected to this test to determine compliance with the requirements of 3.3. Average velocity is computed by dividing the time measurement, indicated on the applicable equipment drawing, by its corresponding distance. All recorded data from this test shall be distributed in accordance with 6.4. (See 6.7)

4.3.2.1 Discarded data.-Recorded data required by 4.3.2.2 shall be discarded if any one of the following occurs:

a. Impact velocity less than 100 fps
b. Equipment malfunction
c. Poor orientation on impact
d. External interference to ball while in flight

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

4,3.2.2 Recorded data.-The following information shall be recorded: (See 6.4)

a. Total ball travel (to be computed on X, Y, Z axes)
b. Ball travel which is too short for measurement, but is not an in-housing burst.
c. Details of each grenade failure
d. Delay time for each shot, including those grenade failures where the delay time can be recorded.
e. Average delay time for the quantity tested.
f. Impact velocity

NOTE: When results are discarded, additional grenades shall be fired to comply with sample quantity specified.

5. PREPARATION FOR DELIVERY
(Not applicable to this specification)

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in MIL-STD-1167.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor. (See 6.3.5)

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" ain the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6, 3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (See 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procurement of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 3. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of test data.-In addition to the normal distribution of records, when the grenade is procured by the US Army Munitions Command, one (1) copy of all ballistic data and ammunition data cards shall be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

6.5 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

6.6 Preparation of grenade for functioning test.-The housing assembly (Dwg 9211947) selected for this test shall be modified as follows: a standard one-sixteenth (1/16) inch hole shall be drilled through the restrictor, centering the drill 0.0312 (1/32) of an inch from the outer edge of the restrictor. The hole shall be drilled to a depth of 0.125 (1/8) inch. CAUTION: Care shall be taken to prevent chips from entering the hole by the use of compressed air, or other suitable means, during the drilling operation. The item shall then be loaded in accordance with the normal loading operations and then tested as specified on the applicable drawing of the Equipment List.

6.7 Barricades.-Tests conducted on assemblies containing an explosive component, shall be conducted using approved equipment, procedures and barricades.

6.8 Cost of check test.-The contracting officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the check test for deterioration of detonator assemblies. The tests shall be conducted at Government expense without cost to the contractor who loaded the delay detonator assemblies, or to the contractor assembling the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.

delay detonator assemblies into the grenade; and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc., permitted while the delay detonator assembly lot was under the jurisdiction of either contractor.

6.9 Supersession data.-This specification includes the requirements of, and supersedes Purchase Specification AEI-391, dated 13 February 1968.

6.10 Grenade functioning.-Satisfactory functioning of the grenade is defined as the grenade hitting the impact media at the specified velocity and ejection of the submissile with high order detonation.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No: 1330-A002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:44Z
Check the source to verify that this is the current version before use.