MIL-M-60922A (MU)
18 December 1970
SUPERSEDING
MIL-M-60922 (MU)
26 September 1967

MILITARY SPECIFICATION

MINE, APERS, M26

TOP AND BOTTOM CUP ASSEMBLY FOR

1. SCOPE

1.1 This specification covers the top and bottom cup assembly for Mine, Apers, M26.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-I-45607	-	Inspection Equipment, Acquisition, Maintenance and Disposition of

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-1168	-	Lot Numbering of Ammunition
MIL-STD-1169	-	Packaging, Packing and Marking for Shipment of Inert Ammunition Components
MIL-STD-1235	-	Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

US ARMY MUNITIONS COMMAND

D-8840341	-	Top and Bottom Cup Assembly

PUBLICATIONS

ARMY

ET-8840341	-	Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS

ASTM B 117-64	-	Standard Method of Salt Spray (Fog) Testing

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

ASTM E 18-67 - Standard Methods of Test for Rockwell Hardness and Rockwell Superficial Hardness of Metallic Materials

(Application for copies should be addressed to: Amercian Society for Testing and Materials, 1916 Race Street, Philadelphia, Pa. 19103)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts.-The parts shall comply with all requirements specified on Dwg D-8840341, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Internal air pressure of top and bottom cup assembly (prior to interior coating).-The top and bottom cup assembly shall withstand an internal air pressure of fifteen (15) pounds per square inch gage (psig) plus one (1) pound per square inch (psig) for four (4) seconds, minimum (min) with no evidence of leakage when tested as specified in 4.4.2.

3.4 Strength of weld of top and bottom cup assembly (as applicable).-The equatorial weld line of the top and bottom cup assembly shall not exhibit a visible crack when crushed to a dimension of 1.250 + 0.125 inches in the plane of the weld when tested as specified in 4.4.4.

3.5 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any parts, nor shall the parts be contaminated by the cleaning agents.

3.6 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (See 6.4)

3.7 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptanee, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

4.1.2 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings, and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "Critical" be accepted solely on the basis of the contractor's records.

4.2 First article inspection.

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of the following:

a. Twenty (20) each of every component and sub-assembly.
b. Fifty (50) consecutively produced top and bottom cup assemblies (prior to internal coating).
c. Two (2) stock specimens from the coil of stock prior to forming. Each specimen shall comprise the width of the stock to be used for production, and the length equivalent to the circumference of the tool to be utilized for production. One specimen shall be taken from the beginning of the coil; the other specimen taken from the end of the coil. Each specimen shall be identified for the direction of rolling and identified with an index position of the tool.
d. Twenty (20) top and bottom cup assemblies (coated and painted).

All parts, completed assemblies and specimens submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Assemblies and components will be subjected by the Government to any or all the examinations or tests specified in this specification, and any or all requirements of the applicable drawings. In addition, any or all of the following examinations and tests will be performed.

4.2.2.1 Quantities for first article inspection.-After classification of defects and other inspections have been performed as specified in 4.2.2, the following quantities shall be subjected to the indicated tests.

4.2.2.1.1 Internal air pressure of top and bottom cup assembly (prior to internal coating) (See 3.3).-The fifty (50) top and bottom cup assemblies shall be subjected to this test.

4.2.2.1.2 Pull test of locating lug welds (See Dwg D-8840341).-After completion of test specified in 4.2.2.1.1, the fifty (50) top and bottom cup assemblies shall be subjected to this test.

4.2.2.1.3 Strength of weld of top and bottom cup assembly (See 3.4).-Following completion of the test specified in 4.2.2.1.2 the fifty (50) top and bottom cup assemblies shall be subjected to this test.

4.2.2.1.4 Salt spray test of top and bottom cup assembly (See Dwg D-8840341).-The twenty (20) coated and painted top and bottom cup assemblies shall be subjected to this test.

4.2.2.1.5 Hardness of obturator (See Dwg C-8840346).-The twenty (20) obturators shall be subjected to this test.

4.2.2.1.6 Torque of obturator crimp on bottom cup assembly or top and bottom cup assembly (See Dwg C-8840344 or Dwg 8840341, as applicable).-The twenty (20) bottom cup assemblies shall be subjected to this test.

4.2.2.1.7 Dimensional inspection of stock specimen.-The two (2) sample specimens referenced in 4.2.1 (c) shall be subjected to the dimensional inspection specified in 4.4.1 and 4.4.1.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

4.2.3 Rejection.-If any part, assembly or stock specimen fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly, component, or stock specimen in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (See 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. In addition, at the option of the procuring activity, defect characteristics of the same classification which have been separated into two (2) groups to specifically allow the optional method of inspection in accordance with 4.3.3.1 may be combined into one (1) group when the option of 4.3.3.1 is not exercised. The AQL for the combined grouping will be as indicated in the applicable classification of defects paragraph. Equipment necessary for the performance of the inspection listed shall be in accordance with 4.3.4.

4.3.2.1 Cup (See Dwg D-8840345 covering a detail of Dwg D-8840-341).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor	*AQL 0.65 Percent (See 4.3.3.1)		
201.	Spherical radius improper	Gage	01001
Minor	AQL 0.65 Percent		
202.	Evidence of poor workmanship (See 3.5)	Visual	01002

*Combined AQL for Minor defects 201 and 202, inclusive, is as follows: AQL 1.00 Percent (See 4.3.2)

4.3.2.2 Bottom cup assembly (See Dwg C-8840344 covering a detail of Dwg D-8840341).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Total thickness through obturator and cup wall, maximum (max)	Gage	02001
102.	True position of inside diameter of obturator hole with large inside diameter of obturator	Gage	02002

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.5)	Visual	02003

4.3.3.3 Top and bottom cup assembly (See Dwg D-8840341).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	True position of inside diameter of obturator with ball diameter	Gage	03001
102.	Location of notch on obturator with location lug	Gage	03002
103.	Diameter of ball, min (as applicable)	Gage	03003
104.	Diameter of ball, max	Gage	03004
105.	Diameter of obturator hole	Gage	03005
106.	Distance from ball surface to top of locating lug (2 places)	Gage	03006
107.	Location of location lugs	Gage	03007
108.	Width of locating lugs	Gage	03008
109.	Total height	Gage	03009
110.	Any part cracked or distorted	Visual	03010
111.	Protective finish with bare spot	Visual	03011
Minor	AQL 1.50 Percent		
201.	Spherical radius improper (as applicable)	Gage	03012
202.	Flute radius, max. (as applicable)	Gage	03013
203.	Evidence of poor workmanship excluding scratches (See 3.5)	Visual	03014

4.3.3 Testing

4.3.3.1 Dimensional control of stamped parts.-In place of the normal sampling associated with the Classification of Defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check shall be returned to the contractor for corrective action.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

All tools removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request.

4.3.3.2 Internal air pressure of top and bottom cup assembly (prior to internal coating) (See 3.3) Major defect (Defect Code 04001).-One hundred twenty-five (125) top and bottom cup assemblies shall be selected from each lot and subjected to this test. If four (4) or more assemblies fail to comply with the specified requirement, the lot shall be rejected. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.3 Pull test of locating lug welds (See Dwg D-8840341) Major Defect (Defect Code 05001).-Thirteen (13) top and bottom cup assemblies shall be selected from each four (4) hours of production from each machine in operation and subjected to this test. If any assembly fails to comply with the requirement specified on the applicable drawing, the four (4) hour's production represented by the failing sample shall be rejected. The test shall be performed as specified in 4.4.3 using equipment in accordance with 4.3.4.

4.3.3.4 Strength of weld of top and bottom cup assembly (See 3.4) Major Defect (Defect Code 06001).-Five (5) top and bottom cup assemblies shall be selected from each four (4) hours of production from each machine in operation and subjected to this test. If any assembly fails to comply with the specified requirement, the four (4) hour's production represented by the failing sample shall be rejected. The test shall be performed as specified in 4.4.4 using equipment in accordance with 4.3.4.

4.3.3.5 Salt spray test of top and bottom cup assembly (See Dwg D-8840341) Major Defect (Defect Code 07001).-Fifteen (15) top and bottom cup assemblies from each shift's production shall be subjected to the salt spray test as specified on the applicable drawing. If any assembly fails to comply with the specified requirement, the quantity represented by this sample shall be rejected. The test shall be performed as specified in 4.4.5.

4.3.3.6 Hardness of obturator (See Dwg C-8840346) Major Defect (Defect Code 08001).-Ten (10) obturators shall be selected from each heat treatment batch (See NOTE) and subjected to this test. If any obturator fails to comply with the requirement specified on the applicable drawing, the batch represented by the failing sample shall be rejected. The test shall be performed as specified in 4.4.6 using equipment in accodance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

NOTE 1-A heat-treatment batch shall be defined as parts that have been heat treated at the same time in the same furnace and quench bath for each of all phases of the entire heat treatment process.

4.3.3.7 Torque of obturator crimp on bottom cup assembly or on top and bottom cup assembly (See Dwg C-8840344 or Dwg D-8840341, as applicable) Major Defect (Defect Code 09001).-Sampling plans and procedures for this test shall be in accordance with MIL-STD-105 using code letter J and an AQL of 0.65 percent. Any assembly which fails to comply with the requirement specified on the applicable drawing shall be classed defective. The test shall be performed as specified in 4.4.7 using equipment in accordance with 4.3.4.

4.3.3.8 Dimensional inspection of stock specimen (See Dwg D-8840345) Major Defect (Defect Code 10001).-Two (2) stock specimens shall be taken from each coil of stock prior to forming. Each specimen shall comprise the width of the stock to be used for production, and the length equivalent to the circumference of the tool to be utilized for production. One specimen shall be taken from the beginning of the coil; the other specimen taken from the end of the coil. Each specimen shall be identified for the direction of rolling and identified with an index position of the tool.

If the average value of fifteen (15) measurements for the .115, .030 or .0814 dimensions fails to fall within the drawing requirements, or if the direction of rolling fails to comply with the drawing requirement, the coil from which the stock specimen was taken shall be rejected. If forming of the parts has begun, parts or assemblies, represented by the rejection coil, shall be rejected. The dimensional inspection shall be performed as specified in 4.4.1 using equipment in accordance with 4.3.4.

4.3.3.8.1 Die control.-Whenever a new, repaired or altered die is entered into the production line, a stock specimen shall be taken. In addition, to the dimensions specified in 4.3.3.8, fifteen (15) measurements for the .010R and .068 dimension shall be determined. If the average value of a dimension exceeds the drawing requirement, the die shall be removed from production. If forming of the parts has begun, parts or assemblies represented by the rejected die, shall be rejected. The dimensional inspection shall be performed as specified in 4.4.1.1 using equipment in accordance with 4.3.4.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 8840341 and Equipment Lists (EL's) referenced theron identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures.

4.4.1 Dimensional inspection of stock specimen.-Fifteen (15) measurements shall be taken on each sample specimen of the .115, .030 and .0814 dimensions (Dwg D-8840345). There shall be three (3) points of measurement across the width of the specimen at five (5) places along the length. The spacing of the readings shall be approximately uniform. One measurement of each of the three (3) above dimensions shall be taken at each of the fifteen (15) measuring points on the specimen. Determination of the .030 dimension may be made either directly or indirectly. The indirect determination may be the difference between the direct measurement of the web thickness and the .115 dimension. An average value for each dimension on each specimen shall be calculated from the measurements obtained. One (1) copy of production data shall be forwarded on a monthly basis to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

4.4.1.1 Die control.-Measurements shall be taken as specified in 4.4.1 with the addition of the .010R, max and .068 dimensions.

4.4.2 Internal air pressure of top and bottom cup assembly (prior to internal coating).-The top and bottom cup assembly shall be placed in a fixture as specified on the Equipment List and the air pressure specified in 3.3 applied. This is a non-destructive test. Assemblies so tested may be returned to the lot.

4.4.3 Pull test of locating lug welds.-The top and bottom cup assembly shall be placed in a fixture specified on the Equipment List and the pull specified on Dwg D-8840341 shall be applied. This is a non-destructive test. Parts so tested may be returned to the lot.

4.4.4 Strength of weld of top and bottom cup assembly (as applicable).-The top and bottom cup assembly shall be placed in a fixture specified on the Equipment List and the load specified in 3.4 applied. Observation shall be made for evidence of cracks or shearing of the welded area around the assembly. This is a destructive test. Parts so tested shall not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

4.4.5 Salt spray test of top and bottom cup assembly.-The assemblies selected shall be subjected to the salt spray test in accordance with Dwg D-8840341 and ASTM standard method B 117-64. The sodium chloride solution shall be as specified on the applicable drawing. This is a destructive test. Assemblies so tested shall not be returned to the lot.

4.4.6 Hardness of obturator.-The obturator shall be subjected to the Rockwell hardness test in accordance with ASTM test method E 18-67. This is a non-destructive test. Parts so tested may be returned to the lot.

4.4.7 Torque of obturator crimp on bottom cup assembly or on top and bottom cup assembly.-The bottom cup assembly shall be placed in a fixture specified on the Equipment List and the torque specified on Dwg C-8840344 applied. This is a non-destructive test. Assemblies so tested may be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level C.-Top and bottom cup assemblies shall be preserved and packaged in accordance with MIL-STD-1169.

5.2 Packing.

5.2.1 Level C.-Top and bottom cup assemblies, preserved and packaged as specified in 5.1.1, shall be packed in accordance with MIL-STD-1169.

5.3 Marking.-Marking of cartons and boxes shall be in accordance with Army Regulation AR 380-55 and MIL-STD-1169.

5.4 Shipping.-When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples. (when spec requires first article sampling).

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.

mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (see 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 3. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:05Z
Check the source to verify that this is the current version before use.