MIL-T-52582A(ME)
20 September 1972
SUPERSEDING
MIL-T-52582(ME)
2 August 1967

MILITARY SPECIFICATION

FOR

TREEDOZERS, TRACTOR MOUNTING

1. SCOPE

1.1 Scope. This specification covers hydraulic-operated treedozers and components for mounting on crawler tractors.

1.2 Classification. Treedozers shall be of the following types as specified (see 6.2):

Type I - Angle blade.
Type II- V-blade or off-set V-blade.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

Federal

WW-C-633	- Couplings, Hose: (Half), Pneumatic, Universal Type.

Military

MIL-P-514	- Plates, Identification, Instruction and Marking Blank.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-T-3351	- Tractor, Full-Tracked, Low Speed; Tractor, Wheeled, Agriculture; and Tractor, Wheeled Industrial: and Their Attachments, Packaging of.
MIL-F-3541	- Fittings, Lubrication.
MIL-C-10924	- Grease, Automotive and Artillery.
MIL-D-43095	- Dispensing Pump, Hand Driven, Piston Type.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.

STANDARDS

Military

MIL-STD-448 - Test Methods for Construction and Industrial Machinery.

(Copies of specifications and standards required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

SOCIETY OF AUTOMOTIVE ENGINEERS

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, 485 Lexington Avenue, New York, NY 10017.)

NATIONAL BUREAU OF STANDARDS

Handbook H28 - Screw-Thread Standards for Federal Services.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

AMERICAN WELDING SOCIETY

Standard Qualifications Procedure.

(Application for copies should be addressed to the American Welding Society, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Boiler and Pressure Vessel Code.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

DEPARTMENT OF THE ARMY

SC-4940-97-CL-E05 - Department of the Army Supply Catalog - Shop Equipment, Contact Maintenance, Truck Mounted.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to Commanding Officer, U.S. Army Adjutant General, Publications Center, 1655 Woodson Road, St. Louis, MO 63114.)

3. REQUIREMENTS

3.1 Description. Each treedozer shall consist of a blade (moldboard, push arms, pushbar, cutting edge, splitting point, and web), heavy-duty cab assembly, engine side guards, louvered radiator guard, remote air intake (see 3.7.4), water pump, pneumatic grinder, and hydraulic cylinder guards. The treedozer shall withstand heavy tree splitting, cutting and windrowing operations without damage or permanent deformation. The treedozer shall be attachable, without alteration, to the tractor on which it is intended to be mounted. Treedozer push arms shall mount on the outside of the track frame. The type I treedozer shall be an angle blade and the type II treedozer shall be a V-blade or off-set V-blade. The treedozer shall be designed for mounting on a crawler tractor of the make, model, and serial number range, as specified (see 6.2), without interfering with the intended use of the tiedown and lifting attachments on the tractor.

3.2 First article (preproduction model). The supplier shall furnish a treedozer for examination and test within the time frame specified (see 6.2) to prove, prior to starting production, that his production methods and choice of design detail will produce treedozers and components that comply with the requirements of this specification. Examination and tests shall be as specified in section 4 and, unless otherwise specified herein, all examination and tests shall be conducted by the supplier, subject to the surveillance and approval by the Government (see 6.3). When specified (see 6.2), the Government will conduct any or all of the preproduction model examination and tests as specified, (see 6.2).

3.3 Initial production. When specified (see 6.2), the supplier shall furnish to the Government one or more treedozers for examination and test as specified in 4.4.

3.4 Material. Material shall be as specified herein. Material not specified shall be selected by the supplier and shall be subject to all the provisions of this specification. Welding procedures and identification of high strength steel shall be included in the technical publications (see 6.4).

3.4.1 Threaded parts. Threaded parts shall be in accordance with Handbook H28. All capscrews, bolts, and nuts shall be SAE grade 5 or 8 and shall be so marked.

3.5 Maintainability. All major assemblies and installed attachments shall be accessible for maintenance, repair and replacement without the removal of other major assemblies and installed attachments. Ease of maintenance provisions shall incorporate features insuring operating tool and lubrication component clearances and shall facilitate maintenance and

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.

and servicing operations at low temperatures. Dimensions of hand-access openings shall be in accordance with SAE J925. Each maintenance, assembly, or disassembly operation performed as a result of testing in accordance with 4.7 shall be accomplished by two men using tools as provided in Supply Catalog 4940-97-CL-E05 and special tools furnished with the treedozer. The ratio of the man-hours of maintenance required to the hours of operation performed shall not exceed 0.25. The man-hours of maintenance shall be based on man-hours consumed in performing all preventative and corrective maintenance, excluding daily checks and services, performed at operational, organizational and direct support levels. The maintenance ratio shall be computed by dividing the man-hours of maintenance by the total operating hours. After completion of any maintenance operation, the treedozer shall operate as specified herein. Maintenance on the tractor shall not be impeded after installation of the treedozer. A hoist and hoist operator may be used as necessary.

3.6 Characteristics. The treedozer blade with all related blade components for mounting on the tractor shall weigh not less than 7,000 pounds. This weight shall not include the treedozer components specified in 3.7. The treedozer shall withstand impact loads without permanent deformation.

3.7 Components.

3.7.1 Heavy duty cab assembly. The cab assembly shall be heavy duty, tractor frame mountable and shall protect the operator and tractor from falling trees and limbs. The assembly shall consist of vertical posts, two side panels, a rear panel, top, front sweep assembly and front and rear mounting brackets with deflector plates and support between the front mounting brackets. The cab shall be of sufficient size to extend to the outside of the fenders in width and from behind the fuel tank to front edge of fenders in length. All posts and bracing shall be square tubing not smaller than 4 inches square.

3.7.1.1 Side and rear panels. The right and left panels shall be not less than 1/4 inch thick and shall extend not less than 27 inches above the operator's compartment deck. When it becomes necessary to hinge any portion of either side panel for clearance or tractor maintenance, a means shall be provided to secure the hinged portion in an open position. The rear panel shall be not less than 3/8 inch thick and shall extend not less than 18 inches above the operator's compartment deck. The remaining side and rear openings of the cab shall be enclosed with steel wire mesh having square openings and made of wire not less than 1/2 inch in diameter and on 2-1/2-inch centers; except means shall be provided for fueling the tractor from the rear. Both sides of the cab shall be reinforced with not less than two 4-inch square tubing diagonal braces. These braces shall extend from the solid panel at the front and rear to the top panel member approximately 1/3 of the length from each end.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.

3.7.1.2 Deflector plates and support. The two front supports of the cab shall be connected by a horizontal steel pipe not less than 2-1/2 inches in diameter with the top of the pipe not less than 17 inches above the tractor fenders. The pipe shall be located as far forward as possible under the steering-clutch-control-lever housing and shall not interfere with the operation of any controls. Steel plates not less than 3/8 inch thick with the top 4 inches pitched forward at a 45 degree angle shall enclose both forward sides of the operators compartment extending from the floor plates to the top of the pipe. The top of each steel plate shall be attached to the horizontal pipe in such a manner as to form a "step" between the pipe and the 45 degree portion of the steel plate.

3.7.1.3 Front sweep guards. Not less than two 4-inch-square-tubing longitudinal braces, pinned or bolted, shall extend from the cab top to the top of the radiator guard. The longitudinal braces shall be cross braced and all openings between the braces shall be covered with steel wire mesh as specified in 3.7.1.1 securely welded to all braces and cross braces. A clear opening of 10 inches shall be maintained between the front crossbrace and the radiator mounting provisions.

3.7.1.4 Cab top. The cab top shall be of the arched type (right to left or front to rear), constructed of two steel plates, each not less than 3/16 inch thick with vertical reinforcing between the plates, to form a reservoir having a capacity of not less than 50 gallons. The inside of the reservoir shall be coated to prevent corrosion. Provisions shall be included for filling the reservoir. The filler opening shall be not less than 4 inches in diameter, recessed or protected (to prevent damage), and shall be located to allow filling of the reservoir from the rear of the tractor. The filler cap shall be removable without the use of tools, and shall be captive chained with a brass or noncorrosive material chain. A screen shall be furnished in the filler opening to prevent entry of dirt or debris. The reservoir shall be vented and shall prevent water from sloshing out of vent holes during operation. Draining facilities shall be provided to assure 95-percent drainage of water when tractor is on a 5-percent slope on any axis. The bottom of the cab top shall be not less than 42 inches from the top of the operator's seat cushion when the seat is raised to its full height.

3.7.1.5 Exhaust expeller. Means shall be provided to expel all exhaust smoke through a box opening in the top of the cab or front sweep guard. The box shall be of welded steel plate, large enough to allow proper operation of the exhaust rain cap, and shall extend down the exhaust stack a sufficient distance to prevent exhaust smoke from entering the operators compartment. The box shall protect the exhaust rain cap when fully open.

3.7.2 Engine enclosures. A perforated hood, when specified (see 6.2), and perforated-heavy gage engine side guards to completely enclose and

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.

protect the engine shall be furnished. All hydraulic cylinder lines that are not protected by the engine side guards shall be redesigned so as to be protected by these guards. The engine side guards shall have access doors for maintenance of the engine compartment. All doors or openings shall have adequate hinging and locking devices for opening and fastening the doors.

3.7.3 Louvered radiator guard. A louver type radiator guard shall be furnished that will not decrease the airflow below that of the radiator guard furnished on the tractor. Each louver shall be steel plate not less than 5/8-inch thick and 5 inches wide. Each louver shall be positioned at a 45-degree angle with the leading edge up and held in place by 3 steel rods not less than 1 inch in diameter, running vertically thru the center of each louver. The louvered guard shall be attached in front of the standard radiator grill guard in such a manner as to allow it to swing to one side and not interfere with opening of standard radiator grill guard or the hydraulic cylinder guards when installed. The louvered guard shall be of sufficient length to protect and cover the radiator grill guard of the tractor. The guard shall fit as close as possible to the contour of the radiator guard to prevent debris from falling behind the guard or tree limbs from being jammed under the guard.

3.7.4 Remote air intake. When specified (see 6.2), a remote air intake shall be provided. The capacity of the remote air intake shall equal or exceed the capacity of the standard air intake. The intake end of the remote air intake shall be screened with the same size screen as used on the standard tractor air intake. When mounted, the remote air intake shall have at least 1-1/2 inches of clearance between lowest extremity of the remote air intake and the hood. The mounting shall not interfere with the operation of any control or restrict the operator's visibility of any instrument or device on the tractor which requires frequent checking for satisfactory operation of the tractor. The rear of the air intake shall be parallel with the instrument panel and mounted to the firewall utilizing the rear hood bolts on the tractor.

3.7.5 Water pump. A hand operated water pump conforming to MIL-D-43095, including 25 feet of 5/8 inch ID reinforced neoprene hose with reuaable fittings and a pistol grip type water nozzle shall be provided inside the cab. A 90-degree throw-lever, shut-off valve shall be installed between the water tank and water pump. The water pump shall be securely mounted in the extreme right front corner of the cab and shall be readily accessible to the operator. Location of the pump shall not interfere with the operator mounting or dismounting from the cab. A rack shall be provided inside and on the right side of the operator's compartment for storage of the hose.

3.7.6 Hydraulic dozer cylinder line guards. All hydraulic lines on the dozer lift cylinders of the tractor shall be protected by steel guards

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the currentversion before use.

capable of withstanding all forces imposed during heavy land clearing operations. The guards shall be of the bolt-on type and shall be removable. The existing hardware and components on the hydraulic dozer cylinders shall not be used for mounting of these guards.

3.7.7 Pneumatic grinder. A pneumatic rotary vertical grinder with 10 replaceable grinding wheels and of sufficient power and speed rating to sharpen the cutting edge(s) and splitter point within a period of 1 hour shall be furnished with each treedozer. The grinder shall not require an air supply in excess of 90 psi at a flow of 125 cfm. The grinder shall be equipped with a 50-foot-length of 3/4-inch-diameter hose equipped with couplings conforming to WW-C-633, type II or type III.

3.8 Performance. The treedozer, when mounted on the Government-loaned tractor (see 3.12), shall cut, clear, and windrow a uniform covering of trees and brush for a period of 500 hours at the rate of 0.35 acre/hour. The land to be cleared shall contain not less than 400 trees, 2 inches and over in diameter, per acre. The tree diameter shall be measured at breast height. Four percent of the trees shall be over 12 inches in diameter, 4 percent from 8 to 12 inches in diameter, 8 percent from 6 to 8 inches in diameter, the remainder may be under 6 inches in diameter.

3.9 Lubrication.

3.9.1 Lubrication fittings. Lubrication fittings shall conform to MIL-F-3541, type I, II, or III. Fittings shall be located in a protected position and shall be accessible to a hand-operated grease gun.

3.9.2 Delivery lubrication service. When delivered, grease lubrication shall be with grease conforming to MIL-G-10924.

3.10 Identification marking. The treedozer shall be identified by identification plates conforming to MIL-P-514, type I, style 4, composition C, of type I, grade A, class 1 material.

3.11 Treatment and painting. The portions of the treedozer and its components normally painted shall be cleaned, treated, and painted in accordance with MIL-T-704, type A.

3.12 Government-loaned property. The following property in the quantities indicated will be loaned by the Government (see 6.6):

Item No.	Description	Identification	Quantity
1	Tractor, Full Tracked, Low Speed, Medium DBP, With Winch.	FSN 2410-990-6469 (Make, model, and serial number range shall be as specified (see 6.2))	1

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.

3.13 Type I, angle blade. The type I treedozer blade shall conform to table I.

Table I. Characteristics

	Dimensions
Blade angle, minimum (degrees).	25
Blade tilt, minimum (degrees).	15
Blade pitch, minimum (degrees).	9
Blade height, overall (with pushbar), minimum (inches).	60

3.13.1 Push arms. The treedozer blade push arms shall be of heavy, box section construction and shall connect the moldboard to the track frame of the tractor. The push arms shall be in the form of a yoke or C-frame and shall have strength to resist, without permanent deformation, all stresses caused by all operations as specified herein.

3.13.2 Moldboard. The moldboard shall perform as specified herein when used either as a tree cutter or for windrowing the cut material. The bottom of the moldboard shall be fastened to the push arms or yoke through pivot arrangements. The top of the moldboard shall be supported at both ends by adjustable struts extending from the moldboard to the push arms. The top of the moldboard shall be adjustable forward and backward. The moldboard shall be provided with a cutting edge extending the full width of the moldboard, a splitting point with a connecting web, and a square tubular pusher bar above and extending the full length of the moldboard to direct the fall of the trees. There shall be no openings between the pusher bar and top of the moldboard except that a 10-inch opening shall be provided on the left side for operator visibility.

3.14 Type II, V-blade or off-set V-blade. The type II treedozer blade shall consist of push arms and moldboard with two cutting edges joined together to form either a V or offset-V configuration. The blade shall be capable of being disassembled for transporting.

3.14.1 Push arms. The push arms shall be of heavy box section construction and shall connect the moldboard to the track frame of the tractor. The push arms shall have strength to resist without permanent deformation all stresses caused by operations as specified herein.

3.14.2 Moldboard. The moldboard shall perform as specified herein when used as a tree cutter or for windrowing the cut material. The moldboard

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

shall be fastened to the push arms as an integral portion or by pivot arrangements. The moldboard shall be provided with serrated hardfaced cutting edges, a splitter point, and square tubular pushbars above and extending the full length of the moldboard to direct the fall of trees. All openings between the pusher bars and top of the moldboard shall be filled in. The overall height of the treedozer blade including the push-bar shall be not less than 48 inches.

3.15 Safety and human factors.

3.15.1 Safety. The operator shall be adequately protected from falling trees and tree limbs.

3.15.2 Human factors. The characteristics of the tree dozer and its protective cab shall provide for use by personnel ranging from the small man (5th percentile) clothed, through the large man (95th percentile) arctic clothed, in accordance with SAE J833.

3.16 Workmanship. The treedozer shall be free from defects such as incomplete welds, rust, cracks, and other defects that could impair its operation or serviceability.

3.16.1 Steel fabrication. Steel used in the fabrication of the tree-dozers shall provide original quality surface finish and shall be free from kinks and sharp bends. Steel having corroded surface is not acceptable. The straightening of material shall be done by methods that will not cause injury to the metal. Shearing and clipping shall be done neatly and accurately. Corners shall be square and true, and all sharp edges and burrs shall be removed. Burned surfaces of flamecut material shall be free of burrs, sharp edges, and slag. Precautions shall be taken to avoid over-heating, and heated metals should be allowed to cool slowly except where heat treatment is required. All bends of a major character shall be made with metal dies or fixtures to insure uniformity of size and shape.

3.16.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided. All bolts, nuts, and screws shall be tight and correctly torqued. Devices securing bolts or capscrews shall be of sufficient strength to withstand a force equal to the tensile strength of the bolt.

3.16.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall completely fill the holes. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.

3.16.4 Welders and welding.

3.16.4.1 Welders. Before assigning any welder to manual welding work covered by this specification, the supplier shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operation to be performed and that such qualification is effective as defined by the particular code:

Standard Qualification Procedure of the American Welding Society.
Welding Qualification of the ASME Boiler and Pressure Vessel Code.

3.16.4.2 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, and other foreign matter. Welds shall transmit stress without permanent deformation or failure when the parts connected by the welds are subjected to proof and service loadings.

3.16.5 Machine work. Tolerances and gages for metal fits shall conform to the limitations specified herein.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. The supplier is responsible for assuring that components and materials used are manufactured, examined, and tested in accordance with the requirements of referenced specifications and standards.

4.2 Classification of inspection. Inspection shall be classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.5).
(d) Inspection comparison (see 4.8).
(e) Inspection of preparation for delivery (see 4.9).

4.3 Preproduction inspection. The treedozer shall be mounted on the Government-loaned tractor (see 3.12).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

4.3.1 Examination. Prior to being tested, the treedozer shall be examined for the defects marked "X" in column 1 of table II. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. Upon successful completion of the examination specified in 4.3.1, the treedozer shall be subjected to the tests marked "X" in column 1 of table III. Failure of any test shall be cause for rejection.

4.3.3 Post-test examination. Upon completion of all tests, the treedozer shall be examined for major structural defects, cracked welds and sheared bolts. Presence of one or more defects shall be cause for rejection.

4.4 Initial production inspection. When specified (see 3.3), one or more initial production treedozer(s) will be selected at random by the Government from treedozers being produced from production tooling and will be examined for the defects marked "X" in column 2 of table II and subjected to the tests marked "X" in column 2 of table III to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site or sites selected by the Government. Acceptance of an initial production treedozer shall not exclude the remaining treedozers from the quality conformance inspection and acceptance provisions specified in section 4.

4.4.1 Inspection failure. Failure of an initial production treedozer to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production treedozer and shall be cause for refusal by the Government to continue acceptance of production treedozers until evidence has been provided by the supplier that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the supplier at no cost to the Government on treedozers previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all treedozers accepted prior to the completion of initial production inspection are similarly deficient unless evidence to the contrary is furnished by the supplier and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Examination. Each treedozer shall be examined for the defects marked "X" in column 3 of table II. Presence of one or more defects shall be cause for rejection.

4.5.2 Test. One out of every 20 treedozers or major fraction thereof shall be tested as specified in 4.7.2 Failure of the test shall be cause for rejection of the lot.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the currentversion before use.

4.6 Inspection schedule.

4.6.1 Examination. Examination shall be in accordance with table II.

Table II. Examination schedule.

Preproduction	Initial Production	Individual	Defect	Requirement Paragraph
1	2	3	4	5
X	X	-	101. Material not as specified.	3.4
X	X	-	102. Threaded parts not in accordance with Handbook H28.	3.4.1
X	X	-	103. Parts and components not accessible.	3.5
X	X	-	104. Parts not interchangeable.	3.5
X	X	-	105. Dimensions and weight not as specified.	3.6 and 3.7
X	X	-	106. Heavy duty cab assembly not as specified.	3.7.1
X	X	-	107. Engine enclosures not as specified.	3.7.2
X	X	-	108. Louvered radiator guard not as specified.	3.7.3
X	X	-	109. Remote air intake not as specified.	3.7.4
X	X	-	110. Water pump not as specified.	3.7.5
X	X	-	111. Hydraulic dozer cylinder line guards not as specified.	3.7.6
X	X	-	112. Pneumatic grinder not as specified.	3.7.7
X	X	X	113. Lubrication and lubrication fittings not as specified.	3.9
X	X	X	114. Identification marking not as specified.	3.10
X	X	X	115. Treatment and painting not as specified.	3.11
X	X	-	116. Type I treedozer not as specified.	3.13

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

Table II. Examination schedule (cont'd)

1	2	3	4	5
X	X	-	117. Type II treedozer not as specified.	3.14
X	X	X	118. Workmanship not as specified.	3.16
X	X	X	119. Assembly not correct or incomplete.	Section 3
X	X	X	120. Parts or components missing or do not function.	Section 3
-	X	X	121. Material not of same quality as used on preproduction model.	Section 3

4.6.2 Tests. Tests shall be in accordance with table III.

Table III. Test schedule

Preproduction	Initial * Production	Production	Tests	Test Paragraph
1	2	3	4	5
X	(X)	-	Test conditions.	4.7.1
X	(X)	X	Mounting and operating.	4.7.2
X	(X)	-	Horizontal rigidity.	4.7.3
X	(X)	-	Sharpening of cutting edge(s) and splitter point.	4.7.4
X	(X)	-	Performance.	4.7.5
X	(X)	-	Maintainability.	4.7.6

* Tests marked "(X)" will not normally be duplicated during the Initial Production Test when successfully passed during the Preproduction Test conducted by the Government.

4.7 Test procedure.

4.7.1 Test conditions. All test apparatus shall be accurate within the limits specified in MIL-STD-448, section 6, except as specified herein. Throughout the test evaluate safety and human factors considerations in accordance with 3.15.

4.7.2 Mounting and operation. Mount the treedozer on the Government-loaned tractor. Operate the treedozer through 10 complete movement cycles of raise and lower. Incorrect mounting, evidence of interference with the tractor, or malfunction of the treedozer shall constitute failure of this test.

4.7.3 Horizontal rigidity. Mount the treedozer on the tractor and raise the blade 24 to 30 inches above ground level. With the tractor traveling

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the currentversion before use.

full speed in second gear, cause the splitting point to contact a large tree or similar wooden object of sufficient size to stop the tractor. The tractor transmission shall not be disengaged prior to impact. Conduct the test a minimum of five times. Evidence of breakage or permanent deformation of the treedozer shall constitute failure of this test.

4.7.4 Sharpening of cutting edge(s) and splitter point. The cutting edge(s) and splitter point of the moldboard shall be sharpened in 1 hour using the pneumatic grinder specified in 3.7.7, after a minimum of 8 hours tree cutting. Inability to sharpen the cutting edge(s) and splitter point in allotted time shall constitute failure of this test.

4.7.5 Performance. With the treedozer mounted on the tractor, clear land as specified in 3.8 and pile the cleared material into windrows not less than 150 feet apart for a period of 500 hours. The cutting edge, and splitting point shall not be sharpened more than once for each 8 hours of operation. Failure to clear land and pile material at the rate specified in 3.8 or damage to or breakage of the treedozer shall constitute failure of this test.

4.7.6 Maintainability. Maintenance operations required during testing shall be accomplished in accordance with the maintenance rates specified in 3.5. Nonconformance to 3.5 shall constitute failure of this test. During the test, maintenance support elements such as manuals, lubrication charts, repair parts, special tools shall be evaluated. Inability of the treedozer to be properly maintained utilizing the support elements shall constitute failure of this test and shall require revision of the document(s). Errors or inadequacies in the document(s) shall not be considered in assessing the maintenance ratio.

4.8 Inspection comparison. The Government may select treedozers at any time during the contract production period and subject these treedozers to the examinations specified in column 2 of table II and to the tests specified in column 2 of table III to determine that the quality of the selected treedozer is equal to the quality standards established during initial production inspection. The inspection will be performed by the Government at a site selected by the Government. Treedozers will be selected at random from those which have been accepted by the Government and will not include the previously inspected preproduction model and initial production treedozers.

4.8.1 Inspection failure. Failure of any treedozer to meet any requirement specified herein during and as a result of the tests specified in 4.7 shall be cause for rejection of the treedozer and shall be cause for refusal by the Government to continue acceptance of production treedozers

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.

until evidence has been provided by the supplier that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the supplier at no cost to the Government on treedozers produced and accepted under the contract since approval of the initial production treedozer. Any deficiencies found as a result of inspection comparison inspection will be considered prima facie evidence that all treedozers accepted after approval of the initial production treedozer are similarly deficient unless evidence to the contrary is furnished by the supplier and such evidence is acceptable to the contracting officer.

4.9 Inspection of preparation for delivery. The preservation, packaging,packing and marking of the treedozer components shall be examined and tested to determine compliance with the Quality Assurance Provisions of MIL-T-3351.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging,packing and marking. The components comprising a complete treedozer shall be preserved, packaged, packed and marked in accordance with MIL-T-3351, as specified for tractor attachments. The level of preservation and packaging shall be level A, B, or C and the level of packing shall be level A, B, or C, as specified (see 6.2). When level A or B preservation and packaging is specified the interior surfaces of the water pump and pneumatic grinder shall be coated with preservative as specified for priming pumps in MIL-T-3351.

6. NOTES

6.1 Intended use. Treedozers covered by this specification are intended for treecutting, underbrush removal, and for piling the material into windrows for disposal.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Type treedozer required (see 1.2).
(c) Make, model, and serial number range of tractor on which treedozer is to be mounted (see 3.1 and 3.12).
(d) Time frame required for submission of the preproduction model (see 3.2).
(e) When the Government will conduct any or all of the preproduction model examination and tests. When the Government will conduct some but not all of the preproduction examination and tests, the contracting officer should specify which examination and tests

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

will be conducted by the Government, and which examination and tests shall be conducted by the supplier (see 3.2).
(f) When initial production inspection is required and the number of treedozers to be furnished (see 3.3).
(g) When a perforated hood is required (see 3.7.2).
(h) When a remote air intake is required (see 3.7.4).
(i) Level of preservation and packaging and level of packing required (see 5.1).

6.3 Preproduction model. Any changes or deviations of production treedozers from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the supplier of his obligation to furnish treedozers conforming to this specification. The supplier shall provide a written report to the contracting officer covering all deficiencies, malfunctions, and test failures. This report shall be presented within 48 hours from time of failure and shall describe components and parts affected, both directly and indirectly corrective action taken or to be taken by the supplier and the supplier's proposed method of proving the adequacy of the corrective action.

6.4 Data requirements. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and supplier's maintenance and operation manual to be furnished with each treedozer.

6.5 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment of treedozers. "Shipment of treedozers shall include repair parts, maintenance tools, operational instructions, and accessories, unless exceptions are provided elsewhere in the contract."

6.6 Government-loaned property. The contracting officer should arrange to loan the property specified in 3.12.

Custodian:

Army - ME

Preparing activity:

Army - ME

Project No. 3830-A130

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
U. A. ARMY MOBILITY EQUIPMENT COMMAND
RESEARCH, DEVELOPMENT AND ENGINEERING DIRECTORATE
ATTN: AMSME-RZD
FORT BELVOIR, VIRGINIA 22060

OFFICIAL BUSINESS

POSTAGE AND FEES PAID

DEPARTMENT OF THE ARMY
U. S. ARMY MOBILITY EQUIPMENT COMMAND
RESEARCH, DEVELOPMENT AND ENGINEERING DIRECTORATE
ATTN: AMSME-RZD
FORT BELVOIR, VIRGINIA 22060

FOLD

D—30,455—Ft Belvoir

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:26Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION MIL-T-52582A(ME) Treedozers, Tractor Mounting

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426 REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:26Z
Check the source to verify that this is the current version before use.