INCH-POUND

MIL-B-44418(GL)
28 June 1991

MILITARY SPECIFICATION

BOOT WALL, FABRIC ASSEMBLIES,

STANDARDIZED INTEGRATED COMMAND POST SYSTEM (SICPS)

This specification is approved for use by the Natick Research, Development, and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers five types of boot walls.

1.2 Classification. The boot wall shall be of the following types and classes as specified (see 6.2).

Type I - SICPS, M577 Tracked Command Post Boot Wall
Type II - SICPS, Rigid Wall Shelter (RWS) Boot Wall
Type III - SICPS, M1037, S250/G Boot Wall
Type IV - SICPS, M1037, S250E Boot Wall
Type V - SICPS, M998, M1038 Troop - Cargo Carrier Boot Wall

Class 1 - Green
Class 2 - Desert tan

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be used in improving this document should be addressed to: U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5017 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 8340

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

FEDERAL

A-A-50083	-	Bag, Plastic, Folded Garment
DDD-L-20	-	Label: For Clothing, Equipage, and Tentage, (General use)
PPP-B-601	-	Boxes, Wood, Cleated-Plywood
PPP-B-636	-	Boxes, Shipping, Fiberboard

STANDARDS

FEDERAL

FED-STD-601	-	Rubber: Sampling and Testing
FED-STD-751	-	Stitches, Seams and Stitchings

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables For Inspection by Attributes
MIL-STD-129	-	Marking For Shipment and Storage
MIL-STD-147	-	Palletized Unit Loads
MIL-STD-731	-	Quality of Wood Members For Containers and Pallets

(Unless otherwise indicated, copies of federal and military specifications, standards and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein Unless otherwise specified, the issues are those cited in the solicitation.

DEPARTMENT OF THE ARMY FIELD MANUAL

FM 10-16 - General Repair of Tents, Canvas and Webbing

(Copies of documents required by contractors in connection with the specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

DRAWINGS

U.S. ARMY NATICK RESEARCH, DEVELOPMENT, AND ENGINEERING CENTER

5-4-7409 - Boot Wall, Assembly, S250/G

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

5-4-7484 - Boot Wall, Assembly, M577, SICPS
5-4-8183 - Boot Wall, Assembly, Rigid Wall Shelter
5-4-8213 - Boot Wall, Assembly, S250E
5-4-8456 - Boot Wall, Assembly, Soft Top

(Copies of drawings are available from the U.S. Army Natick Research, Development, and Engineering Center, ATTN: STRNC-UXT, Natick, MA 01760-5017.)

2.2 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3951 - Standard Practice for Commercial Packaging

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103-1187.)

(Non-Government standards and other publications are normally available from organizations that prepare or distribute the documents. These documents also
may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.2 Materials and components. The materials and components used shall conform to the applicable referenced specifications, standards, and requirements specified herein. Where materials are not definitely specified, they shall be of the quality normally used by the manufacturer in his standard commercial practice provided the completed items comply with all provisions of this specification. It is encouraged that recycled material be used when practical as long as it meets the requirements of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

3.2.1 Alternate components. Components offered as equivalent to components specified hereinafter and on the referenced drawings as a specific manufacturer's part or model number or equal, shall be functionally equal to the manufacturer's model number identified, and of equal or better quality. The incorporation and inclusion of such a component in the design of the specified end product shall not require modification or change to any other specified component, and shall not reduce ease of maintenance to it or any other components, unless such modification or change is specially approved by the contracting officer. Prior to the manufacture of the first article, or if none is required, prior to commencing production, the contractor shall submit for the contracting officer's approval, a list identifying each component, together with proof that each listed component complies with requirements specified above. The contracting officer, at his option, may require a sample of the proposed substitution. Approval of the submitted listing, together with the necessary supporting data, authorizes commencement of manufacture but does not relieve the contractor of responsibility that these components perform in accordance with specified requirements when incorporated into the end product.

3.3 Design and construction.

3.3.1 Boot Wall type.

3.3.1.1 Type I. The design and construction for the type I boot wall shall conform to Drawing 5-4-7484 and all subsidiary drawings and parts lists and as specified herein.

3.3.1.2 Type II. The design and construction for the type II boot wall shall conform to Drawing 5-4-8183 and all subsidiary drawings and parts lists and as specified herein.

3.3.1.3 Type III. The design and construction for the type III boot wall shall conform to Drawing 5-4-7409 and all subsidiary drawings and parts lists and as specified herein.

3.3.1.4 Type IV. The design and construction for the type IV boot wall shall conform to Drawing 5-4-8213 and all subsidiary drawings and parts lists and as specified herein.

3.3.1.5 Type V. The design and construction for the type V boot wall shall conform to Drawing 5-4-8456 and all subsidiary drawings and parts lists and as specified herein.

3.3.2 Fusing of ends of synthetic cord, webbing and tape. All ends of synthetic cord, webbing and tape shall be fused. The apparatus used to fuse the cord, webbing, and tape ends shall be capable of providing sufficient heat to provide a smooth edge with the cut ends of the cord, webbing and tape yarns all fused together. Fusing of the cord, webbing and tape shall be accomplished prior to being assembled for stitching.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

3.3.3 Stitching, machine.

3.3.3.1 Types of stitching. All stitch types, except bartacking, shall conform to FED-STD-751 as follows:

For all stitching except zig-zag stitching and stitching indicated by "Z" on drawings	-	Type 301, 5 to 7 stitches per inch
For stitching indicated by "Z" on drawings	-	Type 401, 5 to 7 stitches per inch
	-	Chain portion of stitching shall not appear on outside of tent or cover
For bartacking	-	Bartack, length as specified on drawings 1/8 inch in width (bight) and shall be free of thread breaks and loose stitching

3.3.3.2 Thread breaks. Thread breaks in stitching shall be overstitched not less than 1 inch at each break on stitch type 301; and not less than 1-1/2 inches at each break on stitch type 401. Thread breaks, in type 401 shall be overstitched with stitch type 301. Thread breaks noted during inspection shall be repaired by overstitching the existing stitching starting from a distance of 1 inch beyond the break, across the defective area, to a distance of 1 inch beyond the break. The ends of repair stitching are not required to be backstitched.

3.3.3.3 Stitching ends. The ends of type 301 stitching shall be overstitched not less than 1 inch except where ends are turned under in a hem or held down by other stitching. Where 301 stitching is performed automatically on stitch patterns such as box, box with cross-stitch, "W" stitching or straight line tacking, at least three tying, overlapping, or back stitches shall be used to secure the ends of stitching.

3.3.3.4 Skipped stitches. Two or more consecutively skipped stitches occurring in types 301 stitching shall be overstitched not less than 1 inch. Any skipped stitches in type 401 stitching shall be overstitched not less than 1-1/2 inches. Skipped stitches in 401 stitching shall be overstitched with type 301 stitching. Skipped stitches noted during inspection shall be repaired as specified for thread breaks. (See 3.3.3.2).

3.3.3.5 Lubrication of thread. The addition of any lubrication to the polyester sewing thread prior to or during the sewing operations is prohibited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

3.3.3.6 Automatic stitching. Automatic stitching machines may be used to perform any of the required stitch patterns provided the requirements of the stitch pattern, stitches per inch, size and type of thread are met, and at least three or more tying, overlapping or backstitches are used to secure the ends of the stitching.

3.3.3.7 Thread ends. All thread ends that are visible on the finished item shall be trimmed to a length of not more than 1/2 inch.

3.3.3.8 Stitching margins. Unless otherwise specified, all stitch margins shall be 1/8 inch +1/16 -0 inch.

3.3.4 Splicing of cloth. There shall be no splicing of fabric. The number of panel seams shall not exceed the requirements specified on the applicable drawings.

3.3.5 Setting of grommets. Holes punched to receive the grommets shall be smaller than the outside diameter of the grommet barrel so that the barrel must be forced through the hole. The grommets shall be securely clinched without cutting the materials.

3.3.6 Wicking of sewing thread (cup test). There shall be no wicking of water through the stitching on the boot wall assemblies when they are tested as specified in 4.5.1. The cup test is intended to insure that non-wicking thread has been utilized and that no lubrication has been added to the polyester thread prior to or during the sewing operation. Repairs required as a result of failure of the cup test and when authorized by the contracting officer, shall be performed by treating the exposed stitching on the wall assembly with seam sealant specified in 3.3.7.

3.3.7 Leakage of sealed seams. All exposed stitching on the exterior of the boot walls shall be treated with Kenyon Consumer Products K-Kote Seam Sealer-J (clear) #83-234C or equal (see 6.4). The requirements for infrared reflection does not apply to seam sealant. The fabric surface shall be cleaned so that it is free of dirt and moisture prior to application of seam sealant. Sealant shall be applied with a brush or roller, and shall evenly cover an area 1/2 inch wide on each side and on top of all stitching. There shall be no more than a 10-ml leakage of water through the seams when tested as specified in 4.5.2.

3.3.8 Seam strength. The strength of the seams shall be 80 percent of the fabric strength when tested as specified in 4.5.3.

3.3.9 Repairs to boot walls. No more than one repair to holes, cuts, tears or burn through resulting from the heat sealing operation shall be allowed. Repairs on holes, cuts, tears or burn through not more than one inch in diameter or length shall be performed as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

a. Repairs shall be accomplished by the application of cemented patches. Cemented patches shall be large enough to overlap the damaged area with a margin of at least 3/4 inch on all sides, using cement per Minnesota Mining and Manufacturing 847 or equal (see 6.5).

b. For repairs of burn-through on panel lap seams, the width of the patch shall be such that the overlap on each side of the burn-through shall be equal to the width of the seam.

c. Patches shall be applied to the top side of the assemblies and the patched area shall be smooth, i.e., with the torn or cut edged securely and completely sealed and corners shall have a radius.

3.4 Marking. All markings and labels shall conform to DDD-L-20.

3.4.1 Special markings. The letters "US" and the item nomenclature on the boot wall assemblies shall conform to type IV, class 9 in the size characters and in the locations shown on the drawings. Class 9 markings shall be clearly legible after subjection to accelerated weathering.

3.4.2 Identification label. Identification labels shall conform to type VI, class 6 and shall be 3-1/2 inches by 5-1/2 inches minimum and a blank space of at least 1-1/4 inches shall be provided on the bottom of the label for the Department of Defense inspector's stamp. Identification labels shall be stitched to the tent components in the locations shown on the drawings.

3.5 Workmanship. Cloth components shall be clean and free of holes, cuts, tears, and cloth defects such as multiple floats or broken or missing yarns. Webbing and tape shall not have frayed or scalloped edges and rope components shall be free of cuts and breaks. Thread tension shall be maintained with seams properly sewed so that no runoffs, twists, pleats, or open seams shall result. Care shall be taken in sewing to see that no metal chews occur. All thread ends shall be trimmed to 1/2 inch or less. Metal components shall be free of burns, sharp edges, and corroded areas and shall not be broken or malformed. Heat welded seams shall be free of wrinkles, pleats and folds. A heat welded seam, regardless of its length, shall not have more than a total of two wrinkles, pleats, or folds.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

4.1.1 Responsibility for compliance. All items shall meet all requirements of section 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 Responsibility for dimensional requirements. Unless otherwise specified in the contract or purchase order, the contractor is responsible for ensuring that all specified dimensions have been met. When dimensions cannot be examined on the end item, inspection shall be made at any point or at all points in the manufacturing process necessary to ensure compliance with all dimensional requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3)
b. Quality conformance inspection (see 4.4)

4.3 First article inspection. When a first article is required (see 3.1 and 6.2), it shall be examined for the defects specified in 4.4.3 and 4.4.4 and shall be tested as specified in 4.4.5. Any nonconformance or failure of any test shall be cause for rejection of the first article.

4.4 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this specification or applicable purchase document.

4.4.2 In-process examination. Examination shall be made of the following fabrication operations to establish conformance with specified requirements.

a. There shall be no lubrication of polyester thread prior to or during the sewing operations for compliance with 3.3.3.5.

b. Holes punched to receive grommets are in compliance with 3.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

c. Heat sealing operation shall be monitored. A sample seam specimen of sufficient size to conduct testing in accordance with 3.3.7 shall be produced each time the heat sealing equipment is started and every 300 linear feet of sealed seam there after.

Whenever nonconformance is noted, correction shall be made to the items affected and to the process. When correction cannot be made the item affected shall be removed from the process.

4.4.3 End item visual examination. The end item units shall be examined for the defects listed in table I. The lot size shall be expressed in units of boot walls. The sample unit shall be one boot wall. The inspection level shall be II. The acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 4.0 for major defects and 10 for major and minor A combined and 40 for total (major, minor A and minor B combined) defects.

TABLE I. End item visual defects

Examine	Defect	Classification Major	Minor A	Minor B
Tape, webbing, & synthetic cord	Edge or end frayed or scalloped			301
	Cut or tear			302
Cloth for boot wall assemblies	Cut, tear, or hole (including exposed drill holes) greater than 1/8 inch in length or diameter	101		
	Cut, tear, or hole (including exposed drill holes) 1/8 inch or less in length or diameter:			
	- more than five but less than ten		201	
	- more than ten	102		
Cloth for transport covers	Cut tear, or hole (including exposed drill holes) greater than 1/8 inch in length or diameter		202	
	Cut tear or hole (including exposed drill holes) less than 1/8 inch in length or diameter:			
	- more than ten		203	
	- more than five but less than ten			303
Hardware and metal components	Broken	103		
	Malformed:			
	- fails to perform intended function	104		
	- but will perform intended function		204	

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Hardware and metal components (cont'd)	Corroded area			304
	Burn or sharp edge which may cause injury in handling or damage to fabric	105		
Grommets	Improperly set, two or more teeth exposed (except where grommet is set as specified but is in an area of uneven thickness which prevents uniform clinching			305
	Clinched loosely, allowing grommet to rotate around hole		205	
	Clinched excessively tight; i.e., cutting cloth:	106		
	Insecurely clinched; i.e., grommets or washers become disengaged:	107		
	Grommet set with barrel inserted from top of webbing instead of bottom			306
	Roll of a grommet contains more than three scores (splits)			307
Rope, tent lines, and cord components	Any cut or break:			
	- on eave guy line		206	
	- eye splice omitted		207	
	Eye splice not as specified			308
	Free end not finished as specified			309
Seams and stitching	Open seam on stitch type 301:			
	- for more than 1/4 inch but not more than 1 inch			310
	- for more than 1 inch		208	
	NOTE: A seam shall be classified as open when one or more stitches joining a seam are broken, or when one or more skipped or run-off stitches occur. On double stitched seams, a seam shall be classified as open when either one or both sides of a seam are open.			

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Seams and stitching (cont'd)	Fabric edges caught in stitching:			
	- more than 1 inch but not more than 3 inches			311
	- more than 3 inches		209	
	Thread breaks:			
	- overstitched less than 1-1/2 inches on stitch type 401			312
	- overstitched less than 1 inch on stitch type 301			313
	NOTE: Thread breaks not overstitched shall be classified as open seams.			
	Needle chews resulting in cut, tear or hole (see cut, tear or hole)			
	Skipped stitches:			
	- overstitched less than 1-1/2 inches on stitch type 401		210	
	- overstitched less than 1 inch on stitch type 301 (when two or more skipped stitches occur consecutively)		211	
	NOTE: Skipped stitches not overstitched shall be classified as open seams.			
	One or more required rows of stitching omitted (except on boxstitching)	108		
Heat sealed seams	Open pleated, puckered, burned through, wrinkled, or folded	109		
Box stitching	Incomplete:			
	- one row of stitching omitted			314
	- two or more rows of stitching omitted		212	
	More or less than specified length by more than 1/8 inch			315
Bartacking	More or less than specified length by more than 1/8 inch			316

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Stitching ends	Overstitched less than 1 inch on stitch type 301 or 401 (except where ends are held down by other stitching or turned under in a hem, or where stitching is performed automatically)		213	
	Secured with less than three tying, overlapping, or back stitches when automatic stitching is performed			317
	Secured with less than 1/4 inch of back stitching, overstitching, or an increased number of stitches per inch at the end of stitch type 304			318
Seams	Pleated on boot wall assembly		214	
Seam type	Wrong seam type	110		
Stitch type	Wrong stitch type	111		
Stitch tension	Loose, resulting in an exposed bobbin or top thread for more than 6 inches		215	
	Tight, as evidenced by puckering on fabric for more than 6 inches		216	
Stitches per inch	Less than minimum specified (except on panel joining seams):			
	- one stitch			319
	- two or more stitches		217	
	Less than minimum specified on panel joining seams		218	
	More than maximum specified:			
	- one stitch			320
	- two or more stitches		219	
	NOTE: Variation in the number of of stitches per inch, caused by the operator speeding up the machine and pulling the fabric in order to sew over heavy places or heavy seams or in turning corners, shall be classified as follows:			

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Stitches per inch (cont'd)	a. Within the minor "B" defect classification - no defect			
	b. Within the minor "A" defect classification - minor "B" defect			
Stitching gage	Not as specified		220	
Stitching margin	Larger than specified:			
	- for more than 2 inches but not more than 4 inches			321
	- for more than 4 inches in length		221	
	Less than specified:			
	- for more than 2 inches but not more than 4 inches in length			322
	- for more than 4 inches in length		222	
Stitching	Chain portion of stitching shows on outside of boot wall assemblies		223	
Mends, darns, or patches	Repairs not in accordance with Department of the Army Field Manual FM 10-16 or not authorized by the contracting officer (see 3.3.9)	112		
Components and assembly	Any component part omitted, not assembled or fabricated of applicable referenced material	113		
Hems	Constructed with partial turn under when double turn under is required		224	
	Twisted or pleated			323
Reinforcements	Improperly applied, causing excessive fullness on reinforcements or reinforced parts	114		
Cloth splicing	Splice in boot wall panels	115		
	Splices not joined as shown on applicable drawings			324

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

system of quality program. The absence of any inspection requirements in the

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Marking and labels	Omitted, incorrect, illegible, or misplaced			325
Cleanness	Grease or oil stains			326
	Thread ends not trimmed to 1/2 inch or less			327

4.4.4 End item dimensional examination. The end items shall be examined for the defects listed in table II. The lot size expressed in units of boot walls. The sample unit shall be one boot wall. The inspection level shall be S-3. The AQL, expressed in terms of defects per hundred units, shall be 2.5 for major defects, 10 for major and minor A combined defects, and 40 for total (major, minor A and minor B combined) defects.

TABLE II. End item dimensional defects

Examine	Defect	Classification Major	Minor A	Minor B
Overall dimensions of boot wall	Smaller than specified dimensions less applicable minus tolerances indicated on drawings	101		
	Larger than specified dimensions and applicable plus tolerance indicated on drawings			301
Location dimensions (unless otherwise specified)	Not within specified tolerance: - not exceeding twice the applicable tolerance			302
	- exceeding twice the applicable tolerance		201	
Webbing, tie tapes	Finished length less than specified by more than 1 inch			303
Grommets	Set beyond specified location by more than 1/2 inch		202	
Rope components	Eye on foot stop or line less than specified by more than 1/2 inch			304

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

TABLE II. End item dimensional defects

Examine	Defect	Classification Major	Minor A	Minor B
Rope components (cont'd)	Finished length of guy line less than specified:			
	- by not more than 4 inches			305
	- by more than 4 inches but not more than 12 inches		203	
	- by more than 12 inches	102		
Hems	Required to finish less than 3/4 inch or less in width, less than specified		204	
Reinforcements	Finished dimensions less than specified by more than 1/2 inch		205	

4.4.5 End item testing. The end items shall be tested as specified in 4.5.1, 4.5.2 and 4.5.3. The end items shall be tested as specified in 4.5.4 for the first article test only. The lot size shall be expressed in units of boot walls. The sample size shall be one boot wall. The inspection level shall be S-2. Any test failure shall be cause for rejection of the lot.

4.4.6 Packaging examination. The fully packaged end items shall be examined for the defects listed below. The lot size shall be expressed in units of shipping containers. The sample unit shall be one shipping container fully packaged. The inspection level shall be S-2, and the AQL, expressed in terms of defects per hundred units, shall be 2.5.

Examine	Defect
Markings, (exterior and interior)	Omitted, incorrect, incomplete, illegible; of improper size, location, sequence or method of application
Materials	Any component missing, damaged, or not as specified
Workmanship	Inadequate application of components, such as: incomplete sealing or closure of flap, improper taping, loose strapping or inadequate stapling Bulged or distorted container
Content	Other than specified

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

4.4.7 Palletization examination . The fully packaged and palletized end items shall be examined for the defects listed below. The lot size shall be expressed in units of palletized unit loads. The sample unit shall be one palletized unit load, fully packaged. The inspection level shall be S-1 and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

Examine	Defect
Finished dimensions	Length, width, or height exceeds specified maximum requirement
Palletization	Pallet pattern not as specified Load not bonded as specified
Weight	Exceeds maximum load limits
Marking	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application

4.5 Methods of inspection.

4.5.1 Wicking test. The end item shall be tested once on a boot wall assembly panel feld seam (see 3.3.6). The end item unit shall be laid over a 6 ± 1/8 inch diameter hoop as to form a 1 ± 1/4 inch deep depression with the seam to be tested running through the center of the depression. A 500-ml quantity of water at 77°F ± 4° shall be slowly poured into the depression and the under surface of the seam shall be observed. Any wicking of water along the sewing thread, identified by a discoloration or darkening of the thread within 5 minutes after water is poured, shall be considered a test failure. Water leakage through the needle holes or between the plies of the seamed fabrics shall not be considered a failure.

4.5.2 Seam leakage test. The end item unit shall be tested on one boot wall assembly for seam leakage on an area of stitching that has been treated with seam sealant (see 3.3.7). The end item unit shall be laid over a 6 ± 1/8 inch diameter hoop as to form a 1 ± 1/4 inch deep depression with the seam to be tested running through the center of the depression. A 500-ml quantity of water at 77°F ± 4° shall be slowly poured into the depression and the under surface of the seam shall be observed. Leakage of more than 10-ml water through the sealed seam within 5 minutes after water is poured, shall be considered a test failure.

4.5.3 Seam strength test. The end item unit seams shall be tested in accordance with Method 8311 of FED-STD-601. Any break in the seam that indicates the seam strength is less than 80 percent of the fabric strength shall be considered a test failure (see 3.3.8).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

4.5.4 Erection test. Each boot wall shall be erected and attached to the SICPS tent and applicable vehicle in accordance with the erection instructions. Any nonconformance shall constitute a test failure.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or Commercial, as specified (see 6.2).

5.1.1 Level A preservation. Each boot wall shall be folded and/or rolled in a manner so as to achieve a compact unit. Type I boot walls shall measure approximately 29 inches in length, 21 inches in width, and 8 inches in depth. Type II boot walls shall be inserted into a plastic bag in accordance with A-A-50083. Each type II frame shall be cushioned to prevent damage to the finish. Type III and type IV boot walls shall measure approximately 29 inches in length, 24 inches in width, and 12 inches in depth. Type V boot walls shall measure approximately 20 inches in length, 16 inches in width, and 10-1/2 inches in depth.

5.1.2 Commercial preservation. Boot walls shall be preserved in accordance with ASTM D 3951.

5.2 Packing. Packing shall be level A, B or Commercial, as specified (see 6.2).

5.2.1 Level A packing. Boot walls, preserved as specified in 5.1, shall be packed in a shipping container conforming to overseas type, style A, grade A or B of PPP-B-601. Approximate inside dimensions of the box for type I boot walls shall be 29 inches in length, 21 inches in width and 8 inches in depth. One complete type II boot wall with frame, preserved as specified in 5.1, shall be packed in a close-fitting shipping container measuring approximately 80-1/2 inches in length, 24-1/2 inches in width, and 12 inches in depth conforming to overseas type, style A, type 3 load of PPP-B-601. Approximate inside dimensions of the box for the type III and IV boot walls shall be 29 inches in length, 24 inches in width, and 12 inches in depth. Approximate inside dimensions for type V boot walls shall measure 20 inches in length, 16 inches in width, and 10-1/2 inches in depth. Each box shall be closed and strapped in accordance with the applicable specification.

5.2.2 Level B packing. Boot walls preserved as specified in 5.1, shall be packed in a shipping container conforming to style RSC-L, type CF (variety SW) or SF, class domestic, grade 275 of PPP-B-636. Approximate inside dimensions of the box for type I boot walls shall be 29 inches in length, 21 inches in width and 8 inches in depth. One complete type II boot wall with frame, preserved as specified in 5.1, shall be packed in a close-fitting shipping container measuring approximately 80-1/2 inches in length, 24-1/2 inches in width, and 12 inches in depth conforming to overseas type, style A, type 3 load of PPP-B-601. Approximate inside dimensions of the box for

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

stitch type 401 or 401 (except

type III and type IV boot walls shall be 29 inches in length, 24 inches in width, and 12 inches in depth. Approximate inside dimensions for type V boot walls shall be 20 inches in length, 16 inches in width, and 10-1/2 inches in depth. Each box shall be closed in accordance with the appendix of the applicable specification.

5.2.2.1 Weather-resistant shipping container. When specified (see 6.2), the shipping container shall be grade V3c, V3s or V4s fiberboard box fabricated in accordance with PPP-B-636 and closed in accordance with the appendix of PPP-B-636, except that the inspection shall be in accordance with 4.4.6.

5.2.3 Commercial packing. Boot walls preserved as specified in 5.1 shall be packed in accordance with ASTM D 3951.

5.3 Palletization. When specified (see 6.2), boot walls packed as specified in 5.2.2 and 5.2.3, shall be palletized on a 4-way entry pallet in accordance with load type I or Ia of MIL-STD-147. Pallet types shall be type I (4-way entry), type IV or type V in accordance with MIL-STD-147. Pallets shall be fabricated from wood groups I, II, III, or IV of MIL-STD-731. Each prepared load shall be bonded with straps in accordance with bonding means C and D or film bonding means F or G. Pallet pattern shall be number 89 for type I, type III and type IV, and 95 for type V boot walls in accordance with the appendix of MIL-STD-147.

5.4 Marking. In addition to any special marking required by the contract or purchase order, unit packs, shipping containers and unit loads shall be marked in accordance with MIL-STD-129 or ASTM D 3951, as applicable.

5.4.1 Additional marking. The outside of the shipping container shall contain the following markings:

For type I boot walls: "M577 SICPS BOOT WALL"
For type II boot walls: "SICPS, RIGID WALL SHELTER, BOOT WALL"
For type III boot walls: "M1037, S250/G BOOT WALL"
For type IV boot walls: "M1037, S250E, BOOT WALL"
For type V boot walls: "M998 / M1038 TROOP - CARGO CARRIER BOOT WALL"

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The boot walls are intended to provide an interface panel between a SICPS tent command post and a vehicle. The class 1 boot wall is to be used in all theaters except the desert, the class 2 boot wall is to be used in the desert.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

6.2 Acquisition requirements. Acquisition documents must specify the following:

a. Title, number, and date of this specification.
b. Type and class of boot wall required (see 1.2).
c. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
d. When a first article is required (see 3.1, 4.3, and 6.3).
e. Levels of preservation and packing (see 5.1 and 5.2).
f. When palletization is required (see 5.3).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of Federal Acquisition Regulation (FAR) 52.209. The first article should be a preproduction sample. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should include specific instructions in acquisition documents regarding arrangements for selection, inspection, and approval of the first article.

6.4 Commercial seam sealant. Source of supply for K-Kote Seam Sealer-J (clear) #83-234C specified in 3.3.7 is:

Kenyon Consumer Products
P.O. Box 3715
1425 Kingstown Rd.
Peace Dale, RI 02883

6.5 Commercial adhesive. Source of supply for the 3M 847 adhesive coating specified in 3.3.9 is:

Minnesota Mining and Manufacturing Co.
St. Paul, MN 55144

6.6 Subject term (key word) listing.

M577
M998
M1037
M1038
Rigid wall shelter
S250

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

Custodian:

Army - GL

Review activities:

Army - MD
DLA - CT

Preparing activity:

Army - GL

(Project 8340-0546)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:57Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-B-44418(GL)	1991 June 28

3. DOCUMENT TITLE
BOOT WALL, FABRIC ASSEMBLIES, STANDARDIZED INTEGRATED COMMAND POST SYSTEM (SICPS)

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
U.S. Army Natick RD&E Center	508-651-4531	256-4531
c. ADDRESS (Include Zip Code) Commander, U.S. Army Natick RD&E Center ATTN: STRNC-UXT Natick, MA 01760-5017	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil -- Downloaded: 2025-09-27 15:02:34 EDT
Check the source to verify that this is the current version before use.