MIL-D-2088B (MU)
27 August 1968
SUPERSEDING
MIL-D-2088A (MU)
18 March 1966

MILITARY SPECIFICATION

DEMOLITION KIT, BANGALORE TORPEDO,
M1A2 AND TORPEDO, BANGALORE, M1A1, INERT
PARTS FOR

1. SCOPE

1.1 This specification covers the parts for two types of demolition kits designated as Demolition Kit, Bangalore Torpedo, M1A2 and Torpedo, Bangalore, M1A1, Inert.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition

FSC: 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U. S. ARMY MUNITIONS COMMAND

8863371 - Sleeve Nose
8863372 - Sleeve Connecting
8863374 - Tube
8863375 - End Cap and Detonator Well Assembly
8863376 - End Cap and Detonator Well Assembly (Alternate)

PUBLICATIONS

U. S. ARMY MUNITIONS COMMAND

ET - 8780448 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.- Materials shall be in accordance with applicable drawings and specifications.

3.2 Parts.- The parts shall comply with all requirements specified on Drawings (dwgs.) 8863371, 8863372, 8863374, 8863375 and 8863376 and with all requirements specified in the applicable specifications.

3.3 Waterproofness of the tube.- The tube shall be able to withstand an internal air pressure of five (5) pounds per square inch gage (p.s.i.g.) without any evidence of leakage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

3.4 Dents.- The tube shall be classed defective if there is evidence of any dent within three (3) inches of a flange, or if there is evidence of more than four (4) dents or any dent deeper than 1/16 inch beyond three (3) inches from a flange.

3.5 Workmanship.- All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, cracks, chips, sharp edges, unblended radii, surface defects, dirt, grease, hot rolling defects, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Surface coatings shall be continuous except for a few light scratches. All required markings shall be neat and sharply defined.

3.6 First article inspection.- This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.- At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

a. A statement that the lot complies with all quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by defect code, for all inspections performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.- The contractor shall submit a first article sample (see 6.1c) as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of the following items in the quantities specified:

Item	Without Protective Finish	With Protective Finish
Nose sleeve	15	10
Connecting sleeve	15	10
Tube	15	10
End Cap	15	--
Detonator Well	15	--
End Cap and Detonator Well Assembly	15	10

The first article sample shall have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same source of

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

supply as will be used in regular production. Prior to submission the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials (see 4.1.1e). A sample containing known defects will not be submitted unless specifically authorized by the contracting officer. A first article sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed.- Components will be subjected by the Government to any or all of the examinations or tests specified in 4.3.2 and 4.3.3 of this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.- If any component fails to comply with any or all of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of any component in the sample to comply with any or all of the stated requirements. In the event of rejection the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

4.3 Inspection provisions

4.3.1 Lot formation.- The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

produced by one manufacturer, in one unchanged process, in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of the lot. Inspection lots shall comply with MIL-STD-105. Unless otherwise approved by the contracting officer the inspection lot size of end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more than the largest monthly quantity contractually scheduled for delivery during the contract period. Inspection lots of components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size mutually convenient to both the contractor and the Government inspector. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examinations.- Sampling plans and procedures for the following classifications of defects shall be in accordance with MIL-STD-105 except that inspection for critical defects (and majors, when so specified) shall be 100 percent. Contractor's sampling plans, if used, shall be approved by the Government and shall provide, as a minimum, the protection afforded the Government by the sampling plans in MIL-STD-105. Continuous sampling plans in accordance with MIL-STD-1235 for defects other than critical may be used if approved by the procuring activity. Also, at the option of the procuring activity AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Cap, end (see dwg. 8863378 covering a detail of dwg. 8863375).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

Major:	AQL 1.00 percent		
101.	Center hole below thread not concentric with minor diameter of thread	Gage	01001
102.	Thread, incorrect	Gage	01002
103.	Minor diameter of thread, minimum (min.)	Gage	01003
104.	Small inside diameter below thread, incorrect	Gage	01004
105.	Large outside diameter, min.	Gage	01005
106.	Thread depth, min., of cavity incorrect	Gage	01006
107.	Evidence of crack or split	Visual	01007
Minor:	AQL 1.00 percent		
201.	Minor diameter of thread, maximum (max.)	Gage	01008
202.	Evidence of poor workmanship (see 3.5)	Visual	01009

4.3.2.2 Cap, end, alternate (see dwg. 8863380 covering a detail of dwg. 8863376).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Center hole not concentric with outside diameter	Gage	02001
102.	Outside diameter, min.	Gage	02002
103.	Evidence of crack or split	Visual	02003
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	02004

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

4.3.2.3 Well detonator, alt. (see dwg. 8863381 covering a detail of dwg. 8863376).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Thread, incorrect	Gage	03001
102.	Minor diameter of thread, min.	Gage	03002
103.	Large outside diameter, min.	Gage	03003
104.	Wall thickness, min.	Gage	03004
105.	Inside diameter, min.	Gage	03005
106.	Inside diameter of well not concentric with minor diameter of thread	Gage	03006
107.	Evidence of crack or split	Visual	03007
Minor:	AQL 1.00 percent		
201.	Minor diameter of thread, max.	Gage	03008
202.	Evidence of poor workmanship (see 3.5)	Visual	03009

4.3.2.4 Well, detonator (see dwg. 8863379 covering a detail of dwg. 8863375).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Wall thickness, min.	Gage	04001
102.	Thickness of flange, min.	Gage	04002
103.	Diameter of flange, min.	Gage	04003
104.	Diameter of flange not concentric with outside diameter	Gage	04004
105.	Evidence of crack or split	Visual	04005

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5).....	Visual	04006

4.3.2.5 End cap and detonator well assembly (see dwg. 8863375).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Inside diameter of detonator well not concentric with minor diameter of threads of end cap..	Gage	05001
102.	Foreign matter on interior surfaces of threads and detonator well.....	Visual	05002
103.	Protective finish omitted, incomplete or inadequate.....	Visual	05003
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5).....	Visual	05004

4.3.2.6 End cap and detonator well assembly, alternative, (see dwg. 8863376).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Inside diameter of detonator well not concentric with outside diameter of end cap.....	Gage	06001
102.	Detonator well not flush or above reference surface of end cap.....	Gage	06002

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

103.	Juncture of end cap and detonator well not clinched full 360 degrees or tight around entire periphery.....	Manual-Visual	06003
104.	Soldering of juncture of end cap and detonator well, omitted or inadequate.....	Visual	06004
105.	Evidence of foreign matter on interior surfaces of threads or detonator well.....	Visual	06005
106.	Protective finish omitted, incomplete or inadequate.....	Visual	06006
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5).....	Visual	06007

4.3.2.7 Sleeve, nose (see dwg. 8863371).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Large inside diameter, max.....	Gage	07001
102.	Wall thickness.....	Gage	07002
103.	Clip, omitted, or improperly located or incorrectly formed...	Gage	07003
104.	Protective finish, omitted, improper or inadequate.....	Visual	07004
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5).....	Visual	07005

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

4.3.2.8 Sleeve connecting (see dwg. 8863372).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Large inside diameter, max.....	Gage	08002
102.	Wall thickness.....	Gage	08003
103.	Overall length.....	Gage	08004
104.	Clip, omitted, improperly located or incorrectly formed...	Gage	08005
Minor:	AQL 1.50 percent		
201.	Incorrect width of butt lap.....	Gage	08006
202.	Protective finish, omitted, improper or inadequate.....	Visual	08007
203.	Evidence of poor workmanship (see 3.5).....	Visual	08008

4.3.2.9 Tube (see dwg. 8863374).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Flange not concentric with outside diameter.....	Gage	10001
102.	Thickness of flange.....	Gage	10002
103.	Wall thickness.....	Gage	10003
104.	Large outside diameter, max.....	Gage	10004
105.	Diameter of flange, min.....	Gage	10005
106.	Total length, incorrect.....	Gage	10006
107.	Evidence of welding burrs, when applicable.....	Gage	10007
108.	Evidence of dents (see 3.4).....	Visual	10008
109.	Evidence of coating on flanged ends.....	Visual	10009

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

110.	Protective finish, omitted, improper or inadequate.....	Visual	10010
111.	Marking omitted, improper or inadequate.....	Visual	10011
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5).....	Visual	10012

4.3.2.10 Carton sealed (see Section 5).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Carton damaged so that contents are exposed or liable to become exposed.....	Visual	11001
102.	Sealing strip incomplete, badly wrinkled, or not in contact with surface for at least 1/2 inch around entire carton.....	Visual	11002
Minor:	AQL 1.00 percent		
201.	Contents move when carton is shaken.....	Manual	11003
202.	Marking misleading or unidentifiable.....	Visual	11004

4.3.3 Testing

4.3.3.1 Waterproofness of tube (see 3.3) - Major defect - Code No. 10013.- The sampling plan for this requirement shall be in accordance with MIL-STD-105, using Code Letter K and an AQL of 0.40 percent. The test shall be performed as specified in 4.4.1, using test equipment specified in 4.3.4. Any tube which fails to comply with the specified requirement shall be classed defective and removed from the lot. Samples complying with the requirement may be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

4.3.3.2 Moisture and waterproofness of end cap and detonator well assembly (see dwg. 8863375) - Major defect - Code No. 05005 and moisture and waterproofness of end cap and detonator well assembly, alternate (see dwg. 8863376) - Major defect - Code No. 06008.- The sampling plan for this requirement shall be in accordance with MIL-STD-105, using Code Letter K and an AQL of 0.40 percent. The test shall be performed as specified in 4.4.2 using test equipment specified in 4.3.4. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. Samples complying with the requirement may be returned to the lot.

4.3.4 Inspection equipment.- Equipment Tabulation Number ET - 8780448 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.- Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.- Supply and maintenance of the equipment listed in the ET shall be in accordance with MIL-I-45607.

4.3.4.3 Government use of contractor's inspection and test equipment.- The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

4.4 Test methods and procedures

4.4.1 Waterproofness of tube.- The tube shall be assembled to the applicable test equipment and the specified internal air pressure applied for 5 seconds, minimum, while the entire assembly is submerged under a minimum of two (2) inches of water. Any assembly which shows evidence of leakage by emitting air bubbles at any point other than where the test equipment assembles to the tube, shall cause the tube to be classed defective.

4.4.2 Moisture and waterproofness of end cap and detonator well assembly and end cap and detonator well assembly, alternative.- The assembly shall be assembled to the applicable test equipment and the specified internal air pressure applied for 5 seconds, minimum, while the entire assembly is submerged under a minimum of two (2) inches of water. Any assembly which shows evidence of leakage by emitting air bubbles at any point other than where the test equipment assembles to the assembly, shall cause the assembly to be classed defective.

5. PREPARATION FOR DELIVERY

5.1 Packaging, packing and marking.- Packaging, packing and marking shall be in accordance with MIL-STD-1169.

6. NOTES

6.1 Ordering data.- Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.- Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

c. Submission of first article quantity.- Instructions as to the location of the facility at which the evaluation of the first article quantity shall be carried out, may be obtained from the contracting officer.

6.2 Inspection code numbers.- The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

6.3 Inspection equipment.- The contractor shall design inspection equipment as required by the inspection Equipment Lists (EL) referenced on the applicable ET in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Inspection equipment lists (EL).- Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Inspection equipment list codes.- The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.- Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

6.3.4 Contractor designs.- Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.- All submitted designs shall contain a reference to the applicable five digit Code Number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND1. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1375-A-018

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel *either Government or contractor*, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. *Comments and the return of this form* will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 OCT 64 1426

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
PICATINNY ARSENAL
DOVER, NEW JERSEY 07801

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

COMMANDING OFFICER
United States Army
Picatinny Arsenal
ATTN: SMUPA-ND
Dover, New Jersey 07801

FOLD

343-220 (A-324)

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.