MIL-D-2088B(AR)
AMENDMENT 2
14 August 1981
SUPERSEDING
AMENDMENT 1
19 March 1971

MILITARY SPECIFICATION

DEMOLITION KIT, BANGALORE TORPEDO, M1A2
AND TORPEDO, BANGALORE, M1A1, INERT, PARTS FOR

This amendment forms a part of Military Specification MIL-D-2088B (MU), dated 27 August 1968.

Page 1

*Add the following Preamble underneath the title: "This specification is approved by the US Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense."

2.1 Specifications, Military: Delete "MIL-I-45607 - Inspection Equipment, Supply and Maintenance of."

*3.4: Delete in its entirety and substitute the following: "3.4 Dents. - The tube shall be classed defective if there is evidence of any dent within four (4) inches of a flange, or if there is evidence of more than four (4) dents or any dent deeper than 1/8 inch beyond four (4) inches from a flange."

4.1.1: Delete statements "b" through "g" and substitute the following:

"b. Drawing and specification number and date, together with identification and date of changes thereto.

c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and the certificates of conformance are on file and available for review.

d. Number of items in the lot.

e. Date submitted."

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

Page 4

4.2.1, Fifth sentence: Delete "(see 4.1.1e)."

Page 5

4.2.3, Third and fourth sentences: Delete in their entirety.

4.3.1: Delete in its entirety and substitute the following: "4.3.1 Lot formation. - The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspecton. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, using the same materials and methods, in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specifed herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168."

Page 6

4.3.2: Delete in its entirety and substitute the following: "4.3.2 Examination. - The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.

When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspections system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4."

Page 7

4.3.2.2, Major Category: Delete Major Defect 101 in its entirety and substitute the following: "101. Concentricity of hole with tube mating shoulder ... Gage 02001."

Page 9

4.3.2.6, Major Category: Delete Major Defect 101 in its entirety and substitute the following:
"101. Concentricity of inside diameter of detonator well with tube mating shoulder of end cap...Gage 06001."

Page 11

*4.3.2.9, Major Category:
Delete Major Defect 109 in its entirety.
Add new Major Defect 112 follows:
"112. Dent deeper than 1/8 inch....Gage 10014."

Page 13

4.3.4.2: Delete in its entirety.

4.3.4.3: Delete in its entirety.

"The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment."

Custodian:
Army - AR

Preparing Activity:
Army - AR

Project No: 1375-A205

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:20Z
Check the source to verify that this is the current version before use.