MILITARY SPECIFICATION

EQUIPMENT, CABLE REINFORCEMENT, FOR PANEL BRIDGE:

M-2 (BAILEY TYPE)

This specification is approved for use by the USA Belvoir Research and Development Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers all structural components necessary to post-tension and reinforce 100 to 180 foot spans of M-2 Panel Bridge in its triple single configuration.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified (see 6.2), the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-S-781	- Strapping, Steel, and Seals.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research and Development Center, ATTN: STRBE-DS, Fort Belvoir, VA 22060-5606 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 5420

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-C-104	- Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted.
MIL-P-116	- Preservation, Methods of.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-C-3774	- Crates, Wood: Open (12,000 and 16,000 Pound Capacity).
MIL-C-16173	- Corrosion Preventive Compound, Solvent Cutback, Cold Application.
MIL-G-20241	- Gasket Material, Wool Felt, Impregnated, Adhesive, Pressure-Sensitive.
MIL-S-81733	- Sealing and Coating Compound, Corrosion Inhibitive.
MIL-E-52715	- Erection and Maintenance Equipment for Cable Reinforcement Set for Panel Bridge, M-2 (Bailey Type).

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-163	- Steel Mill Products, Preparation for Shipment and Storage.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking, and Water-Proofing; with Appropriate Test Methods.

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein.

DRAWINGS

ME

TA13217E2170	- Equipment, Cable Reinforcement, for Panel Bridge, M2 (Bailey Type).

PUBLICATIONS

TECHNICAL MANUALS

TM 5-277	- Bailey Bridge.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, and drawings required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI/ASME - Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.
ANSI/AWS A5.1 - Covered Carbon Steel Arc Welding Electrodes.
ANSI/AWS A5.18 - Carbon Steel Filler Metals for Gas Shielded Arc Welding.
ANSI/AWS D1.1 - Structural Welding Code-Steel, Section 5, Qualification.

(Application for copies should be addressed to the American National Standards Institute, Inc., 1430 Broadway, New York, NY 10018.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3951 - Standard Practice for Commercial Packaging.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The cable reinforcing equipment shall be in accordance with TA13217E2170 and as specified herein. The contractor shall furnish any or all of the components on the data list, as specified (see 6.2).

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescirbed on the drawings to insure correct fit, assembly, and operation of the cable reinforcement equipment. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available upon request, for inspection by the contracting officer or the designated representative.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

3.2 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 4.3 and 6.3).

3.3 Material. Material shall be as specified herein and on drawings. Material not specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.5).

3.3.1 Material deterioration and control. The cable reinforcement equipment shall be fabricated from compatible materials, inherently corrosion and deterioration resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environment to which the item may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals as defined in MIL-STD-889, shall be electrically insulated from one another to minimize or prevent galvanic corrosion. Insulation may be provided by an insulating barrier such as a corrosion inhibiting sealant conforming to MIL-S-81733 or chromate tape conforming to MIL-G-20241. Protection against any galvanic corrosion could also be obtained by exclusion of the electrolyte if feasible.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with components and sub-components, and shall make information available, upon request, to the contracting officer or designated representative.

3.4 Welding electrodes. Welding electrodes shall conform to ANSI/AWS A5.1 or A5.18, classification and size as required.

3.5 Cable. The cable when tested in accordance with 4.5.2.1 shall not show any slippage of the buttons or threaded end on the cable.

3.6 Identification marking. The cable reinforcement equipment shall be metal die stamped as shown on the drawings. Die stamping shall be legible after painting.

3.7 Stenciling. Each component, except pins, bolts, and washers shall be stenciled with the Federal Stock Number, nomenclature, and contract number. Stenciling shall be in accordance with MIL-T-704 and shall be Gothic capitals and numerals, 2 inches high where space permits. Stenciling on small components shall be as large as practicable.

3.8 Treatment and painting. All parts of the cable reinforcement equipment shall be cleaned, treated, and painted in accordance with MIL-T-704, type F, lusterless forest green color. Pins, bolts, nuts, threaded surfaces, and cables shall not be painted but shall be coated with a preservative conforming to MIL-C-16173, grade 2.

3.9 Performance. The cable reinforcement equipment shall withstand the mission specified in 4.5.2.2 without evidence of material defects (i.e., cracks, open joints, weld deterioration), permanent deformation or damage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

3.10 Government-furnished property. When specified (see 6.2), the following property in the quantities indicated will be furnished by the Government (see 6.2):

Item No.	Nomenclature	National Stock Number	Quantity for each
1.	Bridge, Fixed, Steel Bailey Type M2.	5420-00-530-3784	1
2.	Bridge Erection Set, Fixed Bridge, Bailey Type, M2.	5420-00-530-3785	1
3.	Truck, Dump, 5 Ton, 6 x 6, M51 (or equivalent).	2320-00-835-8336	30
4.	Trailer, basic utility, Pole type, 2-1/2 T, 2 whl (or equivalent).	2330-00-697-8102	9

3.11 Workmanship.

3.11.1 Steel fabrication. Steel used in the fabrication of the cable reinforcement equipment shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the metal. Shearing and chipping shall be done neatly and accurately. Corners shall be square and true. Flame cutting may be employed instead of shearing or sawing. Burned surfaces of flame-cut material shall be ground or machined sufficiently to remove ash and cooling checks. All bends of a major character shall be made with metal dies or fixtures in order to insure uniformity of size and shape.

3.11.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed.

3.11.3 Welders and welding.

3.11.3.1 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall obtain certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

ANSI/ASME, Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.
ANSI/AWS D1.1, Structural Welding Code, Section 5, Qualification.

Contractors who only make horizontal welds need not qualify welders for "all position welding". Subject to approval by the Government, the contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with ANSI/ASME and ANSI/AWS codes. The certification shall be made available for review by the contracting officer or the contracting officer's representative.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

3.11.3.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of ANSI/AWS D1.1 Structural Welding Code. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed, and the deposit and adjoining base metal shall be wire-brushed clean.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all section 3 and 5 requirements. The inspections in section 4 are the minimum to be used to demonstrate compliance. Sampling in quality conformance inspection does not authorize submission of known defective material, either indicated or actual, nor does it commmit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined and tested in accordance with the referenced specifications and standards.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.6 and 6.7).

4.2 Classification of inspections. Inspections specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6)

4.3 First article inspection.

4.3.1 Examination. The first article cable reinforcement equipment shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

4.3.2 Tests. The first article cable reinforcement equipment or separately procured components shall be tested as specified in 4.5.2. Failure of any test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling for examination. Sampling for examination shall be in accordance with MIL-STD-105.

4.4.2 Examination. Samples selected in accordance with 4.4.1 shall be examined as specified in 4.5.1. AQL shall be 2.5 percent defective for major defects and 4.0 percent defective for minor defects.

4.5 Inspection procedure.

4.5.1 Examination. The cable reinforcement equipment shall be examined as specified herein for the following defects:

Major

101. Any part or component not in accordance with the QAP requirements as shown on the drawings.
102. Material not as specified.
103. Components missing or not as specified.
104. Any drawing requirement, other than those identified by QAP data, not as specified.
105. Qualification of welders not as specified.
106. Workmanship not as specified.
107. Bolted connections not as specified.
108. Welding not as specified.

Minor

201. Identification markings incorrect or missing.
202. Stenciling incorrect or missing.
203. Treatment and painting not as specified.

4.5.2 Tests. All tests shall be conducted at an ambient air temperature between +40° and 90° F.

4.5.2.1 Proof load. Place the cable shown on Drawing 13217E2181 in a test frame and apply a proof load of 135,000 pounds to each button and the threaded end. Any slippage of the buttons or the threaded end shall constitute failure of this test.

4.5.2.2 Mission. Cable reinforcement equipment components shall be tested for a total of 24 missions. This equipment is used in conjunction with the Erection and Maintenance Equipment of MIL-E-52715. A mission shall consist of the following:

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

a. Load the equipment on the dump truck in accordance with instructions contained in TM 5-277.
b. Transport the equipment in accordance with the following schedule:

(1) Ten miles paved road.
(2) Ten miles secondary road.
(3) Five miles cross country (Aberdeen Proving Ground, Course Perryman No. 3 or equivalent).

c. Off load the cable reinforcement equipment at the site and install the cable reinforcement equipment on the M-2 Panel Bridge using the erection equipment.
d. During 88 crossings of the bridge with Military Load Class (MLC) 60 vehicles use the maintenance equipment to check or adjust cable tension required for the span erected (see TM 5-277). Checks and adjustments, if required, shall be made after 22, 44, 66 and 88 crossings of the MLC 60 loads.

4.5.2.2.2 Failure criteria. During performance of the 24 missions the cable reinforcement equipment shall be used in accordance with TM 5-277 and shall perform without evidence of the following defects:

a. Evidence of permanent deformation or failure of any component.
b. Material defects, cracks, open joints or weld deterioration.

4.6 Inspection of packaging.

4.6.1 First article inspection.

4.6.1.1 Examination. Examine the first article pack for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.1.2 Test. The first article pack of crated equipment for level A shall be subjected to the rail-impact test in accordance with MIL-STD-1186, Appendix A. At the conclusion of the first article pack test, the pack shall be examined. Any shifting of contents, loosening or breakage of holddowns, ties, stays, blocking or bracing, or any visual damage to the components shall constitute failure of the first article pack and shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

109. Threaded and unprotected metal surfaces requiring the application of a preservative in accordance with the referenced document, not coated with preservative for level A or commerical.
110. Wire rope not preserved and packed in accordance with the referenced document for level A.
111. Consolidation not as specified for level A.
112. Packing not as specified for level A.
113. Blocking, bracing, and anchoring not in accordance with the referenced documents for level A.
114. Marking missing, illegible, incorrect, or incomplete for level A or commercial.

5. PACKAGING

5.1 First article pack. The contractor shall furnish a first article pack for examination and test within the time frame specified, to prove, prior to starting production packaging that the applied preservation, packing, and marking comply with the packaging requirements of this specification. Examination and test shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article pack may be accomplished utilizing either the first article equipment or the production equipment. If the first article model is utilized, any preservation and packing shall be removed by the contractor at no expense to the Government when requested by the Government to facilitate comparison between the first article model equipment and the production equipment.

5.2 Preservation. Preservation shall be level A or commercial as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Threaded and unpainted surfaces. Threaded and unpainted surfaces of components such as bolts, nuts, chord plates, pull rods or any other similiar type components requiring the application of a contact preservative in accordance with MIL-P-116, shall be coated with type P-1 preservative. The preservative shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

5.2.1.2 Wire rope. The wire rope furnished on reels shall be preserved in accordance with the level A requirements of MIL-STD-163.

5.2.1.3 Consolidation. Nuts, bolts, and any other loose components requiring the protection of a container to prevent loss or to aid in accomplishing the packing specified herein shall be consolidated together in close fitting boxes conforming to PPP-B-621, class 2, style optional or PPP-B-601, overseas type, style optional. Box closure shall be in accordance with the appendix to the applicable box specification. Boxes to be packed in a crate shall not require strapping.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

5.2.2 Commerical. Threaded and unpainted surfaces shall be preserved as specified in 5.2.1.1. Additional preservation of the equipment shall be as required to afford protection against deterioration and damage in accordance with ASTM D 3951.

5.3 Packing. Packing shall be level A or commercial as specified (see 6.2).

5.3.1 Level A.

5.3.1.1 When procured as complete kits.

5.3.1.1.1 Wire rope. Wire rope, preserved as specified in 5.2.1.2 shall be packed in accordance with the level A requirements of MIL-STD-163 and shall be shipped separate from but at the same time as the crate containing the other erection equipment components (see 5.3.1.1.3).

5.3.1.1.2 Pull rods. Three pull rods shall be placed together in a close fitting box conforming to PPP-B-621, class 2, style 2, or PPP-B-601, overseas type, style A or B. Blocking and bracing shall be provided within the box to prevent movement or damage to the threaded surfaces. Box closure shall be in accordance with the appendix to the applicable box specification. Strapping shall not be required. The required pull rods for the kit shall then be packed in the crate with the other components specified in 5.3.1.1.3.

5.3.1.1.3 Other components. The kit components except for the wire rope contained on reels, preserved as specified in 5.2, shall be packed in a crate conforming to MIL-C-3774, type I, style A or MIL-C-104, type I, class 1 or 2, style A. The components shall be arranged within the crate, in a manner to provide maximum compactness, low center of gravity, and in a manner that void spaces are held to a minimum. Blocking, bracing, and anchoring of the contents shall be in accordance with the crate specification and MIL-STD-1186.

5.3.1.2 When procured as individual components. Individual components procured as replacements or spares, except for the wire rope contained on reels shall be packed together in close-fitting boxes conforming to PPP-B-601, overseas type, style optional; PPP-B-621, class 2, style optional or in a crate conforming to MIL-C-3774, type I, style A, as applicable to the weight and quantities of components procured. Only components of like description shall be packed together in the same container. Blocking, bracing and anchoring of the contents to prevent movement or damage shall be in accordance with the crate specification and MIL-STD-1186. Closure and strapping shall be in accordance with the crate or applicable box specification. Strapping shall conform to QQ-S-781, class 1, type I or IV, finish B.

5.3.2 Commercial. The equipment components, preserved as specified in 5.2, shall be packed in accordance with ASTM D 3951.

5.4 Marking.

5.4.1 Military. Marking for military levels of protection (level A) shall be in accordance with MIL-STD-129.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

5.4.2 Commercial. Commercial marking shall be in accordance with ASTM D 3951. In addition, weight and cube data shall be marked on the shipping container.

6. NOTES

6.1 Intended use. The cable reinforcement equipment is intended for use as a rapid means of post tensioning the triple-single configuration of the M-2 panel bridge. The bridge is reinforced using the king/queen post prinicple. The reinforced bridge is capable of supporting a class 60 load over spans between 100 and 170 feet and class 50 load over the 180 foot span.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number and date of this specification.
b. Designation of equipment desired (see 3.1).
c. Date of issue of DoDISS applicable and exceptions thereto (see 2.1.1).
d. When a first article is required for inspection and approval and the number of units required (see 3.2).
e. When other than finish B strapping is required (see 5.2.1).
f. Degree of preservation and degree of packing required (see 5.2 and 5.3).

6.3 First article. When a first article inspection is required, the items should be an initial production item. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, tests and approval of the first article test results and disposition of the document's first articles.

6.4 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the contractor of his obligation to preserve, pack, and mark the equipment or components when procured separately, in accordance with this specification.

6.5 Recycled material. It is encouraged that recycled material be used, when practical, as long as it meets the requirements of this specification (see 3.3).

6.6 Quality assurance provisions (QAP) record. The contracting officer should require the contractor to maintain records of all QAP inspections. A suggested paragraph is as follows:

"The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include, as a minimum, lot size, sample size, drawing requirements, actual measurement, number, and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

6.7 Definitions.

6.7.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-A345

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-E-52714B(ME)	Equipment, Cable Reinforcement, for Panel Bridge: M-2 (Bailey Type)

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER *(Specify)*: _____
b. ADDRESS *(Street, City, State, ZIP Code)*	

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY
USA Belvoir R&D Center
STRBE-DS
Fort Belvoir, VA 22060-5606

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
USA Belvoir R&D Center
STRBE-DS
Fort Belvoir, VA 22060-5606

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.