MIL-P-52281B(ME)
8 November 1978
SUPERSEDING
MIL-P-52281A(ME)
16 August 1967

MILITARY SPECIFICATION

PROCESSING MACHINE,

PHOTOGRAMMETRIC DIAPOSITIVE PLATES

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1.1 Scope. This specification covers a photographic processing machine for the processing of 54-millimeters by 54-millimeters (mm) and 9-1/2- (241 mm) by 9-1/2-inch (241 mm) glass diapositive plates.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-636 - Boxes, Shipping, Fiberboard.

FSC 6675

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:12Z
Check the source to verify that this is the currentversion before use.

MILITARY

MIL-C-104	- Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted.
MIL-P-116	- Preservation-Packaging, Methods of.
MIL-V-173	- Varnish, Moisture-and-Fungus-Resistant (for Treatment of Communications, Electronic, and Associated Equipment).
MIL-P-514	- Plates, Identification, Instruction and Marking, Blank.
MIL-C-3774	- Crates, Wood; Open 12,000- and 16,000-Pound Capacity.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-461	- Electromagnetic Interference Characteristics Requirements for Equipment.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with Appropriate Test Methods.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

DRAWINGS

ME

TA13208E4914	- Processing Machine, Photogrammetric Diapositive Plates.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN WELDING SOCIETY, INC. (AWS)

D1.1 - Structural Welding Code.

(Application for copies should be addressed to the American Welding Society, 2501 North West Seventh Street, Miami, FL 33125.)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

No. 70 - National Electrical Code.

(Application for copies should be addressed to the National Fire Protection Association, 470 Atlantic Avenue, Boston, MA 02110.)

SOUTHERN CALIFORNIA AIR POLLUTION CONTROL DISTRICT

Rule 102 for Photochemically Reactive Solvents.

(Application for copies should be addressed to the Southern California Air Pollution Control District, 434 South San Pedro Street, Los Angeles, CA 90013.)

(Technical society and technical association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

3. REQUIREMENTS

3.1 Description. The processing machine shall be in accordance with Top Assembly TA13208E4914 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the processing machine. Any data (e.g. shop drawings, layouts, flow sheets,

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article (preproduction model). The contractor shall furnish one processing machine for examination and testing within the time frame specified (see 6.2) to prove prior to starting production that his production methods will produce processing machines that comply with the requirements of this specification. Examination and tests shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.3 Material. Material shall be as specified herein and on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.8).

3.4 Performance.

3.4.1 Leakage. The developing unit, wash unit, and the water lines and refrigerant lines shall show no evidence of leakage when tested as specified herein.

3.4.2 Water-heating element. The water-heating element shall raise the temperature of the water in the developing tanks and in the circulating system from 50° F (10° C) to 68° F (20° C), plus or minus 2° F (1° C), within 2 hours and shall maintain 68° F (20° C), plus or minus 2° F (1° C), in the developing tanks for not less than 2 hours at an ambient atmospheric temperature of 55° F (13° C).

3.4.3 Refrigeration unit. The refrigeration unit shall cool the water in the developing tanks and in the circulating system from 80° F (27° C) to 68° F (20° C), plus or minus 2° F (1° C), within 2 hours and shall maintain 68° F (20° C), plus or minus 2° F (1° C), in the developing tanks for not less than 2 hours at an ambient temperature of 100° F (38° C).

3.4.4. Wash-water, temperature-control unit. The thermostatic mixing valve shall control the temperature of blended hot and cold wash water at 68° F (20° C), plus or minus 2° F (1° C). The unit shall automatically shut off when the cold-water supply is interrupted.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:12Z
Check the source to verify that this is the current version before use.

3.4.5 Lubrication seals. There shall be no evidence of motor or pump lubricants in the photographic fixing bath solution.

3.5 Electrical equipment. All electrical equipment and wiring shall conform to NFPA No. 70. A plastic laminated or an etched-metal wiring diagram detailing color-coded wires and identifying controls shall be mounted on the machine.

3.6 Fungus and moisture resistance. The electrical circuitry, including all components and connections, except as specified below, shall be protected from the effects of fungus growth and moisture by an overall treatment with a varnish conforming to MIL-V-173, Composition I or II, as applicable (see 3.6.1), with 1 percent copper 8-quinolinolate (by weight) based on the nonvolatile content of the varnish.

(a) Components or circuit elements that are inherently fungus and moisture resistant or which are hermetically sealed need not be treated.

(b) Components or circuit elements whose functions will be adversely affected by the varnish coating shall not be treated.

When used, the varnish shall be applied by spray, brush, or a combination of both to give a dry-film thickness of not less than 1 mil to component or element surfaces previously cleaned and prepared so that the surfaces are free from all foreign matter which would interfere with the adherence or function of the varnish.

3.6.1 Composition. Composition II shall be used only in the case when local air pollution regulations governing the application of varnish precludes the use of Composition I. When Composition II is used, the contractor shall provide evidence to the Government that the use of Composition II is required, and shall certify that the Composition II material complies with Rule 102, Southern California Air Pollution Control District, 434 South San Pedro Street, Los Angeles, CA.

3.7 Diapositive plate holder. The diapositive plate holder shall hold 54- by 54-mm and 9-1/2- (241 mm) by 9-1/2-inch (241 mm) diapositive plates. When the holder is in a vertical position, the plate shall slip into the appropriate holder without binding and shall not fall out when the holder is tilted up to 45 degrees in any direction.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

3.8 Electromagnetic interference. The electromagnetic interference emission characteristics of the processing machine shall conform to MIL-STD-461, Class IC.

3.9 Lubrication. All parts requiring lubrication shall be provided with a means for lubricating.

3.9.1 Delivery lubrication service. When delivered, all components shall be lubricated. If required, all pumps and motors shall be sealed after lubrication. Each lubricated component shall be tagged to indicate the temperature range and grade of oil and grease used (see 6.7).

3.10 Identification marking. The processing machine shall be identified in accordance with MIL-STD-130. The marking shall be applied to the processing machine on plates conforming to MIL-P-514, Type I, Style 3, Composition C, of Type I, Grade A, Class 1 material. Each plate shall be attached by screws, bolts, or rivets in a location where the plates will be both visible and legible.

3.11 Finish. The exterior front and side surfaces of the processing machine shall be buffed to a bright finish.

3.12 Workmanship. Bolt and rivet holes shall be punched or drilled within specified tolerances and all burrs shall be removed. All edges shall be rounded or beveled. Flame cutting shall not be used on corrosion-resisting steel sheets.

3.12.1 Welding. Welding of corrosion-resisting steel shall be in accordance with the AWS D1.1, Structural Welding Code. Welds shall be of uniform configuration and shall provide watertight seams.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards, as applicable.

4.1.2 Disassembly inspection. Failure of any examination or test by the preproduction model shall be cause for disassembly, in the presence of a Government representative, of the preproduction model to the extent necessary to determine the cause of the failure. Each disassembled part shall be examined in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, tolerances, and workmanship. Parts not complying with such requirements shall be rejected and shall be cause for rejection of the preproduction model. Reassembly with replacement parts and retesting shall be the responsibility of the contractor.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).
(c) Inspection of packaging (see 4.6).

4.3 Preproduction inspection.

4.3.1 Examination. The processing machine shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection, or for performing the disassembly inspection specified in 4.1.2.

4.3.2 Tests. The processing machine shall be tested as specified in 4.5.2. Failure of any test shall be cause for rejection or for performing the inspection specified in 4.1.2.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for tests shall be in accordance with MIL-STD-105.

4.4.2 Examination. Each processing machine shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:12Z
Check the source to verify that this is the current version before use.

4.4.3 Tests.

4.4.3.1 Individual. Each processing machine shall be subjected to the tests specified in 4.5.2.1, 4.5.2.3, and 4.5.2.4. Failure of any test shall be cause for rejection.

4.4.3.2 Samples. Samples selected in accordance with 4.4.1 shall be subjected to the tests specified in 4.5.2.2 and 4.5.2.5. AQL shall be 4 percent defective.

4.5 Inspection procedure.

4.5.1 Examination. The processing machine shall be examined as specified herein for the following defects:

101. Material not as specified.
102. Dimensions not as shown on drawings.
103. Components missing or not as specified.
104. Electrical equipment not as specified.
105. Electromagnetic interference suppression components and network not identical to the approved model.
106. Fungus and moisture resistance not as specified.
107. Lubrication not as specified.
108. Identification marking missing, incomplete, or illegible.
109. Finish not as specified.
110. Workmanship not as specified.

4.5.2 Tests.

4.5.2.1 Leakage.

4.5.2.1.1 Developing unit. The outer sink of the developing unit shall be filled with water that is within plus or minus 5° F (3° C) of the room ambient temperature, and the circulating pump shall be turned on. The outside of the sink, the inside of the developing tanks, and all related plumbing including the temperature control unit shall be visually inspected for the presence of leaks. The water shall be drained from the sink and the middle compartment of the developing tank shall be filled with water. A visual check shall be made for leaks into the other compartments. Presence of any leak shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

4.5.2.1.2 Wash unit. Each compartment of the wash unit shall be separately filled with water that is within plus or minus 5° F (3° C) of the room ambient temperature and the water shall be allowed to circulate as in normal operation. The outside surfaces of the different compartments being tested shall be visually inspected for leaks. All related plumbing including the mixing valve shall be inspected during this test. Presence of any leak shall constitute failure of this test.

4.5.2.1.2.1 Water pressure. Water lines shall be connected and subjected to an internal pressure of 55 psi (379 KPa), plus or minus 5 psi (34.5 KPa). Any evidence of leakage shall constitute failure of this test.

4.5.2.2 Temperature control unit.

4.5.2.2.1 Water-heating element. Place the units in an ambient temperature of not more than 55° F (13° C) and allow the equipment to stabilize. Fill the developing tank and the circulation system to operating capacity with water at a temperature of not more than 50° F (10° C). Failure of the temperature control unit to heat the water in the developing tank to 68° F (20° C), plus or minus 2° F (1° C), within 2 hours in an atmosphere of not more than 55° F (13° C) shall constitute failure of this test. Inability to maintain a temperature of 68° F (20° C), plus or minus 2° F (1° C), in the developing tank for not less than 2 hours shall also constitute failure of this test.

4.5.2.2.2 Refrigeration unit. Place the units in an ambient temperature of not less than 100° F (38° C) and allow the equipment to stabilize. Fill the developing tank and the circulation system to operating capacity with water at a temperature of not less than 80° F (27° C). Failure of the temperature control unit to cool the water in the developing tank to 68° F (20° C), plus or minus 2° F (1° C), within 2 hours in an atmosphere of not less than 100° F (38° C) shall constitute failure of this test. Inability to maintain a temperature of 68° F (20° C), plus or minus 2° F (1° C), in the developing tank for not less than 2 hours shall also constitute failure of this test.

4.5.2.2.3 Refrigerant. All refrigerant connections and components shall be tested for leaks with a halide leak detector. Any evidence of leakage shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:12Z
Check the source to verify that this is the currentversion before use.

4.5.2.3 Wash-water, temperature-control unit. Hot and cold water shall be turned on and the temperature mixing valve shall be set to secure wash water at a temperature of 68° F (20° C). The temperature of the hot water shall be varied from not less than 75° F (24° C) to not more than 180° F (82° C), and the temperature of the delivered, blended, wash water shall be observed. The cold-water source shall then be shut off and the unit shall be observed for operation. Inability of the unit to control temperature of blended hot and cold water at 68° F (20° C), plus or minus 2° F (1° C), or failure of the unit to automatically shut off when the cold water supply is interrupted shall constitute failure of this test.

4.5.2.4 Diapositive plate holder. Each diapositive plate holder shall be tested for proper fit of the diapositive plates. With the holder in a vertical position, three 54- by 54-mm or one 9-1/2-(241 mm) by 9-1/2-inch (241 mm) plate, as applicable, shall be placed in the holder. The holder shall then be tilted to not less than 45 degrees from the vertical in at least four positions. Any evidence of binding, inability or the holder to accept the plate, or the plate falling out of the holder when the holder is tilted shall constitute failure of this test.

4.5.2.5 Lubrication seals. Five gallons of photographic fixing bath solution shall be mixed, placed in the proper sink, and circulated through the agitator pump for 1 hour. Any evidence of the presence of motor or pump lubricants in the solution shall constitute failure of this test.

4.5.2.6 Electromagnetic interference. The preproduction model shall be tested to determine conformance to 3.8. The contractor shall furnish the contracting officer a report of tests required by MIL-STD-461. Disapproval of the report shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 Preproduction pack inspection.

4.6.1.1 Examination. The preproduction pack shall be examined for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

4.6.1.2 Test. The crated processing machines for Level A and Level B shall be tested as specified in 4.6.1.2.1. At the conclusion of the preproduction pack test, the pack shall be examined. Any shifting of contents, loose or broken holddowns, ties, stays, blocking, or bracing, or any visible damage to the barrier material or shroud or to the contents shall constitute failure of the preproduction pack and shall be cause for rejection.

4.6.1.2.1 Railroad-car impact. The crated processing machine shall be subjected to the railroad-car test as specified or guided-impact tests in MIL-STD-1186, Appendix A. The car shall strike a string of five empty cars with draft gear extended and the brakes set, at a speed of between 10 and 11 miles per hour.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following major defects. AQL shall be 2.5 percent defective.

111.	Materials, methods, or containers not as specified for Level A and Level B. Each incorrect material, method, or container shall be considered one defect.
112.	Units not secured to container base as specified for Level A.
113.	Components requiring preservation in a fiberboard box not cushioned and blocked within the box as specified for Level A.
114.	Boxes not secured to the units as specified for Level A.
115.	Closure and strapping of crates not as specified for Level A and Level B.
116.	Strapping not as specified.
117.	Crated contents not protected with a shroud as specifed for Level B.
118.	Marking illegible, incorrect, incomplete, or missing.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:12Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Preproduction pack. The contractor shall furnish a preproduction pack for examination within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied preservation, packing, and marking comply with the packaging requirements of this specification. Examination shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The preproduction pack may be prepared utilizing either the first article or a production processing machine. When the first article is utilized, any packaging shall be removed by the contractor at no expense to the Government, when requested by the Government, to facilitate comparison between the first article and production processing machine.

5.2 Preservation. Preservation shall be Level A or Commercial, as specified (see 6.2).

5.2.1 Level A. The developing unit, wash unit, drying unit, and temperature control unit shall each be preserved in accordance with MIL-P-116, Method IIa. Each unit shall be secured by bolting directly through the barrier material to the base of the container specified in 5.3. Before the units are enclosed in the barrier material, the hangers, repair parts, maintenance tools, technical publications, and any unattached components or components removed in accordance with the contractor's recommendation shall be preserved in one or more boxes as required. The boxes shall conform to PPP-B-636, Type CF, Class Domestic. The contents shall be cushioned and blocked within the boxes in accordance with MIL-STD-1186. The boxes shall be secured to the units under the barrier material in any available space in a manner to prevent damage to the units, boxed contents, or barrier material.

5.2.2 Commercial. Each processing machine shall be preserved in accordance with MIL-STD-1188.

5.3 Packing. Packing shall be Level A, Level B, or Commercial, as specified (see 6.2).

5.3.1 Level A. Each complete processing machine shall be packed in a crate conforming to MIL-C-104, Type I or II, Class 1 or 2, Style A. The crate shall be closed and strapped in accordance with the appendix to the crate specification. Strapping shall be zinc coated.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:12Z
Check the source to verify that this is the current version before use.

5.3.2 Level B. Each complete processing machine shall be packed in a crate conforming to MIL-C-3774, Type I, Style A. The contents shall be waterproofed with a shroud in accordance with MIL-STD-1186 and the appendix to the crate specification. The crate shall be closed and strapped in accordance with the appendix to the crate specification.

5.3.3 Commercial. Each complete processing machine shall be packed in accordance with MIL-STD-1188.

5.4 Marking.

5.4.1 Military packaging. Marking shall be in accordance with MIL-STD-129.

5.4.2 Commercial packaging. Marking shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. The processing machine is intended for use in the preparation of glass diapositive plates to be used with stereophotogrammetric plotting instruments. The machine will normally be housed and operated in a shelter where environmental conditions are partially controlled.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of preproduction model (see 3.2).
(c) Time frame required for submission of preproduction pack (see 5.1).
(d) Degree of preservation and degree of packing required (see 5.2 and 5.3).

6.3 Preproduction model. Any changes or deviations of production processing machine from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the contractor of his obligation to furnish processing machines conforming to this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

6.4 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to preserve, pack, and mark the processing machines in accordance with this specification.

6.5 Data requirements. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and contractor's maintenance and operation manual to be furnished with each processing machine.

6.6 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools, as necessary (including any special tools), and instructions regarding shipment of processing machines.

6.7 Lubricants. The contracting officer should furnish a list of military lubricants applicable to the processing machine covered by this specification as contained in the Federal Supply Catalog, Department of Defense Section, Identification List C9100-IL, for FSC Group 91.

6.8 Recycled material. It is encouraged that recycled material be used, when practical, as long as it meets the requirements of this specification (see 3.3).

Custodian:
Army - ME

Preparing activity:
Army - ME

Review activity:
DLA - GS

Project 6675-A219

User activity:
Army - CR

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

MIL-P-52281B(ME) Processing Machine, Photogrammetric Diapositive Plates

NAME OF ORGANIZATION AND ADDRESS	CONTRACT NUMBER
	MATERIAL PROCURED UNDER A ☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3 IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4 REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*	TELEPHONE NO
	DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 68 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research
and Development Command
ATTN: DRDME-DS
Ft. Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:12Z
Check the source to verify that this is the current version before use.