MILITARY SPECIFICATION

TEST SET, GUIDED WEAPON AN/DSM-92C

This specification is approved for use by the Naval Air Systems Command, Department of the Navy and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. The equipment (Test Set) covered by this specification shall be for flightline and shop use to perform an operational readiness check (GO/NO-GO) of WALLEYE weapons defined in 6.1.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on the date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Federal

PPP-B-636	- Boxes, Shipping, Fiberboard

Military

MIL-P-116	- Preservation-Packaging, Methods of
MIL-E-5400	- Electronic Equipment, Airborne, General Specification for
MIL-T-5422	- Testing, Environmental, Aircraft Electronic Equipment
MIL-E-17555	- Electronic and Electrical Equipment, Accessories, and Repair Parts; Packaging and Packing of

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer, Naval Air Engineering Center, Engineering Specifications and Standards Department (ESSD) Code 93, Lakehurst, NJ 08733, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 4935

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

MIL-T-18303 - Test Procedures; Preproduction, Acceptance, and Life, for Aircraft Electronic Equipment, Format for

MIL-T-28800 - Test Equipment for use with Electrical and Electronic Equipment, General Specification for

MIL-F-23419 - Fuses, Instrument Type, General Specification for

MIL-A-55339 - Adapter, Connector, Coaxial, Radio Frequency (Between Series and Within Series), General Specification for

STANDARDS

Federal

FED STD 123 - Marking for Shipment (Civil Agencies)

Military

MIL-STD-108 - Definitions of and Basic Requirements for Enclosures for Electric and Electronic Equipment

MIL-STD-129 - Marking for Shipment and Storage

MIL-STD-130 - Identification Marking of US Military Property

MIL-STD-167 - Mechanical Vibrations of Shipboard Equipment (Type I - Environmental and Type II - Internally Excited)

MIL-STD-461 - Electromagnetic Interference Characteristics Requirements for Equipment

MIL-STD-704 - Electric Power, Aircraft Characteristics and Utilization of

MIL-STD-781 - Reliability Tests: Exponential Distribution

MIL-STD-810 - Environmental Test Methods

MIL-STD-965 - Parts Control Program

MS17322 - Meter, Time Totalizing, Miniature, Digital, 115 Volt, 400 Hertz

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

DRAWINGS

Naval Air Systems Command

DL 1008AS1000	-Data List for Guided Weapon Test Set AN/DSM-92C

OTHER PUBLICATIONS

Military

NAVAIR 16-30DSM92-2	-Maintenance Instructions (Organizational, Intermediate, Depot), Calibration Instructions, Alignment Instructions, Illustrated Parts Breakdown for Guided Weapon Test Set AN/DSM-92C

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 First Article. When specified (see 6.2), the contractor shall furnish sample unit(s) for first article inspection and approval (see 4.4 and 6.3).

3.2 Parts and materials.

3.2.1 General. The parts and materials specified in the drawings and related documents for use in the construction of this equipment were selected to ensure the fulfillment of all the requirements of this specification. Any deviation by the contractor from the use of these specified parts and materials necessarily places both the burden of proof for the acceptability of the change and the associated cost upon the contractor. Approval for deviations must be requested from the procuring activity by the contractor and granted by the Government representative prior to submission of equipments for preproduction (first article) tests. Approval of parts and material deviations shall not be construed by the contractor to constitute a waiver of the performance requirements or any other requirements of this specification.

3.2.2 Nonstandard parts and material approval. Approval for the use of nonstandard parts and materials shall be obtained by the contractor as specified in MIL-STD-965.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.2.3 Supplemental requirements. In the event that the contractor proposes to alter the equipment delineated by this specification and applicable drawings, the following supplemental requirements for the selection of parts and materials shall be applicable.

3.2.3.1 Basic conformance. Materials selected for use in the equipment shall be as specified in MIL-T-28800. Parts shall be selected from those conforming to MIL-E-5400, unless the parts listed therein will not perform adequately in the intended applications and environments specified herein in which case 3.2.2 applies.

3.2.3.2 Interchangeability. All parts and materials shall meet the interchangeability requirements as specified in MIL-T-28800. The drawings conforming to DL 1008AS100 shall be the standard for measuring interchangeability of all applicable units, assemblies, subassemblies and parts.

3.3 Design and construction. The Test Set shall be manufactured in accordance with the drawings and subsidiary specifications conforming to DL 1008AS100 and related lists, except that errors of omission or commission on the drawings may be incompatible with the requirements of this and related specifications. In any case, it is a condition of final acceptance that the equipment manufactured shall meet all the design, construction, and workmanship requirements of this specification and applicable acceptance test documents. Proposed changes, either to correct drawing discrepancies or to effect improvements, shall be specifically approved by the procuring activity prior to being incorporated. (see 6.2)

3.3.1 Reliability.

3.3.1.1 Operational stability. The Test Set shall operate satisfactorily, continuously or intermittently, for a period of at least 300 hours. During this time, it shall not be necessary to readjust any controls that are inaccessible to the operator during normal use.

3.3.1.2 Operating life. The Test Set shall have a minimum total operating life of 2000 hours with reasonable servicing and replacement of parts. A list of parts requiring scheduled replacement due to wear during the life of the equipment, and the wearout life of such parts, shall be made available to the procuring activity.

3.3.1.3 Reliability in mean-time-between-failures (MTBF). The Test Set shall have a specified mean (operating) time between failures of 300 hours when tested in accordance with 4.6.3.

3.3.1.4 Time totalizing meter. The Weapon Control Assembly (drawing 1008AS107 of DL 1008AS100) of the equipment shall contain a time totalizing meter of the type specified in MS17322-6A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.3.2 Standard conditions. The following conditions shall be used to establish the normal performance characteristics under standard conditions for performing laboratory bench tests:

a. Temperature	Room ambient (30 ± 10°C)
b. Altitude	Normal ground
c. Vibration	None
d. Humidity	Room ambient up to 90% relative humidity
e. Input Power Voltage	115 ± 11.5 VAC, 400 ± 20 Hz, 3-phase (Rotation ABC)

3.3.2.1 Service conditions. The test set shall operate satisfactorily under the following environmental service conditions.

3.3.2.1.1 Temperature-altitude. The test set shall meet the operating requirements of this specification at temperatures between +88°C and -62°C at altitudes between ambient and 50,000 feet (16,000 meters).

3.3.2.1.2 Drip-proof. The test set shall meet the test requirements of MIL-STD-108 for drip proof test except the equipment shall be inclined only 15 degrees. The equipment shall operate during and after exposure.

3.3.2.1.3 Humidity. The test set shall meet the test requirements of MIL-STD-810, Method 507.1, Procedure I, including Method 507.1 paragraph entitled Summary, except the maximum temperature shall be 50°C.

3.3.2.1.4 Salt spray. The test set shall meet the test requirements of MIL-STD-810, Method 509.1, Procedure I, including Method 509.1 paragraph entitled Summary.

3.3.2.1.5 Explosive atmosphere. The test set shall meet the test requirements of MIL-STD-810, Method 511.1, Procedure I, including Method 511.1 paragraph entitled, Summary, except the maximum temperature shall be 55°C and the maximum altitude shall be 10,000 feet (3,000 meters).

3.3.2.1.6 Vibration. The test set shall meet the test requirements of MIL-STD-167, Type I.

3.3.2.1.7 Shock. The test set shall meet the test requirements of MIL-STD-810, Method 516.1, Procedure I, including Method 516.1 paragraph entitled Summary. The equipment shall not be operating during the test.

3.3.3 Warm-up time. The time required for the equipment to warm-up prior to operation shall not exceed 10 minutes under standard conditions and 20 minutes under service conditions.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.3.4 Primary input power requirements. The test set shall meet all applicable input power requirements as specified in MIL-STD-704 for class 2 equipment. The power required shall be of the following type and shall not exceed the specified values:

115 ± 11.5 VAC, 400 ± 20 Hz,
3-phase, 4 wire system (neutral
ground), phase rotation (ABC),
100 VA.

3.3.4.1 Protection. The Test Set shall be capable of withstanding input power variations imposed by abnormal electric system operations as specified in MIL-STD-704.

3.3.5 Electromagnetic interference suppression. The generation of radio interference by the Test Set and the vulnerability of the equipment to radio interference shall be as specified in MIL-STD-461 for class ID equipment except that the limits for conducting electromagnetic emissions (switching transients) are in excess of the values of MIL-STD-461. Limits for test methods CE01, CE02, CE03, CE04, and CE05 apply. Limits on the transients are as follows:

a. POWER ON/OFF switch transients are permissible on the equipment input power leads 30 dBA above the limits of MIL-STD-461 in the frequency range of 30 Hz to 50 MHz.

b. STATION SELECT switch transients are permissible on the equipment input power leads 10 dBA above the limits of MIL-STD-461 in the frequency range of 30 Hz to 50 MHz.

c. Transients caused by operating the equipment POWER ON/OFF switch are permissible on the equipment power leads (400 Hz) to the load (WALLEYE weapon) 50 dBA above the limits of MIL-STD-461 in the frequency range of 30 Hz to 50 MHz.

3.3.6 Dimensions. The dimensions of the Test Set case shall be as follows:

a. Length - 12" (30.48 cms)
b. Width - 19-1/2" (49.53 cm)
c. Depth - 13-5/8" (34.61 cm)

3.3.7 Weight. The total weight of the equipment, including cables shall not exceed 50 pounds (22.5 kgs).

3.3.8 Color and finish. The color and finish of the equipment shall be in accordance with drawing 1008AS105 of DL 1008AS100.

3.3.9 Identification plate and item markings. Nomenclature and identification marking shall be in accordance with MIL-STD-130 and as specified in DL 1008AS100.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.4 Performance. The performance of the test set shall be as specified herein in addition to the performance requirements specified in DL 1008AS100. Unless otherwise specified, these requirements shall apply under both standard and extreme service conditions. When reduced performance requirements for service conditions are acceptable, such variations are specified.

3.4.1 Functions. The Test Set shall perform the functions specified herein.

3.4.1.1 Power ON/OFF switch. The power ON/OFF switch shall permit the vidicon gyro to attain rated speed, and the vidicon filaments to warm up prior to uncaging the gyro and totally energizing the WALLEYE weapon.

3.4.1.2 Time-delay relay. A 2-minute thermal time-delay relay shall be incorporated to prevent mechanical uncaging of the vidicon gyro before the gyro has attained operating speed.

3.4.1.3 Station select. The STATION SELECT switch shall energize the guidance section of various weapons. This switch shall also control the mechanical caging and uncaging of the vidicon gyro.

3.4.1.4 Lock-on. The LOCK-ON switch shall enable the locking of the cross hairs of the weapon's vidicon onto the target-pattern display of AN/DSM-77B Test Sets. This checks weapon lock-on and tracking functions.

3.4.1.5 Gimbal enable. The GIMBAL ENABLE switch and circuitry shall be capable of offsetting the vidicon gyro in azimuth and elevation.

3.4.1.6 Roll gyro. The roll gyro circuit shall be capable of caging the gyro.

3.4.1.7 Dome-heater overriding circuit. Prevention of operation of the dome heater in the WALLEYE weapon shall be accomplished with the dome-heater overriding circuit.

3.4.1.8 CRAB. The caging retainer and boresighter test circuit shall return the mechanically-caged position of the vidicon gyro to weapon boresight.

3.4.1.9 Film advance. The FILM ADV switch and circuit shall start and stop the motor of the video tape recorder (Mk 4 Mods 1 and 4).

3.4.1.10 Intent-to-launch. The INTENT-TO-LAUNCH circuit shall supply +28 VDC to the launch relay of Mk 4 weapons only.

3.4.1.11 Self-test. The Test Set shall have a self-test capability. This shall include testing of +12, -12, and +28 VDC power supply outputs and video indicator operation test without the use of an external video generator.

3.4.1.12 Video display. The video display shall be capable of presenting external video or of monitoring internal video patterns for self-test purposes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.4.1.13 Video switch. The video switch shall provide the following functions:

a. cockpit
b. guidance
c. test
d. 300 lines
e. 200 lines
f. shades

3.4.1.13.1 Cockpit. In the COCKPIT position, the video display shall exhibit external video when a video signal is applied to pin 37 of connector W1P1.

3.4.1.13.2 Guidance. In the GUIDANCE position, external video shall appear on the video display when a video signal is applied to pin 50 of connector J2.

3.4.1.13.3 Test. In the TEST position, the video display shall exhibit external video when a video signal is applied to connector W2P4 or to pin 5 of connector W2P2.

3.4.1.13.4 300 lines. In the 300 LINES position, a 300-line stable and clearly distinguishable resolution pattern shall appear on the video display in the form of vertical black-and-white lines when video out connector W2P3 is connected to video in connector W2P4.

3.4.1.13.5 200 lines. In the 200 lines position, a 200-line stable and clearly distinguishable resolution pattern shall appear on the video display in the form of vertical black-and-white lines when video out connector W2P3 is connected to video in connector W2P4.

3.4.1.13.6 Shades. In the SHADES position, seven shades of gray shall appear on the video display in the form of vertical bars when video out connector W2P3 is connected to video in connector W2P4.

3.4.1.14. Quality meter. GO/NO-GO conditions shall be indicated on the front panel QUALITY METER. The QUALITY METER shall be a zero-center, left-right indicating DC microammeter. The meter shall conform to the requirements of drawing 67A58D14 of DL 1008AS100. When a test signal is of the correct magnitude and polarity, the needle shall be in the white boxed GO area. Incorrect test signals shall cause the needle to point in the NO-GO area.

3.4.1.15 Push-to-test switch. All QUALITY METER indications shall be obtained with the PUSH-TO-TEST switch held depressed (closed).

3.4.1.16 Function switch. The Function Switch shall provide the capability to select the various circuits presented to the quality meter for go/no-go indication.

3.5 Detailed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.5.1 Function and description. The function and description of the test set is covered in NAVAIR manual 16-30DSM92-2.

3.5.2 Components. The test set shall contain the following basic components:

a. Weapon Control Assembly, TS-2711C/DSM-92

b. Cover and Case Assembly, CY-6505C/DSM-92

c. Cable Assemblies

d. Accessory Materials

3.5.2.1 Weapon control assembly. The weapon control assembly shall be manufactured to meet the requirements of drawing 1008AS107 of DL 1008AS100. This assembly contains the following basic circuits:

a. +28, -12, +28 VDC Power Supply Circuits

b. Video Display Circuit

c. Video Generator Circuit

d. Sync. Level Detector Circuit

e. Safety Interlock Circuit

f. Quality Meter Circuit

g. Film Advance Circuit

h. Station Select Circuit

i. Time Delay Circuit

j. Lock-On Circuit

k. Gimbal Enable Circuit

l. Dome Heater Override Circuit

m. Caging Retainer and Boresight (CRAB) Circuit

n. Intent-to-Launch Circuit

o. Roll Gyro Circuit

3.5.2.1.1 Power supply circuits.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.5.2.1.1.1 +12 VDC supply. The +12 volt dc supply shall be capable of providing +12 ± 1 volts dc to the various circuits within the test set with the input power varied from 103.5 to 126.5 volts ac and from 380 to 420 hz. The output voltage of the supply shall be variable within the range of +11 to +17 volts dc.

3.5.2.1.1.2 -12 VDC supply. The -12 volt dc supply shall be capable of providing -12 ± 1 volts dc to the various circuits within the test set with the input power varied from 103.5 to 126.5 volts ac and from 380 to 420 hz. The output voltage of the supply shall be variable within the range of -11 to -17 volts dc.

3.5.2.1.1.3 +28 VDC supply. The +28 volt dc supply shall be capable of providing +28 ± 2 volts dc to the various circuits within the test set with the input power varied from 103.5 to 126.5 volts ac and from 380 to 420 hz. The output voltge of the supply shall be variable within the range of +23 to +35 volts dc.

3.5.2.1.2 Video display circuit. The video display circuit shall meet the requirements of drawing 67A58F123 of DL 1008AS100. The video display shall contain externally accessible controls for brightness, contrast, vertical, and horizontal adjustments.

3.5.2.1.3 Video generator circuit. The video generator circuit shall meet the requirements of drawing 1008AS115 of DL 1008AS100. The video generator shall have outputs of 300 lines, 200 lines, and shades as described in 3.4.1.13.

3.5.2.1.4 Sync level detector circuit. The sync level detection circuit shall meet the requirements of drawing 67A58C205 of DL 1008AS100. The sync level detection circuit shall be capable of detecting incoming video and providing a dc level output to the quality meter indicating the level of video sync.

3.5.2.1.5 Safety interlock circuit. The safety interlock circuit shall be capable of preventing high voltage from being present at the pins of connector W1P1 when the cable (W1) is not connected to a weapon - i.e., for test set self-checks.

3.5.2.1.6 Quality meter circuit. The quality meter circuit shall be capable of indicating (qualitatively) input power levels, internal voltage levels, and weapon voltage levels. The circuit shall be capable of being used when the test set is connected to a weapon, or when the test set is operated alone - for self-test purposes.

3.5.2.1.7 Film advance circuit. The film advance circuit shall be capable of activating the video tape recorder in practice guided weapons, and illuminating the RECORD light on the test set.

3.5.2.1.8 Station select circuit. The station select circuit shall be capable of activating the guidance section in all WALLEYE weapons. The circuit shall also control the mechanical cage/uncage relay of the vidicon gyro.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.5.2.1.9 Time delay circuit. The time delay circuit shall be capable of preventing the vidicon gyro from being uncaged before the gyro has attained full operating speed. The time delay shall be 120 +30 -10 seconds.

3.5.2.1.10 Lock-on circuit. The lock-on circuit shall be capable of actuating weapon circuitry causing the weapon's vidicon cross-hairs to lock-on to the target-pattern display of the AN/DSM-77 test set. The circuit shall also control the mechanical caging/uncaging of the vidicon gyro.

3.5.2.1.11 Gimbal enable circuit. The gimbal enable circuit shall be capable of offsetting the vidicon gyro in azimuth and elevation to check operation of the MK 4 practice weapon circuits. An interlock shall disconnect this circuit when weapons other than the MK 4 are being tested.

3.5.2.1.12 Dome heater override circuit. The dome heater override circuit shall be capable of preventing operation of the dome heater in the weapon being tested.

3.5.2.1.13 Caging retainer and boresight (CRAB) circuit. The CRAB circuit shall be capable of positioning the weapon vidicon to boresight. This circuit shall be applied only to the MK 1, Mods 6 and 7 weapons.

3.5.2.1.14 Intent-to-launch circuit. The intent-to-launch circuit shall be capable of energizing the launch relay of MK 4 weapons only.

3.5.2.1.15 Roll gyro cage circuit. The roll gyro cage circuit shall be capable of providing a caging signal to the MK 1 weapon and MK 2 practice weapon roll gyro circuits. Additionally, the circuit shall visually indicate whether the roll gyro is caged or uncaged.

3.5.2.2 Cover and case CY-6505C/DSM-92. The cover and case of Test Set shall be manufactured in accordance with requirements of drawing 1008AS105 of DL 1008AS100.

3.5.2.3 Cable assemblies. Cable assemblies shall be manufactured to meet the requirements of this specification and the following:

3.5.2.3.1 Umbilical cable W-1. The umbilical cable shall connect the Test Set to a primary 3-phase power source and to the weapon being tested, and shall be manufactured to conform to the requirements of drawing 67A58F55 DL 1008AS100.

3.5.2.3.2 VTR power adapter cable W-2. The VTR power adapter cable shall connect to an external video tape recorder. It shall also permit the application of a video signal directly to the Test Set. It shall be manufactured to meet the requirements of drawing 1008AS200 of DL 1008AS100.

3.5.2.3.3 Power adapter cable W-3. The power adapter cable shall connect the power connector of the umbilical cable (3.5.2.3.1) to the aircraft's WALLEYE umbilical plug, and shall be manufactured to conform to the requirements of drawing 67A58F87 of DL 1008AS100.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

3.5.2.4 Accessory materials. The test set shall be supplied with the following accessory materials:

a. Hex-key wrenches (2 ea.)

b. Coaxial Adapter

c. Spare Fuses

3.5.2.4.1 Hex-key wrenches. Two hex-key wrenches shall be provided as follows to remove knobs from the control panel of the Test Set:

a. The hex-key wrench required to remove pointer illuminator knob, GIMBAL ADJUST knob, and VIDEO knob shall conform to drawing 58A5A294-4 of DL 1008AS100.

b. The hex-key wrench required to remove knobs from CONTRAST, BRIGHT, HORIZ, and VERT controls shall conform to drawing 58A5A294-2 of DL 1008AS100.

3.5.2.4.2 Coaxial adapter. One each coaxial adapter M55339/16-00914, shall be provided with the test set as shown by drawing 1008AS100 of DL 1008AS100.

3.5.2.4.3 Spare fuses. Two 1-ampere, type FMO3250VIA of MIL-F-23419, and two, 3-ampere, type FMO3250V3A of MIL-F-23419 fuses shall be provided as spares with each Test Set. Test set shall be provided with spring clips mounted in test set lid in accordance with drawing 1008AS100 of DL 1008AS100 for storing fuses.

3.6 Workmanship. The test set shall conform in every respect to the requirements of this specification and DL 1008AS100.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification, where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. Preproduction (First article) Inspections (4.4)

b. Initial production Inspections (4.5)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

c. Quality Conformance (Acceptance) Inspections (4.6)

d. Life test (4.8)

e. Environmental tests (4.12)

4.3 Inspection conditions. Unless otherwise specified herein, all inspections shall be performed in accordance with the conditions specified as follows:

a.	Temperature	Room ambient (25° ± 10°C)
b.	Altitude	Normal ground
c.	Vibration	None
d.	Humidity	Room ambient up to 90% relative humidity
e.	Input power	115 ± 11.5 VAC, 400 ± 20 Hz, 3-phase (Rotation ABC)

4.3.1 Performance characterics.

4.3.1.1 Before testing. The equipment shall satisfy the requirements for interference control (3.3.5) and warm-up time (3.3.3).

4.3.1.2 During inspection acceptance testing. The equipment shall satisfy the requirements of Section 3.

4.4 First article inspection.

4.4.1 Requirement. First article tests shall be made on an equipment representative of the production equipments to be supplied under the contract. First article test performance shall be the responsibility of the contractor and shall be performed in accordance with approved test procedures (see 4.13). The Government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all the required tests shall obtain the services of a commercial laboratory acceptable to the Government. No preproduction inspections shall be conducted prior to approval of the preproduction test procedure by the contracting officer. (see 6.2)

4.4.2 First article test data. The contractor shall prepare all data, see (6.2), collected in conducting these tests for procuring agency review and approval. On first production contracts, this data shall include a list of all electrical and electronic parts giving their specified voltage, and ambient and surface temperatures. The ambient and surface temperature shall be obtained under the extreme high temperature operating condition.

4.4.3 Scope of first article tests. First article tests shall include all tests deemed necessary by the procuring activity to determine that the equipment meets all the requirements of this specification and contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

These shall include environmental and interference tests in accordance with MIL-T-5422 as specified in MIL-T-28800. Test methods shall be in accordance with MIL-STD-810 except as modified by this specification.

4.4.4 First article approval. Approval of the first article shall be done by the procuring activity upon satisfactory completion of all tests and the first article test report being made available (see 6.2). No production equipments shall be delivered prior to the approval of the first article. Prefabrication of production equipment prior to the approval of the first article is at the contractor's risk. The approved first article sample shall be retained by the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The first article sample shall not be considered as one of the deliverable equipments under the contract.

4.4.5 Production equipments. Equipment supplied under the contract shall, in all respects including design, construction, workmanship, performance and quality, be equivalent to the approved first article sample (see 6.2). Each equipment shall be capable of successfully completing the same test as imposed on the first article sample. Evidence of non-compliance with the above shall constitute cause for rejection of an equipment and of an equipment already accepted by the Government. It shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.5 Initial production tests. One out of the first 10 production equipment shall be selected and sent at the contractor's expense to a designated Government laboratory for tests. This equipment shall be selected by the procuring activity after the equipment has successfully completed all individual tests. The first article sample shall not be selected for this test.

4.5.1 Scope of tests. This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved first article sample in design, construction, workmanship, performance and quality, and that it meets all applicable requirments.

4.5.2 Accessory material. In addition to having the complete equipment for initial production tests, the contractor shall have available such accessory material and data necessary to test the equipment.

4.5.3 Initial production sample approval. Approval of the initial production sample shall be by the procuring activity upon completion of all tests and preparation of an initial production test report. Any design, material or performance defect discovered during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Failure of the initial production sample to pass any of the tests shall be cause for stopping delivery of equipment under the contract until proper corrective action is accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

4.5.4 Reconditioning of initial production test sample. On completion of the initial production tests, the equipment shall be reworked by the contractor by replacing all wear or damaged items. After reworking, the contractor shall resubmit the equipment for acceptance.

4.6 Acceptance tests. The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests see(6.2). All inspection and testing shall be to the approved acceptance test procedures under the supervision of the Government inspector. Contractors not having testing facilities acceptable to the procuring activity shall engage the services of a commercial testing laboratory approved by the procuring activity. The contractor's test reports shall show quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

a. Individual tests (4.6.1)

b. Sampling tests (4.6.2) or Reliability Assurance tests (4.6.3)

c. Special tests (4.6.4)

4.6.1 Individual tests. Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests:

a. Examination of product

b. Operational test

c. Manufacturing run-in test

4.6.1.1 Examination of product. Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.6.1.2 Operational test. Each equipment shall be operated long enough to permit the temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.6.1.3 Manufacturing run-in test. Each equipment shall be operated under the conditions specified herein for a period of 6 hours without failure. A failure shall be defined as anything which causes malfunctioning of the equipment. Only those adjustments will be permitted which can be made using controls that are accessible to the operator during normal use of the equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

a.	Temperature	Room ambient
b.	Humidity	Room ambient
c.	Vibration	Any selected frequency within the range of 20 to 30 Hz (excluding resonant points) and a minimum amplitude of ±3 g's.

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 6-hour period of operation. Where feasible, the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration shall be vertical to the normal mounting plane for 5 minutes and lateral to the plane for 5 minutes. Where it is not feasible to vibrate the equipment in two directions, the vertical shall be used. During the 6-hour period of operation following the 10-minute vibration period, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, the equipment shall be repaired and the test started over, except that the 10-minute vibration period need not be repeated when it is established that the failure was not a result of vibration. Should failures occur repeatedly, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be made up of several shorter periods to conform to normal working hours.

4.6.2 Sampling tests. Equipment selected for sampling tests shall first have passed the individual tests. (Sampling tests shall not be conducted unless reliability assurance tests of 4.6.3 are deleted by contractual action.) Equipments shall be selected for sampling tests by the Government inspector in accordance with the following:

	Quantity of equipments offered for acceptance	Quantity to be selected for sampling tests
a.	First 10	0
b.	Next 50	1
c.	Next 75	1
d.	Next 100	1
		1 for each additional 200 or fraction thereof.

(If by contract action the initial production tests (4.5) are deleted, then a sample test shall be conducted on one equipment from the first 10 produced.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

4.6.2.1 Scope of tests. As a minimum, each equipment selected for sampling tests shall be subjected to the following:

a. Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

b. Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the first article, initial production, individual, and special tests.

c. Manufacturing run-in test specified in 4.6.1.3 except that the test duration shall be 120 hours with no restriction on the number of failures. However, each failure shall be analyzed as to cause and remedial action necessary to reduce the possibility of its recurrence in future equipments.

4.6.3 Reliability assurance tests. Reliability assurance tests shall be conducted in accordance with the requirements of MIL-STD-781. Tests shall be conducted as required for both the qualification phase and the production acceptance (sampling) phase.

4.6.3.1 Reliability qualification phase. Prior to acceptance of equipments under the contract or purchase order, a contractually specified quantity of equipments (or a minimum of three if not specified) shall be subjected to the combined reliability qualification requirements for unsheltered shipboard equipment (category 3.B) of MIL-STD-781, using Test Plan IC therein (θ_1 = 200).

4.6.3.2 Reliability acceptance phase. Production lot samples of the equipments shall be subjected to the combined production reliability acceptance requirements for unsheltered shipboard equipment (category 3.B) of MIL-STD-781, using Test Plan VC therein (r_1 = 100).

4.6.3.2.1 Acceptance phase sample size. The entire contract quantity (except for those equipments used in the qualification phase) shall be considered one lot. The reliability acceptance sample size shall be ten percent of the contract quantity, but not less than three units. The test program shall start the first month after the qualification phase has been completed. The samples shall be tested until an accept/reject decision has been reached. In the meantime, other equipments manufactured may be shipped in place, with approval from the contracting officer. The test results shall be summarized monthly for the procuring activity. The procuring activity reserves the right to stop the acceptance of equipment anytime after one more reject decisions have been reached, pending a review of the contractor's efforts to improve the equipment, parts, quality control, etc.; in order that the entire contract quantity will result in an accept decision.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

4.6.3.3 Test details. The test details such as the length of the test cycle, the length of the heat portion of the cycle, the performance characteristics to be measured, special failure criteria, and preventive maintenance to be allowed during the test, shall be part of the test procedure made available to the procuring activity prior to the beginning of the qualification test phase of the reliability assurance tests.

4.6.3.3.1 Temperature extremes. The temperature extremes shall be limited to -40°C to +55°C storage, and -28°C to +55°C operating.

4.6.3.3.2 Voltage cycling. Voltage cycling in accordance with MIL-STD-781 is not required.

4.6.4 Special Tests. Special tests shall be conducted on a quantity of equipments as specified by the procuring office for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure quality control. The equipments selected for special test may be from equipments previously subjected to the sampling or reliability assurance tests.

4.6.4.1 Special test schedule. Selection of equipments for special tests shall be made as follows:

a. On early equipments after an engineering or material change.

b. Whenever failure reports or other evidences indicate that additional tests are required. (This will be determined by the procuring activity.)

4.6.4.2 Scope of tests. Special tests shall consist of such tests as approved by the procuring activity. Test procedures previously approved for the first article tests may be used where applicable. When not applicable, the contractor shall prepare a test procedure for procuring activity approval prior to conducting the tests, see (6.2).

4.7 Equipment failure. Should a failure occur during either the sampling, reliability assurance or special tests, the following action shall be taken:

a. Determine the cause of failure.

b. Determine if the failure is an isolated case or due to design defect.

c. Prepare for procuring activity approval proposed corrective action intended to reduce the possibility of the same failure occurring in future tests. (See 6.2)

d. Where practical, include a test (in the individual test) to check all equipment for this requirement until reasonable assurance is forthcoming that the defect has been satisfactorily corrected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

4.8 Life test. The contractor shall furnish all samples and shall be responsible for accomplishing the life test. The test shall be of 300 hours duration and shall be conducted on equipments that have passed the individual tests. The life test shall be performed under the conditions specified in 4.8.1. The life test sample shall be selected by the Government inspector in accordance with the following: (Equipments which have successfully completed the initial production test, sampling tests, reliability tests, or special tests may be selected for life tests.)

Quantity of equipments offered for acceptance	Quantity to be selected for life test
a. First 25	1
b. Next 175	1
c. Next 300	1
	1 for each additional 500 or fraction thereof.

When reliability tests are conducted, the life test may be omitted if, during the reliability tests, quantity of equipments equal to or more than that listed above receive at least 300 hours each of test time.

4.8.1 Life test conditions. The life test shall be conducted under the following simulated service conditions:

a. Temperature	Room ambient (30°C ± 10°C)
b. Altitude	Normal ground (0 - 5000 ft.) (0 - 1600 meters)
c. Humidity	Room ambient up to 90% relative humidity
d. Input voltage	Nominal
e Vibration	None

4.8.2 Life test period. The life test may be run continuously or intermittently. Any period of operation shall be of sufficient duration to permit the equipment temperature to stabilize. Periodically, the equipment shall be turned on and off several times, and put through its various phases of operation.

4.8.3 Performance check. At approximately 8-hour intervals during the test, a limited performance check shall be made. The performance check shall be proposed by the contractor and shall be approved by the procuring activity. (see 6.2)

4.8.4 Test data. The contractor shall keep a daily record of the performance of the equipment, making particular note of any deficiencies or failures. In the event of part failures, the defective part shall be re-

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

placed and the operation resumed for the remainder of the test period. A record shall be kept of all failures throughout the test. This record shall indicate the following:

a. Part number

b. Circuit reference symbol number

c. Part function

d. Name of manufacturer

e. Nature of failure

f. Number of hours part operated prior to failure.

4.8.4.1 Failure report. In the event of a failure, the Government inspector shall be notified immediately. A report shall be prepared for the procuring activity upon completion of the test. In this report, the contractor shall propose suitable and adequate design or material corrections for all failures. The procuring activity will review such proposals and determine whether they are acceptable. (see 6.2)

4.9 Reconditioning of test samples. Equipment which has been subjected to acceptance or life test shall be reconditioned as follows:

a. On completion of the test, the equipment shall be reworked by the contractor by replacing all wear items. The wear items shall be determined by agreement between the contractor and the procuring activity.

b. After reworking, the contractor shall resubmit the equipment for acceptance.

4.10 Presubmission testing. No item, part, or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.11 Rejection and retest. Equipment which has been rejected may be reworked or have parts replaced to correct the defects and then resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original equipment shall be furnished to the Government inspector.

4.12 Environmental tests. The equipment shall operate satisfactorily when subjected to the following tests.

4.12.1 Temperature - altitude. The test set shall be tested in accordance with MIL-STD-810, Method 504.1, Procedure 1, including Method 504.1 paragraph entitled Summary, except the following operating conditions shall be used in place of table 504.1-II. Adjustment of video controls shall be allowed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

a. Step 1a shall be omitted.

b. Step 1b shall be at a temperature of -62°C and altitude of 50,000 feet (16,000 meters).

c. Step 2 shall be at a temperature of -40°C and altitude at standard ambient.

d. Step 3 shall be at a temperature of -40°C and altitude of 10,000 feet (3,000 meters).

e. Step 4 shall be omitted.

f. Step 5 shall be at a temperature of 85°C and standard ambient altitude.

g. Step 6 shall be at a temperature of 55°C and standard ambient altitude.

h. Step 7 shall be at a temperature of 71°C and altitude of 10,000 feet (3,000 meters) with an equipment ON-time of 20 minutes.

i. Step 8 thru 12 shall be omitted.

j. Step 13 shall be at a temperature of 88°C and altitude of 50,000 feet (16,000 meters). The equipment shall be non-operating, and shall remain in the chamber for 4 hours.

k. Step 14 shall be at a temperature of 25°C and standard ambient altitude.

l. Step 15 shall be at standard ambient conditions.

4.12.2 Drip-proof. The test set shall be drip-proof tested in accordance with MIL-STD-108, except the equipment shall be inclined only 15 degrees. The equipment shall be operated during and after exposure.

4.12.3 Humidity. The test set shall be humidity tested in accordance with MIL-STD-810 Method 507.1, Procedure 1, including Method 507.1 paragraph entitled Summary, except the maximum temperature shall be 50°C.

4.12.4 Salt spray. The test set shall be salt spray tested in accordance with MIL-STD-810, Method 509.1, Procedure 1, including Method 509.1 paragraph entitled Summary.

4.12.5 Explosive-atmosphere. The test set shall be explosive tested in accordance with MIL-STD-810, Method 511.1, Procedure 1, including Method 511.1 paragraph entitled Summary, except the maximum temperature and altitude shall be 55°C and 10,000 feet (3,000 metters), respectively.

4.12.6 Vibration. The test set shall be submitted to vibration tests in accordance with MIL-STD-167, Type 1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

4.12.7 Shock. The Test Set shall be shock tested in accordance with MIL-STD-810, Method 516.1, Procedure 1, including Method 516.1 paragraph entitled Summary, except the equipment shall not be operated during the test.

4.13 Methods of examination and test. The procedures used for conducting first article tests, acceptance tests, and life tests shall be prepared by the contractor for procuring activity approval (see 6.2). The right is reserved by the procuring activity or the Government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification and the contract. MIL-T-18303 shall be used as a guide for preparation of test procedures. When approved test procedures are available from previous contracts, such procedures may be used when their use is acceptable to the procuring activity. However, the right is reserved by the procuring activity to require modification of such procedures, including additional tests, when deemed necessary.

5. PACKAGING

5.1 General. Packaging shall be in accordance with the general requirements of MIL-E-17555, supplemented as follows:

5.2 Preservation-packaging. Unless otherwise specified in the contract or purchase order, preservation-packaging whall be in accordance with MIL-P-116, Method III.

5.3 Packing. Unless otherwise specified in the contract or purchase order, packing shall be level A. The packaged equipments shall be packed in fiberboard containers conforming to PPP-B-636, class weather resistant, style optional, normal requirements. Sealing (taping) and reinforcing (banding) shall be in accordance with the appendix to PPP-B-636.

5.3.1 Unitized loads. Unitized loads, commensurate with the level of packing specified herein or in the contract, shall be used whenever the total quantities for shipment to one destination equal 40 cubic feet or more. Quantities less than 40 cubic feet need not be unitized. Unitized loads shall be uniform in size and quantities to the greatest extent possible.

5.4 Marking. In addition to any special marking required by the contract (see 6.2); each unit package, intermediate and exterior contriner and unitized load shall be marked in accordance with MIL-STD-129. When specified (see 5.2), the marking of domestic shipments for civil agencies shall be in accordance with Fed. Std. No. 123.

6. NOTES AND CONCLUDING MATERIAL

6.1 Intended use. The NA/DSM-92C Test Set is intended for use in determining the operational readiness (GO/NO-GO) of WALLEYE weapons either

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

prior to loading on the aircraft, or while loaded on the aircraft. The Test Set will check out the following WALLEYE weapons:

a. Practice Guided Weapon MK 4 all Mods
b. Practice Guided Weapon MK 27 all Mods

6.2 Ordering Data.

6.2.1 Procurement Requirements. Purchasers should exercise any desired options offered herein; and procurement documents should specify the following:

a. Title, number, and date of this specification

b. Selection of applicable levels of packaging and packing (see Section 5)

c. When a first article is required for inspection and approval (see 4.4)

6.2.2 Data requirements. When this specification is used in a procurement which incorporates a DD Form 1423 and invokes the provisions of 7-104.9 (n) of the Defense Acquisition Regulations, the data requirements identified below will be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved Contract Data Requirements List (DD Form 1423) incorporated into the contract. When the provisions of DAR-7-104.9(n) are not invoked, the data specified below will be delivered by the contractor in accordance with the contract requirements. Deliverable data required by this specification is cited in the following paragraphs:

Paragraph	Data Requirement	Applicable DID
4.4.1, 4.13	Procedure, First Article Test	DI-T-4901
4.4.4, 4.4.5	Report, First Article Test	DI-T-4902
4.5.2	Procedure, Initial Production Test	DI-T-4903
4.5.3	Report, Initial Production Test	DI-T-4904
4.6, 4.13	Procedure, Acceptance Test	DI-T-4903
4.6	Report, Acceptance Test	DI-T-4904
4.6.3.2.1	Report, Reliability (monthly)	DI-R-7035
4.6.3.3	Procedure, Reliability Assurance Test	DI-R-7035
4.6.4.2	Procedure, Special Test	DI-T-4903
3.3	Engineering Change Proposal	DI-E-2037

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

Paragraph	Data Requirement	Applicable DID
4.7	Proposal, Corrective Action	UDI-T-23719
4.8.3, 4.13	Procedure, Life Test	DI-T-4903
4.8.4	Report, Life Test	DI-T-4904
4.8.4.1	Report, Failure	UDI-R-21141A
4.11	Report, Corrective Action	UDI-T-23719

(Copies of data item descriptions required by the contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

6.3 Instructions for first article. When a first article is required for inspection and approval, see 3.3, 4.4, 6.3.1.

6.3.1 First article. One preproduction unit shall be tested in accordance with 4.4.

6.4 Miscellaneous notes.

6.4.1 Performance objectives. Minimum size and weight, simplicity of operation, ease of maintenance, and improvement in the performance and reliability of the specific functions beyond the requirements of the specification are objectives which shall be considered in the production of this equipment. Where it appears that a substantial reduction in size or improvement in simplicity of design, performance, ease of maintenance or reliability will result from the use of materials, parts and processes other than those specified in DL 1008AS100, it is desired that their use be investigated. When investigation shows advantages can be realized, a request for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

6.4.2 Precedence of documents. When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply.

a. Contract. The contract shall have precedence over any specification.

b. This specification. This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

c. The drawings of DL 1008AS100. The drawings shall have precedence over other referenced specifications. Any deviation from the drawings shall be specifically approved by the procuring activity.

d. Referenced specifications. Any referenced specifications shall have precedence over all subsidiary specifications referenced therein. All referenced specifications shall apply to the extend specified.

6.4.3 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Preparing Activity:
Navy - AS

(Project 4935-N044)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE
MIL-T-85032A(AS) Guided Weapon Test Set AN/DSM-92C

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?
   [ ] YES [ ] NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

S/N 0102-014-1802

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T10:05Z
Check the source to verify that this is the current version before use.