NOTICE OF
REINSTATEMENT

INCH-POUND
MIL-M-52005C(ME)
NOTICE 3
13 January 1997
SUPERSEDING
NOTICE 2
19 August 1996

MILITARY SPECIFICATION

MAST SET, AIRPORT MARKER LIGHT

MIL-M-52005C(ME), dated 5 June 1978, is hereby reinstated and may be used for acquisition.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 6210-A659

AMSC N/A

FSC 6210

DISTRIBUTION STATEMENT A. Approved for public release, distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:04Z
Check the source to verify that this is the current version before use.

MIL-M-52005C(ME)
5 June 1978
SUPERSEDING
MIL-M-52005B(ME)
14 February 1966

MILITARY SPECIFICATION

MAST SET, AIRPORT MARKER LIGHT

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a telescoping mast set for mounting airport obstruction lights. Guy lines and stakes for anchoring the mast to the ground are not covered by this specification.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

QQ-S-781	-	Strapping, Steel, and Seals.
PPP-B-621	-	Boxes, Wood, Nailed and Lock-Corner.

FSC 6210

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:04Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-P-116	-	Preservation-Packaging, Methods Of.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-130	-	Identification Marking of US Military Property.
MIL-STD-1188	-	Commercial Packaging of Supplies and Equipment.

DRAWINGS

ME

TA13200E6240	-	Mast Set, Airport marker Light.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Description. The mast set shall be in accordance with Top Assembly TA13200E6240 and shall consist of four mast assemblies, two boots, and two web straps for rigidly holding the masts together during shipment. Each mast assembly shall consist of five telescoping actions of steel tubing, collapsible to a minimum length of 9 feet 5 inches and extensible to a length of 41 feet.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the cable reels. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article (preproduction model). The contractor shall furnish the mast set as specified (see 6.2), for examination and testing within the time frame specified (see 6.2), to prove prior to starting production that his production methods will produce mast sets that comply with the requirements of this specification. Examination and tests shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.2).

3.3 Operation. The mast assembly shall be rigid and straight when fully erected and anchored to the ground with three guy lines and ground stakes and with the base anchored to a stake.

3.4 Operational reliability. The mast assembly shall be capable of being erected to its normal operating position and collapsed a minimum of 50 times without failure or permanent damage.

3.5 Identification marking. The mast sets shall be identified in accordance with MIL-STD-130.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:04Z
Check the source to verify that this is the current version before use.

3.6 Technical publications. Such technical publications as are specified shall be furnished (see 6.2).

3.7 Workmanship. The mast set shall be free from defects such as rust, cracks, or burrs on metal parts; loose components; defective stitches or scratches in the leather; or any other defects that could impair its operation or serviceability.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspections. The inspections requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).
(c) Inspection of packaging (see 4.5).

4.3 Preproduction inspection.

4.3.1 Examination. The mast set shall be examined for the characteristics listed in Table I. Presence of one or more defects shall be cause for rejection.

Table I. Examination Schedule.

Number	Characteristic	Requirement Paragraph
Major		
101.	Dimensions not as shown on the drawings.	3.1
102.	Components missing or not as specified.	3.1
103.	Parts or components are not in alinement.	3.3
Minor		
201.	Identification marking not in accordance with MIL-STD-130.	3.6
202.	Technical publications that are specified (see 6.2) are not furnished.	3.6
203.	Workmanship not as specified.	3.7

4.3.2 Tests. The mast set shall be tested as specified in 4.3.2.1 and 4.3.2.2. Failure of any test shall be cause for rejection.

4.3.2.1 Operating test. The four mast assemblies (one mast set) shall be erected to their normal operating position and collapsed five times. The boots and web straps shall be installed each time. Failure of the mast to extend or collapse to the lengths specified in 3.1 or damage to any component shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:04Z
Check the source to verify that this is the current version before use.

4.3.2.2 Operational reliability. The four mast assemblies shall be erected and collapsed a minimum of 50 times. Failure of the masts to extend or collapse, or deformation or damage to components or parts shall constitute failure of this test.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination and tests for lots of 16 or more mast sets shall be in accordance with MIL-STD-105, Inspection Level S-3. In lots of 15 or less mast sets, only one mast set shall be inspected.

4.4.2 Examination.

4.4.2.1 Samples. Samples selected in accordance with 4.4.1 shall be examined as specified in 4.3.1. AQL shall be 2.5 percent defective for major defects and 4.0 percent defective for minor defects.

4.4.3 Tests.

4.4.3.1 Individual. Each mast set shall be tested as specified in 4.3.2.1. Failure of the test shall be cause for rejection.

4.4.3.2 Samples. Samples selected in accordance with 4.4.1 shall be tested as specified in 4.3.2.2. AQL shall be 4.0 percent defective.

4.5 Inspection of packaging.

4.5.1 Quality conformance inspection of pack.

4.5.1.1 Units of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.5.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.5.1.3 Examination. Samples selected in accordance with 4.5.1.2 shall be examined for the characteristics listed in Table II. AQL shall be 2.5 percent defective for major defects and 4.0 percent defective for minor defects.

Table II. Examination Schedule.

Number	Characteristics	Requirement Paragraph
Major		
104.	Preservation not Level A or Commercial as specified (see 6.2).	5.1
105.	The mast set not preserved for Level A as specified.	5.1.1
106.	The mast set not preserved for Commercial as specified.	5.1.2
107.	Packing not Level A, Level B, or Commercial as specified (see 6.2).	5.2
108.	Each mast set not packed for Level A as specified.	5.2.1
109.	Each mast set not packed for Level B as specified.	5.2.2
110.	Each mast set not packed for commercial in accordance with MIL-STD-1188.	5.2.3
Minor		
204.	Marking for military levels of protection not in accordance with MIL-STD-129.	5.3.1
205.	Marking for commercial levels of protection not in accordance with MIL-STD-1188.	5.3.2

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:04Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Preservation. Preservation shall be Level A or Commercial as specified (see 6.2).

5.1.1 Level A. The mast set shall be enclosed in the boots and secured with the straps provided. The technical publications shall be preserved in accordance with MIL-P-116, Method IC-1 or IC-3.

5.1.2 Commercial. The mast set shall be enclosed in the boots and secured with the straps provided. The technical publications shall be placed in a commercial waterproof sealed bag.

5.2 Packing. Packing shall be Level A, Level B, or Commercial as specified (see 6.2).

5.2.1 Level A. Each mast set with technical publications shall be packed in close-fitting box conforming to PPP-B-621, Class 2, Style 2. The box shall be closed and strapped in accordance with the appendix to the box specification. Strapping shall conform to QQ-S-781, Class 1, Type I or IV, size as applicable. Unless otherwise specified (see 6.2), strapping shall be Finish B. When specified (see 6.2), strapping shall be Finish A.

5.2.2 Level B. each mast set with technical publications shall be packed in a close-fitting box conforming to PPP-B-621, class 1, style 2. The box shall be closed and strapped in accordance with the appendix to the box specification.

5.2.3 Commercial. Each mast set with technical publications shall be packed in accordance with MIL-STD-1188.

5.3 Marking.

5.3.1 Military. Marking for military levels of protection shall be in accordance with MIL-STD-129.

5.2.2 Commercial. Marking for Commercial packaging shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. The mast set is intended for use to support obstacle light assembly.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of preproduction model, and number of mast sets required (see 3.2).
(c) Technical publications required (see 3.6).
(d) Degree of preservation and degree of packing required (see 5.1 and 5.2).
(e) When other than Finish B strapping is required (see 5.2.1).

Custodian:
Army - ME

Preparing activity:
Army - ME

Review activity:
DLA - GS

Project 6210-A509

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:04Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.

2. The submitter of this form must complete blocks 4, 5, 6, and 7.

3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	**1. DOCUMENT NUMBER** Mil-m-52005C (ME)	**2. DOCUMENT DATE (YYMMDD)** **780605**

3. DOCUMENT TITLE **Mast Set. Airport Marker Light**

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME *(Last, First, Middle Initial)*	b. ORGANIZATION	
c. ADDRESS *(Include Zip Code)*	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON *(if applicable)*	**7.DATE SUBMITTED** (YYMMDD)

8. PREPARING ACTIVITY

a. NAME Belvoir Cecom South	b. TELEPHONE *Include Area Code)* (1) Commercial (703)704-3468 (2) AUTOVON DSN 654-3468
c. ADDRESS *(Include Zip Code)* BELVOIR CECOM SOUTH 10115 GRIDLEY ROAD STE 228 FORT BELVOIR, VA 22060-5849	**IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT:** DEFENSE QUALITY AND STANDARDIZATION OFFICE 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22401-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:04Z
Check the source to verify that this is the current version before use.