MIL-C-36337B
19 February 1980
SUPERSEDING
MIL-C-36337A
14 July 1972

MILITARY SPECIFICATION

COOLER, X-RAY FILM PROCESSING UNIT

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers one type of water cooler having a water-cooled refrigeration unit (see 6.1).

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bid or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

BR-F-1421	- Fluorocarbon Refrigerants.
TT-C-490	- Cleaning Methods and Pretreatment of Ferrous Surfaces for Organics Coatings.
TT-E-529	- Enamel, Alkyd, Semi-Gloss.
TT-P-1757	- Primer Coating, Zinc Chromate.
PPP-B-601	- Boxes, Wood, Cleated, Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock Corner.
PPP-B-1055	- Barrier Material, Waterproofed, Flexible.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Defense Personnel Support Center, Directorate of Medical Materiel, DPSC-ATT, 2800 South 20th Street, Philadelphia, PA 19101, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 6525

Source: https://assist.dla.mil -- Downloaded: 202610-21T08:25Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-M-7290 - Manuals, Technical; Commercial Equipment.

STANDARDS

FEDERAL

FED-STD-66 - Steel; Chemical Composition and Hardenability.
FED-STD-595 - Colors.

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-1472 - Human Engineering Design Criteria, Equipment and Facilities.

(Copies of specifications and standards required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bid or request for proposal shall apply.

UNDERWRITERS' LABORATORIES, INC. (UL)

UL 207 (c) Refrigerant Containing Components.
UL 399 Water Coolers.

(Applications for copies should be addressed to the Underwriters' Laboratories, Inc., Walt Whitman Road, Melville, LI, NY 11749, 207 East Ohio Street, Chicago, IL 60611, 1655 Scott Blvd., Santa Clara, CA 95050 and 333 Pfingsten Road, Northbrook, IL 60062.)

3. REQUIREMENTS

3.1 First article. When specified in the procurement document, the contractor shall furnish sample unit(s) for first article inspection and approval (see 4.1.2.1 and 6.2).

Source: https://assist.dla.mil -- Downloaded: 202610-21T08:25Z
Check the source to verify that this is the current version before use.

3.2 Fire and casualty hazards.

3.2.1 The contractor shall provide proof, prior to delivery, that the items to be delivered under the contract conform to the applicable requirements of UL 207(c) and UL 399. Proof shall consist of one of the following:

A. UL label and UL listing of the product, provided the contractor agrees to have Underwriters' Laboratories, Inc. forward a copy of the UL report directly to the contracting officer, upon the latter's request.

B. Laboratory report from a nationally recognized independent laboratory. If an independent laboratory is used, it must be adequately equipped and competent to determine compliance with UL standards. The Government reserves the right to require a facilities report and to conduct a facilities survey. Any laboratory report submitted shall include actual test methods, data taken, and results of tests. Detailed findings of examinations necessary to determine compliance shall also be included. The test report shall also have a section that describes the test sample in such a way that the report can be used to insure identity of production items with the test sample. This section shall be supplemented with construction information such as materials used, spacings between electrical components, types of bushings, photographs, wiring diagrams, sketches, and parts list, all appropriately identified. Compliance with this paragraph does not excuse compliance with all other requirements of the contract and specifications.

3.3 Materials. Satisfactory high-grade materials shall be used throughout. All parts entering into the construction of the equipment covered by this specification shall be fabricated from materials which are entirely satisfactory for the purpose and of sufficient strength to maintain operational alignment for the life of the equipment. All tubing, piping, and fittings shall be made of copper, brass or corrosion-resisting steel. All hardware shall be corrosion-resisting steel, or plated steel.

3.3.1 Refrigerant. Refrigerant shall be dichlorodifluoromethane (CCl_2F_2), conforming to Type 12 of BB-F-1421.

3.3.2 Steel. Unless otherwise specified, steel shall conform to AISI 1008 to 1038 of FED-STD-66.

3.4 Design and construction. The cooler shall be designed to operate satisfactorily from 230 volts, 60 Hertz, single phase, electric power. An outlet box or similar compartment shall be provided for the connection of the incoming power cable. The cooler shall be rated at 18,000 BTUH. All screws used on the construction of the cooler shall be drawn up tight and securely seated in place. Screws or bolts used to mount the compressor shall be suitably locked in place to prevent loosening during use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T08:25Z
Check the source to verify that this is the current version before use.

3.4.1 Housing. The cooler shall be housed in a sturdy, carbon steel cabinet not more than 38 inches in height. The cabinet top shall be flat. Unit shall meet the accessibility for maintenance requirements of MIL-STD-1472.

3.4.1.1 Frame. A frame, constructed of 1 x 1 x 1/8 inch carbon steel angles, shall support the cabinet along its entire perimeter and the underside of the shelf on which the compressor is mounted. The frame joints shall be fully welded.

3.4.2 Refrigeration unit. The refrigeration unit shall be hermetically sealed. The condenser shall be the water cooled type. The suction line to compressor shall be insulated to prevent condensation. A dehydrator containing silica gel or activated alumina shall be provided in the refrigerant line. The dehydrator shall be equipped with an auxiliary screen or other protective means to prevent passage of dessicant in the event of rupture of the cartridge screen outlet. All heat transfer coils and tubing shall be positively secured in position.

3.4.3 Drain plugs. Drain plugs shall be provided which shall permit the condenser coils, water cooling coils, and inlet and outlet pipes to be completely drained. All drain plugs shall be easily accessible and located to preclude the soaking of electrical insulation.

3.4.3.1 Residual water. When tested as specified in 4.5.2, there shall be no residual water in the unit prior to packing for shipment.

3.4.4 Wiring. All wiring shall be located so as to be free from contact with all oil-bearing surfaces and moving parts. All electrical connections shall be in accordance with the applicable UL Standards. The cooler shall pass the dielectric strength test specified in 4.5.2.

3.4.5 Plumbing connections. The external service connections shall be 1/2 inch National Pipe thread female fittings. The inlet, outlet and cooling water connections shall be permanently identified.

3.5 Performance. The cooler shall have all components and controls necessary to deliver continuously 60 $\pm$ 6 gallons per hour (g.p.h.) of water at $68^{0} \pm 1^{0}$ Fahrenheit (F.), with condenser and incoming water at any temperature from 68^{0} to 90^{0}F. and any room temperature from 68^{0} to 98^{0}F., and at any line pressure from 20 to 70 psi. The cooling water shall flow only when the refrigeration unit is operating. No more than 3.5 gallons of condenser water per gallon of cooled water shall be required. The flow of cooled water shall be controlled by an automatic water flow regulator. The regulator and thermostat shall be adjusted by the manufacturer at the factory to maintain the flow of water and the temperature at the specified rate. The cooler shall be tested as specified in 4.5.1.

Source: https://assist.dla.mil -- Downloaded: 202610-21T08:25Z
Check the source to verify that this is the currentversion before use.

3.5.1 Operation and pressure. When tested as specified in 4.5.1.1, all controls and components shall function as specified herein. There shall be no leakage of water or refrigerant from the unit.

3.6 Finish. The entire cabinet and frame, including outside and inside surfaces, shall be finished with acid-, alkali-, and solvent-resisting enamel, before assembly, as follows:

3.6.1 Cleaning and preparation. Cleaning and surface preparation of ferrous metal surfaces shall be accomplished as specified for type I of TT-C-490. All welds shall be thoroughly and completely cleaned of flux, and scale, prior to application of primer.

3.6.2 Primer. After cleaning, all parts shall be given one coat of primer conforming to TT-P-1757.

3.6.3 Enamel. After the primer has been applied, all surfaces shall be covered with two coats of semi-gloss enamel conforming to TT-E-529, class B. Each coat shall be baked on separately for not less than 45 minutes at a temperature of 300°F., or for an equivalent baking period at a higher or lower temperature, as recommended by the paint supplier and approved by the contracting officer. The enamel coats shall be applied so as to produce a final smooth, uniform surface without runs, wrinkles, orange peel or grit. The total dry-film thickness shall not be less than 0.003 inch at any point. Color shall be gray, color No. 26492 of FED-STD-595 (see 6.3).

3.7 Identification marking. Each unit shall be marked permanently and legibly with the following information:

National stock number.
Name or registered trademark of the manufacturer.
Contract or purchase order number.
Type or model number.
Serial number.
Electrical characteristics.
Refrigerant used, expressed in chemical and common form, and amount used.
Factory test pressure.

Source: https://assist.dla.mil -- Downloaded: 202610-21T08:25Z
Check the source to verify that this is the current version before use.

3.8 Service data. The contractor shall furnish, with each unit, two copies each of a technical manual which contains complete instructions for installation, operation, and maintenance and lists of component parts. The manual shall contain instructions for use of a water filter and conditions which require use of the filter (see 6.5). The manual shall comply with the requirements of MIL-M-7298. As soon as practicable after award of the contract or purchase order, the contractor shall furnish to the Contracting Officer, via the cognizant Government inspector, two preliminary copies of his proposed technical manual for review and comment by the Directorate of Medical Materiel, Defense Personnel Support Center. The preliminary manuals shall be submitted sufficiently early to permit adequate review by the Directorate of Medical Materiel, Defense Personnel Support Center (based on a maximum period of 30 days for such review) and to allow incorporation by the contractor of any required revisions and corrections in the final manual without delaying delivery under the contract, or purchase order. In addition, the Contractor shall furnish 15 copies of the approved technical manual to the Contracting Officer for distribution. Should the supplier have furnished acceptable manuals for the identical item within two years preceding the date of the contract and propose to furnish manuals identical with those previously accepted, then the requirements for review of drafts and submission of 15 additional copies shall be at the option of the Government.

3.9 Welding. Welding shall be durable, sound in every detail and in accordance with the latest practices recommended by the American Welding Society. All welds shall be produced by qualified welding operators with satisfactory welding equipment using satisfactory filler metal or electrode where applicable to provide the best possible weld. Surfaces to be welded shall be free from grease, oil, oxides or any other foreign matter. Any cleaning method which will remove these substances and leave the surface clean is satisfactory. All weld joints shall blend into the adjacent metal in gradual, smooth curves. Welds shall be smooth and free of slag, excessive undercut, or excessive splatter. Sufficient metal shall be added to provide a suitable fillet or reinforcement unless otherwise specified. Welds shall not be oxidized. All welds shall have no visible voids, pin holes, or cracks. Welds, except spot welds, shall be continuous.

3.10 Workmanship. Workmanship shall be first class throughout. The cooler shall be rigidly constructed for strength and durability. All exposed edges, if not hemmed, beaded, or flanged, shall be smoothly finished to remove all sharp edges. The finished cooler shall be clean, well made, and free from any defect which affects its appearance or may impair its serviceability.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T08:25Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Records. Records of examinations and tests performed by or for the contractor shall be maintained by the contractor and made available to the Government, upon the Government's request, at any time, or from time to time, during the performance of the contract and for a period of three years after delivery of the supplies to which such records relate.

4.1.2 Inspection. Inspection, as used in this specification, is defined as both examination (such as visual and auditory investigation without the use of special laboratory appliances or procedures) and testing (determination by technical means of physical and chemical properties) of the item.

4.1.2.1 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection.
b. Quality conformance inspection.

4.1.2.1.1 First article inspection. First article inspection shall be performed on one unit when a first article sample is required (see 3.1). This inspection shall include examination of 4.3 and tests of 4.5.

4.1.2.1.2 Quality conformance inspection. Quality conformance inspection shall include the examination of 4.3 and tests of 4.5.

4.1.3 Certificates of quality. Certificates of quality, supplied by the manufacturer of the materials may be furnished in lieu of actual performance of such testing by the contractor, provided lot identity has been maintained and can be demonstrated to the Government. The certificate shall include the name of the contractor, the contract number, the name of the manufacturer or supplier, the NSN, the Item Identification, the name of the component/material, the lot number, the lot size, the sample size, the date of testing, the test method, individual test results, and the specification requirements.

Source: https://assist.dla.mil -- Downloaded: 202640-21T08:25Z
Check the source to verify that this is the currentversion before use.

4.1.4 Inspection lot.

4.1.4.1 Raw materials. An inspection lot for raw material inspection shall be all material produced under the same conditions and controlled to the degree that uniformity of product within the designated lot can be assured. Lot identification of the raw material by the manufacturer is one method of control, as cited above, which is considered acceptable.

4.1.4.2 End product. An inspection lot for inspection of end product shall consist of all coolers of the same type produced under essentially the same conditions and offered for inspection one time.

4.2 Sampling.

4.2.1 For examination. Sampling for examination shall be conducted in accordance with MIL-STD-105 and table I.

TABLE I. Sampling for examination.

	Inspection level	AQL (defects per hundred units)
For visual examination		
Major defects	II	1.0
Major and Minor combined	II	4.0
For dimensional examination	S-1	2.5

4.2.2 For tests. The coolers shall be subjected to the tests indicated in table II.

TABLE II. Sampling for tests.

Characteristic	Requirement	Test procedure	Inspection level	AQL
Performance Operation and Pressure	3.5	4.5.1	S-2	Zero
	3.5.1	4.5.1.1	100%	Reject defective units
Dielectric strength	3.4.4	4.5.2	100%	Reject defective units
Residual water	3.4.3.1	4.5.3	100%	Reject defective units

Source: https://assist.dla.mil -- Downloaded: 202610-21T08:25Z
Check the source to verify that this is the current version before use.

4.2.3 Raw materials. A sufficient quantity of each lot of each metal used in the manufacture of the cooler shall be selected for chemical analysis.

4.3 For examination. The coolers shall be examined to determine compliance with all requirements contained in this specification.

4.3.1 Classification of defects. Examination shall be conducted in accordance with the following classification of defects, as shown in table III. Examination shall not be restricted to the classified possible defects listed below.

TABLE III. Classification of defects.

Categories	Defects
Major	
101	Cooler not complete with all required parts, subassemblies, and materials.
102	Components and parts not free of cracks, tears, ruptures, and deformed surfaces.
103	Components, mating parts, loose or not properly aligned and fitted.
104	Seam or fillet welds have burn holes, are cracked, fractured or otherwise not fused.
105	Spot welds not sound.
106	Exposed or accessible edges, corners, and surfaces not free of burrs, sharpness, and sharp projections.
107	Heat transfer coils or tubing not positively secured in place.
108	Solder or brazing not adherent.
109	Compressor not securely mounted in place.
110	Components in the electrical system not in accordance with requirements.
111	Electrical systems in units not consistent in layout and neatly wired.
112	Insulation of wire connectors not clear of, or protected from, framework edges to avoid occurrence of shock hazard or shorts due to vibration.
113	Electrical wiring not free of cracks, breaks, and cuts in the insulation.
114	Electrical system not free of taut leads, loose or improperly fastened terminal connections, and poor solder joints.
115	Does not meet accessibility for maintenance requirements in 3.4.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T08:25Z
Check the source to verify that this is the current version before use.

TABLE III. Classification of defects. - Continued

Categories	Defects
Minor	
201	Overall dimensions not within specified limits.
202	Fasteners not tight.
203	Finish not free of chipped areas, blisters, peeling, thin areas, cracks, scratches or roughness.
204	Marking, including piping connection markings, not present, properly located, legible, correct or permanently affixed.
205	Service data not present in duplicate.
206	Unit not clean, dry.
207	Slags in welds, welds undercut; scale or flux not removed, not free of pitting, splatter and discoloration.
208	Soldering or brazing not clean.

4.3.2 Dimensional examination. The cooler shall be examined for defects in dimensions. Any dimension not within the tolerances specified herein shall be classified as a defect.

4.4 Packaging inspection. The inspection of the unit packaging, packing and marking for shipment and storage shall be in accordance with quality assurance provisions of the applicable container specification and the marking requirements of MIL-STD-129.

4.5 Tests. Tests shall be conducted to determine compliance with specification requirements. All measurements shall be accurate within one percent.

4.5.1 Performance. The cooler shall be set-up in accordance with the manufacturer's instructions and operated for a period of not less than one hour. The test shall be conducted in an ambient temperature of not less than 98^{0} F. The condenser water and inlet water shall have a temperature of not less than 90^{0} F. Data shall be taken with inlet water temperature 20 $\pm$ 2 psi and 70 $\pm$ 2 psi. The temperature of the outlet water and the rate of flow of the outlet water shall be determined at both of the above pressures. The rate of flow of condenser water shall be determined and compared to the rate of flow of cooled water. It shall also be determined if the condenser water is shut off when the cooler is not operating.

Source: https://assist.dla.mil -- Downloaded: 202610-21T08:25Z
Check the source to verify that this is the currentversion before use.

4.5.1.1 Operation and pressure. Each unit shall be operated in accordance with the manufacturer's directions to determine whether all controls and components are functioning as specified without any leakage of water. Pressure tests shall be performed in accordance with the "Manufacturing and Production Tests" of UL 399, using a leak detector capable of detecting refrigerated leaks of 0.5 ounces, or less, per year (see 3.3.1 and 6.9).

4.5.2 Residual water. The unit shall be visually examined to insure that there is no residual water present anywhere in the unit.

4.5.3 Dielectric strength. The unit shall pass the dielectric strength test specified in UL 399.

4.5.4 Chemical composition. Four ounces from each lot of material shall be tested in accordance with FED-TEST METHOD STD-151.

5. PACKAGING

5.1 Packaging. Packaging shall be level A or C, as specified (see 6.1).

5.1.1 Unit of issue. One cooler, as specified, constitutes one unit of issue.

5.1.2 Level A.

5.1.2.1 Unit packaging. The refrigerating unit shall be locked in position in such a manner as to prevent vibration or movement. The exterior surfaces of the unit shall be protected by wrapping kraft paper and cushioning with excelsior pads, paper pads, or other suitable materials. Wrapping and cushioning materials shall be secured by tying with twine or by sealing with kraft gummed paper tape. Work shall be accomplished in such a manner as to insure against marring, scratching, or damage to the unit.

5.1.3 Level C. Each cooler shall be packaged in a manner that will afford adequate protection against cororsion, deterioration and physical damage during shipment from the supply source to the first receiving activity.

5.2 Packing. Packing shall be level A, B or C, as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T08:25Z
Check the source to verify that this is the current version before use.

5.2.1 Level A. Each unit shall be overpacked in an exterior container designed for type 3 load, and constructed in accordance with PPP-B-601, overseas type or PPP-B-621, class 2. Closure and strapping shall comply with appendix thereto. The unit shall be adequately secured within the exterior container by means of bolts, wood braces, or other interior fittings, to insure against shifting or breakage. Each unit shall be protected by a shroud fabricated of waterproof barrier material conforming to PPP-B-1055, class L-2. The exterior container design shall include three skids of not less than 1-1/2 inches in thickness applied crosswise of base, so positioned as to facilitate handling with a forklift truck and to maintain unit in an upright position.

5.2.2 Level B. Each unit shall be overpacked in an exterior container constructed in accordance with PPP-B-621 class 1, or PPP-B-601, domestic type. Closure and strapping shall comply with appendix thereto. The unit shall be adequately secured within the exterior container by means of bolts, wood braces, or other interior fittings, to insure against shifting or breakage. The exterior container design shall include three skids or not less than 1-1/2 inches in thickness applied crosswise of base, so positioned as to facilitate handling with a forklift truck and to maintain unit in an upright position.

5.2.3 Level C. The packaged coolers shall be packed in shipping containers in a manner that will afford adequate protection against damage during direct shipment from the supply source to the first receiving activity. These packs shall conform to the carrier's rules and regulations.

5.3 Marking. Marking shall be as specified in MIL-STD-129.

6. NOTES

6.1 Intended use. This item is intended to provide cooled water (68° F.) at a flow rate of 60 gallons per hour to manual type X-ray film processors.

6.2 Ordering data. Procurement documents should specify the following information:

a. Title, number and date of this specification.
b. Selection of applicable levels of packaging and packing required (see 5.1 and 5.2).
c. When a first article is required (see 3.1 and 6.8).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T08:25Z
Check the source to verify that this is the current version before use.

6.3 Availability of color chips. The individual 3 by 5 inch chips of the color referenced in 3.5.3 are available from the Naval Publications and Forms Center, 5801 Tabor Avenue, Philadelphia, PA 19120.

6.4 The water cooler shall be suitable for use with manual processing units such as:

National Stock Number	Item Identification
6525-00-616-7651	PROCESSING UNIT, X-RAY FILM, 2 COMPARTMENT
6525-00-571-9502	TANK, MASTER, X-RAY FILM PROCESSING (MUST SHELTER)

6.5 Water filter noted in 3.8 is covered by National Stock Number 4330-00-028-6754.

6.6 This specification covers the following item appearing in the Federal Supply Catalog:

National Stock Number	Item Identification
6525-00-299-8269	COOLER, X-RAY FILM PROCESSING UNIT, 60 gal. Capacity per Hour, 220 volt, 60 Hz, AC.

6.7 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

6.8 First article. When a first article is required, it shall be tested and approved under the appropriate provisions of the Defense Acquisition Regulation. The contract or purchase order specifies the quantity, procedure for delivery and other specific instructions for inspection and approval of the first article.

6.9 Leak detector. General Electric Co.'s model H-10 electronic leak detector can meet the leak detection capabilities required in 4.5.1.1.

Custodians:
Army - MD
Navy - MS
Air Force - 03

Preparing activity:
DLA - DM

Project No. 6525-1137

Review activity:
DoD - MB

Source: https://assist.dla.mil Downloaded: 2026-10-21T08:25Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T08:25Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.

NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE

MIL-C-36337B COOLER, X-RAY FILM PROCESSING UNIT

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1 OCT 76 1426

EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 202640-21T08:25Z
Check the source to verify that this is the current version before use.

FOLD

DEFENSE PERSONNEL SUPPORT CENTER
2800 SOUTH 20TH STREET
PHILADELPHIA, PA 19101

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

POSTAGE AND FEES PAID



DEFENSE PERSONNEL SUPPORT CENTER
DIRECTORATE OF MEDICAL MATERIEL, CODE ATT
2800 SOUTH 20TH STREET
PHILADELPHIA, PA 19101

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T08:25Z
Check the source to verify that this is the current version before use.