MIL-B-13587E(ME)
16 September 1986
SUPERSEDING
MIL-B-13587D(ME)
30 October 1973

# MILITARY SPECIFICATION

## BIN, STORAGE, AGGREGATE, PORTABLE, 60 TON

This specification is approved for use within the USA Belvoir Research, Development, and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

## 1. SCOPE

1.1 Scope. This specification covers a one-compartment, 60-ton-capacity, portable aggregate storage bin for use in the loading of trucks.

## 2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications, and standards form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto, cited in the solicitation.

SPECIFICATIONS

FEDERAL

| | |
|---|---|
| QQ-S-781 | - Strapping, Steel, and Seals. |
| TT-V-121 | - Varnish, Spar, Water Resisting. |
| UU-T-81 | - Tags, Shipping and Stock. |
| PPP-B-601 | - Boxes, Wood, Cleated-Plywood. |

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development, and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 3895
DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

| | |
|---|---|
| PPP-H-1581 | - Hardware (Fasteners and Related Items), Packaging of. |
| PPP-P-40 | - Packaging and Packing of Hand Tools. |

MILITARY

| | |
|---|---|
| MIL-P-116 | - Preservation, Methods of. |
| MIL-R-196 | - Repair Parts Accessories, and Kits, Mechanical, Packaging of. |
| MIL-P-514 | - Plate, Identification, Instruction and Marking, Blank. |
| MIL-T-704 | - Treatment and Painting of Materiel. |
| MIL-C-3774 | - Crate, Wood; Open, 12,000- and 16,000-Pound Capacity. |
| MIL-C-46168 | - Coating Aliphatic, Polyurethane, Chemical Agent Resistant. |

STANDARDS

FEDERAL

| | |
|---|---|
| FED-STD-H28 | - Screw-Thread Standards for Federal Services. |

MILITARY

| | |
|---|---|
| MIL-STD-105 | - Sampling Procedures and Tables for Inspection by Attributes. |
| MIL-STD-129 | - Marking for Shipment and Storage. |
| MIL-STD-130 | - Identification Marking of US Military |
| MIL-STD-889 | - Dissimilar Metals. |
| MIL-STD-1186 | - Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with Appropriate Test Methods. |

(Copies of specifications and standards, required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted shall be those listed in the issue of the DoDISS specified in the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS shall be the issue of the non-government documents which is current on the date of the solicitation.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

| | |
|---|---|
| A 36 | - Structural Steel. |
| A 120 | - Pipe, Steel, Black and Hot-Dipped Zinc-Coated (Galvanized) Welded and Seamless Steel Pipe for Ordinary Uses. |
| A 575 | - Steel Bars, Carbon Merchant Quality, M-Grades. |
| D 3951 | - Standard Practices for Commercial Packaging. |



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

Steel Construction Manual.

(Application for copies should be addressed to the American Institute of Steel Construction, 101 Park Avenue, New York, NY 10017.)

AMERICAN WELDING SOCIETY, INC. (AWS)

D1.1 - Structural Welding Code - Steel.

(Application for copies should be addressed to the American Welding Society, Inc, 2501 NW 7th Street, Miami, FL 33125.)

(Non-Government standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The bin shall be of steel construction and shall be of the bolted, knockdown, single-compartment type with a gate at the bottom for loading trucks. The bin shall have a heaped capacity of not less than 60 tons based on aggregate weighing not less than 100 pounds per cubic foot by commercial standards. The bin shall be provided with four supporting steel columns and with support braces located in such a manner to create a passageway under the bin with the sides formed by cross bracing. Lateral clearance of the passageway shall be not less than 11 feet, and vertical clearance shall be not less than 10 feet from the lowest point of the bin gate to the top of the base plates. The inside dimensions of the bin measured at the top, shall be not more than 12 feet 10 inches square. The slope of the sides of the bin hopper shall be not less than 45 degrees from the horizontal. With the gate fully open, the bin shall discharge completely when loaded with aggregate.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 4.3 and 6.3). Any changes or deviations of bins from the approved first article during production will be subject to the approval of the contracting officer. Approval of the first article will not relieve the contractor of his obligation to furnish bins conforming to this specification.



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

3.3 Materials. Materials shall be as specified herein. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The bin shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operation and storage environment to which the bin may be exposed.

3.3.2 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.3 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.3.4 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the bin may be newly fabricated from recovered materials to the maximum extent practicable, provided the bin produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the bin.

3.3.5 Structural steel. Structural steel shall conform to ASTM A 36.

3.3.6 Steelbar and pipe. Steelbar shall conform to ASTM A 575 and pipe shall conform to ASTM A 120.

3.4 Construction details. The bin sidewalls shall be made of steel not less than 3/16 inch in nominal thickness and the sloping bottom plates shall be not less than 1/4 inch in nominal thickness. Steel columns shall be constructed in accordance with the requirements of the AISC Steel Construction Manual to withstand the weight of the bin loaded to maximum capacity and the weight of the structural members when subjected to a wind load of not less than 20 pounds per square foot. Each column shall be provided with a base plate having not less than two holes to accommodate bolts not less than 1 inch in diameter. Support braces and bin stiffeners shall be provided and located to provide a safety factor of not less than 1.5 based on the minimum yield point of the material used. Bolts used in the construction of the bin and for fastening the braces shall be provided and spaced so as to have a safety factor of 4 in shear based on the minimum ultimate tensile strength of the material used for the bolts and with the bin filled to maximum capacity. The bin gate shall be of the single- or double-clam type constructed of cast steel or fabricated from structural steel. The clear opening of the bin gate shall be not less than 200 square inches. A manual control shall be provided for the bin gate which shall permit a variable gate opening between wide open and closed. The control shall be



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

accessible to an operator standing on the ground at a safe distance from bin discharge and shall provide sufficient leverage to open and close the gate on the fully loaded bin. The control shall be labeled "GATE CONTROL" and shall be provided with a double-ended arrow showing direction of operation and labeled at each end (OPEN and CLOSE) to indicate the functional result. Two complete sets of step-by-step erection drawings shall be furnished with each bin. Each part shall be identified with a part number corresponding to the part number on the erection drawings. When loaded to capacity, the bin shall show no visual evidence of distortion or permanent deformation of any part, member, or supporting structure, or failure of any welded or bolted connection. The bin shall be assembled and disassembled without being cut or welded and each section of the bin weighing 100 or more pounds shall be provided with removable lifting attachments. Disassembly shall be accomplished in not more than 6 hours, with a total of not more than 24 manhours. When disassembled, no part of the bin shall exceed 13 feet in length and 8 feet in width.

3.4.1 Screw threads. All screw threads shall be in accordance with FED-STD-H28.

3.5 Identification marking. The bin shall be identified in accordance with MIL-STD-130. The marking shall be applied to the bin on plates conforming to MIL-P-514, type I, style 3, composition C. Plates shall be attached by screws, bolts, or rivets in a conspicuous protected location.

3.6 Treatment and painting. The portions of the storage bin normally painted shall be cleaned, treated, and painted in accordance with MIL-T-704, type F or G, as applicable. Unless otherwise specified (see 6.2) top coat color shall be camouflage green 383 conforming to MIL-C-46168. The storage bin shall then be overcoated in accordance with the Government furnished camouflage patterns with MIL-C-46168 top coat of the colors specified in the camouflage patterns, with the exception that the first article may be camouflage green 383.

3.7 Data for camouflage patterns. The contractor shall generate camouflage pattern data (see 6.2).

3.8 Government-furnished property. The following property will be furnished by the Government (see 6.7).

| Item No. | Description | Identification | Quantity |
|---|---|---|---|
| 1 | Pattern drawings | Camouflage patterns | As required |

3.9 Workmanship. All parts, components, and assemblies of the storage bins including castings, forgings, molded parts, stampings, bearings, seals, machined surfaces, and welded parts shall be clean and free from sand, dirt, fins, pits, sprues, scale, flux, and other harmful extraneous material. External surfaces shall be free of burrs and sharp edges.



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

3.9.1 Steel fabrication. Steel used in the fabrication of the equipment shall be free from kinks and sharp bends. The forming of material shall be done by methods that will not cause damage to the metal. Corners shall be square and true. Burned surfaces of flame-cut material shall be ground to remove slag. Precautions shall be taken to avoid overheating, and heated metals should be allowed to cool slowly. All bends of a major character shall be made with metal dies or fixtures to insure uniformity of size and shape.

3.9.2 Bolted connections. Bolt holes shall be accurately formed or drilled and shall have the burrs removed. Washers or lockwashers shall be provided where necessary. All bolts, nuts, and screws shall be correctly torqued. Matching threaded areas securing bolts or cap screws shall withstand all stresses imposed by the bolt.

3.9.3 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, and other foreign matter. Welds shall transmit stress without permanent deformation or failure when the parts connected by the welds are subjected to proof and service loadings. Welding shall be in accordance with AWS D1.1 Structural Welding Code - Steel. Welds shall be free from discontinuities such as base metal cracks adjacent to or behind welds, cracks in the weld metal, lack of fusion with parent metal or between parts, incomplete penetration, lack of prescribed fit, or spatter.

3.9.3.1 Qualifications for welders and welding equipment operators. The contractor shall be responsible for qualifying all welders and welding equipment operators in accordance with AWS D1.1 using the contractor's or manufacturer's qualified welding procedure. The Government may require the recertification of any welder or welding operator. The contractor shall make certification available for inspection by the contracting officer or designated representative upon request.

3.10 Safety. The storage bin shall be provided with a grating as means of guarding the top opening. The grating shall not materially obstruct the opening but will be substantially constructed to prevent persons from falling in.

## 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.2 Classification of inspection. Inspections shall be classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection comparison (see 4.6).
d. Inspection of packaging (see 4.7).

4.3 First article inspection.

4.3.1 Examination. The first article bin shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Test. The first article bin shall be tested as specified in 4.5.2.1 through 4.5.2.4. Failure of any test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Examination. Each bin shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The bin shall be examined for the following defects:

101. Dimensions not as specified.
102. Material not as specified.
103. Materials are not resistant to corrosion or deterioration or treated to be made resistant to corrosion or deterioration for the applicable storage and operating environment.
104. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other.
105. Contractor does not have documentation available for identification of material, material finishes or treatments.
106. Used, rebuilt or remanufactured components, pieces, or parts incorporated in the bin.
107. Steel columns not constructed as specified.
108. Base plate not as specified.
109. Safety not as specified.
110. Gate not single- or double-clam type.
111. Bin gate opening less than 200 square inches.
112. Manual control to bin gate not as specified or not accessible.
113. Two complete sets of erection drawings not furnished.
114. Assembly instructions not complete or not correct.
115. Parts or components missing or do not function.
116. Threads not as specified.
117. Identification marking not as specified.



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

118. Lifting attachments missing.
119. Treatment and painting not as specified.
120. Color not as specified.
121. Camouflage pattern data not as specified.
122. Camouflage patterns not as specified.
123. Workmanship not as specified.
124. Steel fabrication not as specified.
125. Bolted connections not as specified.
126. Welding not as specified.
127. Welders not qualified as specified.

4.5.2 Tests. The bin shall be tested as follows.

4.5.2.1 Assembly. Erect the bin in accordance with the erection drawings (see 3.4). A suitable crane shall be used during assembly. Eyes provided on the bin components shall be used during assembly. Measure the lateral and vertical clearance of the passageway. Inability to erect the bin in accordance with the step-by-step procedures on the drawings (see 3.4), clearance not as specified in 3.1, or any permanent damage to the lifting eyes shall constitute failure of this test.

4.5.2.2 Loading. Load the bin with 60 tons of aggregate weighing the equivalent of not less than 100 pounds per cubic feet. Inability of the bin to hold the specified capacity, or visual evidence of distortion or permanent deformation of any part, member, supporting structure, or welded or bolted connection shall constitute failure of this test.

4.5.2.3 Operational. Drive trucks under the loading-bin gate. Open and close the gate as each truck is loaded until the bin is completely empty of aggregate. Inability of the bin gate to be full-opened or closed by one operator, or failure of the bin to discharge (without aid) all the aggregate when the gate is open shall constitute failure of this test.

4.5.2.4 Sectionalization. Disassemble the bin after completion of the operational test using a suitable crane and the lifting eyes provided on the applicable bin components. Failure of the bin to be disassembled within 6 hours, with a total of not more than 24 manhours, into parts not more than 13 feet long nor more than 8 feet wide; or any permanent damage to the lifting eyes or to the components to which they are attached shall constitute failure of this test.

4.6 Inspection comparison. The Government may select bins at any time during the contract production period and subject these bins to the examination specified in 4.5.1 and the tests specified in 4.5.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government, on units selected at random from those which have been accepted by the Government and will not include the previously inspected first article bins. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

4.6.1 Inspection failure. Failure of any bin to meet any requirement specified herein during and as a result of the examination and tests specified in 4.6 shall be cause for rejection of the bin and shall be cause for refusal by the Government to continue acceptance of production bins until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on bins produced and accepted under the contract since approval of the first article bin. Any deficiencies found as a result of inspection comparison inspection will be considered prima facie evidence that all bins accepted after approval of the first article bin are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.7 Inspection of packaging.

4.7.1 First article packaging inspection. The first article packaging inspection shall be as follows.

4.7.1.1 Examination. The first article packaging shall be examined for the defects listed in 4.7.2.3. Presence of one or more defects shall be cause for rejecting the first article packaging. Any deficiencies shall be corrected and the packaging re-examined for conformance with the specification.

4.7.1.2 Test. First article packaging shall be tested for its adequacy in accordance with the rail-impact test as set forth in appendix A to MIL-STD-1186.

4.7.1.2.1 Test failure criteria. Failure of the test shall be based on the failure criteria set forth in MIL-STD-1186. Any deficiencies shall be corrected and the packaging retested.

4.7.2 Quality conformance inspection of pack.

4.7.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.7.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.7.2.3 Examination. Samples selected in accordance with 4.7.2.2 shall be examined for the following defects. Acceptable quality level (AQL) shall be 1.0 percent defective.

| | | A | COMM. |
|---|---|---|---|
| 128. | Disassembly not as specified | 5.2 | 5.2 |
| 129. | Matchmarking not as specified. | 5.3 | 5.3 |
| 130. | Unpainted surfaces not preserved as specified. | 5.4.1.2 | |
| 131. | Applicable components and assemblies not bundled as specified. | 5.4.1.3 | |
| 132. | Bundles not secured with two or more of the specified straps. | 5.4.1.3 | |
| 133. | Bolts, nuts and washers not preserved as specified. | 5.4.1.4 | |



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

| | | | | |
|---|---|---|---|---|
| 134. | Technical publications and erection drawings not preserved as specified. | 5.4.1.5 | | |
| 135. | Repair parts, when required, not preserved as specified. | 5.4.1.6 | | |
| 136. | Maintenance tools, when required, not preserved as specified. | 5.4.1.7 | | |
| 137. | Consolidation not as specified. | 5.4.1.8 | | |
| 138. | Commercial preservation not as specified. | | 5.4.2 | |
| 139. | Packing not as specified. | 5.5.1 | 5.5.2 | |
| 140. | Marking not as specified. | 5.6.1 | 5.6.2 | |

5. PACKAGING.

5.1 First article packaging (preproduction pack). The contractor shall furnish a first article pack for examination and testing within the time frame specified (see 6.2), to prove, prior to starting production packaging, that the applied preservation, packing and marking comply with the requirements of this specification. Examination and testing shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article pack may be accomplished by utilizing either the first article storage bin or a production storage bin. When the first article storage bin is utilized, and the Government requests a comparison between the first article bin and a production bin, any preservation and packing shall be removed by the contractor at no expense to the Government.

5.2 Disassembly. The bin shall be disassembled in accordance with the manufacturer's recommendations, and in a manner to comply with the requirements of 3.4 and to reduce cubage to a reasonable minimum.

5.3 Matchmarking. To facilitate assembly, large parts and assemblies shall be matchmarked with lusterless white enamel, overcoated with water-resisting clear spar varnish conforming to TT-V-121. Small parts and assemblies shall have the matchmaking information on cloth shipping tags conforming to UU-T-81, type A. Tags shall be marked tags with waterproof ink. The marked tags shall be attached to mating parts and assemblies.

5.4 Preservation. Preservation shall be level A or commercial, as specified (see 6.2).

5.4.1 Level A.

5.4.1.1 Preservative application and selection. The provisions of MIL-P-116 shall apply when selecting and determining the applicability of preservatives. Preservatives specified herein by "P" numbers shall conform to the applicable specifications listed in MIL-P-116 and shall be applied in accordance with MIL-P-116.

5.4.1.2 Unpainted surfaces. Unpainted metal surfaces of bin components requiring the application of a contact preservative (see 5.4.1.1), shall be coated with type P-1 preservative.



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

5.4.1.3 Components and assemblies. The components and assemblies shall be prepared for shipment as single pieces, or bundled together in quantitites most convenient to handle and to accomplish the packing specified herein. Each bundle shall be secured with not less than two straps conforming to QQ-S-781, type I or IV, finish B, size as applicable.

5.4.1.4 Bolts, nuts and washers. Bolts, nuts and washers shall be preserved in accordance with the level A preservation requirements of PPP-H-1581. The application of unit containers and intermediate containers shall be as specified therein except that the quantity per container(s) shall be limited to the quantities required for the assembly of one complete bin.

5.4.1.5 Technical publications and erection drawings. Technical publications and erection drawings for each bin shall be preserved in accordance with MIL-P-116, method IC-1 or IC-3.

5.4.1.6 Repair parts. Repair parts, when required (see 6.5), shall be preserved in accordance with the level A requirements of MIL-R-196. Parts not specifically mentioned therein shall be preserved as specified for parts of similar design and construction.

5.4.1.7 Maintenance tools. Maintenance tools, when required (see 6.5), shall be preserved in accordance with the level A preservation and packaging requirements of PPP-P-40.

5.4.1.8 Consolidation. Bolts, nuts, washers, technical publications erection drawings, repair parts and maintenance tools when required, and any other small component requiring the protection afforded by a wood box to prevent damage or loss, shall be consolidated together in the quantities required for one bin, into one or more close-fitting boxes as practicable, conforming to PPP-B-601, domestic type, style optional. The contents shall be cushioned, blocked and braced within the box to prevent free movement or damage. Box closure shall be as specified in the appendix thereto. Strapping shall not be required.

5.4.2 Commercial. The complete bin, disassembled and matchmarked as specified in 5.2 and 5.3 respectively, shall be preserved in accordance with ASTM D 3951.

5.5 Packing. Packing shall be level A or commercial as specified (see 6.2).

5.5.1 Level A. The components comprising a completed bin, disassembled as specified in 5.2, matchmarked as specified in 5.3 and preserved as specified in 5.4, shall be packed in one or more crates, as applicable, conforming to MIL-C-3774, type I, style A. Anchoring, bracing and blocking shall be in accordance with MIL-STD-1186.

5.5.2 Commercial. The components comprising a complete bin, disassembled as specified in 5.2, matchmarked as specified in 5.3 and preserved as specified in 5.4, shall be packed in accordance with ASTM D 3951.

5.6 Marking.



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

5.6.1 Level A. In addition to any special or identification marking required by the contract or purchase order, markings for level A shall be in accordance with MIL-STD-129.

5.6.2 Commercial. Commercial marking shall be as specified in ASTM D 3951. Additionally, each shipping container shall be marked with the cube and gross weight.

6. NOTES

6.1 Intended use. The aggregate storage bin is intended for use during the construction of military roads and airfields.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.
b. Time frame required for submission of first article bin (see 3.2).
c. When the Government will conduct any or all of the first article examination and test. When the Government will conduct some but not all of the first article examination and tests, the contracting officer should specify which examination and tests will be conducted by the Government and which examination and tests shall be conducted by the contractor (see 3.2).
d. Color required when other than as specified (see 3.6).
e. Time frame when camouflage pattern data is required (see 3.7).
f. Time frame required for submission of first article pack (see 5.1).
g. Degree of preservation and degree of packing (see 5.4 and 5.5 respectively).
h. Any special marking (see 5.6.1).

6.2.1 Data requirements. When this specification is used in an acquisition which incorporates a DD Form 1423, Contract Data Requirements List (CDRL), the data requirements identified below shall be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with he approved CDRL incorporated into the contract. When the provisions of DOD FAR Supplement, Part 27, Sub-Part 27.410.6 are invoked and the DD Form 1423 is not used, the data specified below shall be delivered by the contractor in accordance with the contract or purchase order requirements. Deliverable data required by this specification is cited in the following paragraphs:

| Paragraph No. | Data requirements | Applicable DID No. |
|---|---|---|
| a. 3.7 | Color Photograph Prints | DI-MISC-80192 |
| b. 3.7 | Camouflage Line Art Data | DI-MISC-80176 |

6.3 First article. When a first article inspection is required, the items should be preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, tests, and approval of the first article test results and disposition of the first article.



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

6.4 First article pack. Any deviation or change of the production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the contractor of his obligation to preserve, pack, and mark the bins in accordance with this specification.

6.5 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment of bins.

6.6 Degrees of packing. Degrees of packing have not been specified as the packing specified is applicable for all degrees of packing. For purposes of preservation/packing level marking the marking shall be level A.

6.7 Government-furnished property. The contracting officer should arrange to furnish the property listed in 3.8.

6.8 Subject term (Key word) listing.

Aggregate bin
Bin
Bin - 60 Ton
Bin stationary
Cold feed bin
Hopper
Knockdown bin
Portable bin
Single Compartment bin
Storage bin

6.9 Changes from previous issue. Asterisks (or vertical lines) are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army - ME

Preparing activity:
Army - ME

Review activity:
DLA - CS

Project 3895-A225

User activity:
Army - MT



Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.

# STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

*(See Instructions – Reverse Side)*

| 1. DOCUMENT NUMBER | 2. DOCUMENT TITLE |
|---|---|
| MIL-B-13587E(ME) | Bin, Storage, Aggregate, Portable, 60-Ton |

| 3a. NAME OF SUBMITTING ORGANIZATION | 4. TYPE OF ORGANIZATION *(Mark one)* |
|---|---|
| | ☐ VENDOR |
| b. ADDRESS *(Street, City, State, ZIP Code)* | ☐ USER |
| | ☐ MANUFACTURER |
| | ☐ OTHER *(Specify)*: _____ |

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

| 7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional | b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional |
|---|---|
| c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional | 8. DATE OF SUBMISSION *(YYMMDD)* |

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:53Z
Check the source to verify that this is the current version before use.