MIL-F-2473D
23 May 1969
SUPERSEDING
MIL-F-2473C
3 March 1967
(see 6.6)

MILITARY SPECIFICATION

FLOUR HANDLING PLANTS

The specification is mandatory for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope.- This specification covers mechanical flour handling plants.

1.2 Classification.- The flour handling plants shall be mechanical with a dump bin flour capacity of 800 to 1000 pounds, and of the following styles as specified (see 6.2).

Style 1 - With a traveling weighing hopper to service more than one mixer.
Style 2 - With a fixed weighing hopper to service one mixer.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

CC-M-636 - Motors, Alternating-Current, (Fractional Horsepower)
CC-M-641 - Motor, Alternating Current, (Integral Horsepower, 200 HP and Smaller).

FSC 3605

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

QQ-N-281 - Nickel-Copper Alloy Bar, Rod, Strip, Wire, Forgings, and Structural and Special Shaped Sections.
QQ-W-423 - Wire, Steel, Corrosion-Resisting.

MILITARY

MIL-B-2316 - Bakery Equipment, Including Unit Assemblies, Repair Parts and Tools, Preparation For Delivery Of.
MIL-F-3541 - Fittings, Lubrication.
MIL-T-10727 - Tin Plating, Electrodeposited or Hot Dipped, For Ferrous and Nonferrous Metals.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables For Inspection By Attributes.
MIL-STD-130 - Identification Marking Of U. S. Military Property.
MIL-STD-461 - Electromagnetic Interference Characteristics, Requirements for Equipment.
MIL-STD-462 - Electromagnetic Interference Characteristics, Measurement of.

(Copies of specifications and standards required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

2.2 Other publications.- The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

Baking Industry Sanitation Standards Committee (BISSC)

Standard No. 1 - Flour Handling Equipment For Bakeries

(Application for copies should be addressed to the Baking Industry Sanitation Standards Committee, 521 Fifth Ave., New York, N. Y. 10017).

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

UNDERWRITERS' LABORATORIES, INC. (UL)

Electrical Construction Materials List

(Application for copies should be addressed to the Underwriters' Laboratories, Inc., 207 East Ohio Street, Chicago, Illinois 60611; 1285 Walt Whitman Road, Melville, L. I., New York 11746; or 1655 Scott Boulevard, Santa Clara, California 95050.)

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

Standard MG-1 - Motors and Generators (1967)

(Application for copies of NEMA Standard MG-1 may be made to the National Electrical Manufacturers Association, 155 East 44th Street, New York, N. Y. 10017.)

Technical society and technical association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal Agencies.

3. REQUIREMENTS

3.1 First article.- When specified (see 6.2) before production is commenced, a sample flour handling plant covered by this specification, shall be submitted or made available to the contracting officer or his authorized representative for approval in accordance with 4.2. The approval of the preproduction sample authorizes the commencement of production, but does not relieve the supplier of responsibility for compliance with all applicable provisions of this specification. The preproduction sample shall be manufactured in the same facilities to be used for the manufacture of the production items.

3.2 Standard product.- The flour handling plants covered by this specification shall be the manufacturer's commercially current product except for any modifications necessary to comply with specification requirements. All flour handling plants furnished under this specification for any one contract, including parts and assemblies thereof, shall be interchangeable.

3.3 Standards compliance.- The flour handling plants covered by this specification shall conform to the applicable requirements of The Baking Industry Sanitation Standard Committee (BISSC) Standard No. 1 for "Flour Handling Equipment for Bakeries". All electrical components except the motor, shall conform to the Underwriters Laboratories Inc. (UL) standards as applicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

3.3.1 BISSC certification.- The supplier shall submit satisfactory evidence to the contracting officer or his authorized representative that the flour handling plants he proposes to furnish under this specification meet the applicable requirements of BISSC Standard No. 1 as follows:

(1) Display of the BISSC seal on the finished flour handling plant, and a photostatic copy of the current BISSC certificate of authorization for the style flour handling plant being furnished shall be submitted prior to approval of the preproduction sample if one is submitted, or prior to approval of the first shipment, or

(2) A certified test report from a recognized independent testing laboratory acceptable to the medical department of the service for which the flour handling plants are being procured, indicating that the plants have been tested and conform to BISSC Standard No. 1 shall be submitted prior to the approval of the preproduction sample, if one is submitted, or prior to commencing production.

3.3.2 UL Certification.- Prior to approval of the preproduction sample if one is submitted, or prior to approval of the first shipment, the supplier shall submit satisfactory evidence to the contracting officer or his authorized representative that the electrical components of the flour handling plants he proposes to furnish under this specification meet the requirements of the UL standards as applicable. Acceptable evidence of meeting the applicable requirements of these standards shall be the U.L. label, a listing in the U.L. "Electrical Construction Materisl List," or a certified test report from a recognized independent testing laboratory acceptable to the Government, indicating that the electrical components of the flour handling plant offered, have been tested and conform to the requirements of applicable UL standards.

3.4 Materials.- Materials not definitely specified shall be of the quality normally used by the manufacturer in his commercial flour handling plants.

3.4.1 Wire.-

3.4.1.1 Corrosion-resisting steel.- Corrosion-resisting steel wire shall conform to composition 302, or 304, Form I of QQ-W-423.

3.4.1.2 Nickel-copper alloy.- Nickel-copper alloy wire shall conform to class A, Form 7 of QQ-N-281.

3.5 Design and construction.- The flour handling plant shall consist essentially of a dump bin, a sifter, and a weighing hopper and shall move flour from the dump bin through the sifter to the weighing hopper. The components shall include tracks, suspending equipment for the tracks, elevators, and conveyors. Flour handling plants shall service the number, location,

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

and dimensions of mixers specified (see 6.2 and 6.3). The weighing hopper shall include a beam scale or electronic device to weigh the sifted flour, and shall have controls to stop the flour flow automatically when a predetermined weight of flour is deposited in the hopper. All plants shall move not less than 80 pounds of flour per minute from the dump bin to the weighing hopper when tested as specified in 4.4.2. All moving parts shall be removable for replacement. Flour handling plants shall move flour mechanically from the dump bin, using a bottom screw conveyor, a lifting elevator, and an overhead screw conveyor, through a sifter to the weighing hopper or hoppers. The style 1 plant shall have a weighing hopper designed to service, and be filled over one mixer, and to move over tracks to service other mixers. The style 2 plant shall have a fixed weighing hopper designed to service and to be filled over one mixer.

3.5.1 Dump bin.- The flour dump bin shall be constructed of metal and shall have a flour capacity of 800 to 1000 pounds when tested as specified in 4.4.3.1. The dumping height of the bin shall be not less than 36 inches and not more than 40 inches. There shall be a full length dumping bag rest on the front of the bin. The bin shall have an enclosed dust hood with dust-tight doors and latches to hold doors closed after flour is dumped. There shall be a removable sack screen with openings between 2 by 2 and 3 by 3 inches, located 6 to 10 inches down from the top edge of the dump bin to protect the screw conveyor. Dump bins shall be equipped with either air jets or electrical vibrators to prevent arching of flour.

3.5.2 Conveyors.- Conveyors shall be of the steel screw type. The bottom screw conveyors shall have a separate section, with a minimum 12 inch length, located between the discharge end of the dump bin and the elevator boot. When the dump bin and elevator housing are connected as a unit the 12 inch section is not required.

3.5.2.1 Conveyor housings.- Conveyor housings shall be fabricated of metal not less than 0.060 inch in thickness. The top and bottom of the 12 inch section of the screw conveyor housing (see 3.5.2) between the dump bin and the elevator, and the bottom of the screw conveyor housing between the top of the elevator and the sifter shall have readily removable panels.

3.5.3 Elevators.- The elevators shall move the flour from the lower conveyor to the upper conveyor and shall be either a screw, continuous bucket, or shelf type with detachable link chains and disc sprockets with equalizing take ups.

3.5.3.1 Elevator housings.- Elevator housings shall be constructed of metal not less than 0.060 inch thick, and shall have readily removable access panels to facilitate cleaning of housings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

3.5.4 Sifter.- The sifters shall be the multi-screen gyrating, single flat vibrating, or gyrating screen type, and shall separate and expel foreign matter into a separate removable container or containers. The screens shall be constructed of material specified in 3.4.1.1 or 3.4.1.2 and shall be 30 by 30 mesh with openings not greater than 0.027 inch wide.

3.5.4.1 Sifter gate-hopper loading.- The flour handling plants shall be equipped with a flour gate to stop the flow from the sifter into the hopper quickly, for accurate weight without compensating adjustment of the scale beam or electronic measuring device.

3.5.5 Weighing hopper.- The weighing hopper shell shall be constructed of corrosion-resisting steel. The upper and lower structural members and the support members for the hopper if fabricated from carbon steel, shall be tin plated in accordance with type I or type II of MIL-T-10727 with 0.0003 inch minimum thickness. The weighing hopper shell shall have a flour capacity of 400 pounds minimum, unless a hopper of 600 or 800 pounds flour capacity is specified, (see 6.2). Removable transparent air vents, extending from the bottom to within 2 inches of the top of the hopper shell, shall be provided. There shall be a pressure seal type discharge gate on the bottom of the hopper shell, with an operating lever, and a corrosion-resisting steel dust-proof cone chute for discharging the flour into a mixer. The loading positon of the hopper shall be the same as its discharge position, over the first mixer, next to the elevator. The hopper components shall include either a beam scale (see 3.5.6) or an electronic measuring device (see 3.5.7) connected to stop the flow of flour into the hopper when a preset weight of flour is reached. The hopper for style 1 plant shall be of the traveling and weighing type with a four point suspension, and shall be designed with rollers to travel over a track system when moved by an attached handle by an operator. The hopper for style 2 plant shall be of the stationary weighing type, designed to be suspended over the flour inlet of a single mixer. Hopper shell capacity shall be verified by the test specified in 4.4.3.2.

3.5.6 Beam scale.- Beam scale, when used, shall be located at the front of the hopper (see 3.5.5) at a convenient elevation for operation from the floor. It shall have a double beam with inclosures readily removable for adjusting the switch and balancing the beam. The scale shall be designed to activate controls which will stop the flow of flour after a predetermined weight of flour has been deposited in the hopper. The double beam shall have a weighing capacity at least equal to the flour capacity of the hopper.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

3.5.7 Electronic weight control.- When an electronic weight control is used in lieu of a beam scale it shall activate controls to stop the flow of flour when a predetermined weight of flour has been deposited in the hopper. The electronic weight control shall have a weighing capacity at least equal to the flour capacity of the hopper.

3.6 Electrical.- Unless otherwise specified (see 6.2), the flour handling plant shall operate on a nominal 208-volt, 60-hertz, 3-phase, alternating current.

3.6.1 Motors.- The electric motors shall be of the totally-enclosed, dust ignition-proof, non ventilated, or totally enclosed, fan-cooled type conforming to style B5 of CC-M-636 or CC-M-641, and design D of NEMA Standard MG-1.

3.6.2 Controls.- Motor controllers and switches shall be of dust-tight construction. Opening of any motor controller on a flour handling plant shall de-energize all other motors of the plant, when tested as specified in 4.4.1. There shall be controllers at the dump bin and at the hopper on each plant. Controllers shall be capable of being locked in the open position.

3.6.3 Wiring.- The interwiring of the electrical components of the flour handling plant shall not prevent disassembly for shipment.

3.7 Operation.- When tested as specified in 4.4.1, while connected to electric power and operating without using flour, the moving components of the flour handling plant shall operate as intended without binding and the adjustable components shall be capable of adjustment over the entire range without binding. The controller and starters shall operate as intended and there shall be no loose, broken or missing parts after operation.

3.8 Electromagnetic compatibility.- When specified (see 6.2), equipment shall be designed and equipped for electromagnetic compatibility in accordance with class II B of MIL-STD-461 (see 4.4.4).

3.9 Lubrication.- Bearings and other parts requiring grease lubrication shall be provided with pressure type grease fittings conforming to MIL-F-3541 at accessible points. Closed oil cups shall be provided on bearings requiring oil lubrication unless otherwise lubricated. The plant shall be lubricated by the manufacturer just prior to delivery with the manufacturer's standard lubricant.

3.10 Lubricating chart.- The supplier shall affix to each plant a lubricating chart (metal or decal) indicating points of the equipment requiring lubrication, grade of lubricant required, and time interval when lubrication should be accomplished.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

3.11 Finish.- All exterior surfaces of the flour handling plant shall conform to BISSC Standard No. 1.

3.12 Marking for identification.- Each plant shall be marked in accordance with MIL-STD-130.

3.13 Instruction manuals.- Instruction manuals shall be supplied with each plant. The manual contents and distribution shall be as specified in the contract or order (see 6.2).

3.14 Repair and maintenance.- Provisions shall be made to allow for adjustment, service, and replacement of electrical components without disturbing or disassembly of any major component. There shall be free access to inspect, service, and adjust any component or equipmemt as provided for by the specification or as indicated by the component or equipment manufacturer without disassembly of any other component.

3.15 Workmanship.- There shall be no slivers, burrs, dents, or cracks and there shall be no sharp edges at corners.

3.15.1 Welds.- Welds shall have no pits, holes, or fissures and the deposited metal shall be fused along all exposed surfaces and edges.

3.15.2 Solder and brazing.- Surface of parts soldered or brazed shall be free of flux, scale, grease, or other foreign matter.

3.15.3 Threads and threaded fasteners.- Threads shall not be missing, broken, stripped, or fractured. Threaded fasteners shall not be loose, broken, or missing.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

4.2 First article inspection.- When a preproduction sample is required, it shall be examined for defects in table I and for compliance with dimensions specified and tested as specified in 4.4.1 through 4.4.4. Failure to pass the tests in 4.4.1 through 4.4.4 shall be cause for rejection of the preproduction sample. The presence of any defects listed in table I or any dimension not within specified requirements shall be cause for rejection of the preproduction sample.

4.3 Inspection.- Sampling for inspection shall be performed in accordance with MIL-STD-105, except where otherwise indicated hereinafter.

4.3.1 Component and material inspection.- In accordance with 4.1 above, components and materials shall be inspected and tested in accordance with all requirements of referenced specifications, drawings, and standards, unless otherwise excluded, amended, modified, or qualified in this specifiction or applicable purchase document.

4.3.2 End item inspection.- The lot shall consist of all complete flour handling plants of the same style offered for acceptance at one time. The sample unit shall be one complete flour handling plant.

4.3.2.1 Visual examination.- Examination of the end item shall be in accordance with the major defects in table I. The inspection level shall be II with an acceptable quality level (AQL) of 2.5 expressed in terms of defects per hundred units.

TABLE I.- Table of defects

Examine	Defect
Flour dump bin	Not specified type No dust hood with dust-tight doors Dumping bag rest not as specified
Conveyors	Bottom and overhead not steel screw type
Conveyor housing	Removable panels not as specified
Elevators	Not continuous bucket, shelf type, or steel screw
Elevator housing	Removable panels not as specified
Flour sifter	Not multiscreen gyrating, or single flat vibrating or gyrating type
Sifter gate-hopper loading	Not quick-closing type

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

TABLE I.- Table of defects (cont'd)

Examine	Defect
Weighing hopper	Track and suspension incomplete or defective, as applicable Not double beam or electronic weight control type Discharge gate not pressure seal
Beam scale	Not in convenient location for operation from floor Beam not inclosed
Electronic weight control	Weight control insufficient size
Motors	Not totally inclosed, dust ignition proof
Controls	No controller at flour dump bin or at hopper Controls cannot be locked in open position
Wiring	Prevents disassembly for shipment Insulation defective, damaged, omitted, broken, or deteriorated
Lubrication	Pressure type grease fittings not provided at accessible points for parts requiring grease lubrication No closed oil cups on bearings requiring oil lubrication Lubricating points inaccessible Fittings not grease or oil tight
Lubricating chart	Lubrication instruction chart missing
Identification marking	Missing, incomplete, not legible

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

TABLE I.- Table of defects (cont'd)

Examine	Defect
Instruction manuals	Missing, incomplete, not legible
Repair and maintenance	No provision for ready adjustment, service, or replacement of electric power system components No free access to inspect, service, or adjust components or equipment
Workmanship	Slivers, burrs, dents, cracks, or sharp edges on corner
Welds	Missing or incomplete Pits, holes, or fissures
Solder and brazing	Missing, not adherent, or incomplete Flux, scale, grease, or foreign matter not removed
Threaded fasteners	Missing, broken, stripped, fractured loose, broken, or missing
Electrical	Loose connection or terminal No slack between connections Insulation excessively stripped Wire cut or abraded

4.3.2.2 Dimensional examination.- The end item shall be examined to determine compliance with dimensional requirements. Any deviation from specified requirements shall be classified as a defect. The inspection level shall be S-2 with an AQL of 6.5 for total defects, expressed in terms of defects per hundred units.

4.3.2.3 Testing of the end item.- Each end item shall be tested in accordance with 4.4.1. Nonconformance shall be cause for rejection of the item. When a preproduction sample is not required, the initial production unit shall be tested as specified in 4.4.2 through 4.4.3.2 and 4.4.4 if applicable. Any nonconformance shall be cause for rejection of the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

4.3.3 Standards compliance.- The supplier shall have available for the Government representative, proof of compliance with the requirements of UL and BISSC as specified in 3.3.

4.3.4 Examination of preparation for delivery.- Examination shall be made for preservation and packaging, packing, and marking in accordance with MIL-B-2316.

4.4 Tests.-

4.4.1 Operation.- Connect the plant to specified electrical power, (see 3.6) and operate, without using flour, for a minimum of 2 hours to determine compliance with the requirements specified in 3.6.2 and 3.7. While operating, start and stop the machine at least 5 times, and observe bearings for overheating, controllers for starting and stopping, stopping devices for intended operation, and moving components for binding or improper operation; also move each adjustable component over the range of adjustment, and observe for binding or improper operation. After operating, observe for broken, missing, or loose parts or components to determine compliance with the requirements specified in 3.7. Inability of the plant to meet the operational requirements shall constiute failure of the test.

4.4.2 Functional.- Connect the plant to specified electrical power (see 3.6), place a minimum of 200 pounds of flour in the dump bin, and set the beam scale or electronic weighing device for 200 pounds. Measure the time required to move 80 pounds of flour to determine compliance with the requirements specified in 3.5. Inability of the plant to meet functional requirements shall constitute failure of the test.

4.4.3 Flour capacity.- Tests for flour capacity of components shall be made as follows:

4.4.3.1 Dump bin.- Check size of dump bin against known volumeteric dimensions for a given quantity of flour to determine compliance with the flour capacity requirements specified in 3.5.1. Inability of the dump bin to meet capacity requirements shall constitute failure of the test.

4.4.3.2 Weighing hopper.- Check size of weighing hopper shell against known volumetric dimensions for a given quantity of flour to determine compliance with the flour capacity requirements specified in 3.5.5. Inability of the hopper shell to meet the capacity requirements shall constitute failure of the test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

4.4.4 Electromagnetic compatibility test.- When electromagnetic compatibility is required, the preproduction sample or initial unit of production shall be tested by the supplier in accordance with test method CE03 and RE02 of MIL-STD-462. The Government reserves the right to witness tests performed by the supplier or his private testing organization. The supplier shall furnish the contracting officer for approval, the Interference Control Plan, the EMI/EMC Test Plan, and the electromagnetic compatibility test report required by MIL-STD-461. Upon approval of the test report by the contracting officer and provided all other requirements of the specification are met, the preproduction sample or initial unit of production, as applicable, shall be used as a model for all production units.

5. PREPARATION FOR DELIVERY

5.1 Levels A, B, and C.- Each flour handling plant shall be preserved, packaged, packed, and marked for each level of protection in accordance with the applicable requirements of MIL-B-2316 (see 6.2).

6. NOTES

6.1 Intended use.- The flour handling plants covered by this specification are intended to be used in Garrison Bakeries for moving, sifting, and weighing flour into batches before dumping the flour into a horizontal dough mixer, conforming to MIL-D-10921. The style 1 plant will service more than one mixer. The style 2 plant will service one mixer.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Style required (see 1.2).
(c) First article.- When a preproduction sample is required (see 3.1).
(d) Number, location, and dimensions of dough mixers the machinery is to serve (see 3.5).
(e) When a weighing hopper shell of 600 or 800 pounds capacity is required (see 3.5.5).
(f) Electrical requirements, if other than specified (see 3.6).
(g) When electromagnetic compatibility is required (see 3.8).
(h) Manual contents and distribution (see 3.13).
(i) Whether supervision of installation or demonstration service is to be provided (see 6.5).
(j) Selection of applicable levels of preservation, packaging, and packing (see 5.1).
(k) Equipment installation layout or description of installation details (see 6.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.

6.3 Instructions to procurement officer.- To achieve a properly designed plant, the procurement officer should in advance, provide for the guidance of bidders, a proposed installation layout of the equipment to be purchased under this specification showing the placement in premises to be occupied, diameter and height of flour inlet(s) above floor, distance between inlets (if applicable), distance from flour inlet to ceiling or nearest obstruction, make and model number of dough mixing machines (if available) and a statement that sufficient clearance exists for installation of a flour handling plant without blocking or altering existing entrances, partitions, or windows. The floor plan should show the number and type and whether the conveyors to and from the elevator should be right hand or left hand, number of supports required, and whether the dump bin is on the same floor. When such equipment is required, the track and track hangers for the hopper should be shown tentatively for contractor's suggestions.

6.4 Electromagnetic compatibility.- The contracting officer shall submit a copy of the report(s) required in 4.4.4 to the Commanding General, U.S. Army Electronics Command. ATTN: AMSEL-RD-GF, Fort Monmouth, New Jersey for approval.

6.5 Supervision of installation.- Supervision of installation should be required of the supplier on flour handling plant(s). When supervision of installation is required, the supplier should furnish the services of a competent superintendent who should be familiar with the construction, erection, maintenance, and repair of the equipment and the required utility connections. Material required for complete installations other than that specified herein and all installation labor should be furnished by the Government. All utilities should be extended and connected to the equipment by the Government.

6.6 Supersession data.- This specification includes the requirements of type I, style 1 and type I, style 2 of Military Specification MIL-F-2473C Style I of this specification is the same as type I, style 1 of MIL-F-2473C and style 2 of this specification is the same as type I, style 2 of MIL-F-2473C.

Custodians:

Army - GL
Air Force - 84

Preparing activity:

Army - GL

Project No. 3605-0007

Review activities:

Army - MD, EL
Air Force - 84, 85

☆ U. S. GOVERNMENT PRINTING OFFICE: 1969-341-520/A-7164

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T15:01Z
Check the source to verify that this is the current version before use.