MILITARY
SPECIFICATION

MIL-A-13196(SigC)
7 January 1954
Superseding U. S. Army
Specification 71-3119
3 October 1945

ATTENUATOR, VARIABLE CN-7/URA-TI

1. SCOPE

1.1 Scope.- This specification covers one type of equipment designated as Attenuator CN-7/URA-T1. It is used for reducing the range of transmission of transmitters, which are supplied modulation voltages by Training Generator AN/URA-T1 by absorption of r-f power up to 100 watts. This attenuator is used with but is not a part of Training Generator AN/URA-T1.

2. APPLICABLE SPECIFICATIONS, STANDARDS, DRAWINGS, AND PUBLICATIONS

2.1 The following specifications, standards, drawings and publications of the issue in effect on date of invitation for bids, form a part of this specification.

SPECIFICATIONS

FEDERAL

NN-B-591	Boxes, Fiberboard, Wood-Cleated (For Domestic Shipment).
NN-B-601	Boxes, Wood-Cleated Plywood for Domestic Shipment.
NN-B-621	Boxes, Wood, Nailed and Lock Corner.
NN-B-631	Boxes, Wood, Wirebound (For Domestic Shipment).
TT-C-595	Colors; (for) Ready-Mixed Paints.
UU-T-111	Tape; Paper, Gummed, (Sealing and Securing).
LLL-B-631	Boxes, Fiber Corrugated (For Domestic Shipment).

MILITARY

JAN-P-105	Packaging and Packing for Overseas Shipment - Boxes, Wood, Cleated Plywood.
JAN-P-106	Boxes; Wood, Nailed (Military Type).
JAN-P-108	Packaging and Packing for Overseas Shipment - Boxes, Fiberboard (V-Board and W-Board) Exterior and Interior.
MIL-P-116	Preservation, Methods of.
JAN-P-117	Packaging and Packing for Overseas Shipment - Bags, Interior Packaging.
JAN-P-127	Packaging and Packing for Overseas Shipment - Tape, Adhesive, Pressure-Sensitive, Water-Resistant.
JAN-T-152	Treatment, Moisture and Fungus-Resistant of Communications, Electronic and Associated Electrical Equipment: General Process for.
MIL-T-10513	Tropicalization of Materials used in Signal Corps Equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

U. S. ARMY

72-53 Finishes (for Ground Signal Equipment).

STANDARDS

MILITARY

MIL-STD-105 Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129 Marking of Shipments.

DRAWINGS

SIGNAL CORPS

SC-D-15914 Moisture Resistance Test Cycle for Ground Signal Equipment.
SC-D-19999 Standard Extreme-Temperature Cycle.
SC-DL-87662 Drawing and Data List for Attenuator CN-7/URA-TI.

(Copies of specifications, standards and drawings required by contractors in connection with specific procurement functions should be obtained from or as directed by the contracting officer. Both the title and identifying number or symbol should be stipulated when requesting copies.)

3. REQUIREMENTS

3.1 Construction.- The equipment shall be constructed to meet the specified requirements and details covered by the drawings and data listed in the Drawing and Data List SC-DL-87662 and all other requirements, test and inspection of this specification.

3.2 Preproduction samples.-

3.2.1 Quantities.- After the award of contract, preproduction samples shall be furnished for preproduction inspection and approved as follows:

2 complete equipments
2 switches as used in the equipment

3.2.2 Compliance with specified requirements.-

3.2.2.1 Preproduction samples shall meet specified requirements, shall be made and assembled by tools and methods that will be used for quantity production, and shall be accompanied by a statement to that effect. (See 3.2.2.3.)

3.2.2.2 Approval of preproduction samples shall not be construed as a waiver of any specified requirement. After being released to the contractor (3.2.4) preproduction samples to be offered as units on contract shall be refabricated by the contractor if necessary to meet specified requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

3.2.2.3 When deviation from 3.2.2.1 is unavoidable, the preproduction samples may be submitted for approval provided that the accompanying statement describes in detail each nonconforming feature, reason therefor, and manner in which it will be corrected in production of equipment under contract.

3.2.3 Test data.- The preproduction samples shall be accompanied by test data showing compliance with specified performance. The test data shall comprise an engineering report giving test procedure, observations and other data, calculations, test results and essential details of the testing equipment (manufacturer's model, serial number, date of calibration and the like).

3.2.4 Reference standards.- After preproduction samples have been approved and returned to the contractor's plant, they shall be kept intact in custody of the Government inspector until released by him. They shall be used as reference standards to resolve any differences of opinion regarding interpretation of requirements.

3.2.5 Preproduction inspection.- Preproduction samples may be subjected by the Government to the group A inspection specified in table III and to the preproduction inspection specified in table I. Unlisted nondestructive inspection on preproduction samples may be performed to determine compliance with specified requirements. Preproduction inspection will normally be performed in this order: (1) vibration, (2) bounce, (3) shock, bench-handling, (4) shock, ballistic or drop, and (5) immersion; other preproduction inspection may precede, follow, or be interspersed between the foregoing.

Table I - Preproduction inspection

Inspection	Requirement Paragraph	Test Paragraph
Bounce, light equipment	3.13.2	4.8
Moisture-resistance (equipment)	3.12.1	4.3
Shock, drop	3.13.2	4.9
Vibration	3.13.1	4.7
Temperature	3.12.1	4.4
Test for switches	------	4.5

3.3 Ease of adjustment.- Switches shall turn easily and smoothly without excessive motion, binding, scraping or cutting. They shall have a positive mechanical index at each position, operating so as to require no searching for contact by the operator and shall have a positive stop at each end of rotation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

3.4 Interchangeability.- Corresponding components and replaceable subassemblies and parts on contract shall be physically and functionally interchangeable as units without modification thereof or of other items with which the units are used. When dimensions, ratings, characteristics etc, are not specified, the manufacturer's design limits shall be used to determine compliance with the foregoing. Whether subassemblies and parts are to be considered replaceable shall be determined by the contracting officer.

3.5 Fabric and thread.-

3.5.1 Shrinkage.- Fabric and thread shall be presnrunk or allowance shall be made for shrinkage. In either case, satisfactory fit shall be provided both before and after finished articles are soaked in tap water at normal room temperature and then allowed to dry thoroughly at room temperature.

3.6 Plastic material.- Where not machined, plastic material shall have the original smooth or polished surfaces. Surfaces that have been sawed, cut, punched, or otherwise machined shall be as smooth as practicable in accordance with good manufacturing practice for the kind of material used and the intended application.

3.7 Wiring and cabling.- Wiring and cabling shall be neat and sturdy.

3.7.1 Slack.- Wires and cables shall be as short as practicable except that sufficient slack shall be provided to prevent undue stress on cable forms, wires and connections; to enable parts to be removed and replaced during servicing without disconnecting other parts; and to facilitate field repair of broken or cut wires.

3.7.2 Support.- Wires and cables shall be properly supported and secured, to prevent undue stress on conductors and terminals and undue change in position of the wires and cables after the equipment has been subjected to specified service conditions or has been serviced or repaired in a normal manner.

3.7.3 Clearance.- Clearance between wires or cables and parts such as resistors, shall be sufficient to avoid deterioration of the wires or cables because of the heat dissipated by such parts under specified service conditions for the equipment. Clearance between solder connections or bare conductors, on terminal boards, relays or other parts, shall be at least 1/4 inch unless use of specified parts makes such clearance impractical.

3.7.4 Connections.- Soldering leads, lugs, and terminals shall be tinned, silver plated, or lead alloy coated. Wires subjected to breakage at the connections shall be provided with terminals that grip the wire insulation. Solderless terminals may be used on tinned, stranded wire in power circuits, but other connections shall be soldered. Where practicable, wires soldered to terminals shall be looped at least once and not more than twice around the terminals before soldering, or equivalent means shall be employed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

3.8 Soldering.-

3.8.1 Flux and cleaning agents.- No acid or acid salts shall be used in preparation for or during soldering; however, exception is permitted for preliminary tinning of electrical connections and for tinning or soldering of mechanical joints not used to complete electrical circuits, but in no case shall acid or acid salts be used where they can come in contact with insulation material. Where acid or acid salts are used, as permitted above, they shall be completely neutralized and removed immediately after use. Flux for solering of electrical connections shall be rosin, rosin and alcohol, or rosin and turpentine.

3.8.2 Process.- There shall be not sharp points or rough surfaces resulting from insufficient heating. The solder shall feather out to a thin edge, indicating proper flowing and wetting action, and shall not be crystalized, overheated or underheated. The minimum necessary amount of flux and solder shall be used for electrical connections. The soldering shall be so accomplished that no rosin remains on the joint or in the proximity of the joint. Any means employed to remove an unavoidable excess of flux shall not incur the risk of loose particles of flux, brush bristles, or other foreign material remaining in the equipment, flux being spread over a larger area, or resulting damage to the equipment. Insulation materials that has been subjected to heating during the soldering operation shall be undamaged and parts fastened thereto shall not have become loosended.

3.8.3 Cleaning.- Metal parts, after fabrication, shall be cleaned in accordance with good commercial practice, or as specified in an applicable document. Cleaning processes shall have no visible or latent deleterious effects on the equipment. Corrosive material shall be removed completely before parts are assembled into the equipment. After assembly, components shall be cleaned thoroughly and shall be free from particles of solder, flux and other foreign material. If necessary, such cleaning shall also be performed before final assembly of components.

3.9 Finish, protective.- The equipment shall be given protective finish in accordance with Specification 72-53 and the following requirements:

3.9.1 Surface used for electrical contact.- Surfaces used for electrical contact shall be silver or silver alloy except where special contact metals are used.

3.9.2 Mounted hardware.- Hardware shall be given specified finish before being mounted on the equipment. After catches, screws, nuts and the like have been mounted, any break in the film of paint, either on the hardware or the mounting surface, shall be touched up to provide a continuous protective coating. A reasonably exact color match between the painted surfaces and the touch-up coating shall be provided.

3.9.3 Paint finish.- Paint finish on exterior surfaces, and on any interior surfaces that are visible when the equipment is in use, shall be semi-gloss enamel conforming to No. 2430 of Specification TT-C-595 (green color equivalent to olive-drab).

3.10 Tropicalization.- The assembled equipment shall be treated in accordance with Specification JAN-T-152. Before being assembled into the equipment, materials and parts shall be treated in accordance with Specification MIL-T-10513.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

3.11 Welding.- Welds shall be of ample size. Where tack or spot welds are employed, the number of welds shall be sufficient to provide adequate strength and at least two welds shall be used to hold each welded part. Spot or tack welds in aluminum or magnesium shall be limited to lightly stressed noncritical structures. Wherever possible, the welds joint shall be such that grinding on the finished weld will be unnecessary.

3.11.1 Cleaning.- Surfaces to be welded shall be cleaned in accordance with good commercial practice and shall be free from rust, scale, paint, grease and other foreign material. Welded assemblies shall be cleaned to remove scale oxidation products, and excess flux by sand blasting, wire brushing, or other suitable means. Acid used for cleaning shall be completely neutralized and removed.

3.12 Service conditions.- The equipment shall meet the following service conditions:

3.12.1 Equipment operating.- The equipment shall meet the requirements of this specification under any probable combination of the following:

a. Operation. Operation in any specified manner for a period of at least one year, at least 6 hours per day, with no more than normal maintenance and replacement of parts. Compliance shall be determined by examination of the preproduction samples.

b. Temperature. Any ambient temperature in the range of -40° to + 130°F.

c. Elevation. Any elevation up to 10,000 feet above sea level.

d. Relative humidity. Any relative humidity up to 98 percent.

e. Orientation. Any orientation.

3.12.2 Equipment nonoperating.- The equipment shall meet the requirements of 3.12.1 after subjection to any one or more of the following nonoperating conditions:

a. Temperature. Continuous exposure for 72 hours at + 160°F and 72 hours at -80°F at any orientation.

b. Elevation.- Any elevation up to 50,000 feet above sea level.

c. Relative humidity. Relative humidity up to 100 percent, including condensation caused by temperature changes. (See 4.8). Following subjection to such conditions and a power-on period of 6 hours at normal room temperature and relative humidity, the equipment shall meet the requirements of 3.12.1.

d. Orientation. Indefinite storage in any orientation.

e. Vibration, bounce and shock. See 3.13.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

3.13 Vibration, bounce, and shock.-

3.13.1 Vibration.- Except for internal resonance of specified parts and subassemblies, the equipment shall have no mechanical resonance below 55 cycles per second when shock mounts, (if any), are blocked or removed. (See 4.7)

3.13.2 Bounce and shock.- The equipment shall meet the requirements of table II.

Table II - Bounce and shock

Requirement	Inspection Paragraph	Performance after inspection
Bounce, light equipment	4.8	Full specification performance. No physical damage except surface abrasion
Shock-drop	4.9	Equipment shall be operable. Minor mechanical damage is permissible

3.14 Bounce conditioning.- After final assembly, each component on contract, with shock mounts removed or blocked, shall be placed in its normal operating position on the table of the Package Tester as made by the L.A.B. Corporation, Summit, New Jersey, or equal. The package tester, shafts in phase shall have a speed such that it is just possible to insert a 1/32-inch thick strip of material under one corner or edge of the equipment to a distance of 3 inches as the equipment bounces. The component shall be subjected to this conditioning for 1 minute and then shall be capable of meeting the inspection of Section 4.

3.15 Workmanship.- Components, subassemblies and parts shall be manufactured and assembled in a thoroughly workmanlike manner.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

4. SAMPLING, INSPECTION, AND TEST PROCEDURES

4.1 Inspection, general.- Government inspection shall consist of group A, as specified in 4.1.1. (See 6.3.1.)

4.1.1 Group A inspection.- Group A inspection shall be in accordance with table III and Standard MIL-STD-105. Group A inspection shall be performed in any order which is satisfactory to the Government inspector.

Table III - Government Group A inspection

Inspection	Requirement Paragraph	Test Paragraph	AQL Major	AQL Minor
Visual and Mechanical (Removed from case)		4.10	1.5 dphu	6.5 dphu
Final Mechanical and Visual		4.10	1 dphu	4 dphu
Operating test	3.12	4.6	1%	*

* All electrical defects are considered major.

4.2 Disposition of nonconforming products.- When defective sample units or rejected lots are resubmitted for acceptance, such items shall be suitably tagged of identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The record shall be presented to the Government when the items are resubmitted and shall become the property of the Government.

4.3 Moisture-resistance test for equipment.-

4.3.1 Test conditions.-

(a) Do not move components from the humidity chamber for measurements.
(b) Start measurements not more than 5 minutes after power is applied to the components. Complete measurements as rapidly as possible. Do not leave power on after measurements have been completed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

4.3.2 Test procedure.-

(a) Dry at 130° ± 5° F for 24 hours
(b) Condition at 77° ± 5° F and 40 to 50 percent relative humidity for 24 hours.
(c) Take measurements as specified in 4.3.3, and readjust or realine as necessary to meet full specification requirements.

(d) Subject to continuous cycling for five 48-hour cycles. Temperature, relative humidity, and period of time for each portion of the cycle shall conform to Drawing SC-D-15914. The measurements specified in 4.3.3 shall be made during the periods shown on the drawing and shall comply with 4.3.3.

(e) After cycling has been completed, condition the components for 24 hours at 77° ± 5° F and 40 to 60 percent relative humidity. Then adjust for optimum performance, using only those means provided by the components. No repair or replacement of parts shall be made. After adjustment, the components shall meet full specified performance for those measurements specified in 4.3.3.

4.3.3 Performance.- Measurements made during test, and specified performance during cycling shall be as follows:

Paragraph	Measurements	Performance during cycling
4.6	Operating test	Full performance

4.3.4 Failure.- If any component fails to meet the performance specified in 4.3.3 during cycling, it shall be realined or readjusted once. If the component then fails to meet 4.3.3 or fails subsequently during cycling, it does not pass the test. In addition, if the component fails to meet full specification requirements after conditioning and adjustment, as specified in 4.3.2(e), it does not pass the test.

4.4 Temperature test for equipment.- The equipment shall be subjected to the temperature cycle shown on Drawing SC-D-19999. The equipment shall be tested for operation at step 4 (+130° F) and at step 8 (-40° F) for a period of one hour each with the switch on position No. 1, and with 100 watts of power being dissipated by the attenuator. An inspection after the test shall show no evidence of deterioration or inability of the attenuator to function properly resulting from the test.

4.5 Test for switches.- A sample switch shall be connected in a circuit representing that used when the attenuator is dissipating 100 watts at maximum setting and shall be operation shall consist of roteting the movable element of the switch from one extreme position to the other extreme position and then back to the initial position. After completion of 10,000 operations, the switch shall be disassembled and inspected. Any evidence of damage (sticking of contacts, wear on contacts, or bearing, etc.) shall be considered failure to pass the test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

4.6 Operating test.- The "antenna" and "transmitter" terminals shall be connected to a source of a-c power. The switch shall be successively adjusted to each of its four settings and the voltage across the terminals shall be adjusted to provide the specified power dissipation by the attenuator for ten minutes on each setting.

Attenuator Switch Step No.	Power Dissipation by Attenuator (Watts)	Time (Minutes) on each setting
1	100	10
2	90	10
3	75	10
4	50	10

When the attenuator has cooled sufficiently to permit handling, the dielectric strength shall be tested for 10 seconds between the ground terminal and the antenna and transmitter terminals wired together, using 4000 volts d-c or sinusoidal 60-cycle a-c of the same peak value. There shall be no break down of insulation.

4.7 Vibration test.- The equipment shall be tested for resonant frequencies below 55 cycles per second, to determine compliance with 3.13, as follows:

a. The equipment shall be fastened in its normal mounting position on a vibration table that can be controlled within 10 percent of the specified amplitude. Equipment shock mounts, if any, shall be blocked. The vibration table shall provide approximately sinusoidal vibration.

b. The equipment shall be vibrated successively in three mutually perpendicular directions that are paralled respectively to the edges of the equipment, over a frequency range of 10 to 55 cycels per second, in 1-cycle-per second steps. The total excursion shall be constant at 1/64 inch.

c. Mechanical resonance, if any, of the complete structure, of sub-assemblies, and of component parts shall be determined visually by means of a Strobotac, as made by the General Radio Corporation, Cambridge, Massachusetts, or equal, or by energizing the equipment and detecting mechanical vibration through electrical output indications.

4.8 Bounce test; equipment under 1000 pounds.- The equipment, as packaged for shipment, shall be placed on the table of the Package Tester as made by the L.A.B. Corporation, Summit, New Jersey, or equal, and shall be constrained from horizontal motion of more than 2 inches by suitable wooden fences. The package tester, shafts in phase, shall be operated at a speed of 285 rpm ± 1 percent, for total of 3 hours. During each 1/2-hour period of the test, the package equipment shall rest on a different face.

4.9 Shock test; drop.- The equipment, as packaged for shipment, shall be dropped a distance of 30 inches on each corner, (total of 8 drops). Drops shall be made from a quick-release hook; and Acme Drop Tester, or equal; a Conbur Tester (10-degree inclined plane) or equal; or a basket-type pendulum tester. The floor or barrier receiving the impact shall be 2-inch fir, backed by concrete or a rigid steel frame.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

4.10 Visual and mechanical inspection.- Parts and equipment shall be examined for workmanship, mechanical fit, loose nuts and screws, application of specified tropicalization treatments, and miscellaneous defects. Controls and fastening devices shall be examined for mechanical operation. Wiring, soldered connections, ground connections, welds, finished, etc., shall be examined for workmanship. Clearances, dimensions, and mechanical adjustments shall be measured. Labels and markings shall be inspected for conformance with approved facsimiles, when facsimiles are required. Examination also may be made for other visual or mechanical defects, similar to those described above, that are contrary to specified requirements for the equipment. Visual and mechanical defects shall be classified by the Government as major or minor in accordance with the definitions of Standard MIL-STD-105.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.-

5.1.1 Domestic, immediate use.- Attenuator CN-7/URA-T1 shall be packaged in accordance with best commercial practice.

5.1.2 Domestic, limited storage.- Attenuator CN-7/URA-T1 shall be packaged in accordance with Method III of Specification MIL-P-116.

5.1.3 Military, overseas.- Preserve and package Attenuator CN-7/URA-T1 in accordance with procedures specified for the designated methods, as prescribed in Specification MIL-P-116, and futher described in the following paragraphs.

5.1.3.1 Technical manual.- Package each technical manual Method IC-3, as follows: Inclose each technical manual within a close-fitting Type II, Class b bag, conforming to Specification JAN-P-117. Properly seal closure.

5.1.3.2 Attenuator CN-7/URA-T1.- Package each Attenuator CN-7/URA-T1 Method IC-5 as follows: Cushion each item by wrapping in flexible corrugated paper. Secure cushioning with gummed paper type conforming to Specification UU-T-111. Place each item within a close-fitting suitable style and grade fiberboard box conforming to Specification JAN-P-108. Place Technical Manual, packaged as specified in 5.1.3.1 between lid of box and cushioned item. Seal entire box closure, corners and joints with water-resistant pressure sensitive tape, conforming to Specification JAN-P-127.

5.2 Packing.-

5.2.1 Domestic, immediate use.- The Attenuator CN-7( )/URA-T1 shall be so packed as to insure arrival at destination in satisfactory condition and in containers complying with Consolidated Freight Classification Rules, at lowest rates.

5.2.2 Domestic, limited storage.- Place a suitable quantity of Attenuators packaged as specified in 5.1.2 or 5.1.3 in wood cleated fiberboard, wood cleated plywood, nailed wood corrugated fiberboard or wirebound boxes, conforming to Specifications NN-B-591, NN-B-601, NN-B-621, LLL-B-631, or NN-B-631. The gross weight shall not exceed 65 pounds for fiberboard boxes and 200 pounds for plywood or wood boxes. Closure shall be made in accordance with the applicable box specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

5.2.3 Military, overseas.- Place a suitable quantity of Attenuators, packaged as specified in 5.1.3 in a wood cleated plywood, nailed wood box conforming to the requirements of Specifications JAN-P-105 or JAN-P-106 respectively. The approximate gross weight of any exterior shipping container shall not exceed 150 pounds. Close the shipping container, as specified in the appendix of the applicable box specification.

5.2.3.1 Shipping containers shall be strapped in conformance with the requirements of the appendix of the applicable container specification only for direct shipment to ports.

5.3 Marking for shipment.- Interior packages and exterior shipping containers shall be marked in accordance with applicable provisions of MIL-STD-129.

6. NOTES

6.1 Intended use.- Attenuator CN-7/URA-T1, is a unit for use with Signal Corps transmitters to reduce the range of transmission. It absorbs r-f power up to 100 watts.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number and date of this specification.
(b) Whether domestic or oversees shipment is required.
(c) Samples, required (See 3.2.)
(d) Marking and shipping of samples.
(e) Place of final inspection.
(f) Acceptable quality levels.
(g) Classification of defect.

6.3 Contractual requirements.- It is recommended that the following be included in the contract:

6.3.1 Additional inspection.- It should be understood that additional examination, measurement, and nondestructive testing of equipment may be performed by the Government when considered necessary to determine compliance with this specification and other applicable documents. Accordingly, the Government inspector may withdraw material, parts, subassemblies, or components temporarily from production for such inspection performed either at a Government laboratory or the contractor's plant.

6.3.2 Waiver of preproduction samples.- When items for which preproduction samples are required are currently in production on a Government order, the contractor may apply to the contracting officer for waiver of preproduction samples on the new order. Any request for waiver should be made by the prime contractor and should include a statement indicating that: the specified samples have been submitted and approved on the current contract; production of the item under the new order will be concurrent with, or follow without interruption, production on the current order and will be at the same plant; and current production is in strict compliance with specified requirements for new equipment except for such deviations as may be authorized on the current order. These deviations should be described in the statement. Waiver of preproduction samples may be contingent on renegotiation of the contract to reflect the saving in cost to the contractor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.

6.4 Color of textiles.- Standard samples of Olive Drab No. 7 may be obtained from Specifications and Quality Control Branch, Philadelphia Quartermaster Depot, 2800 South Twentieth Street, Philadelphia 45, Pennsylvania. When requesting samples, indication should be given to type of material concerned.

NOTICE: When Government drawings, specifications or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs on responsiblity nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:10Z
Check the source to verify that this is the current version before use.