MIL-C-13212B (MU)
AMENDMENT 1
17 January 1969

MILITARY SPECIFICATION

COMPONENTS, MOLDED, ASPHALT-ASBESTOS FILLED
(FOR USE IN AMMUNITION SHIPPING CONTAINERS)

Paragraph 1.2.1, Grade and color: Following "Grade and color.-The" delete "components" and substitute "molding material."

Paragraph 2.1, STANDARDS FEDERAL: Delete "FED-STD-406 - Plastics, Methods of Testing" and substitute "FED-STD-151 - Metals, Test Methods".

Add a new paragraph:

"2.2 Other publications.-The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) STANDARD:

D792-66 - Specific Gravity and Density of Plastics by Displacement.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, Pennsylvania, 19103)".

Paragraph 3.4, Workmanship: Following "3.4 Workmanship" delete "Molded components" and substitute "Components after molding".

Paragraph 4.2.1, Submission: Following "used in fulfilling the contract" insert "In addition to the components specified, ten test specimens conforming to the requirements of MIL-P-43090 shall be furnished".

FSC: 8140

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:12Z
Check the source to verify that this is the current version before use.

Paragraph 4.2.2, Inspections to be performed: Following "Inspections to be performed.-Assemblies" delete "and components" and substitute ", components and test specimens."

Paragraph 4.2.3: Following "If any assembly" delete "or component" and substitute ", component or test specimen."

Paragraph 4.2.3: Following "Failure of an assembly" delete "or component" and substitute ", component or test specimen."

Paragraph 4.3.3.1, Sampling: Following "shall be selected at Level S4" add "(See 6.5)."

Paragraph 4.3.3.1, Sampling: Following "(1) Applicable to components not procured to" delete "drawing." and substitute "drawings 8799117 and 9216180)."

Paragraph 4.3.3.2, Support assembly (see dwg. 9216180), under Major defects: Delete "104. Core support missing.....Visual, 02003."

Paragraph 4.3.3.2, Support assembly (see dwg. 9216180), under Minor defects: Following "AQL" delete "2.5" and substitute "1.5".

Paragraph 4.3.3.2, Support assembly, (see dwg. 9216180): Delete Minor defects "202. Location of core support from forward face.....Gage, 02006" and "204. Crimp of metal components incorrect.....Gage, 02008" in their entirety.

Add new paragraphs:

"4.3.3.5 Support assembly, prior to applications of asphalt-asbestos material (see dwg. 9216180)."

Categories	Defects	Method of Inspection	Code No.

Critical: None defined.

Major: None defined.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:12Z
Check the source to verify that this is the current version before use.

Minor: AQL 0.65 percent
201. Crimp of metal components incorrect.....Visual-Manual. 02008"

"4.3.4.2 Core support missing, Major defect, Code No. 02003; Location of core support from forward face, Minor defect, Code No. 02006 (see 6.5).-Ten support assemblies shall be selected from each lot for this examination. Failure of any assembly to meet the applicable requirements shall be cause for rejection of the lot. All samples subjected to the tests shall be classed defective and removed from the lot. The tests shall be performed as specified in 4.4.2, using test equipment in accordance with 4.3.5."

"4.3.4.3 Salt spray test, Major defect, Code No. 10001.- Sampling for this test shall be in accordance with Federal Standard, FED-STD-151. Failure of one or more assemblies to meet the applicable requirement shall be cause for rejection of the lot."

Paragraph 4.3.5, Inspection equipment: Delete and substitute:

"4.3.5 Inspection equipment.-For the performance of all tests and examinations specified in 4.3 and 4.4, commercial inspection equipment should be employed (see 6.4). The contractor shall have available, and utilize correctly, this equipment and is charged with the responsibility of insuring that proper calibration procedures are followed. Government approval of all inspection equipment is required prior to its use for acceptance purposes."

Paragraph 4.4.1, Specific gravity: Following "in accordance with Method" delete "5011 of FED-STD-406" and substitute "A3 of ASTM D-792-66."

Add new paragraphs:

"4.4.2 Core support missing; Location of core support from forward face.-The asphalt-asbestos molding material covering the assembly shall be removed from the core support in two areas 90 degrees apart, by any practical method. Care should be exercised

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:12Z
Check the source to verify that this is the current version before use.

in order to prevent deformation or chipping of the material at the forward face. Upon removal of the molding material, examinations shall be performed utilizing the following methods:

Defect	Method of Inspection
Location of support from forward face	Gage
Core support missing	Visual"

"4.4.3 Salt spray test.-The support assemblies shall be tested as specified in Federal Standard FED-STD-151, Method 811.1."

"6.4 Inspection equipment

6.4.1 Commercial inspection equipment is defined in AMC Regulation 702-2.

6.4.2 Contractor-designed equipment.-In the event that a contractor elects to design his own inspection equipment, details of the designs (drawings, description, materials, etc.) shall be submitted to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND12, Dover, New Jersey, for approval prior to fabrication and use. Approval of such designs may be delegated to the contract administration office **for minor defects only.**"

"6.5 Verification of composition.-Test specimens representative of the material used in each production lot, together with the 10 assemblies subjected to the tests specified in 4.3.4.2 shall be furnished an approved Government laboratory for verification of composition. The test specimens shall be furnished simultaneously with the shipment of each production lot and shall be sufficient in number to permit testing for conformance to all requirements of Specification MIL-P-43090. From the 10 assemblies, test samples suitable for determination of inorganic residue and shore hardness shall be cut. Variations in fiber length, distribution, and nature of the asbestos reinforcement and brittleness of the asphalt shall be determined by breaking the material from the assembly and noting the resistance to breaking and the visual appearance of the fractures. Additionally, burning the asphalt from both specimens and assemblies and comparing the visual appearance of the inorganic residues shall be performed. Any significant difference between the test specimens and assemblies shall be considered sufficient justification for rejection of the lot."

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:12Z
Check the source to verify that this is the current version before use.

"6.6 Submission of test data.-In addition to the normal distribution of records, two copies of the test data shall be furnished:

Commanding Officer
Picatinny Arsenal
ATTN: SMUPA-VP-2
and
ATTN: SMUPA-ND2
Dover, New Jersey 07801"

Custodian:
ARMY-MU

Preparing Activity:
ARMY-MU

Project Number: 8140- A - 163

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:12Z
Check the source to verify that this is the current version before use.