MILITARY
SPECIFICATION

MIL-C-12512A(SigC)
17 June 1960
Superseding
MIL-C-12512 (SigC)
3 March 1953

COILS, TELEPHONE REPEATING (COILS C-161( ) AND C-288( ))

1. SCOPE

1.1 This specification covers two types of ring-through, talk-through telephone repeating coils designated as Coil C-161( ) and Coil C-288( ). The two coils differ only in the type of mounting and kind of terminals. (See 6.3)

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, form a part of this specification.

SPECIFICATION

FEDERAL

QQ-S-571	Solder; Lead Alloy, Tin Lead Alloy, and Tin Alloy; Flux Cored Ribbon and Wire. and Solid Form.
UU-T-111	Tape, Paper, Gummed (Sealing and Securing).
PPP-P-291	Paperboard, Wrapping Cushioning.
PPP-B-566	Boxes, Folding, Paperboard.
PPP-B-585	Boxes, Wood, Wirebound.
PPP-B-591	Boxes, Fiberboard, Wood-Cleated.
PPP-B-601	Boxes, Wood, Cleated Plywood.
PPP-B-621	Boxes, Wood, Nailed and Lock-Corner.
PPP-B-636	Boxes, Fiber.

MILITARY

MIL-P-116	Preservation, Methods of
MIL-B-10377	Box, Wood, Cleated, Veneer, Paper-Overlaid

STANDARDS

MILITARY

MIL-STD-22	Welded-Joint Designs.
MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	Marking for Shipment and Storage.

FSC 5950

Source: https://assist.dla.mil -- Downloaded: 20261O-17T22:53Z
Check the source to verify that this is the current version before use.

MIL-STD-169	Extreme-Temperature Cycle.
MIL-STD-170	Moisture Resistance Test Cycle for Ground Signal Equipment.
MIL-STD-252	Wired Equipment, Classification of Visual and Mechanical Defects.

DRAWINGS

SIGNAL CORPS

SC-D-1736	Coil C-161( ) Assembly & Details
SC-D-5745	Coil C-288( ) Assembly & Details
SC-A-7704	Transmission Test Circuit For Coils C-161( ) and C-288( )
SC-A-11581	Test Circuit and Equipment for Coils C-161( ) and C-288( )

(Copies of specifications, standards, drawings, and publicationsrequired by contractor in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

2.2 Other publications.- The following documents form a part of this specification. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

AMERICAN SOCIETY FOR TESTING MATERIALS

E 28-42T	Tentative Method of Test for Softening Point

(Application for copies should be addressed to the American Society for Testing Materials at 1916 Race Street, Philadelphia, Pennsylvania.)

CONSOLIDATED CLASSIFICATION COMMITTEE

Uniform Freight Classification, Rule No. 4.
Consolidated Freight Classification, Rule No. 21.

(Application for copies should be addressed to the Consolidated Classification Committee, 202 Union Station, Chicago 6, Ill.)

AMERICAN TRUCKING ASSOCIATION, INCORPORATED

National Motor Freight Classification No. A-3 and No. 14

(Application for copies, should be addressed to the National Classification Board, 1424 Sixteenth Street, N.W. Washington 6, D.C.)

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:53Z
Check the source to verify that this is the currentversion before use.

3. REQUIREMENTS

3.1 Construction.- Construction of Coil C-161( ) shall be in accordance with SC-D-1736. Construction of Coil C-288( ) shall be in accordance with SC-D-5745.

3.2 Soldering.-

3.2.1 Solder.- Solder used for electrical connections shall be composition SN60 conforming to Specification QQ-S-571.

3.2.2 Flux and cleaning agents.- No acid or acid salts shall be used in preparation for or during soldering; however, exception is permitted for preliminary tinning of electrical connections and for tinning or soldering of mechanical joints not used to complete electrical circuits, but in no case shall acid or acid salts be used where they can come in contact with insulation material. Where acid or acid salts are used, as permitted above, they shall be completely neutralized and removed immediately after use. Flux for soldering of electrical connections shall be rosin, rosin and alcohol, or rosin and turpentine.

3.2.3 Process.- There shall be no sharp points or rough surfaces resulting from insufficient heating. The solder shall feather out to a thin edge, indicating proper flowing and wetting action, and shall not be crystallized, overheated, or underheated. The minimum necessary amount of flux and solder shall be used for electrical connections. Any means employed to remove an unavoidable excess of flux shall not incur the risk of loose particles of flux, brush bristles, or other foreign material remaining in the equipment, flux being over a larger area; or damage to the equipment. Insulation material that has been subjected to heating during the soldering operation shall be undamaged and parts fastened there to shall not have become loosened.

3.3 Welding.- Welds shall be of ample size. Where tack or spot welds are employed, the number of welds shall be sufficient to provide adequate strength and at least two welds shall be used to hold each welded part. Spot or tack welds in aluminum or magnesium shall be limited to lightly stressed, noncritical structures. Wherever practicable, the welded joint shall conform to Specification MIL-STD-22, and shall be such that grinding on the finished weld will be unnecessary.

3.3.1 Cleaning.- Surfaces to be welded shall be cleaned in accordance with good commercial practice and shall be free from rust, scale, paint, grease, and other foreign material. Welded assemblies shall be cleaned to remove scale, oxidation products, and excess flux by sandblasting, wire brushing, or other suitable means. Acid used for cleaning shall be completely neutralized and removed.

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:53Z
Check the source to verify that this is the current version before use.

3.3.2 Process.- Preheating shall be employed where distortion is likely to result from welding. Welds shall have thorough penetration and good fusion and shall be free from scabs, blisters, abnormal pock marks and other harmful defects. Where undesirable internal stresses are likely to result from welding, the welded assembly shall be stress-relieved. Inert-gas-shielded arc welding shall be used, when practicable, for welding of aluminum or magnesium.

3.4 Electrical requirements of Coils C-161( ) and C-288( ).-

3.4.1 Impedance ratio.- The impedance ratio shall be 1:1 ±5% at 1000 cps.

3.4.2 Resistance.- When tested in accordance with 4.6.3, the d.c. resistance of the switchboard side coil windings shall not exceed 58 ohms, and that of the line side coil windings shall not exceed 65 ohms.

3.4.3 Balance.- The balance between the telegraph windings shall be such that the received power shall be down at least 60 db when tested in accordance with 4.6.4.

3.4.4 Transmission loss.- The transmission loss of the coils shall not exceed the values listed below at the specified frequencies when tested in accordance with 4.6.5.

Frequency (c.p.s.)	Loss (d.b.)
20	3.0
200	1.0
1000	1.0
3000	1.0

3.4.5 Breakdown voltage, insulation.- When tested in accordance with 4.6.2 or 4.8, the coils shall be capable of with standing the applied voltage within the time specified without breakdown or visible deterioration.

3.5 Sealing compound.-

3.5.1 Softening temperature of sealing compound.- The softing point of the sealing compound shall occur at a temperature greater than 212°F, when tested as specified in 4.7.1

Source: https://assist.dla.mil -- Downloaded: 20261O-17T22:53Z
Check the source to verify that this is the current version before use.

3.5.2 Cracking temperature of sealing compound.- The ball of sealing compound shall show no evidence of cracks, when inspected as specified in 4.7.2.

3.5.3 Sealing of coils.- Coil C-161( ) and Coil C-288( ) shall be sealed and assembled as specified in the drawings. Sufficient sealing compound shall be used to completely fill the can (with the coil in place). The sealing process shall be so performed that no air bubbles shall be formed on any surface of the coil. The assembled coil and body in each case shall be a waterproof unit capable of meeting the test of 4.8.

3.6 Service conditions.- The Coils C-161( ) and C-288( ) shall meet the following service conditions:

3.6.1 Operation.- Continuous use under the world-wide environmental conditions specified in 3.6.2 through 3.6.4. Where the contractor is required to make a selection of parts, materials, processes, construction methods, etc, he shall be guided by this requirement. Approval of the preproduction sample (see 3.9) shall be considered as compliance with this requirement.

3.6.2 Temperature (see 4.9).-

(a) Operating: Ambient temperature in the range of +132°F to -40°F exposure at the high temperature extreme not to exceed 4 hours, and at the low temperature extreme not to exceed 72 hours, at anyone time.

(b) Nonoperating: Exposure in the range of +160°F to -80°F; exposure at the high temperature extreme not to exceed 4 hours, and at the low temperature extreme not to exceed 24 hours, at any one time.

3.6.3 Relative humidity (see 4.10).- Up to 97 percent relative humidity for 20 hours; and exposure at 100 percent relative humidity, with condensation, for 4 hours.

3.6.4 Orientation.- Storage in any position for a period of two years. Where the contractor is required to make a selection of parts, materials, processes, construction methods, etc, he shall be guided by this requirement. Approval of the preproduction sample (see 3.9) shall be considered as compliance with this requirement.

3.7 Preconditioning.- Coils C-161( ) and C-288( ) shall be capable of meeting the inspection of section 4, without subsequent processing, after subjection to the bounce preconditioning of 4.4.

3.8 Facsimiles.- In addition to any facsimiles specified by referenced documents, facsimile copies as follows shall be submitted for approval to the contracting officer:

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:53Z
Check the source to verify that this is the current version before use.

	Number of copies required
(a) Coil C-161( ) Circuit label	2
(b) Coil C-288( ) Circuit label	2

3.9 Preproduction samples.- The contractor shall furnish preproduction samples for approval, as required by the invitation for bids and contract. (See 6.2(e))

3.10 Technical literature.- Technical literature shall be furnished as specified in the contract. (See 6.2)

3.11 Workmanship.- Coils C-161( )/ and C-288( ) shall be manufactured and assembled in accordance with the applicable portions of the following paragraphs herein:

3.2.1 Solder
3.2.2 Flux and cleaning agents
3.2.3 Process for soldering
3.3 Welding
3.3.1 Cleaning
3.3.2 Process for welding
3.5 Sealing compound

4. QUALITY ASSURANCE PROVISIONS

4.1 Inspection, responsibility and classification of.-

4.1.1 Contractor responsibility.- Unless otherwise specified herein the supplier is responsible for the performance of all inspection requirements prior to submission for Government inspection and acceptance. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. Inspection records of the examination and tests shall be kept complete and available to the Government as specified in the contract or order.

4.1.2 Classification of inspection.- Inspection shall be classified as follows:

(a) Preproduction inspection (does not include preparation for delivery.) (See 4.2)

(b) Procurement inspection. (Procurement inspection shall be the inspection performed by the contractor and by the Government, as specified by 4.3 and 4.11.)

(1) Procurement inspection of items before preparation for delivery. (See 4.3)

Source: https://assist.dla.mil -- Downloaded: 20261O-17T22:53Z
Check the source to verify that this is the current version before use.

(2) Procurement inspection of preparation for delivery. (See 4.11 and section 5.)

4.2 Preproduction inspection.- This inspection will be performed by the Government unless otherwise specified in the contract. It shall consist of the inspection specified for group A, group B, and group C.

4.3 Procurement inspection of items before preparation for delivery.- The contractor, to demonstrate compliance with specified requirements, shall perform the inspection specified in 4.3.1 through 4.3.4. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition the Government--at its discretion--may perform all or any part of the inspection specified herein, to verify the contractor's compliance with specified requirements. (The amount of such verification inspection will depend on the extent to which the contractor's inspection procedures and records insure that the equipment on contract meets the specified procurement inspection.) Each unit which will be subjected to group A, or group C inspection shall be preconditioned after final assembly.

4.3.1 Group A inspection.- This inspection (including sampling) shall conform to Table 1 and the ordinary inspection procedures of Standard MIL-STD-105. Group A inspection shall be performed in any order which is satisfactory to the Government.

Table I - Group A inspection

Inspection	Reqt Para.	Insp Para.	AQL Major	AQL Minor
Visual and Mechanical	3.12	4.5	1.0%	4.0%
Electrical				
Impedance	3.4.1	4.6.1	1.0%	
Breakdown voltage	3.4.5	4.6.2	For	*
D. C. resistance	3.4.2	4.6.3	group	
Balance	3.4.3	4.6.4	combined	

* All electrical defects are considered major.

4.3.2 Group B inspection.- This inspection (including sampling) shall conform to table II and to the special procedures for small-sample inspection of Standard MIL-STD-105. The reduced inspection procedure shall be R-1. Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection.

4.3.2.1 Group B sampling plans.- The group B sampling plans, for the AQL's listed in table II, shall be as follows:

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:53Z
Check the source to verify that this is the current version before use.

AQL	Inspection level for normal and tightened inspection	Inspection level for reduced inspection
4.0%	L-8	L-6
10.0%	L-6	L-4

4.3.2.2 Order of inspection within group B.- Group B inspection shall be performed in any order which is satisfactory to the Government.

4.3.2.3 Procedure in case of failure.- When an inspection lot fails, the contractor shall immediately investigate the cause of failure and take corrective action to assure that subsequent lots do not contain the same defect or defects.

Table II.- Group B inspection of equipment

Inspection	Rqt Para	Insp Para	AQL
Transmission	3.4.4	4.6.5	4.0%
Sealing	3.5.3 and 3.4.5	4.8	10.0%

4.3.3 Group C inspection.- This inspection shall be as listed in Table III. The inspection of the repeating coils shall normally be performed on sample units that have been subjected to, and met group A and group B inspection.

4.3.3.1 Sampling for subgroup I inspection.- Two samples for the sealing compound inspection shall be selected from each batch of compound, except that each sample inspected at the start of the contract shall be selected from the first batch of compound produced.

4.3.3.2 Sampling for subgroup 2 inspection.- Two repeating coils for each group C inspection under subgroup 2 shall be selected for each 500 units produced or once a month, whichever is more frequent, without regard to their quality, except that the units inspected at the start of the contract shall be selected from the first units produced.

4.3.3.3 Noncompliance.- If a sample fails group C inspection, the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results there of and details of the corrective action taken on the process and all units of product which were manufactured with the same conditions, materials, processes, etc. If the Government inspector does not consider that the corrective action will enable the product to meet specified requirements, of if the contractor cannot determine the cause of failure, the matter shall be referred to the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:53Z
Check the source to verify that this is the current version before use.

TAble III - Group C inspection

Inspection	Reqt Par	Insp Par
Subgroup I		
Sealing compound		
Softening temperature	3.5.1	4.7.1
Cracking temperature	3.5.2	4.7.2
Subgroup 2		
Temperature	3.6.2	4.9
Moisture resistance	3.6.3	4.10

4.3.4 Disposition of nonconforming product.- Disposition of nonconforming product shall conform to Standard MIL-STD-105. Such product shall be suitably tagged or identified to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is submitted.

4.4 Bounce preconditioning.- The coil, shall be placed in its normal operation position on the table of the Package Tester as made by the L.A.B Corporation, Skaneateles, New York, or equal. The Package Tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32 inch thick strip of material under one corner or edge of the unit to a distance of 3 inches as the unit bounces. The unit shall be subjected to this preconditioning for 1 minute. After bounce preconditioning, the unit shall not be repaired, alined, cleaned, or otherwise changed prior to subjection to procurement inspection.

4.5 Visual and mechanical inspection.- The coils shall be examined for the defects listed in Standard MIL-STD-252.

4.6 Electrical tests for Coils C-161( ) and C-288( ).-

4.6.1 Impedance ratio: The impedance of the coil windings connected to switchboard terminals 4 and 5, and the coil winding connected to line terminals 1 and 3 shall be measured (1000 cps). The maximum difference in impedance shall be within the limit set forth in 3.4.1 to meet the 1 to 1 ratio required.

4.6.2 Breakdown voltage test.- A 60 cycle alternating potential of 500 volts r.m.s. shall be applied for one minute between one terminal of the SWITCHBOARD side coil windings and the midpoint (telegraph) terminal of the LINE side coil winding, and between each of the above terminals and the metal case. The requirements of 3.4.5 shall be met during, and after the test.

4.6.3 Resistance.- The d.c. resistance of the SWITCHBOARD coil winding shall be measured across terminals 4 and 5, and that of the LINE coil winding across terminals 1 and 3. The requirements of 3.4.2 shall be met.

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:53Z
Check the source to verify that this is the current version before use.

4.6.4 Balance.- The coils shall be tested for compliance with the requirements of 3.4.3 using the test circuit and equipment shown on Drawing SC-A-11581 and the following procedure.

4.6.4.1 Test procedure.- Connect a 1000 cycle (±50 cycles) oscillator, having a balanced output impedance of 600 ohms ±5 percent and capable of delivering a power output of 0.01 watt with less than 5 percent total harmonic distortion, to a 10 db, 600 ohm balanced attenuator. Connect the opposite end of the attenuator to the SWITCHBOARD terminals of the coil under test. Terminate the LINE side of the coil with a center-tapped resistance of 600 ohms ±5 percent. The center tap shall be exact to within 0.01 ohm. (See 4.6.4.2) Connect measuring equipment, having an input impedance of 160 ohms ±10 percent and capable of measuring powers at least 60 db. below one milliwatt with ±1 db, at 1000 cycles, between the TELEGRAPH terminal (Terminal 2) of the coil under test and the center tap of the terminating resistance. Adjust the oscillator output until the power delivered by the attenuator to the SWITCHBOARD terminals of the coil (Terminals 4-5) is 0.001 watt (0.775 volts rms as measured with a high-impedance vacuum-tube voltmeter or power level indicator). Measure the received power.

4.6.4.2 When using the circuit shown on Drawing SC-A-11581, the center-tap on the terminating resistance shall be adjusted to be exact to within 0.01 ohm.

4.6.5 Transmission loss.- The coils shall be tested for compliance with the requirements of 3.4.4 using the following test procedure.

4.6.5.1 Test procedure.- Connect the test equipment as shown on Drawing SC-A-7704. Establish the testing power by connecting zero-loss attenuator B_1, (shown on Table A) in the circuit, and, with Switch SW thrown to STANDARD, adjust the output power of the oscillator (at any one of the specified test frequencies) to give an output power of one milliwatt (0.775 volts as measured by Voltmeter VM, associated with the test circuit). Replace attenuator B_1 with attenuator B_2, B_3 or B_4, depending on the test frequency. Compare the voltage at the output terminals of the attenuator with the voltage at the output terminals of the coil being tested. This shall be accomplished by operating the Switch SW to the TEST position. The test procedure described shall be repeated at all test frequencies.

4.7 Test of sealing compound.-

4.7.1 Softening temperature of sealing compound.- The sealing compound shall be tested to determine that the softening point occurs at a temperature greater than 212°F. The test shall be in accordance with ASTM Standard E28-42T.

4.7.2 Cracking temperature of sealing compound.- A ball of the compound approximately one inch in diameter shall be formed at or above 68°F. This ball shall be maintained between -4°F and 3.2°F for a continuous period of not less than two hours. Immediately at the end of this period, the ball shall be inspected to determine compliance with 3.5.2.

4.8 Test of sealing.- The coils shall be immersed in salt water (2 pounds sodium chloride to one gallon of water) at room temperature for 24 hours. After this period, they shall be removed from the salt water, washed with fresh water and then allowed to stand at room temperature for one hour with air circulating freely around them. The breakdown voltage test of 4.6.2 shall then be performed, except that the specified voltage shall be applied for 5 seconds in lieu of one minute. (See 3.4.5 and 3.5.3.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:53Z
Check the source to verify that this is the current version before use.

4.9 Temperature.- The coils shall be subjected to the temperature cycle shown on Standard MIL-STD-169. The tests of 4.6.1 to 4.6.6 inclusive shall be made at step 4 and step 8. The equipment shall conform to full specification requirements.

4.10 Moisture-resistance test for equipment.-

(a) Do not remove equipment from humidity chamber for measurements.

(b) Start measurements not more than 5 minutes after power is applied to the equipment. Complete test measurements as rapidly as possible. Disconnect from power source when measurements are complete.

4.10.2 Test procedure.- The samples will be tested as follows:

(a) Dry at 130° ± 5°F for 24 hours.

(b) Condition at 77° ± 5°F and 40 to 50 percent relative humidity for 24 hours.

(c) Take measurements as specified in 4.6.1 to 4.6.6 inclusive and readjust or realign as necessary to meet full specification requirements.

(d) Subject to continuous cycling for a total of 5 of 48-hour cycles. Temperature, relative humidity, and period of time of each portion of the cycle shall conform to Standard MIL-STD-170. Repeat measurements of 4.6.1 to 4.6.6 inclusive.

(e) After cycling has been completed, condition the equipment for 24 hours at 77 ± 5°F at 40 to 60 percent relative humidity. At completion of condition period, adjust for optimum performance, using only those means provided by the equipment. No repair or replacement of parts shall be made. After the adjustment, the equipment shall meet the full specification requirements of performance specified in 4.6.1 to 4.6.6 inclusive.

4.10.3 Performance.- Measurements made during test, and specified performance during cycling shall be as specified in 4.6.1 to 4.6.6 inclusive.

4.10.4 Failure.- If the equipment fails to meet the performance specified in 4.10.2 during cycling, it shall be realigned or readjusted once. If the equipment then fails to meet 4.10.2 or fails subsequently during cycling, it does not pass the test. In addition, if the equipment fails to meet full specification requirements, it does not pass the test.

4.11 Procurement inspection of preparation for delivery.- Inspection of preparation for delivery shall conform to Specification MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 20261-17T22:53Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY.

5.1 Preservation and packaging.

5.1.1 Level A.- Coils, Telephone Repeating (Coils C-161( ) and C-288( )) shall be preserved, packaged and tested in accordance with the procedures specified for the designated methods as prescribed in Specification MIL-P-116 and as described herein.

5.1.1.1 Unit packaging.- Coils shall be individually packaged Method III as follows: Cushion each coil within type II paperboard, wrapping cushioning, conforming to Specification PPP-P-291, making a snug conforming wrap. Seal the wrap with class 2, gummed paper tape, conforming to Specification UU-T-111. Place one each cushioned coil within a close-fitting paperboard box, style II, type A, class (a), conforming to Specification PPP-B-566. Box closure shall be in accordance with the referenced box specification or appendix thereto.

5.1.1.2 Intermediate package.- A quantity of coils of like type number shall be placed within a close-fitting regular slotted style corrugated fiber box, class 2, W6c conforming to Specification PPP-B-636. The weight of box with contents shall not exceed 30 pounds. Box closure shall be in accordance with the referenced box specification.

5.1.2 Level C.- Coils, Telephone Repeating (Coils C-161( ) and C-288( )) shall be preserved and packaged in accordance with commercial practice and in a manner that will afford protection against corrosion, deterioration and physical damage during direct shipment to the first receiving activity.

5.2 Packing.-

5.2.1 Level A.- Coils within the intermediate package shall be packed in shipping containers conforming to the requirements of the specifications referenced below for the designated level. The gross weight shall not exceed the weight shown. Closure shall be as prescribed in the applicable box specification or appendix thereto.

	Box Specification	Max. Gross Wt.
Fiberboard (Type 1, Class 2)	PPP-B-636	Table II
Nailed Wood (Style 4, Class 2)	PPP-B-621	200 lbs.
Wirebound (Style 2 or 3, Class 2)	PPP-B-585	200 lbs.
Wood Cleated Fiberboard (Overseas)	PPP-B-591	200 lbs.
Cleated Plywood (Overseas)	PPP-B-601	200 lbs.
Wood Cleated, Veneer, Paper Overlaid (Overseas)	MIL-B-10377	200 lbs.
Nailed Wood (Style 2, Class 2)	PPP-B-621	Specification Limit

Source: https://assist.dla.mil -- Downloaded: 20261O-17T22:53Z
Check the source to verify that this is the current version before use.

5.2.1.1 Metal strapping.- Shipping containers shall be strapped in conformance with the requirements of the appendix of the applicable container specification only for direct shipment to ports.

5.2.2 Level B.-	Box Specification	Max. Gross Wt.
Fiberboard (Type 1, Class 1)	PPP-B-636	Table 1
Nailed Wood(Style 4,Class 1)	PPP-B-621	200 lbs.
Wirebound(Style 3, Class 1)	PPP-B-585	200 lbs.
Wood Cleated Fiberboard(Domestic)	PPP-B-591	200 lbs.
Cleated Plywood (Domestic)	PPP-B-601	200 lbs.
Wood Cleated, Veneer, Paper Overlaid (Domestic)	MIL-B-10377	200 lbs.
Nailed Wood (Style 2, Class 2)	PPP-B-621	Specification Limit

5.2.3 Level C.- Coils, Telephone Repeating (Coils C-161( ) and C-288( ) shall be packed for shipment in a manner conforming to the requirements of Uniform Freight Classification No. 4 and Consolidated Freight Classification, Rule 21 for rail shipment, National Motor Freight Classification No. A-3 and No. 14 for truck shipment, Parcel Post Regulations, and the regulations of other carriers as applicable to the mode of transportation employed at lowest transportation rate.

5.3 Marking.- Interior packages and exterior shipping containers shall be marked in accordance with the applicable provisions of Standard MIL-STD-129.

6. NOTES

6.1 Intended use.- Coil C-161( ) and Coil C-288( ) are intended for use as ring-through and talk-through telephone repeating coils.

6.2 Ordering data.-

(a) Title, number and date of this specification and any amendment thereto.

(b) Type required.

(c) Level of packaging and level of packing required for shipment. (Level A, level B, or level C.)

(d) The specific paragraphs of section 5 which are applicable to the particular procurement.

(e) Preproduction inspection

(1) Two samples of each item cited in section 1 are generally required so that lengthly environmental tests can be completed on one sample while complete performance measurements can be made on the second sample.

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:53Z
Check the source to verify that this is the currentversion before use.

(2) Preproduction pack(s) as follows:
Makeup of pack(s).
Number of each kind of pack to be submitted.
Inspection to be performed thereon.

(f) Marking and shipping of samples.

(g) Place of final inspection.

(h) Technical literature required. (See 3.10)

(i) Facsimiles required. (See 3.8)

6.3 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example C-161-W. The contractor should apply for nomenclature in accordance with the applicable clause in the contract. (See 1.1)

NOTICE: When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government may have formulated, furnished, or in any way supplied the said drawings, specifications or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in anyway be related thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:53Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:53Z
Check the source to verify that this is the current version before use.