GENERATOR, RINGING, HAND GN-38-B

1. Replace Section 2 in its entirety with the following:

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitations for bids or request for proposal, form a part of this specification:

SPECIFICATIONS

FEDERAL

QQ-S-571	Solder, Lead Alloy, Tin Lead Alloy and Tin Alloy, Flux Cored Ribbon and Wire
PPP-T-97	Tape, Pressure-Sensitive Adhesive Filament Reinforced
PPP-B-585	Boxes, Wood, Wirebound
PPP-B-591	Boxes, Fiberboard, Wood-Cleated
PPP-B-601	Boxes, Wood Cleated-Plywood
PPP-B-621	Boxes, Nailed and Lock-Corner
PPP-B-636	Box, Fiberboard

MILITARY

MIL-P-116	Preservation Methods of
MIL-T-152	Treatment, Moisture and Fungus-Resistant of Communications Electronic and Associated Electrical Equipment
MIL-W-583	Wire, Magnet, Electrical
MIL-B-10377	Box, Wood, Cleated, Veneer, Paper-Overlaid

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-170	Moisture Resistance, Test Cycle, for Ground Signal Equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:54Z
Check the source to verify that this is the current version before use.

DRAWINGS

SIGNAL CORPS

SC-DL-67371	Generators GN-38-( ), GN-41-( )
SC-A-362100	Packaging for Preparation of Packaging and packing Illustrations and Bills of Material

(Copies of specifications, standards, and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

2. Paragraph 3.2.1.1 Wire.- Replace, "JAN-W-583", with "MIL-W-583".

3. Paragraph 3.7 Tropicalization.- Replace "JAN-T-152" with "MIL-T-152" and delete last sentence of this paragraph.

4. Insert the following, as the first paragraph in Section 4:

4.0 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any or the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

5. Paragraph 4.1.2 Group B inspection.- Replace entire paragraph with the following:

"4.1.2 Group B inspection.- This inspection, including sampling, shall conform to table I and to the special procedures for small-sample inspection of Standard MIL-STD-105. The reduced inspection procedure shall be R-1. Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection."

6. Paragraph 4.1.2.1 Rejection: Replace the paragraph with the following:

4.1.2.1 Group B sampling plans.- The group B sampling plans, for the AQL's listed in table I, shall be as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:54Z
Check the source to verify that this is the current version before use.

AQL	Inspection level for normal and tightened inspection	Inspection level for reduced inspection
4.0%	L-8	L-6
6.5%	L-7	L-5

7. Table I Inspection procedures

a. Replace Group B AQL column with the following: Overload 4% Peak Voltage 4% and Dielectric 6.5%

b. Delete Shake Test

c. Replace "3.4" with "3.8"

8. Paragraph 4.10.3 Bounce test.- In first line, delete the words "as packaged for shipment" and in its place insert, "Mounted in a unit with which it is commonly used such as Telephone TP-9.

9. Paragraph 4.10.4.1 Test procedure.

a. Subparagraph a, b, and c shall read as follows:

"a. Take measurements as specified in 4.4 and readjust or realign as necessary to meet full specification requirements.

b. Condition at 86°F ±5°F and 40 to 50 percent relative humidity for 24 hours.

c. Dry at +130°F ±5°F for 24 hours."

b. Subparagraph d: In third line, replace Drawing No. SC-D-16286 with MIL-STD-170(SigC) and in last line replace 3.4 with 3.5.

c. Subparagraph e: In second line, replace 77°F ±5°F with 85°F ±5°F.

10. Replace Section 5 in its entirety with the following:

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level A.- Generator Ringing, Hand GN-38-B shall be preserved, packaged and tested in accordance with the applicable provisions of Specification MIL-P-116 and in a manner that will afford adequate protection against corrosion, deterioration and damage during world-wide shipment, handling and open storage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:54Z
Check the source to verify that this is the current version before use.

5.1.2 Level C.- Generator Ringing, Hand GN-38B shall be afforded preservation and packaging in accordance with the suppliers' normal commercial practice.

5.2 Packing.- Generator Ringing Hand, GN-38B packaged as specified, shall be packed in shipping containers conforming to the requirements of the specifications referenced below for the designated level. The gross weight shall not exceed the weight shown unless an individually packed item exceeds that amount. Closure and strapping shall be as prescribed in the applicable box specification or appendix thereto, except that bands of reinforced, pressure-sensitive adhesive tape, 1/2 inch wide and conforming to Specification PPP-T-97 for Grade IV, shall be used for fiberboard boxes in lieu of metal strapping.

5.2.1 Level A.-

BOX SPECIFICATION		MAX. GROSS WT.
Fiberboard (Type I, Class 2)	PPP-B-636	Table VI
Nailed Wood (Style 4, Class 2)	PPP-B-621	200 lbs.
Wirebound (Style 2 or 3, Class 2)	PPP-B-585	200 lbs.
Wood Cleated Fiberboard (Overseas)	PPP-B-591	200 lbs.
Wood Cleated Plywood (Overseas)	PPP-B-601	200 lbs.
Wood Cleated, Veneer, Paper Overlaid (Overseas)	MIL-B-10377	200 lbs.

5.2.2 Level B.-

BOX SPECIFICATION		MAX. GROSS WT.
Fiberboard (Type I, Class 1)	PPP-B-636	Table I
Nailed Wood (Style 4, Class 1)	PPP-B-621	200 lbs.
Wirebound (Style 3, Class 1)	PPP-B-585	200 lbs.
Wood Cleated Fiberboard (Domestic)	PPP-B-591	200 lbs.
Wood Cleated Plywood (Domestic)	PPP-B-601	200 lbs.
Wood Cleated, Veneer, Paper Overlaid (Overseas)	MIL-B-10377	200 lbs.

5.2.3 Level C.- Generator, Ringing, Hand GN-38-B shall be packed in shipping containers of the type, size and kind commonly used for the purpose in a manner that will insure acceptance by common carrier and safe delivery at destination. Shipping containers shall comply with the rules or regulations of the common carrier, applicable to the mode of transportation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:54Z
Check the source to verify that this is the current version before use.

5.2.5 Pilot pack.- When Level "A" packaging and packing is specified above, one acceptable model of Generator, Ringing Hand GN-38B will be pilot packed in a manner that will pass the preproduction tests prescribed in Specification MIL-P-116. Illustrations of the packaging and packing procedure, together with Bills of Material, will be prepared and furnished in accordance with the provisions of Signal Corps Drawing No. SC-A-362100.

5.3 Marking.- In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with the applicable provisions of Standard MIL-STD-129.

11. Paragraph 6.1 Replace with the following:

6.1 Intended use.- This generator is hand-operated ringing generator intended to supply ringing power for telephone circuits.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:54Z
Check the source to verify that this is the current version before use.