MIL-T-12442C(ME)
29 October 1973
SUPERSEDING
MIL-T-12442B(CE)
13 May 1960

MILITARY SPECIFICATION

TOWER, CABLE ANCHOR

1. SCOPE

1.1 This specification covers the structural components of a cable anchor tower used principally for mooring floating bridges.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

Federal

FF-B-575	- Bolts, Hexagon and Square.
FF-N-836	- Nut: Square, Hexagon, Cap, Slotted, Castle, Knurled, Welding and Single Ball Seat.
QQ-Z-351	- Zinc Slab, Spelter.
RR-S-550	- Sockets, Wire Rope.
RR-W-410	- Wire Rope and Strand.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.
PPP-C-650	- Crates, Wood, Open and Covered.

Military

MIL-P-116	- Preservation-Packaging, Methods of.
MIL-T-704	- Treatment and Painting of Materiel.

FSC 5420

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

MIL-N-25027 - Nut, Self-Locking, 250° F., 450° F., and 800° F., 125 KSI FTU, 60 KSI FTU, and 30 KSI FTU.

STANDARDS

Federal

FED. STD. No. 595 - Colors.

Military

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.

MIL-STD-129 - Marking for Shipment and Storage.

MIL-STD-1186 - Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with Appropriate Test Methods.

DRAWINGS

ME

D2775-1 through -8 - Tower, Cable Anchor.

(Copies of specifications, standards, and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN SOCIETY FOR TESTING AND MATERIALS

A36 - Structural Steel.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the currentversion before use.

AMERICAN WELDING SOCIETY

A5.1	- Mild Steel Covered Arc-Welding Electrodes.
A5.18	- Mild Steel Electrodes for Gas Metal-Arc Welding.
B3.0	- Standard Qualification Procedure.
D2.0	- Welded Highway and Railway Bridges.

(Application for copies should be addressed to the American Welding Society, 2501 Northwest Seventh Street, Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

UNIFORM CLASSIFICATION COMMITTEE, AGENT

Uniform Freight Classification

(Application for copies should be addressed to Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION, INC., AGENT

National Motor Freight Classification

(Application for copies should be addressed to the American Trucking Associations, Inc., ATTN: Tariff Order Section, 1616 P Street, NW, Washington, DC 20036.)

3. REQUIREMENTS

3.1 Description. The anchor tower assembly or components as specified (see 6.2), shall be as shown on Drawings D2775-1 through- 8, and as specified herein. The anchor tower assembly shall consist of the following components in the quantities shown:

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the current version before use.

Component	Drawing	Quantity
Tower unit, cable anchorage	D2775-1	2
Pivot unit, cable anchor tower	D2775-2	1
Base, cable anchor tower	D2775-3	1
Frame, hinge	D2775-4	1
Cap assembly, tower	D2775-5	1
Cap adapter, tower, cable	D2775-6, -7, and -8	1

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the supplier or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article.

3.2.1 Preproduction model. The supplier shall furnish a tower assembly or component(s), as applicable, for examination and test, when applicable, within the time frame specified (see 6.2) to prove prior to starting production, that his production methods will produce tower components that comply with the requirements of this specification. Examination and test, when applicable, shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.2.2 Initial production tower, cable anchor. When specified (see 6.2), the supplier shall furnish to the Government one or more towers, cable anchor, for inspection as specified in 4.4.

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the supplier and shall be subject to all provisions of this specification.

3.3.1 Structural steel. Structural steel shall conform to ASTM A36.

3.4 Welding electrodes. Welding electrodes shall conform to AWS A5.1 or A5.18, classification and size as required for the operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

3.5 Tag line assembly. Wire rope for the tag line assembly shall conform to RR-W-410, type I, class 2, construction optional, improved plow steel, independent wire-rope core (IWRC), uncoated, preformed, regular lay, 7/8-inch diameter. The wire-rope socket shall conform to RR-S-550, type A, finish 2. Socketing of wire rope shall be as specified herein. The complete tag line assembly shall withstand a pull of 25,000 pounds on the socket without failure of the rope or permanent slippage of the socket.

3.5.1 Socketing. Socketing of wire rope shall be accomplished as follows:

(a) The wire shall be securely seized for 1 inch longer than the length of the socket before cutting and securely wrapped with a seizing iron to prevent untwisting of the rope and insure equal tension in the strands when load is applied.

(b) After the wire rope is cut, the seizing on the wire rope shall be removed for a distance from the end of the wire rope equal to the length of the socket basket. The fiber core (if present) shall be cut back to this seizing, and the wires shall all be untwisted and "broomed out." Straightening of the wires is not required.

(c) The wires, for the length that they are to be inserted in socket, shall be cleaned with benzine, naphtha, or gasoline. The wires, for a distance not more than 3/4 of the cleaned length, shall then be dipped in commercial muriatic acid for from 30 seconds to 1 minute or until the acid has thoroughly cleaned each wire. To avoid embrittling the wire the acid shall not come in contact with any other portion of the rope.

(d) The wires shall then be dipped in boiling water and soda to neutralize the acid.

(e) The wires shall be inserted into the basket of the socket. The socket shall be in line with the axis of the wire rope.

(f) The base of the socket shall be sealed with caulking compound.

(g) Molten zinc shall be poured into the basket until it is full. The zinc used for socketing shall conform to QQ-X-351, grade A-1. To avoid annealing the wires the temperature of the molten zinc shall not exceed 830° F.

(h) When the zinc has solidified sufficiently, the socket shall be cooled by plunging into cold water.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

3.6 Bolts. Bolts shall conform to FF-B-575, type II, grade 5 steel for 7/8 inch bolts and grade 1 steel for 5/8 inch bolts. The 7/8 inch diameter bolt shall have a 1-1/2 inch thread length, 7/8-9 NC, class 2 fit.

3.7 Nuts. Safety nuts for 7/8 inch bolts shall be hexagonal nuts of the self-locking thread type conforming to MIL-N-25027, 250° F. nuts, noncorrosion-resistant steel, coarse-thread series. Nuts for 5/8 inch bolts shall conform to FF-N-836, type II, style 4, UNC, grade A steel.

3.8 Identification marking. The structural component shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.9 Treatment and painting. All parts of each structural component except as specified herein shall be treated and painted in accordance with MIL-T-704, type B, except that the color number designation shall be 34087 in accordance with FED. STD. No. 595. Bolts, nuts, pins, and threaded portions of components when applicable shall not be painted but shall be preserved as specified in 5.2.1.2.

3.10 Stenciling. The nomenclature, Federal Stock Number, weight, and cubage shall be stenciled on each major tower component. The letters "NET WT" shall precede the numberals in the weight and the letters "CU" shall precede the cubic displacement. Markings shall be Gothic-type capitals and Arabic numerals 3/4 inch high. Stenciling shall conform to MIL-T-704.

3.11 Government-loaned property. Unless otherwise specified (see 6.2) the following property in the quantities indicated will be loaned by the Government (see 6.5):

ITEM	DESCRIPTION	IDENTIFICATION	QTY
1	Inspection equipment for Tower, Cable Anchor.	Quality Assurance Pamphlet, AMSME-FB-P715-137.	1
2	QA Pamphlet "Care, Operation and Maintenance of Inspection Equipment for Tower, Cable Anchor."	AMSME-FB-P715-137	1

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

3.12 Workmanship. The fabricated tower component shall be free of sharp edges, slivers, or burrs. Unless otherwise specified on the drawings, the following tolerances shall be used. Tolerances for the positioning of holes and parts shall be referenced from one side or end of the member. Tolerances shall not be cumulative.

(a) Fractional dimensions showing spacing, location, or both for pin and boltholes shall be held to plus or minus 1/32 inch.
(b) Drilled holes shall be held to plus 1/64 inch or minus 0 inch.
(c) All other dimensions not noted in (a) or (b) above shall be held to plus or minus 1/16 inch.

3.12.1 Steel fabrication. Steel used in the fabrication of the tower components shall be free from laminations, kinks, and sharp bends. Steel shall be cut by shearing, sawing, or flame cutting. Burned surfaces of flame-cut material shall be ground or machined to remove ash and cooling checks. The straightening of material shall be done by methods that will not cause injury to the metal. Precautions shall be taken to avoid overheating, and heated metal shall be allowed to cool slowly.

3.12.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed.

3.12.3 Welders and welding.

3.12.3.1 Welders. Before assigning any welder to manual welding work covered by this specification, the supplier shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined by the particular code:

Standard Qualification Procedure of the American Welding Society (B3.0).
Welding Qualifications of the ASME Boiler and Pressure Vessel Code (Section IX).

3.12.3.2 Welding. The surface of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be

Source: https://assist.dla.mil -- Downloaded: 202640-17T22:49Z
Check the source to verify that this is the currenversion before use.

done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of the American Welding Society publication "D2.0 - Welded Highway and Railway Bridges". All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wirebrushed clean.

3.12.4 Interchangeability. The components of the towers shall be fabricated to be duplicates within the tolerances specified. The tower components shall be interchangeable in the complete units. Jigs and fixtures shall be used to obtain proper configuration and alinement of components so as to assure complete interchangeability of components.

3.12.5 Assembly. The tower assembly components shall be capable of being assembled into a tower and erected and there shall be no misfits or interference of mating parts.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Acceptability criteria. Tower assemblies or components as applicable, which conform to all requirements in sections 3 and 5 of this specification and pass all applicable examinations in section 4 of this specification will be considered acceptable by the Government.

4.1.2 Component and material inspection. The supplier is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the currentversion before use.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Supplementary Quality Assurance Provisions (SQAP) shown on the drawings. The drawings specify the characteristics requiring SQAP inspection, the sampling plan, and the basis for acceptance or rejection (see 6.4 and 6.6.1).

4.2 Classification of inspection. Inspection shall be classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.5).
(d) Inspection comparison (see 4.7).
(e) Inspection of preparation for delivery (see 4.8).

4.3 Preproduction inspection.

4.3.1 Examination. The tower assembly or tower component as applicable shall be examined as specified in 4.5.2.1 and for the defects specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests.

4.3.2.1 Assembly. The tower assembly shall be tested as specified in 4.6.2.1. Failure of the test shall be cause for rejection. When individual tower components are procured separately, the test shall not apply.

4.3.2.2 Tag line. The tag line assembly shall be tested as specified in 4.6.2.2. Failure of the test shall be cause for rejection.

4.4 Initial production inspection. When specified (see 3.2.2), one or more initial production tower(s), cable anchor, will be selected at random by the Government from towers, cable anchor, being produced by production tooling and will be examined as specified in 4.5.2.1 and 4.6.1 and tested as specified in 4.6.2.1 and 4.6.2.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production tower, cable anchor, shall not exclude the remaining towers, cable anchor, from the quality conformance inspection and acceptance provisions specified in section 4. In addition to any test

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the current version before use.

specified as part of the initial production test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the initial production test and failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

4.4.1 Inspection failure. Failure of an initial production tower, cable anchor, to meet any requirement specified herein during and as a result of the examination and tests specified in 4.5 shall be cause for rejection of the initial production tower(s), cable anchor, and shall be cause for refusal by the Government to continue acceptance of production tower(s), cable anchor, until evidence has been provided by the supplier that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the supplier at no cost to the Government on towers, cable anchor, previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all towers, cable anchor, accepted prior to completion of initial production inspection are similarly deficient unless evidence to the contrary is furnished by the supplier and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Sampling.

4.5.1.1 For examination. Sampling for examination shall be in accordance with MIL-STD-105, level II.

4.5.1.2 For test. Sampling for the tap line test shall be in accordance with MIL-STD-105, inspection level S-4.

4.5.2 Examination.

4.5.2.1 Individual. Each tower assembly or tower component, as applicable, shall be inspected for conformance to the dimensions covered by the Supplementary Quality Assurance Provisions (SQAP) shown the drawings under "Major - 100 percent inspection". Nonconformance to any of these dimensions shall constitute failure of this examination and shall be cause for rejection.

4.5.2.2 Samples. Samples selected in accordance with 4.5.1.1 shall be examined for the major and minor defects specified in 4.6.1. AQL shall be 2.5 percent defective for major defects and 4.0 percent defective for minor defects.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

4.5.3 Test. Samples selected in accordance with 4.5.1.2 shall be tested as specified in 4.6.2.2. Failure of the test shall be cause for rejection.

4.6 Inspection procedure.

4.6.1 Examination. Unless otherwise specified (see 3.11) Government-loaned inspection equipment shall be used in accordance with Government-loaned QA Pamphlet to inspect dimensions indicated on the applicable drawings. The tower or tower components shall be examined as specified herein, for the following defects:

Major

101. All dimensions designated major on the SQAP other than those under 100 percent inspection not as specified.
102. Material not as specified.
103. Components missing or not as specified.
104. Workmanship not as specified.
105. Weld defects such as flux inclusions, spatter, undercutting, porosity, incorrect size, or lack of fusion with parent metal.

Minor

201. All dimensions not designated major on the SQAP not as specified.
202. Identification marking incorrect, missing, or illegible.
203. Treatment and painting not as specified.
204. Stenciling not as specified.

4.6.2 Tests.

4.6.2.1 Assembly. The components of the anchor tower shall be assembled into a tower. The assembled tower shall be erected and checked for assembly alinement and fit. Interference of mating members or incorrect fit at joints shall constitute failure of this test.

4.6.2.2 Tag line assembly. Place the tag line assembly in a suitable jig or fixture in such a manner as to permit a tensile load to be applied

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

to the single leg of the assembly. Insert into the tag line loop a round bar having a diameter of not less than 4-1/2 inches to restrain the tag line from movement while under load. Apply a 25,000-pound tensile load to the tag line assembly at the type "A" cable fitting. Rope failure or permanent slippage of sockets shall constitute failure of this test.

4.7 Inspection comparison. The Government may select towers, cable anchor, at any time during the contract production period and subject these towers, cable anchor, to the examinations specified in 4.5.2.1 and 4.6.1 and the tests specified in 4.6.2.1 and 4.6.2.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government, at a site selected by the Government, on towers, cable anchor selected at random from those which have been accepted by the Government and will not include the previously inspected preproduction model and initial production tower(s), cable anchor. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

4.7.1 Inspection failure. Failure of an inspection comparison tower, cable anchor, to meet any requirement specified herein during and as a result of the examination and tests specified in 4.7 shall be cause for rejection of the inspection comparison tower(s), cable anchor, and shall be cause for refusal by the Government to continue acceptance of production tower(s), cable anchor, until evidence has been provided by the supplier that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the supplier at no cost to the Government on towers, cable anchor, previously accepted and produced under the contract. Any deficiencies found as a result of the inspection comparison will be considered prima facie evidence that all towers, cable anchor, accepted prior to the completion of the inspection comparison are similarly deficient unless evidence to the contrary is furnished by the supplier and such evidence is acceptable to the contracting officer.

4.8 Inspection of preparation for delivery.

4.8.1 Preproduction pack inspection.

4.8.1.1 Examination. Examine the preproduction pack for the defects specified in 4.8.2.3. Presence of one or more defects shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the current version before use.

4.8.1.2 Test. The preproduction pack of a complete crated tower or of crated tower components as applicable, for level A shall be subjected to the railroad-car test as specified for guided-impact tests in accordance with MIL-STD-1186, Appendix A. The car shall strike a string of five empty cars with draft gear extended and the brakes set, at a speed of not less than 10 miles or more than 11 miles per hour. At the conclusion of the preproduction pack test, the pack shall be examined. Any shifting of contents, loosening or breaking of holddowns , ties, stays, blocking or bracing, or any visual damage to the components shall constitute failure of the preproduction pack and shall be cause for rejection.

4.8.2 Quality conformance inspection of pack.

4.8.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.8.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.8.2.3 Examination. Samples selected in accordance with 4.8.2.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

106.	Materials and containers not as specified for level A, B, or C. Each incorrect material or container shall be considered one defect.
107.	Disassembly not as specified for level A or B.
108.	Unpainted surfaces not coated with preservative as specified for level A or B.
109.	Small components not packaged as specified for level A or B.
110.	Blocking, bracing, and anchoring not in accordance with the referenced documents for level A.
111.	Strapping not zinc coated for level A.
112.	Marking missing, illegible, incorrect, or incomplete.

5. PREPARATION FOR DELIVERY

5.1 Preproduction pack. The supplier shall furnish a preproduction pack for examination and test within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied preservation, packaging, packing, and marking comply with the preparation

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the currentversion before use.

for delivery requirements of this specification. Examination and test shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.7). The preproduction pack may be accomplished utilizing either the preproduction model tower or the production tower, or tower components, as applicable. If the preproduction model tower is utilized, any preservation, packaging, and packing shall be removed by the supplier at no expense to the Government when requested by the Government to facilitate comparison between the preproduction model tower and the production tower.

5.2 Preservation and packaging. Preservation and packaging shall be level A, B, or C as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Disassembly. When complete towers are procured, they shall be prepared for shipment unassembled in the components shown on the drawings, except that the splice bolts shall be installed in the bolt carrier clips shown on the individual components and the cap adapter with attached tag lines shall be assembled to the tower cap.

5.2.1.2 Unprotected surfaces. Unpainted metal surfaces of components requiring the application of a contact preservative in accordance with MIL-P-116, shall be coated with type P-1 preservative. The preservative shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

5.2.1.3 Small loose parts. Small loose parts for each tower or component shall be packaged together in close-fitting boxes conforming to PPP-B-621, class 2, grade B, style optional; or PPP-B-601, overseas type, grade B, style optional. The contents shall be secured within the boxes to prevent free movement or damage.

5.2.2 Level B. Preservation and packaging shall be as specified in 5.2.1 for level A except boxes specified in 5.2.1.3 shall be domestic type or class as applicable.

5.2.3 Level C. The tower shall be prepared for shipment unassembled. The components shall be preserved and packaged in a manner to afford protection against deterioration and damage from the supplier to the initial destination.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

5.3 Packing. Packing shall be level A or C, as specified (see 6.2).

5.3.1 Level A. The components comprising a complete tower shall be packed in a crate conforming to PPP-C-650, type II, style A. Blocking, bracing, and anchoring shall be in accordance with the appendix to the crate specification and in accordance with MIL-STD-1186. Strapping shall be zinc coated.

5.3.1.1 Individual tower components. Individual tower components when procured separately shall be packed together as specified in 5.3.1. Small components, impractical to pack in crates shall be packed in boxes as specified in 5.2.1.3. Box closure and strapping shall be in accordance with the appendix to the applicable specification. Strapping shall be zinc coated.

5.3.2 Level C. Complete towers and individual tower components when procured separately, shall be packed or prepared for shipment in a manner to assure carrier acceptance and safe delivery to destination at lowest ratings in wooden containers complying with Uniform Freight Classification rules or National Motor Freight Classification rules.

5.4 Marking. Marking shall be in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The cable anchor tower is a component of floating bridge sets. The towers are used as cable supports in anchoring floating bridges between abutments.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Whether complete tower assemblies or component(s) are required (see 3.1).
(c) Time frame required for submission of the preproduction model (see 3.2.1).
(d) When initial production inspection is required and number of towers, cable anchor, to be furnished, when applicable (see 3.2.2).
(e) When Government-loaned property is not to be furnished (see 3.11).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

(f) Time frame required for submission of the preproduction pack (see 5.1).
(g) Level of preservation and packaging and level of packing required (see 5.2 and 5.3).

6.3 Preproduction model. Any changes or deviations of production towers or tower components from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the supplier of his obligation to furnish tower components conforming to this specification.

6.4 Supplementary quality assurance provisions (SQAP). The contracting officer should require the supplier to maintain records of all SQAP inspections. A suggested paragraph is as follows:

"The supplier shall maintain complete records of all examinations and tests performed to verify the requirements of classified SQAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable."

6.5 Government-loaned property. The contracting officer should arrange to loan the inspection equipment specified in 3.11 and should include the terms for the care, use and maintenance, and storage of such equipment. The use of such equipment should be limited to final acceptance inspections only.

6.6 Definitions.

6.6.1 Supplementary quality assurance provisions (SQAP). A SQAP is a contractual requirement that supplements section 4 of the specification. SQAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.7 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the currentversion before use.

the contracting officer. Approval of the preproduction pack will not relieve the supplier of his obligation to preserve, package, pack, and mark the tower or tower components in accordance with this specification.

Custodian:

Army - ME

Preparing activity:

Army - ME

Project No. 5420-A158

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION MIL-T-12442C(MS) Tower, Cable Anchor

ORGANIZATION

CITY AND STATE | CONTRACT NUMBER

MATERIAL PROCURED UNDER A
☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?
   ☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers attach to form and place both in an envelope addressed to preparing activity.)*

SUBMITTED BY *(Printed or typed name and activity - Optional)* | DATE

DD FORM 1426
11 Oct 72 (Rev)

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

4 42.615- Ft Belvoir

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
U. S. ARMY MOBILITY EQUIPMENT
RESEARCH, DEVELOPMENT
CENTER
FORT BELVOIR, VIRGINIA 22060

OFFICIAL BUSINESS

AMSME-RZD-S

POSTAGE AND FEES PAID
DEPARTMENT OF THE NAVY
DOD-316

COMMANDER
U. S. ARMY MOBILITY EQUIPMENT
RESEARCH, DEVELOPMENT CENTER
ATTN: AMSME-RZD-S
FORT BELVOIR, VIRGINIA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.