INCH-POUND

MIL-T-12442D
2 October 1992
SUPERSEDING
MIL-T-12442C(ME)
29 October 1973

MILITARY SPECIFICATION

TOWER, CABLE ANCHOR

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the structural components of a cable anchor tower used principally for mooring floating bridges.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development, and Engineering Center, ATTN: SATBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

RR-S-550	- Sockets, Wire Rope.
RR-W-410	- Wire Rope and Strand.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.

MILITARY

MIL-P-116	- Preservation, Methods of.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-C-52950	- Crates, Wood, Open and Covered.

STANDARDS

FEDERAL

FED-STD-595	- Colors used in Government Procurement.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with Appropriate Test Methods.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13220E6626	- Tower, Cable Anchor.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development, and Engineering Center, ATTN: SATBE-JBS, Fort Belvoir, VA 22060-5606.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DoDISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 36/36M	- Structural Steel.
ASTM B 6	- Zinc.
D 3953	- Strapping, Flat Steel and Seals.
D 4675	- Selection and Use of Flat Strapping Materials.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY (AWS)

A 5.1	- Carbon Steel Electrodes for Shielded Metal Arc Welding.
A 5.18	- Carbon Steel Filler Metals for Gas Shielded Arc Welding.
D 1.1	- Structural Welding Code-Steel.

(Application for copies should be addressed to the American Welding Society, 2501 Northwest Seventh Street, Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard For Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

UNIFORM CLASSIFICATION COMMITTEE (UCC)

Uniform Freight Classification Rules

(Application for copies should be addressed to the Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION, INC. (NMFTA)

National Motor Freight Classification Rules.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the American Trucking Associations, Inc., ATTN: Tariff Order Section, 2200 Mill Road, Alexandria, VA 22314.)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, (except for related associated detail specifications, specification sheets, or MS standards), the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The anchor tower assembly or components as specified (see 6.2), shall be as shown on Top Assembly TA13220E6626, and as specified herein. The anchor tower assembly shall consist of the following components in the quantities shown:

Component	Drawing	Quantity
Tower unit, cable anchorage	13220E6627	2
Pivot unit, cable anchor tower	13220E6628	1
Base, cable anchor tower	13220E6629	1
Frame, hinge	13220E6630	1
Cap assembly, tower	13220E6631	1
Cap adapter, tower, cable	13220E6632	1

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The item shall be fabricated from compatible materials, inherently corrosion resistant, or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environments to which the item may be exposed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

3.3.2 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.3 Identification of materials and finishes. The contractor shall identify the specific material, material finish, or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.3.4 Structural steel. Structural steel shall conform to ASTM A 36.

3.3.5 Cadmium Plating. Cadmium plated fasteners shall not be used.

3.4 Welding electrodes. Welding electrodes shall conform to AWS A 5.1 or A 5.18, classification and size as required for the operation.

3.5 Tag line assembly. Wire rope for the tag line assembly shall conform to RR-W-410, type I, class 2, construction optional, improved plow steel, independent wire-rope core (IWRC), uncoated, preformed, regular lay, 7/8-inch diameter. The wire-rope socket shall conform to RR-S-550, type A, finish 2. Socketing of wire rope shall be as specified herein. The complete tag line assembly shall withstand a pull of 25,000 pounds on the socket without failure of the rope or permanent slippage of the socket.

3.5.1 Socketing. Socketing of wire rope shall be accomplished as follows:

a. The wire shall be securely seized for 1 inch longer than the length of the socket before cutting and securely wrapped with a seizing iron to prevent untwisting of the rope and insure equal tension in the strands when load is applied.
b. After the wire rope is cut, the seizing on the wire rope shall be removed for a distance from the end of the wire rope equal to the length of the socket basket. The fiber core (if present) shall be cut back to this seizing, and the wires shall all be untwisted and "broomed out." Straightening of the wires is not required.
c. The wires, for the length that they are to be inserted in socket, shall be cleaned with benzine, naphtha, or gasoline. The wires, for a distance not more than 3/4 of the cleaned length, shall then be dipped in commercial muriatic acid for from 30 seconds to 1 minute or until the acid has thoroughly cleaned each wire. To avoid embrittling the wire the acid shall not come in contact with any other portion of the rope.
d. The wires shall then be dipped in boiling water and soda to neutralize the acid.
e. The wires shall be inserted into the basket of the socket.
f. The base of the socket shall be sealed with caulking compound.
g. Molten zinc shall be poured into the basket until it is full. The zinc used for socketing shall conform to ASTM B 6, grade A-1. To avoid annealing the wires the temperature of the molten zinc shall not exceed 830 °F.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

h. When the zinc has solidified sufficiently, the socket shall be cooled by plunging into cold water.

3.6 Identification marking. The structural component shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.7 Treatment and painting. All parts of each structural component except as specified herein shall be treated and painted in accordance with MIL-T-704, type B, except that the color number designation shall be 34088 in accordance with FED-STD-595. Bolts, nuts, pins, and threaded portions of components when applicable shall not be painted but shall be preserved as specified in 5.2.1.2.

3.8 Stenciling. The nomenclature, Federal Stock Number, weight, and cubage shall be stenciled on each major tower component. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. Markings shall be Gothic-type capitals and Arabic numerals 3/4 inch high. Stenciling shall conform to MIL-T-704.

3.9 Government-loaned property. Unless otherwise specified (see 6.2) the following property in the quantities indicated will be loaned by the Government (see 6.5):

ITEM	DESCRIPTION	IDENTIFICATION	QTY
1	QA Pamphlet "Care, Operation, and Maintenance of Inspection Equipment for Tower, Cable Anchor."	AMSME-FB-P715-137	1

3.10 Workmanship. The fabricated tower component shall be free of sharp edges, slivers, or burrs. Unless otherwise specified on the drawings, the following tolerances shall be used. Tolerances for the positioning of holes and parts shall be referenced from one side or end of the member. Tolerances shall not be cumulative.

a. Fractional dimensions showing spacing, location, or both for pin and boltholes shall be held to plus or minus 1/32 inch.
b. Drilled holes shall be held to plus 1/64 inch or minus 0 inch.
c. All other dimensions not noted in (a) or (b) above shall be held to plus or minus 1/16 inch.

3.10.1 Steel fabrication. Steel used in the fabrication of the tower components shall be free from laminations, kinks, and sharp bends. Steel shall be cut by shearing, sawing, or flame cutting. Burned surfaces of flame-cut material shall be ground or machined to remove ash and cooling checks. The straightening of material shall be done by methods that will not cause injury to the metal. Precautions shall be taken to avoid overheating, and heated metal shall be allowed to cool slowly.

3.10.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

3.10.3 Welders and welding.

3.10.3.1 Welders and welding operators. Before assigning any welder or welding operator to welding work covered by this specification, the contractor shall obtain certification that the welder or welding operator has passed qualification tests as prescribed by either AWS D 1.1 or the ASME code for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined. Contractors who only make horizontal welds need not qualify welders for "all position welding". The contractor is responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS and ASME codes. In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator (see 6.6).

3.10.3.2 Welding. The surface of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of the American Welding Society publication D1.1 - Structural Welding Code-Steel. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wirebrushed clean.

3.10.4 Interchangeability. The components of the towers shall be fabricated to be duplicates within the tolerances specified. The tower components shall be interchangeable in the complete units. Jigs and fixtures shall be used to obtain proper configuration and alignment of components so as to assure complete interchangeability of components.

3.10.5 Assembly. The tower assembly components shall be capable of being assembled into a tower and erected and there shall be no misfits or interference of mating parts.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for insuring that components and materials are manufactured, examined, and tested in accordance with referenced specifications and standards, as applicable.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance or rejection (see 6.4 and 6.7.1).

4.2 Classification of inspection. Inspection shall be classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The tower assembly or tower component, as applicable, shall be examined as specified in 4.4.2.1 and for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests.

4.3.2.1 Assembly. The tower assembly shall be tested as specified in 4.5.2.1. Failure of the test shall be cause for rejection. When individual tower components are procured separately, the test shall not apply.

4.3.2.2 Tag line. The tag line assembly shall be tested as specified in 4.5.2.2. Failure of the test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling.

4.4.1.1 For examination. Sampling for examination shall be in accordance with MIL-STD-105, level II. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.4.1.2 For test. Sampling for the tag line test shall be in accordance with MIL-STD-105.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

4.4.2 Examination.

4.4.2.1 Individual. Each tower assembly or tower component, as applicable, shall be inspected for conformance to the dimensions covered by the Quality Assurance Provisions (QAP) shown on the drawings under "Major - 100 percent inspection". Nonconformance to any of these dimensions shall constitute failure of this examination and shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1.1 shall be examined for the major and minor defects specified. Presence of one or more defects shall be cause for rejection.

4.4.3 Test. Samples selected in accordance with 4.4.1.2 shall be tested as specified in 4.5.2.2. Failure of the test shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. Unless otherwise specified (see 3.9) Government-loaned inspection equipment shall be used in accordance with Government-loaned QA pamphlet to inspect dimensions indicated on the applicable drawings. The tower or tower components shall be examined as specified herein, for the following defects:

Major

101. All dimensions designated major on the QAP other than those under 100 percent inspection not as specified (see 3.1 and 3.1.1).
102. Material not as specified (see 3.3).
103. Components missing or not as specified (see 3.1).
104. Materials are not resistant to corrosion or deterioration or treated to be made resistant to corrosion or deterioration for the applicable storage and operating environment as specified (see 3.3.1).
105. Dissimilar metals as specified in MIL-STD-889 are not effectively insulated from each other as specified (see 3.3.2).
106. Contractor does not have documentation available for identification of material, material finishes, or treatments (see 3.3.3).

4.5.2 Tests.

4.5.2.1 Assembly. The components of the anchor tower shall be assembled into a tower. The assembled tower shall be erected and checked for assembly alignment and fit. Interference of mating members or incorrect fit at joints shall constitute failure of this test.

4.5.2.2 Tag line assembly. Place the tag line assembly in a suitable jig or fixture in such a manner as to permit a tensile load to be applied to the single leg of the assembly. Insert into the tag line loop a round bar having a diameter of not less than 4-1/2 inches to restrain the tag line from movement while under load. Apply a 25,000-pound tensile load to the tag line

Source: https://assist.dla.mil -- Downloaded: 20260-17T22:49Z
Check the source to verify that this is the current version before use.

assembly at the type "A" cable fitting. Rope failure or permanent slippage of sockets shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 First article pack inspection.

4.6.1.1 Examination. Examine the first article pack for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.1.2 Test. The first article pack of a complete crated tower or of crated tower components as applicable for level A, shall be subjected to the railroad-car test as specified for guided-impact tests in accordance with MIL-STD-1186, appendix A. The car shall strike a string of five empty cars with draft gear extended and the brakes set, at a speed of not less than 10 miles or more than 11 miles per hour. At the conclusion of the first article pack test, the pack shall be examined. Any shifting of contents, loosening or breaking of holddowns, ties, stays, blocking or bracing, or any visual damage to the components shall constitute failure of the first article pack and shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. Presence of one or more defects shall be cause for rejection.

Major

107. Disassembly not as specified for level A or B (see 5.2.1.1 and 5.2.2).
108. Unpainted surfaces not coated with preservative as specified for level A or B (see 5.2.1.2 and 5.2.2).
109. Small components not packaged as specified for level A or B (see 5.3.1 and 5.2.2).
110. Blocking, bracing, and anchoring not in accordance with the referenced documents for level A (see 5.3.1.1).
111. Strapping not zinc coated for level A (see 5.3.1.1).
112. Marking missing, illegible, incorrect, or incomplete (see 5.4).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 First article pack. The contractor shall furnish a first article pack for examination and test within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied preservation, packing, and marking comply with the packaging requirements of this specification. Examination and test shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.8). The first article pack may be accomplished utilizing either the first article model tower or the production tower, or tower components, as applicable. If the first article model tower is utilized, any preservation, packaging, and packing shall be removed by the contractor, at no expense to the Government, when requested by the Government to facilitate comparison between the first article model tower and the production tower.

5.2 Preservation. Preservation shall be level A, B, or C as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Disassembly. When complete towers are procured, they shall be prepared for shipment unassembled in the components shown on the drawings, except that the splice bolts shall be installed in the bolt carrier clips shown on the individual components and the cap adapter with attached tag lines shall be assembled to the tower cap.

5.2.1.2 Unprotected surfaces. Unpainted metal surfaces of components requiring the application of a contact preservative in accordance with MIL-P-116, shall be coated with type P-1 preservative. The preservative shall conform to the applicable specification listed in, and shall be applied in accordance with, MIL-P-116.

5.2.1.3 Small loose parts. Small loose parts for each tower or component shall be packaged together in close-fitting boxes conforming to PPP-B-621, class 2, grade B, style optional; or PPP-B-601, overseas type, grade B, style optional. The contents shall be secured within the boxes to prevent free movement or damage.

5.2.2 Level B. Preservation and packaging shall be as specified in 5.2.1 for level A except boxes specified in 5.2.1.3 shall be domestic type or class as applicable.

5.2.3 Level C. The tower shall be prepared for shipment unassembled. The components shall be preserved and packaged in a manner to afford protection against deterioration and damage from the supplier to the initial destination.

5.3 Packing. Packing shall be level A or C, as specified (see 6.2).

5.3.1 Level A. The components comprising a complete tower shall be packed in a crate conforming to MIL-C-52950, type II, style A. Blocking, bracing, and anchoring shall be in accordance with the appendix to the crate

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

specification and in accordance with MIL-STD-1186. Strapping shall conform to ASTM D 3953, type 1 or 2, zinc coated, size as applicable; and ASTM D 4675.

5.3.1.1 Individual tower components. Individual tower components when procured separately shall be packed together as specified in 5.3.1. Small components, impractical to pack in crates, shall be packed in boxes as specified in 5.2.1.3. Box closure and strapping shall be in accordance with the appendix to the applicable specification, except strapping may be zinc-coated.

5.3.2 Level C. Complete towers and individual tower components when procured separately, shall be packed or prepared for shipment in a manner to assure carrier acceptance and safe delivery to destination at lowest ratings in wooden containers complying with Uniform Freight Classification rules or National Motor Freight Classification rules.

5.4 Marking. In addition to any special marking specified in the contract or purchase order, marking shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The cable anchor tower is a component of floating bridge sets. The towers are used as cable supports in anchoring floating bridges between abutments. This item is a component of the following supply catalogs: SC 5420-97CL-E35, E36, E46, and E51.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of the specification.
b. Issue of DoDISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. Whether complete tower assemblies or component(s) are required (see 3.1).
d. Time frame required for submission of the first article model (see 3.2).
e. When first article inspection is required and number of towers, cable anchor, to be furnished, when applicable (see 3.2).
f. When Government-loaned property is not to be furnished (see 3.9).
g. Time frame required for submission of the first article pack (see 5.1).
h. Level of preservation and packing required (see 5.2 and 5.3).

6.3 First article. When first article inspection is required, the item(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should also include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results, and disposition of the first articles.

Source: https://assist.dla.mil -- Downloaded: 202640-17T22:49Z
Check the source to verify that this is the current version before use.

Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 Quality assurance provisions (QAP). The contracting officer should require the contractor to maintain records of all QAP inspections. A suggested paragraph is as follows:

"The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, and corrected action taken when applicable."

6.5 Government-loaned property. The contracting officer should arrange to loan the inspection equipment specified in 3.9 and should include the terms for the care, use and maintenance, and storage of such equipment. The use of such equipment should be limited to final acceptance inspections only.

6.6 Consideration of data requirements. The following data requirements should be considered when this specification is applied on a contract. The applicable Data Item Description (DIDs) should be reviewed in conjunction with the specific acquisition to ensure that only essential data are requested/ provided and that the DIDs are tailored to reflect the requirements of the specific acquisition. To ensure correct contractual application of the data requirements, a Contract Data Requirements List (DD Form 1423) must be prepared to obtain the data, except where DoD Far Supplement 27.475-1 exempts the requirement for a DD Form 1423.

Reference paragraph	DID Number	DID Title
3.10.3.1	DI-MISC-80876	Welding Procedure Qualification Test Report.
3.10.3.1	DI-MISC-80875	Welding Procedures.

6.7 Definitions.

6.7.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

6.8 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the contractor of his obligation to preserve, package, pack, and mark the tower or tower components in accordance with this specification.

6.9 Subject term key word listing.

Anchor
Anchoring floating bridges
Bridge anchor

6.10 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army - ME

Preparing activity:
Army - ME

Review activity:
DLA-CS

Project 5420-0195

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-T-12442D	2. DOCUMENT DATE (YYMMDD) 921002

3. DOCUMENT TITLE
Tower, Cable Anchor

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (if applicable) (2) AUTOVON	7. DATE SUBMITTED

8. PREPARING ACTIVITY

a. NAME Geraldine F. Harlow	b. TELEPHONE (Include Area Code) (1) Commercial (703) 704-3469 (2) AUTOVON 654-3468
c. ADDRESS (Include Zip Code US Army Belvoir RDE Center ATTN: SATBE-TSE Fort Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:49Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:49Z
Check the source to verify that this is the current version before use.