MIL-B-21160(OS)
AMENDMENT 2
8 June 1978
SUPERSEDING
AMENDMENT 1
12 February 1963

MILITARY SPECIFICATION

BLADDER, FLOTATION, MARK 2 MOD 1

This amendment forms a part of Military Specification MIL-B-21160(NOrd) dated 29 November 1957.

PAGE 1

* Title, and wherever it appears in the specification, delete "Mark 2 MOD 0" and substitute "Mark 2 MOD 1".

Add the following preamble:

"This specification is approved for use by the Naval Sea Systems Command (OS), Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense."

* Wherever it appears in the specification delete "Bureau of Ordnance and substitute "Naval Sea Systems Command;" also delete "BUORD" and substitute "NAVSEA".

* Wherever it appears in the specification delete "LD 288859" and substitute "1332120".

* Bottom of page add:

"

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this docment should be addressed to: Naval Ordnance Station, Attn: Standardization Division (611), Indian Head, MD 20640 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

"

PAGE 2

* 2.1 Under drawings add: "1380921 Liner Assembly".

PAGE 3

* 3.1 Add at the end: "A support frame to carry two standard non-magnetic SCUBA air bottles is fastened to the bottom of the bladder. An electrically initiated explosive valve (not included in the system) provides a method for remote operation of the flotation bladder."

FSC 2050

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:01Z
Check the source to verify that this is the current version before use.

* 3.2.1 Delete the entire paragraph and substitute the following:

"3.2.1 Preproduction sample. An acceptable preproduction sample of a flotation bladder, manufactured at the same location, using the same tooling and equipment proposed for full production and complying with all applicable provisions of this document shall be furnished by the contractor. The preproduction sample shall not be applied as part of the quantity specified for delivery by the contract."

PAGE 6

* 4.1 Delete the entire paragraph and substitute the following:

"4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

PAGE 7

4.1.2 Delete the last sentence.

PAGE 8

4.1.4, line 11: Starting with the word "From" delete the rest of the paragraph and substitute the following: "Inspection shall be in accordance with MIL-STD-105, Inspection Level S-3, acceptance number Zero."

PAGE 9

4.3.1 Delete last sentence and substitute: "Sampling for these tests is defined in 4.4.3.5."

PAGE 10

4.4.3.5 Delete "with acceptance and rejection numbers of 0 and 1, respectively, for sample sizes less than 15."

PAGE 17

* After paragraph 5.3.2, add the following:

"5.4 Preparation for delivery of liner, assembled unit (spare).

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:01Z
Check the source to verify that this is the current version before use.

5.4.1 Preservation and packaging. When Liners, Assembled Unit (Dwg 1380921) are shipped as spares, one liner shall be neatly folded and wrapped with MIL-B-131 barrier material and packaged in a Type I or Type II, Class 1 fiberboard box conforming to PPP-B-636. Completed package dimensions should not exceed 17x17x8 inches.

5.4.2 Packing. One liner packaged as specified in 5.4.1 shall be packed in a box, wood, nailed conforming to the requirements of PPP-B-621, Class 2, Style 2, Type 2. Corrugated fiberboard liners shall be used to provide a firm pack.

5.4.3 Marking.

5.4.3.1 Special marking. Each pack shall be clearly labeled or marked "DO NOT STORE NEAR STEAM PIPES OR OTHER LOCATIONS WHERE TEMPERATURES IN EXCESS OF 125°F ARE LIKELY TO OCCUR." The National Stock Number shall be marked on each pack.

5.4.3.2 Normal marking. In addition to any requirement of the contract, packs shall be marked in accordance with MIL-STD-129."

* 6.2 Delete entire paragraph and substitute:

"6.2 Ordering data. Procurement documents shall specify:

a. Title, number and date of this specification,
b. Production lot size,
c. Test facility where preproduction and periodic production sample is to be shipped for evaluation."

6.3 Delete the notice at the end of 6.3.

* Add DD Form 1426 (attached) to the end of the specification.

* The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the pervious issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:
NAVY - OS

Preparing Activity:
NAVY - OS
Project No: 2050-N026

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:01Z
Check the source to verify that this is the current version before use.