MILITARY SPECIFICATION SHEET

CABLES, RADIO FREQUENCY SEMIRIGID, COAXIAL, SEMI-AIR-DIELECTRIC 0.620 INCH OUTSIDE DIAMETER, 50 OHMS

The complete requirements for procuring cables described herein shall consist of this document and the latest issue of MIL-C-22931.

REQUIREMENTS:

Attenuation (dB/100 ft max):

100 MHz	- 0.91 dB
400 MHz	- 1.95 dB
1000 MHz	- 3.45 dB

Power rating at 1 GHz - 600W average

Jack spark - 5kV rms, min

Dielectric withstanding voltage - 10,000V rms, 60 Hz - 15,000 Vdc

Velocity - 79 percent

Capacitance - 26.6 pf/1b

Impedance - 50 ±2 ohms

Voltage standing wave ratio on 100-foot assemblies including associated connectors:

Frequency range (MHz)	Initial (max)	After bending and temperature cycling (max)
100	1.2	1.25
400	1.2	1.25
1000	1.2	1.25

Vibration: 55 to 2000 Hz

Mandrel size for temperature cycling, bending, and cold bend tests: 10 inches (254 mm)

FSC 6145

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T14:55Z
Check the source to verify that this is the current version before use.

Minimum bending radius: 5 inches (127 mm)

Construction details: See table below

Requirement 1/	M22931/18-005
Inner conductor Overall diameter ±0.002 (0.05) Dielectrics Cable core OD (nominal) Outer conductor Outer diameter Jacket Overall diameter	Copper clad aluminum 0.172 inch (4.37) Foam polyethylene 0.510 inch (12.95 Corrugated solid copper 0.540 Inch (13.72) Polyethylete 0.620 inch (15.75)

1/ Dimensions are in inches; millimeters are in parentheses. Metric equivalents (to the nearest 0.01 mm) are given for general information only and are based upon 1 inch = 25.4 mm.

The following requirements of MIL-C-22931, identified by similarity of paragraph headings, are not applicable to this slash sheet:

Insulation resistance
Pressure tightness
Marking
Sampling plan under group B inspection
Inspection

The following sampling plan is applicable to this slash sheet:

Sampling plan (group B inspection. The sampling procedure shall be in accordance with MIL-STD-105. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The AQL shall be 4 percent. Inspection shall be level 1 for normal and tightened inspection and level S-4 for reduced inspection.

Unit of product. The unit of product shall be defined as 5000 feet of cable having the same classification whether that length be part of a reel, or consisting of one or more reels.

Custodian:
Air Force - 11

Preparing activity:
Air Force - 11

Project No. 6145-F042

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T14:55Z
Check the source to verify that this is the current version before use.