MILITARY SPECIFICATION

TEST BENCH HARNESS FOR RECEIVING SET, RADIO AN/ARR-40

This specification has been approved by the
Bureau of Naval Weapons, Department of the Navy.

1. SCOPE

1.1 Scope - The equipment covered by this specification shall be suitable for installation on a Standard Electronic Work Bench and shall be used for testing Radio Receiving Set AN/ARR-40. The equipment shall have provisions for holding the receiver and any receiver module in such a manner that maintenance can be performed.

1.2 Classification - The Test Bench Harness shall consist of the following items:

Item	Type Designation	Appl. Para.
Interconnecting Box	J-(*)/ARM-(*)	3.4.1
Cable Assembly, Power, Electrical	CX-(*)/ARM-(*)	3.4.2
Cable Assembly, Power, Electrical	CX-(*)/ARM-(*)	3.4.3
Cable Assembly, Power, Electrical	CX-(*)/ARM-(*)	3.4.4
Cable Assembly	CX-(*)/ARM-(*)	3.4.5
Mounting	MT-(*)/ARM-(*)	3.4.6
Mounting	MT-(*)/ARM-(*)	3.4.7
Mounting	MT-1042/ARA-25	3.4.9
Cable Assembly, RF	W-(*) of ARM-(*)	3.4.10
Cable Assembly, RF	W-(*) of ARM-(*)	3.4.11
Cable Assembly, RF	W-(*) of ARM-(*)	3.4.12
Cable Assembly, RF	W-(*) of ARM-(*)	3.4.13
Connector Adapter	W-(*) of ARM-(*)	3.4.14

Source: https://assist.dla.mil -- Downloaded: 202610-19T15:02Z
Check the source to verify that this is the current version before use.

1.3 Associated Equipment - The equipment shall operate with the following associated equipment which shall not be supplied as part of the equipment:

Item	Type Designation	Application
Multimeter	AN/PSM-4	General checking
Signal Generator	AN/URM-25	IF Alignment
Signal Generator	AN/USM-44	RF Alignment
Oscilloscope	OS-8/U	Audio Output Check
Audio Oscillator	AN/USM-30	Modulation Check
AC Voltmeter	ME-6A/U	Audio Output Check
Vacuum Tube Voltmeter	TS-505/U	RF Alignment
HF Meter	TS-323/UR	RF and IF Alignment
LF Meter	IM-14	IF Test

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids form a part of this specification to the extent specified herein:

SPECIFICATIONS

Military

MIL-T-5422	Testing, Environmental, Aircraft Electronic Equipment
MIL-B-15354	Electrical Tests and Maintenance Tables, Table Tops and Back Panel and Shelf Assemblies
MIL-H-15362	Harnesses; Test Bench, Avionic Equipment, General Specification for
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-T-18303	Test Procedures; Preproduction and Inspection, For Aircraft Electronic Equipment, Format for
MIL-N-18307	Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment
MIL-R-18400	Receiving Set, Radio AN/ARR-40
MIL-T-21200	Test Equipment For Use With Electronic and Fire Control Systems, General Specification for
MIL-F-25173	Fastener, Control Panel, Aircraft Equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:02Z
Check the source to verify that this is the current version before use.

STANDARDS

Military

MIL-STD-242 Electronic Equipment Parts

DRAWINGS

Bureau of Ships

S 9101-212410 - PSNS Type Plan - Workbench for Aviation Electronics Shop

PUBLICATIONS

Bureau of Naval Weapons

ET-287 Bench, Pre-Flight & Flight Test Instructions for Radio Receiving Set AN/ARR-40

2.2 Availability of Documents

(1) When requesting specifications, standards, drawings, and publications refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, Code CDS, 5801 Tabor Avenue, Philadelphia 20, Pennsylvania.

(2) Copies of applicable Bureau of Ships drawings may be obtained upon application to Bureau of Ships, Navy Department, Washington 25, D. C.

3. REQUIREMENTS

3.1 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing the following shall govern:

(1) Parts and materials requirements shall conform to Specification MIL-T-21200. Parts selected from specifications called out in Specification MIL-T-21200 shall be limited to those values, styles, tolerances, etc., set forth in MIL-STD-242.

(2) Nonrepairable subassemblies, as outlined in Specification MIL-T-21200, shall be used when practicable. The general size of the subassembly, and the amount of circuitry to be included therein shall be approved by the procuring activity. Nonrepairable subassemblies must be reliable. A mean-time-to failure of more than 5000 hours should be the goal of each.

(3) When previously produced models of this equipment did not use nonrepairable subassemblies, the design shall not be changed to employ nonrepairable assemblies without the approval of the procuring activity.

3.1.1 Nonstandard Parts and Materials Approval - Approval for the use of nonstandard parts and materials shall be obtained as outlined in Specification MIL-T-21200.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:02Z
Check the source to verify that this is the current version before use.

3.2.1 General - The equipment shall conform with all the applicable requirements of Specification MIL-H-15362 for design, construction and workmanship, unless otherwise specified herein. The equipment shall be suitable for attachment to and operation on any electronic test bench described in Specification MIL-B-15354 and Bureau of Ships Drawing S 9101-212410. The equipment when set up for use on the electronic work bench shall not require more than 2 feet of bench length. The top shelf space of the bench shall be available for mounting government-furnished standard test equipment. Additional bench top space will be required for mounting government-furnished standard test equipment. Additional holes shall be provided as required for satisfactory installation in either of the work bench shelf assemblies.

3.2.2 Interchangeability - The equipment shall meet the interchangeability requirements as defined in Specification MIL-T-21200.

3.2.3 Maintenance Provisions and Field Testing - Provisions for maintenance shall be as specified in Specification MIL-T-21200.

3.2.4 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with Specification MIL-N-18307.

3.2.5 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

Temperature	Room ambient (30° ±10°C)
Altitude	Normal ground
Vibration	None
Humidity	Room ambient up to 90% relative humidity

3.2.6 Service Conditions - The equipment shall operate satisfactorily under any of the environmental service conditions or reasonable combination of these conditions as specified in Specification MIL-H-15362.

3.3 Performance -

3.3.1 General - Unless otherwise specified, values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme service conditions. When reduced performance under the extreme conditions is acceptable, tolerances or values setting forth acceptable variations from the performance under the standard conditions will be specified.

3.3.2 Operation - This equipment shall include all provisions and test facilities to perform test, alignment functions and minor repair work normally required in field maintenance of AN/ARR-40 Units as follows:

Relay, Armature	RE-219/ARR-40
Control, Receiver	C-1457/ARR-40
Receiver, Radio	R-550/ARR-40

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:02Z
Check the source to verify that this is the current version before use.

3.4 Detail Requirements -

3.4.1 Interconnecting Box J-(*)/ARM-(*) - This unit shall provide a means for mounting Control, Receiver C-1457/ARR-40. The Box shall employ fasteners in accordance with Specification MIL-E-25173. This unit shall provide the necessary circuitry, jacks, switches, and indicator lamps to be instrumental in the testing of Radio Receiving Set AN/ARR-40 in accordance with ET-287 and Specification MIL-R-18400. The required facilities and functions of the Interconnecting Box are listed as follows:

(1) Receptacle for accepting Electrical Power Cable Assembly CX-(*)/ARM-(*)

(2) Receptacle for accepting Wiring Harness CX-(*)/ARM-(*)

(3) Receptacle for accepting Electrical Power Cable Assembly CX-(*)/ARM-(*)

(4) Receptacle and mounting facilities for connecting Control, Receiver C-1457/ARR-40

(5) AVC test point for measurement of AVC line from Receiver, Radio R-550/ARR-40

(6) +27.5 V test point for measurement of the primary voltage supplied from the AN/ARR-40 to the AN/ARA-25 equipment.

(7) +217 V test point for measurement of B+ supply voltage for Direction Finder Group AN/ARA-25. This voltage is produced by Receiver, Radio R-550/ARR-40.

(8) "Mechanical Drive Ground" binding post used in conjunction with the Tracking Switch to control RF Tuner rotation during alignment.

(9) "Aux Audio Out" jack for monitoring the receiver high fidelity audio of Receiver, Radio R-550/ARR-40 as required for Direction Finder Group AN/ARA-25. A 20,000 ohm load shall be automatically disconnected when phone plug is inserted into the jack.

(10) "Main Audio Out" jack used for monitoring the receiver audio or for measurements of the audio output. A 300 ohm load shall be automatically disconnected when a headset plug or the equivalent is inserted into the jack.

(11) "Tracking Sw" to provide a control for RF Tuner rotation during alignment.

(12) "Cmd-ADF" switch to change the R-550/ARR-40 Receiver Sensitivity from normal to maximum and lengthen the time constant of the AVC line for ADF operational checking.

(13) "Main Power" switch to control the 27.5 volt dc power to the AN/ARR-40 equipment.

(14) "Main Power" indicating lamp shall indicate when the Main Power switch is in the "On" position.

(15) "Main Power Fuse" shall provide overload protection for the AN/ARR-40 equipment.

Source: https://assist.dla.mil -- Downloaded: 202610-19T15:02Z
Check the source to verify that this is the current version before use.

(16) "Receiver Control Aux Functions Test" switch applies 27.5 V dc to the switch sections of Control, Receiver C-1457/ARR-40 which are used to control equipment other than Receiver, Radio R-550/ARR-40. This 27.5 V dc is used to illuminate lamps to test these switch sections.

(17) "Receiver Control Aux Functions Test" indicator lamps shall indicate proper or improper functioning of the switch sections of Control, Receiver C-1457/ARR-40 which are used to control equipment other than Receiver, Radio R-550/ARR-40.

(18) "Audio Output from Main Transceiver" test point for checking the operation of this section of Aux Rec. switch on Control, Receiver C-1457/ARR-40.

(19) "Audio Output to Intercom" test point for checking the operation of this section of Aux Rec. switch on Control, Receiver C-1457/ARR-40.

(20) "Antenna Relay Control" switch to energize or de-energize Relay, Armature RE-219/ARR-40.

(21) "Antenna Relay Test" switch to test Relay, Armature RE-219/ARR-40 contacts by means of indicator lamps.

(22) "Antenna Relay Test" lamps shall indicate proper or improper operation of Relay, Armature RE-219/ARR-40.

3.4.2 Cable Assembly, Power, Electrical, CX-(*)/ARM-(*) - This cable assembly shall be the primary power connecting the bench test equipment to the 27.5 V dc power source. One end shall have a connector to connect to Interconnecting Box J-(*)/ARM-(*) and the other ends shall be stripped and tinned.

3.4.3 Cable Assembly, Power, Electrical CX-(*)/ARM-(*) - This cable assembly, with connectors, shall connect Receiver, Radio R-550/ARR-40 to J-(*)/ARM-(*) for the operation of the receiver during testing.

3.4.4 Cable Assembly, Power, Electrical CX-(*)/ARM-(*) - This cable assembly shall be a 15 conductor extension cable supplied to permit electrical operation of sub-assemblies removed from Receiver R-550/ARR-40.

3.4.5 Cable Assembly CX-(*)/ARM-(*) - This cable, with connectors, shall connect Relay, Armature RE-219/ARR-40 to J-(*)/ARM-(*) for test.

3.4.6 Mounting MT-(*)/ARM-(*) - This mounting shall hold Receiver, Radio R-550/ARR-40 during test. It shall be so constructed that the sides, top, bottom, and front of the receiver are easily accessible. The mount shall allow the receiver to be rotated about its major axis and shall be equipped with a positive locking action.

3.4.7 Mounting MT-(*)/ARM-(*) - This mounting shall hold any of the 5 sub-assemblies of Receiver, Radio R-550/ARR-40, excluding the Dynameter Unit, for test, alignment, and/or repair. The mounting shall allow the sub-assembly to be rotated about both a horizontal and vertical axis for ease of maintenance. It shall be equipped with positive locking action.

3.4.8 Clamp, Cable - A sufficient quantity of cable clamps shall be provided to adequately hold the power and control cables to the standard Navy Test Bench.

Source: https://assist.dla.mil -- Downloaded: 202610-19T15:02Z
Check the source to verify that this is the currentversion before use.

3.4.9 Mounting, MT-1042/ARA-25 - This mounting shall provide a means for mounting Relay, Armature RE-219/ARR-40 to Workbench.

3.4.10 Cable Assembly, RF W-(*) of ARM-(*) - This cable assembly shall be an extension subminiature coaxial cable with a subminiature connector on each end which will permit electrical operation of sub-assemblies removed from Receiver, Radio R-550/ARR-40.

3.4.11 Cable Assembly, RF W-(*) of ARM-(*) - This cable assembly shall be an extension RG-58/U coaxial cable with a male miniature connector on one end and a female miniature connector on the other end which will permit electrical operation of sub-assemblies removed from Receiver, Radio R-550/ARR-40.

3.4.12 Cable Assembly, RF W-(*) of ARM-(*) - This cable assembly shall be an extension RG-58/U coaxial cable with a male miniature connector on one end and a male BNC connector on the other end which will permit electrical operation of sub-assemblies removed from Receiver, Radio R-550/ARR-40.

3.4.13 Cable Assembly, Rf W-(*) of ARM-(*) - This cable assembly shall be an extension RG/U coaxial cable with a female miniature connector on one end and a male BNC connector on the other end which will permit electrical operation of sub-assemblies removed from Receiver, Radio R-550/ARR-40.

3.4.14 Connector, Adapter W-(*) of ARM-(*) - This adapter shall be a BNC to subminiature type which will permit connections to be made between test equipment using BNC fittings and the subminiature connectors used in Receiver, Radio R-550/ARR-40.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:02Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 General - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements:

(1) Preproduction Tests

(2) Production Sample Tests

(3) Acceptance Tests

4.2 Preproduction Tests - Preproduction tests shall be made on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall consist of the following:

(1) Contractor's Demonstration Tests

(2) Service Approval Tests

4.2.1 Contractor's Demonstration Tests - Contractor's demonstration tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of 4.5. The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the services of a commercial testing laboratory.

4.2.1.1 The contractor shall submit all data collected in conducting these tests to the procuring activity for review and approval. This data shall include a list of all electrical and electronic parts giving their specified voltage, current and temperature rating and the applied circuit voltage, current and ambient and surface temperatures. The ambient and surface temperature shall be obtained under the extreme high temperature operating condition. This data may be included as part of the preliminary parts list.

4.2.2 Service Approval Tests - At the completion of the contractor's demonstration tests and when requested by the procuring activity, the equipment shall be delivered to a specified government laboratory for additional testing. This additional testing may consist of duplicating tests previously conducted and such other tests as are deemed necessary to determine compliance with all applicable design and performance requirements.

4.2.2.1 Accessory Material - In addition to the complete equipment submitted for service approval tests, the contractor shall also submit the accessory material and design and test data specified in Specification MIL-T-21200. This information shall indicate the physical and electrical characteristics of the equipment and establish the equipment's compliance with applicable requirements.

4.2.3 Scope of Tests - Preproduction tests shall include all tests deemed necessary to determine that the equipment meets all the requirements of this specification and the contract. Preproduction tests shall include environmental tests in accordance with Specification MIL-T-5422, modifying the test limits of the applicable tests to correspond with the limits specified herein. Drop tests for transit and combination cases shall be in accordance with Specification MIL-T-21200.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:02Z
Check the source to verify that this is the current version before use.

4.2.4 Preproduction Approval - Approval of the preproduction model shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction model. Prefabrication of production equipment prior to the approval of the preproduction model is at the contractor's own risk. The approved preproduction model will be returned to the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction model shall not be considered as one of the equipments under the contract; however, it may be reworked by the contractor and submitted for acceptance as a production equipment.

4.2.5 Equipments supplied under the contract shall in all respects, including design, construction, workmanship, performance and quality be equivalent to the approved preproduction sample. Each equipment shall be capable of successfully passing the same tests imposed on the preproduction sample. Evidence of non-compliance with the above shall constitute cause for rejection or if already accepted by the government it shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.3 Production Sample Tests -When requested by the procuring activity, one equipment shall be selected from the first 10 production equipments submitted for acceptance and sent to a designated government laboratory for tests. The equipment shall be selected by the government inspector after the equipment has successfully passed all individual tests.

4.3.1 Scope of Tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the approved preproduction sample in design, construction, workmanship, performance and quality and that it is capable of meeting all applicable requirements.

4.3.2 Production Sample Approval - Approval of the production sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Upon failure of the production sample to pass any of the tests, delivery of equipment under the contract shall cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

4.3.3 Reconditioning of Production Test Sample - On completion of the production sample test the equipment shall be reworked by the contractor by replacing all wear or damaged items. After reworking the contractor shall resubmit the equipment for acceptance.

4.4 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

(1) Individual Tests

(2) Sampling Tests

(3) Special Tests

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:02Z
Check the source to verify that this is the current version before use.

4.4.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests:

(1) Examination of Product

(2) Operational Test

(3) Manufacturing Reliability Test

4.4.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.4.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.4.1.3 Manufacturing Reliability Test - Each equipment shall be operated under the conditions specified herein for a period of 6 hours without failure. A failure shall be defined as anything which causes malfunctioning of the equipment. Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of the equipment.

Temperature	Ambient room
Humidity	Ambient room
Vibration	Any selected frequency within the range of 20 to 30 cps (excluding resonant points) and a minimum amplitude of ±3 g's

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 6-hour period of operation. Where feasible, the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes and lateral to that plane for 5 minutes. Where it is not feasible to vibrate the equipment in 2 directions the vertical direction shall be used. During the 6-hour period of operation following the 10-minute vibration period, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, it should be repaired and the test started over, except that the 10-minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be composed of two 3-hour periods to conform with standard working hours.

Source: https://assist.dla.mil -- Downloaded: 202610-19T15:02Z
Check the source to verify that this is the current version before use.

4.4.2 Sampling Tests - Sampling tests shall be conducted on equipments which have successfully passed the individual tests. Equipments shall be selected for sampling tests by the Government Inspector in accordance with the following:

Quantity of Equipments Offered for Acceptance	Quantity to be Selected For Sampling Test
First 10	1
Next 50	1
Next 75	1
Next 100	1
	1 for each additional 200 or fraction thereof

4.4.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests:

(1) Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

(2) Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the preproduction, production and special tests.

4.4.3 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling tests.

4.4.3.1 Special Tests Schedule - Selection of equipments for special tests shall be made as follows; except that when a Production Sample is requested and delivered to a government laboratory for test (See para. 4.3) the requirement for a special test on an early production equipment may be omitted.

(1) On an early production equipment.

(2) On an early equipment after an engineering change.

(3) Whenever failure reports or other information indicate additional equipments should be tested. (This will be determined by the procuring activity.)

Source: https://assist.dla.mil -- Downloaded: 202640-19T15:02Z
Check the source to verify that this is the currentversion before use.

4.4.3.2 Scope of Tests - Special tests shall consist of such tests as are approved by the procuring activity. Test procedures previously approved for the preproduction and sampling tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests. As a minimum, the following tests shall be made, except that for those equipments selected as a result of design changes and failure reports, only those tests required to check the characteristics in question need be conducted.

(1) Temperature - Altitude Tests

(2) Vibration Test (60 minutes cycling in each of 3 planes)

(3) Humidity Tests

4.4.4 Equipment Failure - Should a failure occur during either the sampling or special tests, the following action shall be taken:

(1) Determine the cause of failure.

(2) Determine if the failure is an isolated case or design defect.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occuring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

4.5 Test Procedures - The procedures used for conducting preproduction tests, acceptance tests and life tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification or the contract. Specification MIL-T-18303 shall be used as a guide for preparation of test procedures. When test procedures are available from previous contracts such procedures may be used when approved by the procuring activity.

4.6 Presubmission Testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.7 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the government inspector.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:02Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with Specification MIL-E-17555.

6. NOTES

6.1 Use - Equipment covered by this specification is intended for use in bench testing, adjusting or repair of airborne electronic equipment in electronic shops which are located at shore bases or on board naval vessels.

6.2 Test Values - Normal and limiting values of performance data shall be determined at input voltages of 115 ± 1.0 V AC. These data are to be used in testing the equipment at installation points for compliance with minimum acceptable standard of performance.

6.3 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(1) Contract - The contract shall have precedence over any specification.

(2) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(3) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.4 The parentheses (*), when used in the type designation, shall be replaced by either a number or letter furnished by the procuring activity upon application by the contractor for assignment of nomenclature in accordance with 3.2.4. The complete type number shall be used on nameplates, shipping records and instruction books, as applicable.

NOTICE - When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished or in any way supplied the said drawings, specifications or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 20261O-19T15:02Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:02Z
Check the source to verify that this is the current version before use.