MILITARY SPECIFICATION

ROCKET MOTOR, M3A2
PARTS FOR

This amendments forms a part of military Specification MIL-R-46259A(MU) dated 10 October 1962.

Page 1, Specifications, Military: Delete "MIL-M-11472 Magnetic Particle Inspection; Process for Ferromagnetic Material".

Page 2, Publications, IEL: delete "8802332". Add "8799794".

Page 2, paragraph 3.4.1: Delete "200 megohms". Add "50 megohms".

Page 3, paragraph 3.5, line 1: Delete "cracks". Add "cracklike indications".

Page 3. Add paragraph 3.5.1 to read as follows:

"3.5.1 *Evidence of magnetic particle inspection.* At the successful completion of magnetic particle inspection, the nozzle and body shall be marked with the letter M in accordance with 4.4.6.1 to indicate satisfactory passage of magnetic particle inspection as specified in 4.4.6."

Page 9, paragraph 4.3.2.7: Add "Critical 2" to read as follows: "2. Magnetic particle inspection stamp missing..... Visual 07009".

Page 10, paragraph 4.3.2.9: Add "Critical 2" to read as folows: "2. Magnetic particle inspection stamp missing ..... Visual 09007".

Page 11, paragraph 4.3.3.3, line 2: Change "Major Defect" to read "Critical defect".

Page 12. Add paragraph 4.3.4.2 to read as follows:

"4.3.4.2 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement of parts, inspection of items at overhaul, general maintenance of equipment construction, survey and whenever inspection equipment drawings are needed".

Page 13, paragraph 4.4.5.1 and paragraph 4.4.5.2: Delete last sentence from each paragraph and add "There shall be no evidence of leakage while the part is subjected to pressure. The part shall be inspected after test to determine that no permanent deformation in excess of drawing requirements has occurred".

Page 13, paragraph 4.4.6, line 4: Delete "MIL-M-11472". Add "MIL-I-6868" and at end of paragraph add "If an indication can be removed from the nozzle or body without exceeding drawing requirements, the defect may be removed and the nozzle or body re-

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:22Z
Check the source to verify that this is the current version before use.

submitted to magnetic particle inspection for compliance with requirements as specified in 3.5".

Page 13, paragraph 4.4.6, line 5: Change "shell" to read "parts".

**Page 13*. Add paragraph 4.4.6.1 to read as follows: "4.4.6.1 *Magnetic particle inspection marking*. The nozzle and body that satisfactorily pass the magnetic particle inspection shall be marked with the letter "M." This marking shall be applied on the nozzle and body adjacent to the hydro-test stamp. The marking shall be applied using controlled pressure to maintain a maximum impression depth of 0.010 inch".

**Page 14*. Delete paragraph 6.1 through and including 6.3. Add paragraphs:

6.1 Ordering data. Procurement documents shall specify the following:

(a) Title, number and date of this Specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the inspection equipment list by the following codes:

CDOF —Contractor's design responsibility on Ordnance format; ORDM–608–12.
CDCF —Contractor's design responsibility on contractor format.
OD —Ordnance design.
ODMU—Ordnance design, mandatory for use.
CE —Commercial equipment.
SCD —Specification Control Drawing.

6.3.3 *Ordnance designs.* Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and nonmandatory. When an inspection equipment list references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawings.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:22Z
Check the source to verify that this is the current version before use.

only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM 608-12, and in addition, contain the detail and information specified above.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

*Asterisks indicate changes or additions to Amendment 1.

Custodian:
Army—MU

Preparing activity:
Army—MU
Project No. 1340-A162

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:22Z
Check the source to verify that this is the current version before use.