MIL-S-63383(AR)
AMENDMENT 1
2 February 1981

MILITARY SPECIFICATION

SAFE AND ARMING (NON-HAZARDOUS) ASSEMBLY
FOR MINES, M718/M741 SYSTEM

This Amendment forms a part of Military Specification MIL-S-63383(AR), dated 13 March 1980.

Delete:

"Safe and Arming (Clearing Charge Train) Assembly" and substitute, "Safe and Arming (Non-Hazardous) Assembly" wherever mentioned.

PAGE 1

Paragraph 2.1: Under SPECIFICATIONS delete word "FEDERAL" and substitute "MILITARY".

Add: "MIL-S-48747 - Safe and Arming Device for Mines M718/M741 System"

PAGE 2

Paragraph 3.3: Add to the end of the sentence:

"as evidenced by the presence of a length of solder in the dummy center lead and the absence of main charge leads and clearing charge propellant."

PAGE 3

Paragraph 3.4: Delete the second line and substitute:

"aft ejection charge assembly (without M5 propellant) shall all function high order when the detonators".

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:46Z
Check the source to verify that this is the current version before use.

Paragraph 3.4.1: Delete in its entirety.

PAGE 4

Add: "-2" after 9277986 and 9277858 in drawing column.

PAGE 6

Add: "(without M5 propellant)" after "Aft Ejection Charge Assembly" and "Chamber Assembly" in Examination or Test box.

Add: "-2" after drawing no. 9277858 and drawing no. 9277986 in Examination or Test box.

PAGE 7

Paragraph 4.4.1: Delete paragraph in its entirety and substitute the follwoing new paragraph:

"4.4.1 Inspection lot formation. Inspection lots shall comply with the lot formation provisions of MIL-A-48078. In addition, lots of safe and arming assemblies and sub-assemblies shall contain:

a. Parts bearing the same lot interfix number from one manufacturer and drawn from an accepted lot of representative parts used in the assembly of one lot of safe and arm assemblies, part number 9278015.

b. Explosive detonators, transfer leads, and aft-ejection charge assemblies (without M5 propellant) from the same lot interfix number from one manufacturer and drawn from an accepted lot of representative parts used in the assembly of one lot of safe and arm assemblies, part number 9278015.

Lot numbering shall comply with the lot numbering provisions of MIL-A-48078. Each lot of the Safe and Arming (Non-Hazardous Assemblies) shall be assigned a lot interfix number from within the 500 to 599 number group. All other lot number information shall be consistent with the lot number of safe and arming assembly lot, part number 9278015, from which the representative parts have been selected.

For example, if the Safe and Arming Assembly, part number 9278015, has a lot number of ABC80A001-001, the representative non-hazardous safe and arming assemblies, part number 9317620, would have a lot number of ABC80A500-001."



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:46Z
Check the source to verify that this is the current version before use.

PAGE 9

Para. 4.4.2.2 -

Add the following critical defect:

| Category | Exam or Test | No. of Sample Units | AQL | Reqm't Para. | Para. Ref. |
|---|---|---|---|---|---|
| "11. | Deformation of centrifugal lock hole(s) after spring holder staking | 4.4.3.3 | - | 3.2 | 4.5.9" |

Add "(5)" after the word "critical" in the category block.

PAGE 10

Add to the notes:

"(5) para. 4.5.10 applies whenever critical defects are discovered."

PAGE 12

Para. 4.4.2.4 - Add "(3)" after the word "critical" in the category block.

Add to the Notes block:

"(3) para. 4.5.10 applies whenever critical defects are discovered."

Paragraph 4.4.2.4: Critical defect 1 - In Examination or Test box - delete "(radiographic)" and substitute "(Visual and radiographic)". In Para Ref box - delete "4.5.4" and substitute "4.5.4/Visual".

PAGE 13

Paragraph 4.4.2.5: Add "-2" after drawing number 9277986 in drawing number box.

PAGE 14

Paragraph 4.4.2.6: Add "-2" after drawing number 9277858 in drawing number box.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:46Z
Check the source to verify that this is the current version before use.

Delete major defect 101 in its entirety.

PAGE 16

Paragraph 4.4.3.1: Delete in its entirety.

Add the following new paragraph:

"4.4.3.3 Centrifugal lock hole inspection - The inside diameter of the centrifugal lock holes in the S&A housing shall be inspected after staking of the centrifugal lock spring holders. The inspection shall be performed on three (3) centrifugal lock/housing subassemblies from each staking tool at the start of each shift and then on one (1) subassembly randomly selected from each group of 100 produced continuously from lock staking tool. The contractor shall not enter into production with any staking tool unless all three (3) samples pass the initial inspection. Both centrifugal lock holes on each sample shall be inspected. Inspection shall be performed in accordance with 4.5.9. The contractor may request a change in frequency of the inspection provided he presents substantive evidence to support the request."

PAGE 19

Paragraph 4.5.4: Add to the end of the second sentence:

"and the S&A explosive loading complies with the requirement of 3.3."

Paragraph 4.5.5.1: Delete paragraph 4.4.5.1 in its entirety and substitute new paragraph 4.4.5.1 as follows:

"4.5.5.1 Detonator continuity resistance. The measurement of the detonator resistance (value specified on Dwg 9317620) shall be obtained on the final safe and arming assembly, (including staked shield assembly) utilizing an approved milliohmeter whose excitation current does not exceed the no fire condition of the detonators. The resistance measurement shall be obtained across the eyelets on the flexible cable (Dwg. 9277774). Any assembly failing to comply with the specified resistance requirement shall be classed defective. The exposed conductor (shorting loop) in the flexible cable (Dwg. 9277774) must be cut to perform this test and soldered to reconnect the above conductor after completion of test. (Non-destructive test)."



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:46Z
Check the source to verify that this is the current version before use.

PAGE 20

Paragraph 4.5.6.2: Delete in its entirety.

PAGE 21

Delete page 21 in its entirety.

PAGE 22

Delete page 22 in its entirety.

PAGE 23

Delete page 23 in its entirety.

PAGE 24

Delete page 24 in its entirety.

PAGE 25

Delete page 25 in its entirety.

PAGE 26

Delete page 26 in its entirety.

PAGE 27

*Add the following new paragraphs:

"4.5.9 Centrifugal lock hole inspection. Both centrifugal lock spring holders shall be removed using approved tooling and procedures. The housing shall be rotated and the centrifugal locks allowed to fall from the housing.

A .2495 - .0005 inch pin gage shall fall freely (without applying pressure) to the bottom of the hole (shoulder). If one or both locks fail to fall out under their own weight or the pin gage fails to insert freely in one or both holes, the unit shall be classed defective and that quantity of subassemblies from which the sample was drawn shall be rejected (Destructive test).



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:46Z
Check the source to verify that this is the current version before use.

4.5.10 Critical defect reporting. The contractor shall proceed as follows whenever a critical defect is discovered during the examinations or tests described in this specification:

a. Immediately notify the cognizant technical agency.

b. Tentatively reject and quarenteen all previously accepted S&A subassemblies and assemblies in process.

c. Determine root cause of defect and proceed as directed by the contracting officer."

PAGE 28

Add to paragraph 6.2:

"A quantity of Safe and Arming (Non-Hazardous) Assemblies, P/N 9317620 shall be fabricated with each lot of Safe and Arming Assemblies, P/N 9278015 manufactured. Quantity and requirement for delivery shall be as specified in the contract."

Custodian:
Army-AR

Preparing Activity:
Army-AR

Project No.: 1345-A-141



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:46Z
Check the source to verify that this is the current version before use.