MIL-B-63094B(AR)
AMENDMENT 4
26 January 1982
SUPERSEDING
AMENDMENT 3
18 March 1980

MILITARY SPECIFICATION

BLASTING MACHINE, 50 CAP, M34

This amendment forms a part of Military Specification MIL-B-63094B(AR), dated 24 July 1978, and is approved for used by the US Army Armament Research and Development Command and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 3

3.3: Delete in its entirety and substitute the following:

"3.3 Output capacity. The blasting machine shall produce a minimum output of one and five tenths (1.5) amperes Root Mean Square (RMS) for a period of zero (0) to one and five tenths (1.5) milliseconds when tested as specified in 4.5.1."

3.4: Delete in its entirety and substitute the following:

"3.4 Drop test. The blasting machine shall comply with the requirements of 3.3 when subjected to a five (5) foot drop onto a concrete surface."

* 3.8: Delete in its entirety and substitute the following:

"3.8 Extreme temperature performance. The blasting machine shall comply with the requirements of 3.3 when tested at minus forty five degrees centigrade to plus fifty-two degrees centigrade (-45°C to +52°C) when tested as specified in 4.5.6."

PAGE 6

Table I, "First Article Inspection": Under "Sleeve, Rotor" delete the following:

"(Dwg. 9232516)"

and substitute the following:

"(Dwg. 9235516)".

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:11Z
Check the source to verify that this is the current version before use.

PAGE 11

Table I, "First Article Inspection": Under Tests delete the the following:

"Drop test/10 (c)/3.4/4.5.2
Transportation vibration/20 (f)/3.6/4.5.4
Waterproofness/5 (f)/3.5./4.5.3.1
Service life cycle/5 (g)/3.7/4.5.5"

and substitute the following:

"Drop test/10 (e)/3.4/4.5.2
Transportation vibration/10 (f)/3.6/4.5.4
Humidity/10 (f)/3.11/4.5.9
Waterproofness/5 (f)/3.5/4.5.3.1"

PAGE 12

Table I, "First Article Inspection": Delete the following:

"Humidity/10 (f)/3.11/4.5.9" and substitute the following: "Service life cycle/5 (g)/3.7/4.5.5".

Table I, "First Article Inspection": Under "Housing, Electrical" delete the following:

"(Dwg. 9235541)" and substitute the following: "(Dwg. 9238279)".

PAGE 16

4.4.2.1: In "Next Higher Assembly" block delete the following:

"9235509" and substitute the following: "9238276".

PAGE 17

4.4.2.2: In "Next Higher Assembly" block delete the following:

"9235509" and substitute the following: "9328276".

PAGE 24

4.4.2.9: In Next Higher Assembly" block delete the following:

"9235523" and substitute the following: "9328725".

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:11Z
Check the source to verify that this is the current version before use.

PAGE 33

4.4.2.18: Delete this paragraph in its entirety.

PAGE 42

4.4.2.27: In "Next Higher Assembly" block delete the following: "9312773" and substitute the following: "9328276".

PAGE 44

Major 110, "Insulation resistance", add "100%" to AQL column.

PAGE 45

4.4.2.30: In "Drawing Number" block delete the following: "9235541" and substitute the following: 9328279".

In "Next Higher Assembly" block delete the following: "9235509" and substitute the following: "9328276".

PAGE 49

4.4.2.33: In "Next Higher Assembly" block delete the following: "9235504" and substitute the following: "9312773".

PAGE 55

4.4.5: In the second line from the end of this page, delete the period between the words "selected" and "after" and change the "A" in "after" to "a".

PAGE 57

4.5.2: Delete this paragraph in its entirety and substitute the following:

"4.5.2 Drop test. Five blasting machines shall be conditioned at minus forty-five degrees centigrade minus five degrees centigrade (-45° -5°C) and another five at fifty-two degrees centigrade plus five degrees centigrade (52°C $+5^{\circ}$C) for a period of twenty-four hours plus one hour (24 hrs + 1 hr). The machine shall then be dropped once, a vertical distance of five feet (5 ft) onto a solid concrete surface, with the following orientations at each temperature:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:11Z
Check the source to verify that this is the current version before use.

Temp	Connector end down	Connector end up	Handle down	Handle up	Pivoted Handle corner down
-45°C	Unit #1	Unit #2	Unit #3	Unit #4	Unit #5
+52°C	Unit #6	Unit #7	Unit #8	Unit #9	Unit #10

The blasting machine shall then be tested in accordance with the methods of 4.5.1 for output capacity except that it shall indicate a successful firing three (3) sequential times. If the device fails to comply with all the specififed requirements, it shall be classed defective. (Destructive Test)

PAGE 62

5.1.2: Delete this paragraph in its entirety.

5.2.2: Delete this paragraph in its entirety and substitute the following:

"5.2.2 Level B. 100 Blasting Machines shall be packed as in 5.2.1 except replace the wooden box with a fiberboard box, Type CF, Class Domestic, Grade 350, Spec PPP-B-636. Use commercial chipboard as fillers instead of MIL-F-50449. Close and seal the box in accordance with the requirements of the Appendix of PPP-B-636."

PAGE 63

5.3: Delete "5.5.15.8.1 through 5.5.15.8.4" and substitute "5.4.21 and 5.4.22".

The margins of this amendment are marked with an asterisk to indicate where changes from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1375-A234)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:11Z
Check the source to verify that this is the current version before use.