MILITARY SPECIFICATION

FUZE, IMPACT PYROTECHNIC, M733; PLUG
AND SUPPORT FUZE FOR

PARTS FOR

This specification is approved for use by the US Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification contains requirements not normally covered by the drawings and provides quality assurance provisions for the fabrication of parts and packing for Plug and Support Fuze for Fuze, Impact, Pyrotechnic, M733.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. - The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-48078 - Ammunition, Standard Quality Assurance Provisions, General Specification For

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-1169- Packaging, Packing and Marking for Shipment of Inert Ammunition Components

FSC: 1390

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Armament Research and Development Command, Attn. DRDAR-QA, Dover, New Jersey 07801 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

DRAWINGS (see 6.4)

US ARMY ARMAMENT RESEARCH AND DEVELOPMENT COMMAND

9258732 - Support, Fuze
9323259 - Plug

3. REQUIREMENTS

3.1 Material. - Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts. - The parts shall comply with all requirements specified on Drawings (Dwg.) 9258732, 9323259, all associated drawings, and with all requirements specified in applicable specifications.

3.3 First article inspection. - This specification contains technical provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

3.4 Contamination and distortion of lexan parts. - Extreme care shall be taken throughout all phases of manufacture to avoid contacting "lexan" parts with certain solvent materials and vapors which may attack the "lexan" material. Specific information on "lexan" destructive solvents may be obtained from the General Electric Co., Chemical and Metallurgical Division, Pittsfield, Mass.

3.5 Workmanship. - All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products, and other foreign matter. The cleaning method used shall not be injurious to any parts, nor shall the parts be contaminated by the cleaning agents. All marking and stamping shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection and standard quality assurance provisions. - Unless otherwise specified herein or in the contract, the provisions of MIL-A-48078 shall apply and are hereby made a part of this detail specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspections. - The following types of inspection shall be conducted on this item:

a. First Article Inspection
b. Quality Conformance Inspection

4.3 First article inspection.

4.3.1 Submission. - The contractor shall submit a first article as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.3.2. The first article sample shall consist of the following items in sample quantities as indicated.

Part Description	Drawings	Quantity
Support, Fuze	9258732	25
Plug	9323259	25

4.3.2 Inspections to be performed. - See MIL-A-48078 and Table I herein.

4.3.3 Rejection. - See MIL-A-48078.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

TABLE I - FIRST ARTICLE INSPECTION

CLASSIFICATION OF DEFECTS & TESTS

PARAGRAPH	TITLE		SHEET 1 OF 1		DRAWING NUMBER: See Below NEXT HIGHER ASSEMBLY
CATEGORY	EXAMINATION OR TEST	NO. OF SAMPLE UNITS	AQL OR 100%	REQUIREMENT PARAGRAPH	PARAGRAPH REFERENCE /INSPECTION METHOD
	Support, Fuze (Dwg 9258732) Examination for Defects	25			4.4.2.1
	Plug (Dwg 9323259) Examination for Defects	25			4.4.2.2

NOTES:

SARPA-QA FORM 2567 FEB 74 4810

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

4.4 Quality conformance inspection.

4.4.1 Inspection lot formation. - Inspection lots shall comply with the lot formation provisions of MIL-A-48078.

4.4.2 Examination. - See MIL-A-48078.

a. Sampling plans. - Unless otherwise specified in the Classification of Defects and Test Tables, sampling plans for major and minor defects shall be in accordance with MIL-STD-105, Inspection Level II.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

QUALITY CONFORMANCE INSPECTION

CLASSIFICATION OF DEFECTS & TESTS

MIL-F-63132 (AR)

PARAGRAPH	TITLE	SHEET 1 OF 1	DRAWING NUMBER
4.4.2.1	Support Fuze		9258732
			NEXT HIGHER ASSEMBLY

CATEGORY	EXAMINATION OR TEST	NO. OF SAMPLE UNITS	AQL OR 100%	REQUIREMENT PARAGRAPH	PARAGRAPH REFERENCE /INSPECTION METHOD
Critical	None defined				
Major					
101	Concentricity at indicated length on taper with large outside diameter	*	0.40%	3.2	Gage
102	Parallelism	*	0.40%	3.2	Gage
103	Concentricity of large inside diameter with large outside diameter	*	0.40%	3.2	Gage
104	Diameter of large inside diameter	*	0.40%	3.2	Gage
105	Large outside diameter	*	0.40%	3.2	Gage
Minor					
201	Depth of plug cavity	*	0.65%	3.2	Gage
202	Total length	*	0.65%	3.2	Gage
203	Diameter of small inside diameter	*	0.65%	3.2	Gage
204	Concentricity of small inside diameter with large outside diameter	*	0.65%	3.2	Gage
205	Evidence of poor workmanship	*	0.65%	3.5	Visual

NOTES: * See 4.5.1

SARPA-QA FORM 2567 FEB 74 4810

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

QUALITY CONFORMANCE INSPECTION

CLASSIFICATION OF DEFECTS & TESTS

MIL-F-63132 (AR)

PARAGRAPH	TITLE		SHEET 1 OF 1		DRAWING NUMBER
4.4.2.2	Plug				9323259
					NEXT HIGHER ASSEMBLY
CATEGORY	EXAMINATION OR TEST	NO. OF SAMPLE UNITS	AQL OR 100%	REQUIREMENT PARAGRAPH	PARAGRAPH REFERENCE /INSPECTION METHOD
Critical	None defined				
Major					
101	Concentricity of hole with outside straight diameter	(See 4.5.1)	0.40%	3.2	Gage
102	Improper angle		0.40%	3.2	Gage
Minor					
201	Total length		0.65%	3.2	Gage
202	Hole diameter		0.65%	3.2	Gage
203	Evidence of poor workmanship		0.65%	3.5	Visual

NOTES:

SARPA-QA FORM 2567 FEB 74 4810

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

4.4.3 Testing. - Testing is described in the First Article and Quality Conformance Inspection Tables.

4.4.4 Inspection equipment. - The inspection equipment required to perform the examinations and tests prescribed herein is described in the Paragraph Reference/Inspection Method column in the tables starting with Paragraph 4.4.2.1. The contractor shall submit for approval inspection equipment designs in accordance with the terms of the contract. See Section 6 of MIL-A-48078 and 6.3 herein.

4.5 Test methods and procedures.

4.5.1 Dimensional control of molded or plastic parts. - In place of the normal sampling and inspections associated with the Classification of Defects, and after a curing time for the parts has been approved (See Note 1) a sample of three (3) parts (as molded) from each cavity shall be fully inspected dimensionally to qualify a new or reworked cavity for use in production. The molded parts shall carry the individual cavity identification. As a control of each cavity during production, the above quantity defects listed in paragraphs 4.4.2.1 through 4.4.2.2 after continuous production of each 5,000 parts or at the end of each week, whichever occurs first. Of the three (3) samples, one (1) sample shall be the last part produced. If any defective parts are found during qualification of the cavity, the cavity producing the defective part will not be used in production. If any defective parts are found when inspection is performed for the control of the cavity, the cavity producing the defective part shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for inspection for each separate type of defect according to MIL-STD-105, using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. All cavities removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request. Contractor designs of gages and test equipment required to perform the inspections listed herein shall be forwarded to Commander, ARRADCOM, Dover, New Jersey 07801, ATTN: DRDAR-QAA-Q for approval prior to manufacture of equipment. The noted sub-paragraphs identify those items and minimum inspections subject to the requirements of this paragraph.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

NOTE 1: In establishing a curing time, dimensionally check ten (10) parts from each cavity at periodic intervals (e.g. every 30, 60 etc mins) until dimensional stability is attained. The curing time will be from the time the part comes out of the mold until dimensional stability is attained. The inspection data used in determining the curing time shall be sent to ARRADCOM, Dover, New Jersey 07801, ATTN: DRDAR-QAA-Q. If there is a change in material, or in the cycle time, or if a cavity is reworked, or a new cavity is used, a new curing time shall be established and approved.

5. PACKAGING

5.1 Preservation and packaging.

5.1.1 Level C. - The parts shall be preserved and packaged in accordance with MIL-STD-1169.

5.2 Packaging.

5.2.1 Level C. - The parts, preserved and packaged as specified in 5.1.1, shall be packed for shipment in accordance with MIL-STD-1169.

5.3 Marking. - Marking of the cartons shall comply with MIL-STD-1169.

5.4 Shipping. - When components from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Intended use. - The components covered by this specification are intended for use on Fuze, Impact, Pyrotechnic, M733.

6.2 Ordering data. - See MIL-A-48078.

6.3 Submission of inspection equipment designs for approval.- See MIL-A-48078. Submit equipment designs as required to Commander, ATTN: DRDAR-QAA-I, ARRADCOM, Dover, NJ 07801.

6.4 Drawings. - Drawings listed in Section 2 of this specification under the heading US Army Armament Research and

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.

Development Command (ARRADCOM) may also include drawings prepared by and identified as, Edgewood Arsenal, Frankford Arsenal, Rock Island Arsenal or Picatinny Arsenal drawings. Technical data originally prepared by these activities are now under the cognizance of ARRADCOM.

Custodian:
Army- AR

Preparing Activity:
Army- AR

Project Number: 1390-A-153

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:17Z
Check the source to verify that this is the current version before use.