INCH-POUND

MIL-S-55606C(CR)
AMENDMENT 2
20 March 1991
SUPERSEDING
AMENDMENT 1
10 September 1976

MILITARY SPECIFICATION
SHELTER, ELECTRICAL EQUIPMENT
S-412( )/TTC-72

This amendment forms a part of MIL-S-55606C(EL), dated 6 January 1972, and is approved for use by the Communications-Electronics Command, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 1

2.1 Add:
SPECIFICATIONS MILITARY:

Add: MIL-C-55427 Cable Assembly, Radio Frequency General Specification for

Delete: MIL-P-116 and MIL-S-55505.

STANDARDS MILITARY

Add: MIL-STD-454 Standard General Requirements for Electronic Equipment

PAGE 3

3.1 First Article of Production: Delete this paragraph and substitute the following:

"3.1 First Article. - When specified in the contract or purchase order, the contractor shall furnish first article units in accordance with 4.3."

3.3.1 Delete "Power systems wiring and components" and substitute "Power systems and components installation (See 4.7.1)".

PAGE 4

3.3.3 Change paragraph title to: "Signal (audio) system wiring and components installation." and add "(See 4.7.3)".

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the current version before use.

3.3.3.1 and 3.3.4.1 Change titles to: "Continuity of conductors."

3.3.4 Change paragraph title to: "Video systems wiring and components installation (See 4.7.4)".

PAGE 5

3.3.5 Delete this paragraph and substitute the following:

"3.3.5 Cable Assemblies. - (See 4.4)

3.3.5.1 Cable Assemblies, Power and Audio Frequency. - All power and audio frequency cable and cord assemblies shall be fabricated in accordance with the drawings and meet the continuity, dielectric, insulation resistance, and pull-out requirements of MIL-C-3885.

3.3.5.2 Cable Assemblies, Radio Frequency. - Radio frequency cable assemblies required for operation of major items of equipment in 6.1 shall be fabricated in accordance with the drawings and meet the following requirements when tested in accordance with MIL-C-55427:

3.3.5.2.1 DC Resistance. - When tested as specified, the point to point resistance of the conductor shall not be greater than 1 ohm.

3.3.5.2.2 Pull-out Load for Terminations. - When tested as specified the cable assembly shall show no evidence of mechanical damage when a load of 25 pounds is applied.

3.3.5.2.3 Dielectric Withstanding Voltage. - When tested as specified the cable assembly shall show no evidence of breakdown with a test potential of 1500 volts RMS, 25-100 hertz.

3.3.5.2.4 Insulation Resistance. - When tested as specified the insulation resistance shall not be less than 100 megohms with a test potential of 500 volts DC."

PAGE 6

3.5 In first line, after facility add: "when assembled as the AN/TCC-72"

3.6 In first line, after facility add: "when assembled as the AN/TCC-72"

PAGE 7

3.7 In first line, after facility add: "when assembled as the AN/TCC-72"

3.11 Add: "(See 3.22)"

Source: https://assist.dla.mil -- Downloaded: 202640-22T23:41Z
Check the source to verify that this is the current version before use.

3.13 Delete "(See 4.4)" and substitute "(See 3.22 and 4.4)".

3.14 Add "(See 3.22)"

3.15 Add "(See 3.22)"

PAGE 8

3.16 Add "(See 3.22)"

3.17 Add "(See 3.22)"

3.18 Add "(See 3.22)"

PAGE 9

3.19 Add "(See 3.22)"

3.20 Add "(See 3.22)"

PAGE 10

3.22 Delete first sentence and substitute the following: "3.22 Workmanship. - (See 4.17). The equipment shall be manufactured and assembled in accordance with requirement 9 of MIL-STD-454 and the applicable portions of the following paragraphs:" Delete "3.21 Interchangeability" from list.

Add 3.23 as follows:

3.23 System Safety Engineering

3.23.1 Personnel Hazards. Personnel hazards shall be kept to a minimum. The criteria of MIL-STD-454, Requirement 1 and 8 shall be made applicable for tasks and efforts such as the selection of parts, the complete manufacturing and assembly process, and any production baseline configuration changes that may be implemented during the course of the contract. Verification that compliance with this requirement has been achieved shall be through a visual inspection (See 4.17).

PAGE 11

3.23.2 Edge Rounding Exposed. Exposed edges shall be rounded to a minimum radius of 0.04 inch (1 mm), and exposed corners to a minimum of 0.5 inch (13 mm).

3.23.3 Radioactive Materials. Radioactive materials shall not be used (e.g. luminous dials/markings, electron tubes, surge arrestors and lenses).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:41Z
Check the source to verify that this is the current version before use.

4.1 Responsibility for inspection: Delete second and third sentences and substitute the following:

"Except as otherwise specified in the contract or purchase order, the contractor may utilize his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspection are deemed necessary to assure supplies and services conform to prescribed requirements."

4.1.1 Contractor quality assurance: Delete this paragraph.

4.1.2 Government verification: Delete this paragraph.

4.1.3 Accommodation and assistance: Delete this paragraph.

4.2 Change first sentence to:

"The inspection requirements specified herein are classified as follows:"

4.2c, 4.2c(1) and 4.2c(2) Quality conformance inspection. Delete these paragraphs and substitute the following:

"4.2c Quality conformance inspection of equipment before packaging (See 4.5)."

4.3 First article inspection: Delete this paragraph and substitute the following:

"4.3 First article. - Unless otherwise specified in the contract or purchase order, the first article inspection shall be performed by the contractor. (See 3.1)

4.3.1 First article units. - The contractor shall furnish one (1) first article unit of the complete S-412( )/TCC-72.

4.3.2 First article inspection. - The first article inspection shall consist of inspections specified in Table I and shall be performed in the order specified therein.

4.3.3 First article data. The first article test plan and test report(s) shall be as required in the contract or purchase order.

4.3 Delete TABLE I with the notes at bottom and substitute the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:41Z
Check the source to verify that this is the current version before use.

TABLE I First Article Inspection

Inspections	Rqr Para	Test Para
1. Inspection covered by subsidiary documents	-	4.4
2. Interchangeability	3.21	4.16
3. Mounting Insert	3.10	4.14.1
4. Solderless-terminal-lug connections	3.20.4	4.15
5. Visual and Mechanical	3.22	4.17
6. Power systems and components installation	3.3.1	4.7.1
7. Power distribution and operational function	3.3.2	4.7.2
8. Signal (audio) system wiring and components installation	3.3.3	4.7.3
9. Video system wiring and components installation	3.3.4	4.7.4
10. System operation	3.4	4.8
11. Vehicular transportation	3.5	4.9
12. Rail transportation	3.6	4.10
13. Flat drop	3.7	4.11.1
14. Rotational drop	3.7	4.11.2
15. Watertightness	3.8	4.12
16. Fording	3.9	4.13
17. Repeat 6 Power systems and components installation	3.3.1	4.7.1
18. Repeat 7 Power distributional and operational function	3.3.2	4.7.2
19. Repeat 8 Signal (audio) system wiring and components installation	3.3.3	4.7.3
20. Repeat 9 Video and radio frequency (RF), system wiring and components installation	3.3.4	4.7.4
21. Repeat 10 System operation	3.4	4.8

PAGE 13

4.4 Change "Terminals" to "Solderless-Terminal-Lugs" and delete the first sentence and replace with the following:

"4.4 Inspection covered by subsidiary documents: The following shall be inspected under the applicable subsidiary documents as part of the inspection required by this specification, and the inspection requirement specified in the contract or purchase order".

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the currentversion before use.

4.5 Delete "(See 4.1.2)" and the last sentence.

4.5.1 Delete this paragraph and substitute the following:

"4.5.1 Group A inspection. - Each unit on contract or purchase order shall be inspected for conformance to the inspections specified in Table II. Lots shall be formed only from units that pass this inspection. Factors of lot composition not defined herein, or in the contract or purchase order, shall be in accordance with MIL-STD-105. Each lot shall be subject to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels, and AQL's indicated in Table II.

4.5.1.1 Order of inspection within Group A. - Group A inspection shall be performed in the order listed in Table II."

Delete TABLE II Lot Formation

Replace TABLE III with the following:

"TABLE II - Group A Inspection

Inspection	Rqr Para	Insp Para	AQL % Def Major	Minor
Visual and Mechanical	3.22	4.17	1.0	4.0
Electrical installation				**
Power systems and component installation				
Continuity of conductors	3.3.1.1	4.7.1.1		
Dielectric breakdown voltage	3.3.1.2	4.7.1.2		
Insulation resistance	3.3.1.3	4.7.1.3		
Power distributional and operational function	3.3.2	4.7.2		
Signal (audio) system wiring and components installation				
Continuity of conductors	3.3.3.1	4.7.3.1		1.0 for the entire group of power, signal and video wiring
Dielectric breakdown voltage	3.3.3.2	4.7.3.2		
Insulation resistance	3.3.3.3	4.7.3.3		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:41Z
Check the source to verify that this is the current version before use.

"TABLE II - Group A Inspection
(contd)

Inspection	Rqr Para	Insp Para	AQL % Def Major	Minor
Video system wiring and components installation				
Continuity of conductors	3.3.4.1	4.7.4.1		
Dielectric breakdown voltage	3.3.4.2	4.7.4.2		
Insulation resistance	3.3.4.3	4.7.4.3		

** All defects are major

PAGE 15

4.5.2 Group B inspection. - Delete this paragraph and substitute the following:

"4.5.2 Group B inspection. - Group B inspection shall normally be performed on inspection lots that have passed Group A inspection, except for Interchangeability and Mounting Insert Inspections which are performed prior to Group A. This inspection shall conform to Table III and to the special inspection levels of Table I of MIL-STD-105."

4.5.2.1 Group B sampling plans. - Replace "TABLE IV" with "TABLE III."

PAGE 16

4.5.2.2 Order of inspection within Group B. - Delete "in which they appear" and substitute "listed in TABLE III."

Change table number from "TABLE IV" to "TABLE III" and add the following note to TABLE III Group B inspection:

"NOTE: The order of inspection of Group B with respect to Groups A and C shall conform to the order specified in 4.3. The order of inspection within Group B shall be as in 4.5.2.2."

4.5.3 Group C Inspection. - In this paragraph in title of Group C Inspection Table and in note at bottom of table, change "TABLE V" to "TABLE IV".

In Table IV Group C Inspection delete:

"Construction verification 3.2 4.6"

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the current version before use.

PAGE 17

4.5.3.2 Delete in its entirety.

4.5.3.3 Change number to 4.5.3.2

4.5.3.4 Change number to 4.5.3.3

4.5.3.5 Delete this paragraph and replace with the following:

"4.5.3.4 Group C failures. - Actions required relative to Group C failures shall be as specified in the contract or purchase order."

PAGE 18

4.5.4 In the first line delete "Group B and", in the third line delete "Group B" and "or both," and in the fourth line change "Group C" to "Group A".

4.5.5 Delete in its entirety.

4.6 Delete in its entirety.

PAGE 20

4.7.1.1 Continuity of conductors. - In first sentence delete "which meets" and substitute "tests to meet".

PAGE 21

4.7.1.2 Dielectric breakdown voltage. - In first sentence delete "which meets" and substitute "tests to meet".

PAGE 22

4.7.1.3 Insulation resistance. - In first sentence delete "which meets" and substitute "tests to meet".

PAGE 23

4.7.2 Power distribution and operational function tests. - In first sentence delete "which meets" and substitute "to meet".

PAGE 26

4.7.3.1 Continuity of conductors. - In first sentence delete "which meets" and substitute "tests to meet".

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:41Z
Check the source to verify that this is the current version before use.

PAGE 29

4.7.3.2 Dielectric breakdown voltage. - In first sentence delete "which meets" and substitute "to meet".

PAGE 30

4.7.3.3 Insulation resistance. - In first sentence delete "which meets" and substitute "tests to meet".

PAGE 31

4.7.4 Add "(See 3.3.4)" after title.

4.7.4.1 Continuity of conductors. - In first sentence delete "which meets" and substitute "tests to meet".

Change "TABLE VI" to "TABLE V".

PAGE 32

4.7.4.2 Dielectric breakdown voltage. - In first sentence delete "which meets" and substitute "to meet".

PAGE 33

4.7.4.3.a Change "4.7.4.2a" to "4.7.4.2.c"

PAGE 42

4.10 Change title to "Rail transportation test", in the sixth line add "(contractor furnished)" after slings, and add after the sentence ending in line fifteen, the following new sentence - "All cars shall have standard (rigid) draft gear".

PAGE 43

4.10.1 Test flatcar. - In line seven delete "power" and in line ten delete "not".

4.10.2.a Delete "springly" and substitute "springy".

PAGE 46

In figure 3 upper left view delete "*" and substitute "19." In legend delete "*ADJUSTABLE FROM 19 to 40". To item 6 of the NOTES add "TOLERANCE ± 1/2 inch".

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:41Z
Check the source to verify that this is the current version before use.

PAGE 47

4.14 Mounting insert tests. - Replace "Preproduction" with "First article" in 4.14.1 and table.

Change "TABLE VII" to "TABLE VI".

Change "Production" to "Group B" in title of 4.14.2 and in renumbered TABLE VI.

PAGE 48

Change "TABLE VIII" to "TABLE VII".

In table add the following to major defects:

"13. Center pin of rf cable assemblies improperly crimped or soldered, loose or protruding".

4.18 Quality conformance inspection of preparation for delivery. Delete.

4.19 Rough handling test (preparation for delivery). Delete.

PAGE 49

5. Preparation for delivery. - Delete the entire 5 Section and replace with the following:

"5. PACKAGING

5.1 Packaging requirements. The packaging requirements for the desired level(s) of protection shall be as specified by the acquisition activity."

6.2.b On first line delete "Preproduction" and substitute "First article".

PAGE 50

6.4 In last line change "(See 4.5.3.5)" to "(See 4.5.3.4)".

Custodian:
Army - CR

Preparing Activity:
Army - CR
Project No. 5805-A328

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:41Z
Check the source to verify that this is the current version before use.