MIL-D-409C (PA)
Amendment 1
15 April 1974

MILITARY SPECIFICATION

DETONATORS, PERCUSSION, DELAY, 15 SECOND,
M1A2 AND 8 SECOND, M2A1
LOADING, ASSEMBLING AND PACKING

This Amendment forms a part of Military Specification MIL-D-409C (MU) dated 9 January 1970 and is approved for use by all Departments and Agencies of the Department of Defense.

Paragraph 2.1 under Specifications Military:

After MIL-A-2550 Delete "and Special Weapons"

Add:

MIL-P-20444 - Primer, Percussion, M42 Loading, Assembling and Packing

Under DRAWINGS:

Delete "U.S. ARMY MUNITIONS COMMAND"
Substitute: "U.S. ARMY PICATINNY ARSENAL".

Delete PUBLICATION, Delete U.S. ARMY MUNITIONS COMMAND,
Delete ET-8799903 - Equipment Tabulation.

Delete "(Copies of specifications etc.)" and substitute:

(Copies of specifications, standards and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

Paragraph 3.7 Line 1, delete "makes" and subsitute "contains technical".

Paragraph 4.1.1 Add under subparagraph e as follows:

"The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority

FSC: 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:22Z
Check the source to verify that this is the current version before use.

to bind his principal. Substantiation of the agents authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization."

Paragraph 4.2.1 Delete in its entirety and substitute:

"4.2.1 Submission. - Prior to the start of regular production the contractor shall submit a first article sample (see 6.1c) to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2 and 4.2.3. The first article sample shall consist of 100 delay detonators, 100 delay housing and primer holder assemblies, 50 firing pin assemblies and 50 blasting caps which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials including packaging and packing shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including a certificate of conformance for materials. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer. A first article sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

Paragraph 4.2.2 Delete second sentence and substitute "Assemblies will be inspected 100% for column height of delay housing assembly (see 4.3.3.2), surface of delay charge from bottom of delay cavity (see 4.3.3.3), presence of a delay column (see 4.3.3.4) and then the following tests shall be performed."

Paragraph 4.2.3 Delete in its entirety and substitute:

4.2.3 Rejection. - If any component or subassembly fails to comply with any or all of the applicable requirements, the first article sample shall be rejected. The Government reserves the

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:22Z
Check the source to verify that this is the current version before use.

right to terminate its inspection upon any failure of an inert component or subassembly to comply with any of the stated requirements.

Paragraph 4.3.2.6 Delete "AQL 1.00 percent", and substitute "AQL 1.50 percent".

Add Minor "203. Evidence of poor workmanship (see 3.6)...Visual 05005".

Paragraph 4.3.2.7 Add minor "204. Evidence of poor workmanship (see 3.6).....Visual 06006".

Paragraph 4.3.2.8 For Minor add "AQL 0.65 percent".

Add Minor "201. Evidence of poor workmanship (see 3.6)...Visual 07003".

Paragraph 4.3.2.9 Add Minor "204. Evidence of poor workmanship (see 3.6).....Visual 08006".

Paragraph 4.3.3.6 Delete in its entirety and substitute:

"4.3.3.6 Push out force of primer holder assembly (see dwg. 8799911) - Major defect - Code No. 09006.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter J and an AQL of 1.0 percent. The test shall be performed as specified in 4.4.6 using test equipment as specified in 4.3.4."

Paragraph 4.3.3.8 Delete in its entirety and substitute as follows:

"4.3.3.8 Check test for deterioration of primer (see MIL-P-20444), Major Defect, Code No. 09009.-If the total time between original acceptance of any lot and the assembly of that lot into the delay detonators exceeds two years, or if the primers have been subjected to adverse conditions, however brief, at any time since previous test, the primer lot shall be subjected to and must satisfactorily pass, the check test for deterioration specified in MIL-P-20444 immediately before the primer lot is assembled into the delay detonators. This test shall be performed by the contractor on primers selected by the Government Inspector at the facility assembling the primers into the delay detonators (see 6.4)".

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:22Z
Check the source to verify that this is the current version before use.

Paragraph 4.3.4 Delete in its entirety and substitute as follows:

"4.3.4 Inspection Equipment.-Inspection equipment required to perform the inspections prescribed in this specification is identified in the Examination (4.3.2) and Test Method (4.4) paragraphs herein. See 6.3 for details concerning responsibilities for inspection design and approval".

Paragraph 4.3.4.1 Delete in its entirety.

Section 6: Delete paragraphs 6.2, 6.3, 6.3.1, 6.3.2, 6.3.3, 6.3.4, 6.3.5 and 6.4 in their entireties and substitute as follows:

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. They should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.3).

6.3 Inspection Equipment Designs.-Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers under the "Method of Inspection" headings in Section 4. Design responsibility for all other inspection equipment is assigned to the contractor. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3 should he elect to do so.

6.3.1 SIE designs.-SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.
b. A source control drawing or a specification control drawing as defined in MIL-STD-100.
c. An envelope drawing, as defined in MIL-STD-100, which establishes the criteria which a detailed design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:22Z
Check the source to verify that this is the current version before use.

6.3.2 Contractor designs.-Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public). Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of Designs for Approval.-Contractor designs shall be approved by the Government prior to fabricating or procuring the equipment. Designs shall be submitted for approval to Picatinny Arsenal, ATTN: SARPA-QA-A-M, Dover, New Jersey 07801 in accordance with the stipulations, time frame and distribution specified in the Contract Data Requirements List (DD Form 1423) or in the contract. The contractor must include in his submission of designs a listing of any and all Government SIE designs which will be utilized. Partial submission of inspection designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

6.4 Cost of check test.-The contracting officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the check test for deterioration of the primer assemblies. The tests shall be conducted at

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:22Z
Check the source to verify that this is the current version before use.

Government expense without cost to the contractor assembling the primer assemblies into the fuze; and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc., permitted while the primer assembly lot was under the jurisdiction of either contractor.

Custodian:
Army-PA

Preparing Activity:
Army-PA

Project Number: 1375-A-088

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:22Z
Check the source to verify that this is the current version before use.