MIL-B-13265C(ME)
24 April 1985

SUPERSEDING
MIL-B-13265B(ME)
21 May 1975

MILITARY SPECIFICATION

BRIDGES, FIXED, STEEL, RAILWAY, UNIT CONSTRUCTION, 70-FT., 2-GIRDER SPAN: AND CONVERSION SETS: COMPONENTS OF

This specification is approved for use by the Belvoir Research and Development Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the structural components of 70-foot 2-girder railway bridges, and also covers four conversion sets.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified, the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research and Development Center, ATTN: STRBE-DS, Fort Belvoir, VA 22060-5606 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 5420

Source: https://assist.dla.mil -- Downloaded: 202640-18T00:19Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

FF-B-575	- Bolts, Hexagon and Square.
FF-N-836	- Nut: Square, Hexagon, Cap, Slotted, Castle, Knurled, Welding and Single Ball Seat.
FF-S-92	- Screws, Machine: Slotted, Cross-Recessed or Hexagon Head.
QQ-S-781	- Strapping, Steel, and Seals.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.

MILITARY

MIL-P-116	- Preservation, Methods of.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-C-3774	- Crates Wood; Open 12,000- and 16,000-Pound Capacity.
MIL-G-20241	- Gasket Material, Wool Felt, Impregnated, Adhesive, Pressure-Sensitive.
MIL-S-81733	- Sealing and Coating Compound, Corrosion Inhibitive.

STANDARDS

FEDERAL

FED-STD-595	- Colors.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking and Waterproofing; with Appropriate Test Methods.
MS27183	- Washer, Flat-Round, Steel, Cadmium Plated, General Purpose (In/Mm).

2.1.2 Government drawings. The following Government drawings form a part of this specification to the extent specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

DRAWINGS

ME

D2604-1 through -7 - Unit Construction Railway Bridge.

(Copies of specifications, standards, and drawings required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN NATIONAL STANDARDS INSTITUTE, INC. (ANSI)

ANSI/AWS A5.1 - Covered Carbon Steel Arc Welding Electrodes.
ANSI/AWS D1.1 - Structural Welding Code - Steel.

(Application for copies should be addressed to the American National Standards Institute, Inc., 1430 Broadway, New York, NY 10018.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 36 - Structural Steel.
ASTM A 108 - Cold-finished Carbon Steel Bars.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY (AWS)

AWS A3.0 - Welding Terms and Definitions.
AWS B2.1 - Standard for Welding Procedure and Performance Qualification.

(Application for copies should be addressed to the American Welding Society, 550 Northwest LeJune Road, Miami, FL 33126.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION, INC., AGENT

National Motor Freight Classification.

(Application for copies should be addressed to the American Trucking Associations, Inc., ATTN: Traffic Department, 1616 P Street, NW, Washington, DC 20036.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

UNIFORM CLASSIFICATION COMMITTEE, AGENT

Uniform Freight Classification.

(Application for copies should be addressed to the Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. Bridge components and coversion sets shall be as shown on Drawings D2604-1 through -7 and as specified herein. The conversion sets hereinafter shall also be called bridge components.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible whitout prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly and operation of the bridge components. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or the designated representative.

3.2 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 4.3 and 6.3).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.3.1 Material deterioration and control. The bridge components shall be fabricated from compatible materials, inherently corrosion and deterioration resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environment to which the item may be exposed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

3.3.1.1 Dissimilar metals. Dissimilar metals, as defined in MIL-STD-889, shall be electrically insulated from one another to minimize or prevent galvanic corrosion. Insulation may be provided by an insulating barrier such as a corrosion inhibiting sealant conforming to MIL-S-81733 or chromate tape conforming to MIL-G-20241. Protection against any galvanic corrosion could also be obtained by exclusion of the electrolyte if feasible.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with components and sub-components, and shall make information available, upon request, to the contracting officer or designated representative.

3.3.2 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the bridges may be newly fabricated from recovered materials to the maximum extent practicable, provided the bridges produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the bridges.

3.3.3 Structural steel. The bridge components, except as specified herein, shall be fabricated from structural steel conforming to ASTM A 36.

3.3.4 Steel for liners. Steel for end post liner plates shall conform to ASTM A 108, grade 1025.

3.3.5 Steel for driftpins and driftpin pegs. Steel for driftpins and driftpin pegs shall conform to ASTM A 108, grade 1025 for driftpins and grade 1035 for driftpin pegs.

3.4 Welding electrodes. Electrodes for shielded metal arc welding shall conform to ANSI/AWS A5.1.

3.5 Bolts. Bolts shall conform to FF-B-575, type II, 1 inch size, grade 5 steel.

3.6 Screws. Machine screws shall conform to FF-S-92, type I, style 2S, .625 nominal size, UNC-2A steel.

3.7 Nuts. Nuts shall conform to FF-N-836, type II, style 4, grade C steel, UNC-2B.

Source: https://assist.dla.mil -- Downloaded: 202640-18T00:19Z
Check the source to verify that this is the currentversion before use.

3.8 Washers. Washers shall conform to MS27183-27.

3.9 Identification marking.

3.9.1 Stenciling. The nomenclature, erection mark, National Stock Number, weight, and cubic displacement shall be stenciled on one side near the center of each bridge component except nuts, bolts, washers, pins, and pegs. The letters "NET WT" shall precede the numerals in the weight and the letters "CF" shall precede the cubic displacement. The letters shall be gothic capitals and the numerals shall be 2 inches high where space permits. On small components, the stenciling shall be as large as practicable.

3.9.2 Metal stamping. In addition to the stenciling, the bridge components, except for nuts, bolts, washers, pins, and pegs, shall be metal stamped as shown on the drawings. Metal stamping shall be of sufficient depth to be legible after painting.

3.9.3 Nuts, bolts, washers, pins, and pegs. Nuts, bolts, washers, pins, and pegs shall be identified in accordance with MIL-STD-130.

3.10 Treatment and painting. All bridge components, except bolts, pins, pegs, nuts, washers, and threaded portions of components, shall be treated and painted in accordance with MIL-T-704, type B, color No. 30109 of FED-STD-595.

3.11 Workmanship.

3.11.1 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame-cutting, using tips suitable for the thickness of the steel, may be employed instead of shearing and sawing. All bends shall be made with controlled means to insure uniformity of size and shape. Precaution shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. External surfaces shall be free of burrs, sharp edges and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.11.2 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, mill scale that can be removed by chipping and wire brushing, and other foreign matter. Parent materials, weld filler metals and fabrication techniques shall be as required to enable the bridge components to conform to the examination requirements specified in section 4. Welding shall be done by the shielded metal arc method or the submerged arc welding procedure in accordance with the applicable requirements of ANSI/AWS D1.1. All welds shall be visually inspected in accordance with ANSI/AWS D1.1. Work shall be positioned for flat welding whenever practicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

3.11.3 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall obtain certification that the welder has passed qualification tests as prescribed by the following standard for the type of welding operations to be performed:

AWS B2.1 - Standard for Welding Procedure and Performance Qualification, Section 3.3, Qualification by Standard Tests.

Certification shall be made available for review by the contracting officer or designated representitive. Contractors who make only horizontal welds need not qualify welders for "all position welding". The contractor shall be responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS B2.1.

3.11.4 Pinholes and boltholes. Pinholes and boltholes shall be accurately drilled through steel jigs or templates after all welding has been completed. Holes may be drilled undersize or subpunched prior to welding and reamed to full size through a steel template after welding. Where holes are subpunched and reamed, the subpunched holes shall be .25 inch less in diameter than the specified diameter of the finished holes. Boltholes or pinholes on common axes in flanges or ribs of bridge components shall be in alinement.

3.11.5 Jigs and fixtures. Bridge components shall be assembled in steel jigs or fixtures and joined while held in position. Jigs or fixtures shall prevent distortion or limit the distortion to an amount that can be removed by straightening and stress-relieving without changing the physical characteristics of the metal.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined and tested in accordance with referenced specifications, standards and drawing, as applicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).

b. Quality conformance inspection (see 4.4).

c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article bridge components shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.4.2 Examination.

4.4.2.1 Individual. Each bridge component shall be examined for the major defects specified in 4.5.1. Presence of a major defect shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1 shall be examined for the minor defects specified in 4.5.1. AQL shall be 4.0 percent defective.

4.5 Inspection procedure.

4.5.1 Examination. Bridge components shall be examined as specified herein for the following defects:

Major

101. Materials not as specified.
102. Materials are not resistant to corrosion and deterioration or treated to be resistant to corrosion and deterioration for the applicable storage and operating environments.
103. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other.
104. Contractor does not have documentation available for identification of material, material finishes or treatment.
105. Used, rebuilt or remanufactured components, pieces or parts incorporated in the bridge components.
106. Structural steel not as specified.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

107. Steel for liners not as specified.
108. Steel for driftpins and driftpin pegs not as specified.
109. Welding electrodes not as specified.
110. Bolts not as specified.
111. Screws not as specified.
112. Nuts not as specified.
113. Washers not as specified.
114. Metal stamping not as specified.
115. Metal fabrication not as specified.
116. Welding not as specified.
117. Welding certification not available for review.
118. Location of boltholes and pinholes not as specified.
119. Size of boltholes and pinholes not as specified.
120. Depth of the verticals, diagonals and chord-splicing diaphragms not as specified.
121. Flange holes not in alinement.
122. Parallelism of the flanges not as specified.
123. Width, length and height of the end post not as specified.
124. End post holes not in alinement.
125. Perpendicularity between the bottom and end of the end post not as specified.
126. Holes in ribs of chords not in alinement.
127. Distance between ribs not as specified.
128. Perpendicularity between ribs and cover plates not as specified.

Minor

201. Nonconformance to dimensions other than those specified for examination in 4.5.1.
202. Components missing or not as specified.
203. Identification marking incorrect, missing or illegible.
204. Treatment and painting not as specified.

4.6 Inspection of packaging.

4.6.1 First article pack inspection.

4.6.1.1 Examination. The first article pack shall be examined for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.1.2 Tests. The level A first article pack of crated bridge components shall be subjected to the railroad car test as specified for guided impact tests in accordance with MIL-STD-1186, appendix A. The car shall strike a string of five empty cars, with draft gear extended and the brakes set, at a speed of not less than 10 miles per hour nor more than 11 miles per hour. The pack shall be examined at the conclusion of the first article pack test.

Source: https://assist.dla.mil -- Downloaded: 202610-18T00:19Z
Check the source to verify that this is the current version before use.

Any shifting of contents, loosening or breaking of holddowns, ties, stays, blocking or bracing, or any visual damage to the contents shall constitute failure of the first article pack and shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

129.	Materials, methods and containers not as specified.
130.	Unprotected surfaces not coated with preservative as specified for level A.
131.	Blocking and bracing not adequate or not in accordance with the referenced document for level A.
132.	Strapping not finished as specified for level A.
133.	Components of unlike description bundled together for level A.
134.	Bundles not secured as specified for level A.
135.	Secured lifts not strapped as specified for level A.
136.	Marking missing, illegible, incorrect, or incomplete for level A or C.

5. PACKAGING

5.1 First article pack. The contractor shall furnish a first article pack for examination and testing of the crated bridge components within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied preservation, packing, and marking comply with the packaging requirements of this specification. Examination and tests shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article pack may be prepared utilizing either the first article bridge components or production bridge components. When the first article bridge components are utilized, any preservation and packing shall be removed by the contractor at no expense to the Government when requested by the Government, to facilitate comparison between the first article bridge components and production bridge components.

5.2 Preservation. Preservation shall be level A or C, as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

5.2.1 Level A.

5.2.1.1 Disassembly. The bridge components shall be disassembled into the various structural components and assemblies as fabricated.

5.2.1.2 Preservatives. Preservatives specified herein shall conform to the applicable specifications listed in and shall be applied in accordance with MIL-P-116.

5.2.1.3 Unprotected surfaces. Bolts, nuts, washers, driftpins, and pegs requiring a contact preservative in accordance with MIL-P-116 shall be coated with type P-1 preservative.

5.2.1.4 Heavy structural components. Heavy components, such as the chords and posts, and floor beams shall be prepared for shipment as loose pieces or assemblies as fabricated.

5.2.1.5 Components to be boxed. Bolts, nuts, washers, driftpins, and pegs shall be packaged in close-fitting boxes conforming to PPP-B-621, class 2, style optional, or PPP-B-601, overseas type, style optional. Like items shall be packed together. Blocking and bracing to prevent movement of the contents within the box shall be provided. The box shall be closed and strapped in accordance with the appendix to the applicable box specification. Strapping shall conform to QQ-S-781, class 1, type I or IV, size as applicable; and, unless otherwise specified herein, shall be finish B. When specified (see 6.2), strapping shall be finish A.

5.2.1.6 Components to be bundled. All bridge components, except those specified in 5.2.1.4 and shipped as loose pieces or assemblies and those specified in 5.2.1.5 to be boxed, shall be bundled. The components of like description shall be nested and banded together in a secure and compact manner in quantities most convenient to accomplish the packing specified herein. Each buncle shall be secured with bolts or with a minimum of 2 straps conforming to QQ-S-781, type I or IV, heavy duty, finish B, size as applicable, or with a combination of bolts and straps.

5.2.2 Level C. The components shall be preserved to afford adequate protection against deterioration and damage from the supply source to the first receiving activity.

5.3 Packing. Packing shall be level A or C, as specified (see 6.2).

5.3.1 Level A.

5.3.1.1 Heavy structural components. Heavy structural components such as those specified in 5.2.1.4 shall be shipped loose.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

5.3.1.2 Bundled components. Bridge components bundled as specified in 5.2.1.6 shall be shipped as individual bundles or bundled together in secured lifts in quantities not to exceed 5 tons. Secured lifts shall be strapped circumferentially using strapping conforming to QQ-S-781, type I or IV, finish B, size 1.25 inch by 0.035 inch. A minimum of three straps equally spaced shall be applied to lengths up to 12 feet, and, for each 4 feet of added length, one additional intermediate strap equally spaced shall be applied.

5.3.1.3 Consolidated packing. When specified (see 6.2), boxed components and bundled components shall be packed together in one or more crates as required. The crates shall conform to MIL-C-3774, type I, style A. The contents shall be blocked, braced and anchored in accordance with the appendix to the crate specification and in accordance with MIL-STD-1186.

5.3.2 Level C. The components shall be packed to assure carrier acceptance at lowest ratings. Containers shall comply with Uniform Freight Classification rules or National Motor Freight Classification rules.

5.4 Marking. Bundles, packages and shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The bridge components are used in the erection of railway bridges. The railway bridges are used to replace demolished railway bridges or as new railway bridges in line of communication zones. The railway bridges are designed for Cooper's E-45 railway loadings.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number and date of this specification.

b. When a first article is required for inspection and approval, and number of units required (see 3.2).

c. Time frame required for submission of first article pack (see 5.1).

d. Level of preservation and level of packing required (see 5.2 and 5.3).

e. When consolidated packing is required (see 5.3.1.3).

f. When strapping shall be finish A (see 5.2.1.5).

Source: https://assist.dla.mil -- Downloaded: 202640-18T00:19Z
Check the source to verify that this is the currentversion before use.

6.3 First article. When a first article inspection is required, the item should be a first produced structural component. The first article should consist of one or more structural components. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations and approval of the documents first article.

6.4 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the contractor of his obligation to preserve, pack, and mark the bridge components in accordance with this specification.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-A342

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T00:19Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 202610-18T00:19Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
USA Belvoir R&D Center
STRBE-DS
Fort Belvoir, VA 22060-5606

15

Source: https://assist.dla.mil -- Downloaded: 202610-18T00:19Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-B-13265C(ME)	Bridges, Fixed, Steel, Railway, Unit Construction, 70 Ft., 2-Girder Span; and Conversion Sets; Component of

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER *(Specify)*: _____
b. ADDRESS *(Street, City, State, ZIP Code)*	

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

DD FORM 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 202610-18T00:19Z
Check the source to verify that this is the current version before use.