MIL-S-43674B
AMENDMENT-1
28 September 1987

MILITARY SPECIFICATION

SHOWER PAIL, COLLAPSIBLE, COTTON DUCK, 5-GALLON CAPACITY

This amendment forms a part of Military Specification MIL-S-43674B, dated 23 April 1985, and is approved for use by all Departments and Agencies of the Department of Defense.

PAGE 2

2.3: Delete and substitute:

"2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document shall take precedence. Nothing in this document, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained."

PAGE 4

Add the following new paragraph:

"4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this document shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the document shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material."

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

4.4.6: Delete and substitute:

"4.4.6 Packaging examination. The fully packaged end items shall be examined for the defects listed below. The lot size shall be expressed in units of shipping containers. The sample unit shall be one shipping container fully packaged. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 2.5.

Examine	Defect
Marking (exterior and interior)	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application.
Materials	Any component missing, damaged, or not as specified.
Workmanship	Inadequate application of components, such as: incomplete sealing or closure of container flap, improper taping, loose strapping, or inadequate stapling. Bulged or distorted container.
Content	Number per container is more or less than required."

4.4.7: Delete and substitute:

"4.4.7 Palletization examination. The fully packaged and palletized end items shall be examined for the defects listed below. The lot size shall be expressed in units of palletized unit loads. The sample unit shall be one palletized unit load fully packaged. The inspection level shall be S-1 and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

Examine	Defect
Finished dimension	Length, width, or height exceeds specified maximum requirements.
Palletization	Pallet pattern not as specified. Interlocking of loads not as specified. Load not bonded with required straps as specified.
Weight	Exceeds maximum load limits.
Marking	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application."

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

PAGE 11

5.1.1 line 6: Delete "3" and substitute "3-3/4".

5.2.1, line 3: Delete "RSC, grade V3c of PPP-B-636 "and substitute "A of PPP-B-601".
Line 6: Delete "44" and substitute "51".
Delete "13" and substitute "12 1/2".

5.2.2, line 2: Delete "wood cleated-plywood" and substitute "corrugated".
Line 3: Delete "A of PPP-B-601" and substitute "RSC, grade V3c of PPP-B-636".
Line 5: Delete "44" and substitute "51".
Line 6: Delete "13" and substitute "12 1/2".

5.3, line 3: Delete "and secondary".
Line 4: Delete "and L".

PAGE 12

6.3: Delete and substitute:

"6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article should be a preproduction sample. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should include specific instructions in all acquisition instruments regarding arrangements for selection, inspection, and approval of the first article."

Custodians:

Army - GL
Navy - NU

Review activities:

Army - MD
Navy - CG
DLA - CT

Preparing activity:

Army - GL

Project No. 8465-0971

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 202610-21T22:00Z
Check the source to verify that this is the current version before use.