MILITARY SPECIFICATION

FUZE, PD, M536; DELAY DETONATOR ASSEMBLY FOR LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of Delay Detonator Assembly designated as Fuze, PD, M536; Delay Detonator Assembly for.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-P-116	-	Preservation, Method of
MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-C-13739	-	Composition, Delay
MIL-P-45486	-	Pellets, RDX
MIL-I-45607	-	Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions

FSC: 1390

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:02Z
Check the source to verify that this is the current version before use.

MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

8864620 - Delay Detonator Assembly

PUBLICATIONS

ARMY

ET-8864620 - Equipment Tabulation

(Copies of specifications, standard, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

2.2 Other publications.-The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

CODE OF FEDERAL REGULATIONS

Title 49 - Transportation, Parts 171-179

(The Code of Federal Regulations is available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. Orders should specify 49 CFR 171-179 (latest revision).)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts.-The parts shall comply with all requirements specified on Drawing (dwg.) 8864620, all associated drawings, and with all requirements specified in applicable specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:02Z
Check the source to verify that this is the current version before use.

3.3 X-ray examination of delay detonator assembly.-The delay detonator assembly shall be subjected to x-ray examination to determine the presence of RDX, lead azide, delay composition and baffle when tested as specified in 4.4.3.

3.4 Workmanship.-All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, rust, and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required marking and stamping shall be neat and sharply defined.

3.5 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (see 6.4).

3.6 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:02Z
Check the source to verify that this is the current version before use.

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.

b. Drawing and specification number and date, together with identification and date of changes thereto.

c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.

d. Number of items in the lot.

e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a sample of one hundred ten (110) delay detonator assemblies to a Government proving ground designated by the contracting officer for testing is accordance with the provisions of 4.2.2 (see 6.1). All parts and materials shall be the same as will be used in production and shall be obtained from the same source of supply. Prior to submission, the sample shall be inspected by the contractor to the degree necessary to assure that it conforms to the requirements of the contract.

4.2.2 Inspection to be performed.-Assemblies will be subjected by the Government to the following tests:

4.2.2.1 X-ray examination of delay detonator assembly.-The one hundred ten (110) delay detonator assemblies shall be subjected to this test.

4.2.2.2 Delay time of delay detonator assembly.-The one hundred ten (110) delay detonator assemblies shall be subjected to this test.

4.2.3 Rejection.-If any assembly fails to comply with any of the applicable requirements, the first article quantity shall be rejected. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity. Until the first

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:02Z
Check the source to verify that this is the current version before use.

article quantity is accepted, the contractor is not authorized by the Government to proceed with regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a reprsentative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemd to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot shall contain:

a. Metal parts from one interfix lot number from one manufacture.
b. RDX from one interfix lot number from one manufacturer.
c. Lead azide from one interfix lot number from one manufacturer.
d. Delay composition from one interfix lot number from one manufacturer.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:02Z
Check the source to verify that this is the current version before use.

Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Delay detonator assembly, during loading (see 8864620 covering a detail of dwg. 8864618)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Weight of RDX	Balance	01001
102.	Weight of lead azide	Balance	01002
103.	Baffle missing	Visual	01003
Minor:	None defined		

4.3.2.2 Delay detonator assembly (see dwg. 8864620 covering a detail of dwg. 8864618)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Small diameter, max.	Gage	02001
102.	Depth to charge, max.	Gage	02002
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see 3.4)	Visual	02003

4.3.2.3 Inner set-up box assembly, prior to sealing, for delay detonator assembly (see dwg. 8886832)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:02Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.65 Percent		
101.	Incorrect number of delay detonator assemblies	Visual	03001
102.	Delay detonator assembly inverted	Visual	03002
103.	Cushions missing	Visual	03003

Minor: None defined

4.3.2.4 Inner set-up box assembly for Delay Detonator Assembly (see dwg. 8886832)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Box damaged	Visual	04001
Minor:	AQL 0.65 Percent		
201.	Marking misleading or unidentifiable	Visual	04002

4.3.2.5 Outer set-up box assembly for Delay Detonator Assembly, prior to sealing (see dwg. 8886832)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Fillers missing	Visual	05001
102.	Inner box damaged	Visual	05002
103.	Incorrect number of inner boxes	Visual	05003

Minor: None defined

4.3.2.6 Outer set-up box assembly for Delay Detonator Assembly, prior to inserting into barrier bag (see dwg. 8886832)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:02Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.65 Percent		
101.	Sealing strip missing	Visual	06001
102.	Box damaged	Visual	06002
103.	Corners not blunted	Visual	06003
Minor:	AQL 1.00 Percent		
201.	Label missing	Visual	06004
202.	Marking missing or unidentifiable	Visual	06005

4.3.2.7 Box, packing, for Delay Detonator Assembly, prior to sealing (see dwg. 8886833)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Cushions missing	Visual	07001
102.	Bag torn or perforated	Visual	07002
103.	Bag improperly sealed	Visual	07003
104.	Incorrect number of fiber boxes	Visual	07004
Minor:	None defined		

4.3.2.8 Box, packing, for Delay Detonator Assembly (see dwg. 8886833)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Box damaged	Visual	08001
102.	Top improperly assembled	Visual	08002
103.	Strapping missing or improperly assembled	Visual	08003
104.	ICC Nomenclature missing or unidentifiable	Visual	08004
Minor:	AQL 0.65 Percent		
201.	Marking misleading or unidentifiable	Visual	08005

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:02Z
Check the source to verify that this is the current version before use.

4.3.2.9 (Alternate Packing) Set-up box assembly, prior to sealing, for delay detonator assembly (see dwg. 8886937)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Incorrect number of delay detonator assemblies	Visual	09001
102.	Delay detonator assembly inverted	Visual	09002
103.	Cushion missing	Visual	09003
Minor:	None defined		

4.3.2.10 (Alternate Packing) Set-up box assembly for delay detonator assembly (see dwg. 8886937)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Box damaged	Visual	10001
Minor:	AQL 0.65 Percent		
201.	Marking misleading or unidentifiable	Visual	10002

4.3.2.11 (Alternate packing) Fiber box assembly for delay detonator assembly, prior to sealing (see dwg. 8886937)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Fillers missing	Visual	11001
102.	Set-up box assembly damaged	Visual	11002
Minor:	None defined		

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:02Z
Check the source to verify that this is the current version before use.

4.3.2.12 (Alternate Packing) Fiber box assembly for delay detonator assembly, prior to inserting into barrier bag (see dwg. 8886937)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Sealing strip missing	Visual	12001
102.	Box damaged	Visual	12002
103.	Coners not blunted	Visual	12003
Minor:	AQL 1.00 Percent		
201.	Label missing	Visual	12004
202.	Marking missing or unidentifiable	Visual	12005

4.3.2.13 (Alternate Packing) Box, packing, for delay detonator assembly, prior to sealing (see dwg. 8886938)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Cushions missing	Visual	13001
102.	Bag torn or perforated	Visual	13002
103.	Bag improperly sealed	Visual	13003
Minor:	None defined		

4.3.2.14 (Alternate Packing) Box, packing, for delay detonator assembly (see dwg. 8886938)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Box damaged	Visual	14001
102.	Top improperly assembled	Visual	14002
103.	Strapping missing or improperly assembled	Visual	14003
104.	ICC Nomenclature missing or unidentifiable	Visual	14004

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:02Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.65 Percent		
201.	Marking misleading or unidentifiable	Visual	14005

4.3.3.1 Mositure content of delay composition (see dwg. 8864620), Major Defect, Code No. 15001.-At the loading station, at the time of loading, a sample shall be selected in accordance with Specification MIL-C-13739. If the moisture content of the delay composition fails to comply with the requirement specified on the applicable drawing, the quantity represented by the sample shall be rejected. The test shall be performed as specified in 4.4.1, using equipment in accordance with 4.3.4.

4.3.3.2 Binder-lubricant content of RDX (See dwg. 8864620), Major Defect, Code No. 16001.-At the loading station at the time of loading, a sample shall be selected in accordance with Specification MIL-P-45486. If the binder lubricant of RDX fails to comply with the requirement specified on the applicable drawing, the quantity represented by the sample shall be rejected. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.3 X-ray examination of delay detonator assembly (see paragraph 3.3), Major Defect, Code No. 17001.-At the loading station, one hundred ten (110) delay detonator assemblies shall be selected from each lot and subjected to this test. If two (2) or more assemblies fail to comply with the applicable requirement, the lot shall be rejected. The test shall be performed as specified in 4.4.3, using equipment in accordance with 4.3.4.

4.3.3.4 Delay time of delay detonator assembly (see dwg. 8864620), Major Defect, Code No. 18001.-At the loading station, one hundred twenty-five (125) delay detonator assemblies shall be selected at random from each lot and subjected to this test. If the average of the 125 sample assemblies fail to meet the requirement specified on the applicable drawing, or if the standard deviation exceeds .012 seconds, the lot shall be rejected. The test shall be performed as specified in 4.4.4, using equipment in accordance with 4.3.4.

4.3.3.5 Output check of delay detonator assembly, Information Only, Code No. 19001.-At the loading station, during the delay time specified in para. 4.3.3.4, the one hundred twenty-five (125) delay detonator assemblies shall be subject to this test. Measurement of distortion shall be taken and reported to Picatinny Arsenal, SMUPA-ND3. The test shall be performed as specified in 4.4.5, using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:02Z
Check the source to verify that this is the current version before use.

4.3.3.6 Heat seal test of packing seals (see dwg. 8886832 or when applicable dwg. 8886937), Major Defect, Code No. 20001.-The samples shall be selected in accordance with Specification MIL-P-116. The test shall be performed as specified in 4.4.6.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 8864620 and Equipment Lists (EL's) reference thereon identify the inspection equpment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activites for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.4 Test Method and Procedures

4.4.1 Moisture content of delay composition.-The moisture content of the delay composition shall be determined in accordance with Specification MIL-C-13739. This test is a destructive test. Samples shall not be returned to the lot.

4.4.2 Determination of binder-lubricant of RDX.-The binder-lubricant of the RDX shall be determined in accordance with Specification MIL-P-45486. This test is a destructive test. Sample shall not be returned to the lot.

4.4.3 X-ray examination of delay detonator assembly.-The presence of RDX, Lead Azide, delay composition and baffle shall be determined by x-ray equipment satisfactory to the Contracting Officer. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.4 Delay time of delay detonator assembly.-The method of testing shall be by any method approved by the Contracting Officer. This test is a destructive test. Parts so tested shall not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:02Z
Check the source to verify that this is the current version before use.

4.4.5 Output check of delay detonator assembly, Information Only.-The method of testing shall be by the same approved method specified in Para. 4.4.4. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.6 Heat seal test of packing seals.-This test shall be performed in accordance with MIL-P-116. Seals so tested shall not be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging

5.1.1 Level C, Minimum Military Package.-See Para. 5.2.1.

5.2 Packing

5.2.1 Level C, Minimum Military Package.-The delay detonator assembly shall be packed for shipment in accordance with dwgs. 8886833 and 8886832, or as an alternate dwgs. 8886938 and 8886937.

5.3 Marking.-Marking shall be in accordance with dwgs. 8886833 and 8886832, or as an alternate dwgs. 8886938 and 8886837 and Code of Federal Regulations, Title 49 Parts 171-179.

5.4 Shipping.-When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5.).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:02Z
Check the source to verify that this is the current version before use.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawings or Federal Stock Numbers). When an equipment lists references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (see 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:02Z
Check the source to verify that this is the current version before use.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contracotr. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1390-A-791

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:02Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 OCT 64 1426

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:02Z
Check the source to verify that this is the current version before use.