MILITARY SPECIFICATION

WARHEAD SECTION,

GUIDED MISSILE,

PRACTICE: XM198

1. SCOPE

1.1 This specification covers the metal parts, Loading, Assembling and Packing for one type of Warhead designated as Warhead Section: XM198.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-T-5021	-	Tests, Aircraft Welding Operator's Certification
MIL-R-11470	-	Radiographic Inspection: Qualification of Equipment Operators and Procedures
MIL-I-45607	-	Inspection Equipment, Acquisition, Maintenance and Disposition of

FSC: 1340

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

MIL-S-60902 - Soldering Electrical Connections for Nuclear Weapons Systems, Procedure for

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)

MIL-STD-109 - Quality Assurance Terms and Definitions

MIL-STD-202 - Test Methods for Electronic and Electrical Component Parts

MIL-STD-1168 - Lot Numbering of Ammunition

MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

9208260 - Warhead Section, G.M., Practice: XM198

PUBLICATIONS

ARMY

ET-9208260 - Equipment Tabulation

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer).

2.2 Other publications.-The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall appply.

CODE OF FEDERAL REGULATIONS

Title 49 - Transportation, Parts 0-190

(The Code of Federal Regulations is available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. Orders should specify, "49 CFR 0-190 (latest revision)".)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and publications.

3.2 Parts.-The parts shall comply with all requirements specified on Drawing (Dwg.) F-9208260, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Radiographic examination of explosive assemblies.-The Single and Double Lead Cup assemblies shall be radiographically examined for maximum gap between the detonating cord and Lead Cup assembly.

3.4 Soldering.-Unless otherwise specified on the drawing soldering of all electrical joints and connections shall be in accordance with specification MIL-S-60902.

3.5 Functioning of Nose Assembly.-The Nose Assembly when disengaged shall be capable of being moved forward a distance of 9.75 inches minimum and rotated 105 degrees minimum clockwise and returned to the original position and be securely re-engaged without any motion stoppage due to interference between parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

3.6 Welding.-All welds shall be reasonably smooth and free of craters. They shall exhibit characteristics of deposit representative of good welding practice. The process shall be such as to prevent warpage beyond dimensional requirements. Sag of material in the area adjacent to the weld shall not be more than .010 below the unsagged surface. Cracks shall not exceed 1/2 inch in length and porous areas or linear porosity (spaced less than 1/16 inch apart) shall not exceed 1/2 inch in length. The total length of all defects in any weld shall not exceed 2 inches. Blow outs may be repaired by hand welding provided they do not exceed 1/4 inch in width and 1 inch in length. No more than 3 such areas may be repaired in any section. Only welders qualified in accordance with specification MIL-T-5021 shall be permitted to weld.

3.7 Electrical checkout of assembled XM198 Warhead.-The assembled warhead shall meet the following electrical requirements between the points specified below. Unless otherwise specified tolerance shall be ± 10%.

FROM	TO	EXPECTED READING	REMARKS
J1-U	J1-M	< 1.0 OHMS	
J1-U	J1-C	"	
J1-C	J1-$\overline{M}$	"	
J1-$\overline{L}$	J1-M	< 1.5 OHMS	
J1-B	J1-F	4.0 OHMS	
J1-$\overline{A}$	J1-V	"	
J1-$\overline{H}$	J1-Y	< 1.0 OHMS	
J1-G	J1-Z	"	
J1-G	J1-Y	30 OHMS	
J1-X	J1-R	1.0 OHMS	
J1-A	J1-W	"	
J1-A	J1-R	INFINITY	
J1-N	J1-P	< 1.0 OHMS	
J1-B	J1-C	"	
J1-B	J1-N	INFINITY	
J1 SHELL	WH SKIN	< 1.0 OHMS	
J1 SHELL	P5 TAB	"	
J1 SHELL	P6 TAB	"	
J1-A	J1-V	3.6 OHMS	
P6-U	P6-W	< 1.0 OHMS	WITH XM811 DISCONNECTED
J1-A	J1-$\overline{V}$	10 OHMS	" " "
P6-T	P6-Y	< 1.0 OHMS	WITH PINS P4-1 AND P4-8 SHORTED TOGETHER

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

FROM	TO	EXPECTED READING	REMARKS
P6-T	P6-Y	15 OHMS	WITH XM811 DISCONNECTED
P6-U	P6-D	INFINITY	
P6-$\overline{U}$	P6-D	<1.0 OHMS	WITH PINS P4-3 AND P4-7 SHORTED TOGETHER
P6-U	P6-W	INFINITY	
P6-U	P6-$\overline{W}$	<1.0 OHMS	WITH PINS P4-2 AND P4-6 SHORTED TOGETHER
P6-U	P6-$\overline{W}$	<1.0 OHMS	WITH PINS P4-13 AND P4-10 SHORTED TOGETHER
P6-L	P4-1	INFINITY	
P5-C	P5-D	<1.0 OHMS	WITH XM113 DISCONNECTED
P5-A	P5-B	"	" " "
P5-A	P5-C	INFINITY	" " "
P6-F	P6-P	INFINITY	" " "
P6-F	P6-P	<1.0 OHMS	WITH PINS P5-A AND P5-C SHORTED TOGETHER
P6-L	P5-A (P)	INFINITY	
J1-U	J1-M	<1.0 OHMS	
J1-M	J1-C	<1.0 OHMS	
J1-C	J1-$\overline{U}$	<1.0 OHMS	
J1-$\overline{L}$	J1-M	<1.5 OHMS	
P6-L	J1-T	INFINITY	
"	J1-D	"	
"	P4 TO SKIN	"	
"	P4-1	"	
"	P4-2	120K OHMS	
"	P4-3	INFINITY	
"	P4-4	"	
"	P4-5	"	
"	P4-6	"	
"	P4-7	"	
"	P4-8	"	
"	P4-9	"	
"	P4-11	INFINITY	
"	P4-12	"	
"	P4-13	"	
"	P4-14	"	
"	P4-15	"	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

FROM	TO	EXPECTED READING	REMARKS
P6-L	P4-10	120K OHMS	
"	P5-A(P)	"	
"	P5-B(P)	"	
"	P5-C(P)	"	
"	P5-D(P)	"	
"	P5-E(P)	"	
"	P5-F(P)	"	
P6-L(P)	P5-C	200K OHMS	
"	P5-D	"	
P6-EE(P)	J1-Y	INFINITY	
P6-E (P)	P6-J	"	
"	P6-K	"	
P6-E (P)	P6-W	"	
"	P6-N	"	
P6-EE(P)	P6-W	"	
P6-AA(P)	P6-EE	"	
J1-C	J1-P	"	
P6-U	P6-C	CONTINUITY	
P6-N	P6-M	INFINITY	
P6-W	P6-Z	"	
P6-Z	P6-E	"	
P6-G	P6-GG	"	
P6-G	P6-FF	"	
P6-W	P6-J	"	
P6-W	P6-Q	"	
P6-W	P6-Y	"	
P6-S	P6-Q (P)	"	
P6-BB	P6-P	"	
P6-N	P6-CC	"	
P6-P (P)	P6-E	"	
P6-N (P)	P6-E	"	
P6-DD	J1-Y	"	
P6-M	"	"	
J1-B	J1-P	"	
J1-X	J1-W	"	
P6-L	J1-A	"	
"	J1-R	"	
"	J1-C	"	
"	J1-P	"	
"	P6-A	"	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

FROM	TO	EXPECTED READING	REMARKS
P6-L	P6-C	INFINITY	
P6-L	P6-K	CONTINUITY	
P6-L	P6-N	INFINITY	
"	P6-N(P)	"	
"	P6-P(P)	"	
"	P6-Y	"	
"	P6-Z	"	
"	P6-C	"	
"	P6-G	100K OHMS	
"	P6-J	INFINITY	
"	P6-U	"	
P6-J	P6-Y	"	
P6-L	P6-BB	"	
"	P6-CC	"	
"	P6-DD	"	
"	P6-FF	"	
"	P6-GG	"	
"	J1-H	100K OHMS	
J1-Y (P)	P6-EE	56K OHMS	
P6-J (P)	P6-E	45K OHMS	
P6-W	P6-I	INFINITY	
"	P6-H	22.1K OHMS	
P6-X(P)	P6-E	22.2K OHMS	
P6-W (P)	P6-EE	56.2K OHMS	
J1-B	P6-S	10K OHMS	
P6-D	J1-Y	INFINITY	
P6-EE(P)	P6-AA	"	
J1-L	P6-A	CONTINUITY	
"	P6-B	"	
J1-U	P6-C	"	
P6-L	P6-K	"	
J1-M	P6-Z	"	
"	J1-C	"	
J1-U	"	"	
J1-V	P6-Y	"	
J1-V	J1-F	"	
J1-B	J1-A	"	
J1-G	J1-Z	"	
P6-K	WH SKIN	"	
P6-M	J1-Y	29 OHMS	
P6-Z	J1-Y	"	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

FROM	TO	EXPECTED READING	REMARKS
P6-W(P)	P6-E	300 TO 500 OHMS	
P6-N(P)	"	"	
P6-U	P6-D	CONTINUITY	
P6-G(P)	J1-Y	"	
P6-G	J1-H	"	
J1-R	J1-X	"	
P6-L	WH SKIN	"	
J1-C	J1-B	"	
J1-P	J1-N	"	
J1-R	J1-X	"	
J1-W	J1-A	"	
P6-E(P)	P6-V	INFINITY	
P6-E(P)	P6-X	25K OHMS	
P6-G	P6-G	5K OHMS	
"	P6-F	2.8K OHMS	
P6-E	J1-Y	22.2K OHMS	
"	P6-H	44.2K OHMS	
P6-H	J1-Z	22.1K OHMS	
CHASSIS GND (RSD)	P6-L	CONTINUITY	
J1-G(P)	J1-Y	29 OHMS	
J1-B	P6-T	10 OHMS	
P6-Y	"	17 OHMS	
P6-W	J1-Y	14 OHMS	
P6-U	P6-F	"	
P6-A	J1-Y	15 OHMS	
P6-B	J1-Y	"	
J1-V	P6-R	1K OHMS	
"	P6-HH	"	
P6-HH	P6-T	"	
P6-W	P6-V	CONTINUITY	
P6-D	P6-R	"	
P6-P	P6-T	"	
P6-N	P6-Y	"	
P6-U	P6-CC	"	
P6-U	P6-C	"	
P6-J	P6-Q	INFINITY	
P6-L	J1-L	"	
"	J1-U	"	
"	J1-N	"	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

FROM	TO	EXPECTED READING	REMARKS
P6-L	J1-B	INFINITY	
"	J1-C	"	
"	J1-P	"	
"	J1-H	100K OHMS	
"	J1-G	"	
"	J1-Y	"	
"	J1-Z	"	
"	J1-X	INFINITY	
"	J1-W	"	
"	J1-R	"	
"	J1-A	"	
"	J1-F	"	
"	J1-B	"	
"	J1-$\overline{A}$	"	
"	J1-$\overline{V}$	"	
"	J1-C	"	
"	J1-$\overline{M}$	"	
"	J1-J	"	
"	J1-K	"	
"	J1-E	"	
"	J1-S	"	

3.8 Workmanship.-All parts and assemblies shall be fabricated, finished, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any parts, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required marking and stamping shall be neat and sharply defined.

3.9 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (see 6.4).

3.10 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. (See 6.1) The first article sample shall consist of the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

a. Two (2) - Warhead Section, G.M., Practice: XM198 (9208260)
b. Five (5) - G and C Cable Assembly (9208254)
c. Five (5) - Destruct Cable Assembly (9208252)
d. Two (2) - Nose Skin, (9208291)
e. Two (2) - Skin, Forward (9208259)
f. Two (2) - Skin, Aft (9208511)
g. Two (2) - Ring, Fuze (9208257)
h. Two (2) - Ring, Center (9208515)
i. Two (2) - Ring, Aft (9208266)
j. Two (2) - Ring, Mounting RSD (9208491)
k. Two (2) - Ballast, Sta 39.0 (9208270)
l. Two (2) - Ballast, Sta 60.8 (9208269)
m. Two (2) - Ballast, Sta 80.0 (9208504)
n. Two (2) - Aft Ballast Support Assembly (9208253)
o. Ten (10) - Pin, Alignment (8877425)
p. Ten (10) - Pin, Shear (8877426)
q. Five (5) - Booster Assembly (9208777)
r. Six (6) - Double Lead Cup Assembly (9208519, one of each)
s. Five (5) - Single Lead Cup Assembly (9208251)

All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Assemblies and components will be subjected by the Government to any or all the examinations or tests specified in this specification and any or all requirements of the applicable drawings. In addition, any or all of the following examinations and tests will be performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.2.2.1 Proving ground test.-When the provisions of AMCR 700-34, which require Initial Production Testing apply, such testing shall be accomplished in accordance with 6.5.

4.2.3 Rejection.-If any assembly or component fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (See 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 This paragraph applies to all components not listed and listed in 4.3.2.2 through 4.3.2 which require a protective finish (see applicable drawings) and all components and sub-assemblies not listed in 4.3.2.2 through 4.3.2. (See 3.8)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.00 Percent		
201.	Protective finish missing or inadequate	Visual	01001
202.	Evidence of poor workmanship (See 3.8)	Visual	01002

4.3.2.2 Pin, Alignment (See Dwg. 8877425).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	100% Inspection		
101.	Concentricity of thread with body diameter	Gage	02001
Major:	AQL 0.40 Percent		
102.	Diameter of Body	Gage	02002

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Minor:	AQL 1.00 Percent		
201.	Undercut missing	Visual	02003
202.	Evidence of poor workmanship (See 3.8)	Visual	02004

4.3.2.3 Pin, Shear (See Dwg 8877426).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	100% Inspection		
101.	Concentricity of thread with body diameters	Gage	03001
Major:	AQL 0.40 Percent		
102.	Diameter of body	Gage	03002
Minor:	AQL 1.00 Percent		
201.	Undercut missing	Visual	03003
202.	Evidence of poor workmanship (See 3.8)	Visual	03004

4.3.2.4 Pin, Alignment, R.S.D. (See Dwg 9208492).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 2.50 Percent		
201.	Pitch diameter of thread	Gage	04001
202.	Concentricity of thread	Gage	04002
203.	Length from end to shoulder	Gage	04003
204.	Length	Gage	04004
205.	Evidence of poor workmanship (See 3.8)	Visual	04005

4.3.2.5 Block Alignment (See Dwg 9208497).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.50 Percent		
201.	Width (max)	Gage	05001
202.	Diameter of tube hole	Gage	05002
203.	Evidence of poor workmanship (See 3.8)	Visual	05003

4.3.2.6 Block, Alignment (See Dwg 9208267).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.50 Percent		
201.	Width (max)	Gage	06001
202.	Diameter of tube hole	Gage	06002
203.	Evidence of poor workmanship (See 3.8)	Visual	06003

4.3.2.7 Tube, Flared (See Dwg 9208150)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.00 Percent		
201.	Profile incorrect	Gage	07001
202.	Evidence of poor workmanship (See 3.8)	Visual	07002

4.3.2.8 Sleeve (See Dwg 9208748).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Diameter of flange (min)	Gage	08001
102.	Inside diameter (max)	Gage	08002
103.	Thickness	Gage	08003
Minor:	AQL 1.00 Percent		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

201.	Length	Gage	08001
202.	Evidence of poor workmanship (See 3.8)	Visual	08002

4.3.2.9 Connector (See Dwg 9212740).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Pitch diameter of thread	Gage	09001
102.	Inside diameter (max)	Gage	09002
103.	Outside diameter at threaded end (min)	Gage	09003
104.	Chamfer incorrect (max) at threaded end	Gage	09004
Minor:	AQL 1.00 Percent		
201.	Knurl missing	Visual	09005
202.	Evidence of poor workmanship (See 3.8)	Visual	09006

4.3.2.10 Ring, Fuze (9208257).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Pitch diameter of large tapped holes	Gage	10001
102.	Pitch diameter of fuze mounting holes	Gage	10002
103.	Concentricity of largest outside diameter with smallest outside diameter	Gage	10003
104.	Pitch diameter of destruct cable connector mounting holes	Gage	10004
Minor:	AQL 2.50 Percent		
201.	Locating of fuze mounting holes	Gage	10005
202.	Positioning of fuze connector opening incorrect	Gage	10006
203.	Location of large tapped holes	Gage	10007

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

204.	Evidence of poor workmanship (See 3.8)	Visual	10008

4.3.2.11 Ring, Center (See Dwg. 9208515).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Concentricity of largest outside diameter with smallest outside diameter	Gage	11001
102.	Pitch diameter of tapped holes on outside periphery	Gage	11002
Minor:	AQL 2.50 Percent		
201.	Location of tapped holes on outside periphery	Gage	11003
202.	Diameter of lead cup assembly hole(s) (min)	Gage	11004
203.	Width of alignment block slot(s) (min)	Gage	11005
204.	Location of alignment block slot(s)	Gage	11006
205.	Evidence of poor workmanship (See 3.8)	Visual	11007

4.3.2.12 Ring, Mounting, R.S.D. (See Dwg 9208491).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Pitch diameter of R.S.D. mounting holes	Gage	12001
102.	Concentricity of smallest outside diameter with the largest outside diameter	Gage	12002
Minor:	AQL 1.50 Percent		
201.	Location of alignment pin holes	Gage	12003

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

202.	Pitch diameter of alignment pin holes	Gage	12004
203.	Location of R.S.D. mounting holes	Gage	12005
204.	Evidence of poor workmanship (See 3.8)	Visual	12006

4.3.2.13 Ring, Aft (See Dwg 9208266)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	100% Inspection		
101.	Location of shear pin holes	Gage	13001
102.	Location of alignment pin holes	Gage	13002
103.	Concentricity of "O"-Ring groove with outside diameter	Gage	13003
Major:	AQL 1.00 Percent		
104.	Concentricity of shear pin threaded hole(s)	Gage	13004
105.	Concentricity of alignment pin threaded hole(s)	Gage	13005
106.	Depth of "O"-Ring groove	Gage	13006
107.	Width of "O"-Ring groove	Gage	13007
108.	Outside diameter	Gage	13008
109.	Inside diameter at "O"-Ring groove	Gage	13009
110.	Concentricity of inside diameter at "O"-Ring groove	Gage	13010
111.	Tapped holes broken through	Visual	13011
Minor:	AQL 2.50 Percent		
201.	Pitch diameter of shear pin hole(s) (min)	Gage	13012
202.	Pitch diameter of alignment pin hole(s) (min)	Gage	13013
203.	Diameter of shear pin hole(s) (unthreaded portion)	Gage	13014
204.	Diameter of alignment pin hole(s) (unthreaded portion)	Gage	13015
205.	Evidence of poor workmanship (See 3.8)	Visual	13016

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.3.2.14 Ballast, Sta. 39.0 (See Dwg 9208270)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Concentricity of largest outside diameter with smallest outside diameter	Gage	14001
102.	Location of detonating cord holes from outside surface	Gage	14002
103.	Diameter of small detonating cord holes	Gage	14003
104.	Depth of insulation groove	Gage	14004
105.	Depth of double lead cup assembly groove	Gage	14005
Minor:	AQL 1.00 Percent		
201.	Diameter of large detonating cord holes	Gage	14006
202.	Evidence of poor workmanship (See 3.8)	Visual	14007

4.3.2.15 Ballast, Sta. 60.8 (See Dwg 9208269).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Concentricity of largest outside diameter with smallest outside diameter	Gage	15001
102.	Location of detonating cord holes from outside surface	Gage	15002
103.	Diameter of small detonating cord holes	Gage	15003
104.	Depth of insulation groove	Gage	15004
105.	Depth of double lead cup assembly groove	Gage	15005
Minor:	AQL 1.00 Percent		
201.	Diameter of large detonating cord holes	Gage	15006
202.	Evidence of poor workmanship (See 3.8)	Visual	15007

4.3.2.16 Ballast, Sta. 80.0 (See Dwg 9208504).-

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Concentricity of largest outside diameter with smallest outside diameter	Gage	16001
Minor:	AQL 1.50 Percent		
201.	Concentricity of inside diameter	Gage	16002
202.	Inside diameter (min)	Gage	16003
203.	Evidence of poor workmanship (See 3.8)	Visual	16004

4.3.2.17 Plate, mounting S and A (See Dwg 9208501).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Pitch diameter of tapped hole(s)	Gage	17001
Minor:	AQL 1.50 Percent		
201.	Location of tapped hole(s)	Gage	17002
202.	Thickness	Gage	17003
203.	Evidence of poor workmanship (See 3.8)	Visual	17004

4.3.2.18 Aft Ballast Support Assembly (See Dwg 9208253).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.0 Percent		
101.	Runout of forward plate with aft ring	Gage	18001
102.	Parallelism of forward plate with aft ring	Gage	18002
103.	Location of detonating cord holes from outside surface	Gage	18003
104.	Depth of insulation groove	Gage	18004
105.	Depth of double lead cup assembly groove	Gage	18005
106.	Diameter of detonating cord holes	Gage	18006

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

	107. Welding improper or incorrect (See 3.6)	Visual	18007
Minor:	AQL 1.5 Percent		
	201. Outside diameter	Gage	18008
	202. Orientation of aft plate incorrect	Gage	18009
	203. Evidence of poor workmanship (See 3.8)	Visual	18010

4.3.2.19 Skin, Forward (See Dwg 9208259).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	*AQL 0.65 Percent		
	101. Perpendicularity of open ends with inside diameters	Gage	19001
	102. Contour of skin incorrect	Gage	19002
	103. Welding improper or incorrect (when applicable) (See 3.8)	Visual	19003
Minor:	AQL 1.50 Percent		
	201. Thickness before forming	Gage	19004
	202. Length	Gage	19005
	203. Evidence of poor workmanship (See 3.8)	Visual	19006

*When defect 103 is not applicable AQL shall be 0.40 Percent.

4.3.2.20 Skin, Aft (See Dwg 9208511).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	*AQL 0.65 Percent		
	101. Perpendicularity of forward and Aft end with inside diameters	Gage	20001
	102. Skin contour incorrect	Gage	20002
	103. Welding improper or incorrect (when applicable) (See 3.6)	Gage	20003
Minor:	AQL 1.50 Percent		
	201. Length	Gage	20004
	202. Thickness (before forming)	Gage	20005
	203. Evidence of poor workmanship (See 3.8)	Visual	20006

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

*When defect 103 is not applicable AQL shall be 0.40 Percent.

4.3.2.21 Skin, Nose (See Dwg 9208291).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Contour of skin incorrect	Gage	21001
102.	Perpendicularity of open end	Gage	21002
Minor:	AQL 1.50 Percent		
201.	Length	Gage	21003
202.	Thickness	Gage	21004
203.	Evidence of poor workmanship (See 3.8)	Visual	21005

4.3.2.22 Nose Assembly (See Dwg 9208608).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Functioning of latch assembly improper	Manual	22001
Minor:	AQL 1.00 Percent		
201.	Any component missing, damaged or improperly assembled	Visual	22002
202.	Evidence of poor workmanship (See 3.8)	Visual	22003

4.3.2.23 Ring Assembly (See Dwg 9268135).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Soldering incomplete	Visual	23001
Minor:	AQL 1.50 Percent		
201.	Depth of spot face, prior to assembling disc (See Dwg 9268146)	Gage	23002

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

202.	Thickness of ring (See Dwg 9268146)	Gage	23003
203.	Evidence of poor workmanship (See 3.8)	Visual	23004

4.3.2.24 Well, Charge (See 9268134).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Pitch diameter of threaded holes in flange	Gage	24001
102.	Pitch diameter of tapped holes	Gage	24002
103.	Pitch diameter of center threaded hole	Gage	24003
104.	Depth of small counterbore	Gage	24004
Minor:	AQL 1.50 Percent		
201.	Diameter of spotting charge well	Gage	24005
202.	Length of spotting charge well	Gage	24006
203.	Diameter of small counterbore	Gage	24007
204.	Evidence of poor workmanship (See 3.8)	Visual	24008

4.3.2.25 Booster Assembly (See Dwg 9208777).-

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Cover missing	Visual	25001
2.	Crimp and or sealant missing	Visual	25002
Major:	100% Inspection		
101.	Explosive missing	Visual	25003
Major:	AQL 0.40 Percent		
102.	Length	Gage	25004
103.	Diameter	Gage	25005
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.8)	Visual	25006

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.3.2.26 Lead Cup Assembly (See Dwg 9208255).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Weight of PETN	Balance	26001
102.	Evidence of poor workmanship (See 3.8)	Visual	26002
Minor:	None defined		

4.3.2.27 Detonator Assembly (See Dwg 9208409).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	100% Inspection		
101.	Crimp(s) missing or incomplete	Visual	27001
Major:	AQL 0.40 Percent		
102.	Protrusion of detonating, cord assembly (max)	Gage	27002
103.	Any part missing or damaged	Visual	27003
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.8)	Visual	27004

4.3.2.28 Double Lead Cup Assembly (See Dwg 9208519)

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Cup damaged to extent explosive is exposed	Visual	28001
Major:	100% Inspection		
101.	Crimp(s) missing or incomplete	Visual	28002
102.	Explosive charge missing	Visual	28003
Major:	AQL 0.65 Percent		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

103.	Length	Gage	28004
104.	Diameter of lead cup assembly (max)	Gage	28005
105.	Evidence of poor workmanship (See 3.8)	Visual	28006

Minor: None defined

4.3.2.29 Single Lead Cup Assembly (See Dwg 9208251).-

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Cup damaged to extent explosive is exposed	Visual	29001
2.	Open end of detonating cord not sealed	Visual	29002
Major:	100% Inspection		
101.	Crimp(s) missing or incomplete	Visual	29003
102.	Explosive charge missing	Visual	29004
Major:	AQL 0.65 Percent		
103.	Total length	Gage	29005
104.	Diameter of cup (max)	Gage	29006
105.	Evidence of poor workmanship (See 3.8)	Visual	29007

Minor: None defined

4.3.2.30 G and C Cable Assembly (See Dwg. 9208254).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Wiring improper or incorrect	Visual	30001
102.	Soldering improper	Visual	30002
103.	Any component missing or damaged	Visual	30003

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

104.	Potting missing	Visual	30004
105.	Adhesive missing	Visual	30005
Minor:	AQL 1.50 Percent		
201.	Overall length	Gage	30006
202.	Sealing compound missing from threads	Visual	30007
203.	Marking misleading or unidentifiable	Visual	30008
204.	Evidence of poor workmanship (See 3.8)	Visual	30009

4.3.2.31 Destruct Cable Assembly (See Dwg. 9208252).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Wiring improper or incorrect	Visual	31001
102.	Soldering improper	Visual	31002
103.	Any component missing or damaged	Visual	31003
104.	Potting compound missing or incomplete	Visual	31004
105.	Adhesive missing	Visual	31005
Minor:	AQL 2.50 Percent		
201.	Contour of cable incorrect	Gage	31006
202.	Length of transition(s)	Gage	31007
203.	Length from P3 connector to P6 connector	Gage	31008
204.	Sealing compound missing from threads	Visual	31009
205.	Marking misleading or unidentifiable	Visual	31010
206.	Evidence of poor workmanship (See 3.8)	Visual	31011

4.3.2.32 XM198 Warhead Section, G.M., Practice (See Dwg 9208260).-

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Gap between double lead cup assemblies at booster hole (max)	Gage	32001
2.	Detonating cord(s), Lead cup(s) or booster(s) damaged to the extent explosive is exposed	Visual	32002
3.	Red flag show through window of fuze and, or S&A Device	Visual	32003
4.	Setting of fuze incorrect	Visual	32004
Major:	100% Inspection		
101.	Excessive gap(s) between detonating assemblies	Gage	32005
102.	Location of booster hole at aft end	Gage	32006
103.	Diameter of booster hole at aft end	Gage	32007
104.	Location of destruct kit mounting holes	Gage	32008
105.	Depth of booster hole at aft end	Gage	32009
106.	Runout incorrect	Gage	32010
107.	Weight incorrect	Balance	32010
108.	Torque of fuze mounting screw(s) incorrect	Gage	32011
109.	Fuze mounting screw seals missing or broken	Visual	32012
110.	Operation of nose assembly improper	Manual	32013
111.	Any component missing or damaged	Visual	32014
112.	Orientation of J1 connector improper	Visual	32015
Major:	AQL 1.00 Percent		
113.	Pitch diameter of destruct kit mounting holes	Gage	32016
114.	Skin gaps excessive	Gage	32017
115.	Skin surface mismatch excessive	Gage	32018

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

116.	Distance from center ring to end of single lead cup assembly	Gage	32019
117.	Cement between carrier(s) and skin missing or insufficient	Visual	32020

Minor: AQL 4.00 Percent

201.	Protrusion of shear pin(s)	Gage	32021
202.	Protrusion of alignment pin(s)	Gage	32022
203.	Spring pin above flush to too far below flush	Gage	32023
204.	Distance from aft skin to aft ring (max)	Gage	32024
205.	Distance from aft skin to center ring	Gage	32025
206.	Distance from forward skin to fuze ring	Gage	32026
207.	Distance between carrier and alignment block	Gage	32027
208.	Evidence of poor workmanship (See 3.8)	Visual	32028

4.3.2.33 XM198 Warhead Section, G.M., Practice, After painting and marking (See Dwg 9208260).-

Categories	Defects	Method of Inspection	Code No.

Critical: None defined

Major: None defined

Minor: AQL 1.00 Percent

201.	Marking missing, incorrect or unidentifiable	Visual	33001
202.	Evidence of poor workmanship (See 3.8)	Visual	33002

4.3.2.34 XM198 Warhead Section, G.M., Practice, after Assembling into container and prior to assembling cover (See Dwg. 9211190).-

Categories	Defects	Method of Inspection	Code No.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

Critical:			
1.	Ground cable insecurely connected or missing	Manual-Visual	34001
Major:	100% Inspection		
101.	Torque of Warhead "T" bolts incorrect	Gage	34002
102.	Aft missing from kit	Visual	34003
Major:	AQL 0.40 Percent		
103.	Torque of strap bolts incorrect	Gage	34003
104.	Evidence of poor workmanship (See 3.8)	Visual	34004
Minor:	None defined		

4.3.2.35 XM198 Warhead Section, G.M., Practice, Container, after assembly of cover (See Dwg 9211190).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	100% Inspection		
101.	Any bolt not fastened properly	Visual	35001
102.	Seal missing or broken	Visual	35002
Minor:	AQL 1.00 Percent		
201.	Marking misleading, unidentifiable or incorrect	Visual	35003
202.	Evidence of poor workmanship (See 3.8)	Visual	35004

4.3.3.1 Dimensional control of cast parts.-In place of the normal sampling associated with the Classification of Defects, and with the approval of the Contracting Officer, a sample of at least three (3) parts (as cast) from each cavity may be dimensionally inspected to qualify a new or reworked cavity for use in production or as a control of the cavity during production. Inspection for control of each cavity during production shall be performed on

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

the above quantities from each cavity after production of 5000 parts. Individual cavity identification must be provided

If any defective parts are found during qualification of the cavity, the cavity producing the defective part shall not be used in production. If any defective parts are found when inspection is performed for control of the cavity, the cavity producing the defective part shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for corrective action.

All cavities formerly removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test specified above. The contractor may request a change of inspection frequency providing he presents objective evidence to substantiate the request to the Contracting Officer.

4.3.3.2 Dimensional control of stamped parts.-In place of the normal sampling associated with the Classification of Defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check shall be returned to the contractor for corrective action.

All tools removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request.

4.3.3.3 Pull test of crimp of explosive assemblies (See applicable dwg), Major defect.-A sample of five (5) assemblies from each lot of explosive assemblies list below shall be subjected to this test. If any assembly fails to comply with the specified requirement that lot represented by the sample shall be rejected. The test shall be performed as specified in 4.4.1, using equipment in accordance with 4.3.4. Code numbers for this test are as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

Assembly	Code No.
Detonator Assembly (9208409)	41001
*Double Lead Cup Assembly (9208519)	41002
*Single Lead Cup Assembly (9208251)	41003

*After completion of this test, these assemblies are to be subjected to the test in 4.3.3.4.

4.3.3.4 Radiographic examination of explosive assemblies (See 3.3), Major defect.-This test shall be performed 100 percent. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.2, using equipment in accordance with 4.3.4. Code numbers for this test are as follows:

Item	Code No.
Single Lead Cup Assembly (9208251)	42001
Double Lead Cup Assembly (9208519)	42002

4.3.3.5 Ultrasonic inspection of Aft Ring (See Dwg 9208266), Major defect, Code No. 43001.-Each Aft Ring shall be subjected to this test. Any Aft Ring which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in MIL-I-8950, using equipment specified therein.

4.3.3.6 Electrical continuity of Destruct Cable Assembly (See Dwg 9208252), Major defect, Code No. 44001.-Each Destruct Cable Assembly shall be subjected to this test. Any Cable Assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.3, using equipment in accordance with 4.3.4.

4.3.3.7 Insulation resistance of Destruct Cable Assembly (See Dwg 9208252), Major defect, Code No. 44002.-Each Destruct Cable Assembly shall be subjected to this test. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.4, using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.3.3.8 Electrical continuity of G and C Cable Assembly (See Dwg 9208254), Major defect, Code No. 45001.-Each G and C Cable Assembly shall be subjected to this test. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. This test shall be performed as specified in 4.4.5, using equipment in accordance with 4.3.4.

4.3.3.9 Insulation resistance of G and C Cable Assembly (See Dwg 9208254), Major defect, Code No. 45002.-Each G and C Cable Assembly shall be subjected to this test. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.6, using equipment in accordance with 4.3.4.

4.3.3.10 Functioning of Nose Assembly (3.5), Major defect, Code No. 46001.-This test shall be performed 100 percent on every assembled warhead. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

4.3.3.11 Physical characteristics of Assembled XM198 Warhead (See Dwg 9208260), Major defect.-These tests shall be performed 100 percent. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. These test shall be performed as specified in the paragraphs indicated below, using equipment in accordance with 4.3.4. Code Numbers for these tests are as follows:

Characteristic	Code No.	Test Para.
Longitudinal Center of Gravity	47001	4.4.7.1
Radial Center of Gravity	47002	4.4.7.2
Pitch and Yaw Moment of Inertia	47003	4.4.7.3
Roll Moment of Inertia	47004	4.4.7.4

4.3.3.12 Electrical checkout of assembled Warhead Section (See 3.7), Major Defect, Code No. 48001.-Each Assembled Warhead shall be subjected to this test. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.8, using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 9208260 and Equipment Lists (EL's) referenced theron identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures.

4.4.1 Pull test of crimp of explosive assembly.-The applicable explosive assembly shall be assembled to a fixture as specified on the equipment list and the required force shall be applied. This is a destructive test. Assemblies so tested shall not be returned to the lot.

4.4.2 Radiographic examination of explosive assemblies.-The explosive assemblies shall be positioned on a fixture as specified on the equipment list. Each assembly shall be identified to its position on the radiograph and the exposure made. Examinations of the radiographs shall be made for compliance with the applicable cap requirement. Radiographic equipment, operators and procedures shall be qualified in accordance with specification MIL-R-11470. This is a non-destructive test. Parts so tested may be returned to the lot if acceptable.

4.4.3 Electrical continuity of Destruct Cable Assembly.-The destruct cable assembly shall be assembled to a fixture as specified on the equipment list and tested for compliance with the specified requirement. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.4.4 Insulation resistance of Destruct Cable Assembly.-The destruct cable assembly shall be assembled to a fixture as specified on the equipment list and tested for compliance with the specified requirement. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

4.4.5 Electrical continuity of G and C Cable Assembly.-The G and C Cable Assembly shall be assembled to a fixture as specified on the equipment list and tested for compliance with the specified requirement. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

4.4.6 Insulation resistance of G and C Cable assembly.-The G and C Cable Assembly shall be assembled to a fixture as specified on the equipment list and tested for compliance with the specified requirement. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

4.4.7 Physical characteristics of assemblies XM198 Warhead.-

4.4.7.1 Longitudinal center of gravity.-The assembled warhead shall be assembled to a fixture as specified on the equipment list and tested for compliance with the specified requirement. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

4.4.7.2 Radial center of gravity.-The assembled warhead list and tested for compliance with the specified requirement. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

4.4.7.3 Pitch and Yaw Moment of Inertia.-The assembled warhead shall be assembled to a fixture as specified on the Equipment List and tested for compliance with the specified requirement. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

4.4.7.4 Roll moment of inertia.-The assembled warhead shall be assembled to a fixture as specified on the equipment list and tested for compliance with the specified requirement. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.4.8 Electrical checkout of assembled Warhead (Commutated).-The equipment as specified on the Equipment List shall be assembled to the warhead and checkout for compliance with the specified requirement shall be performed. The test shall be conducted in the sequence listed in 3.7 and with the warhead grounded. This is a non-destructive test. Warheads so tested may be returned to the lot if acceptable.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.-

5.1.1 Level A.-The XM198 Warhead shall be preserved and packaged in accordance with the applicable Dwg. 9211190.

5.2 Packing.-

5.2.1 Level A.-The XM198 Warhead, preserved and packaged as specified in 5.1.1, shall be packed in accordance with the applicable Dwg. 9211190.

5.3 Marking.-Marking shall be in accordance with the applicable dwgs and Code of Federal Regulations, Title 49 Parts 171-179.

5.4 Shipping.-When components from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples. (when spec requires first article sampling).

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

his operations. Such contractor-prepared designs (see 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procurement of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subjected to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 3. Legibility and reproducibility shall permit conventional marking of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall froward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

6.5 Proving ground test.-Initial production testing shall be conducted in accordance with U.S. Army Test and Evaluation Command Initial Production Test Plan No._____.

6.6 Electrical checkout of Range Safety Device: XM97.- At the option of the contractor the Range Safety Device can be checked for continuity and insulation resistance prior to its installation into the warhead. If any Range Safety Device does not comply with the following specified resistance readings. It shall be rejected and shall not be assembled into any warhead.

6.6.1 Continuity.-The continuity shall be measured with an instrument whos maximum output current does not exceed 10 milliamperes.

From	To	Resistance in ohms (see Note 1)
J7-B	J7-D	0.7
J7-A	J7-B	1.5
J7-A	J7-D	0.7
J7-A	J8-Z	.25
J7-C	J8-C	"
J7-E	Clip lead	"
J7-F	J7-G	"
J7-H	J7-J	"
J7-K	J8-K	"
J7-L	J8-L	"
J7-M	J7-N	"
J7-P	J7-R	"
J7-S	J7-T	"
J8-p	J8-T	"
J7-U	J7-b	"
J7-Y	J7-Z	"
J7-Y	J8-Y	"
J7-Y	J8-x	"
J7-a	J8-A	"
J7-a	J8-B	"
J7-X	J7-c	"
J7-X	J8-G	"
J8-D	J8-r	"
J8-E	J8-F	"
J8-c	J8-u	.25
J8-w	J8-v	"
J8-d	J8-CC	"

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

From	To	Resistance in Ohms (See Note 1)
J8-P	J8-N	.25
J8-d	J8-U	"
J7-Y	J8-R	1000 ± 100
J7-Y	J8-HH	1000 ± 100
J8-a	J8-b	4.0 ± 1.0
J7-S	J8-T	2.0
J7-S	J8-p	1.0 ± 0.5
J7-S	J8-HH	1000 ± 100
J8-w	J8-G	15 ± 2.0
J8-a	J8-G	15 ± 2.0
J8-m	J8-G	29 ± 2.5
J8-m	J8-z	58 ± 8.0
*J8-W	J8-E	**500
J8-g	J8-f	2.5 K + 0.5 K (See Note 2)
J8-g	J8-G	5 K ± 0.5 K
J7-S	J8-S	10 K ± 1.0 K
J7-U	J8-H	22.1 K ± 2.0 K
J8-w	J8-h	22.1 K ± 2.0 K
J8-q	J8-s	22.1 K ± 2.0 K (see Note 3)
J8-q	J8-t	22.1 K ± 2.0 K (see Note 4)
J8-e	J7-U	22.1 K ± 2.0 K
J8-e	J8-G	22.1 K ± 2.0 K
J7-X	J7-E	100 K ± 8 K
*J8-J	J8-e	30 K (min)
*J8-e	J8-J	20 megohm (min)
*J8-k	J8-e	30 K (min)
*J8-e	J8-k	20 megohm (min)
J7-S	J8-R	1.0 K + .2 K
*J8-w	J8-EE	30 K (min)
*J8-EE	J8-w	20 megohm (min)
*J8-w	J8-P	30 K (min)
*J8-P	J8-w	20 megohm (min)
*J8-n	J8-E	10 K (min)
*J8-E	J8-n	20 megohm (min)
*J8-E	J8-W	20 megohm (min)
*J8-X	J8-E	10 K (min)
J8-U	J8-F	13.0 ± 3.0
J7-W	J8-J	32.3 K ± 3.0 K
J7-V	J8-k	32.3 K ± 3.0 K

*Indicates positive terminal of measuring devices.
** With approx 2 milliamperes current. This resistance is dependent on the current.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

NOTE: 1. Resistance shall be maximum unless specified otherwise,
2. This resistance can vary depending upon the angle of position of the XM97.
3. This point shall reject until XM97 is placed in the negative direction.
4. This point shall reject until XM97 is placed in the positive direction.

6.6.2 Insulation resistance.-When tested at 500 ± 50 volts direct current, the resistance between each circuit and all other circuits and the chassis shall be not less than the resistance values specified. The current of the tester shall be limited to 5 milliamperes with the voltage applied for a duration of 10 seconds minimum to 60 seconds maximum.

From	To	Resistance in ohms (min)
J7-A	To all other listed pins & shells shorted together as one terminal	20 Meg
J7-C	"	"
J7-F	"	"
J7-H	"	"
J7-K	"	"
J7-L	"	"
J7-M	"	"
J7-P	"	"
J7-a	"	"
J8-$\overline{D}$	"	"
J8-M	"	"
J8-V	"	"
J8-c	"	"
J8-$\overline{i}$	"	"
J8-$\overline{AA}$	"	"
J8-BB	"	"
J8-DD	"	"
J8-FF	"	"
J8-GG	"	"

Custodian
Army-MU

Preparing Activity:
Army-MU

Project Number: 1340-A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.