MILITARY SPECIFICATION
Maintenance Kit, Electronic Equipment
MK 495/APQ-72

This specification has been approved by the Bureau of Naval Weapons, Department of the Navy

1. SCOPE

1.1 Scope - The kit covered by this specification shall provide the special tools necessary to perform preventive and corrective maintenance on the APQ-72 Radar (WEC Dwg. 400R928G01).

1.2 Classification - The MK 495/APQ-72 Maintenance Kit shall be of one type and shall consist of the following:

Units	Allowable Size (Inches)	Max. Allow. Weights (Pounds)	Appl. Para.
Transition Seal		.3	3.3.1
Pressure Plate Assembly		1.0	3.3.2
Wrench Set		1.8	3.3.3
Plier Set		2.0	3.3.4
Special Screws		---	3.3.5
Pinion Wrench		.2	3.3.6
Magnetron Maintenance Wrench		.5	3.3.7
Indicator Face Plate Protector		3.0	3.3.8
Spin Generator Adjusting Tool		.5	3.3.9
Wrench, Special		.2	3.3.10
Flushing Blocks		1.00	3.3.11
Actuator Jacking Screws		---	3.3.12
Rotor Jacking Screws		---	3.3.13
Socket Wrench, Special		.1	3.3.14
Connector Alignment Fixtures		1.3	3.3.15
Transit Case	15 1/2 x 12 x 7	8.0	3.3.16

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids, form a part of this specification, to the extent specified herein.

SPECIFICATIONS

Military

MIL-T-21200 Test Equipment for use with Electronic and Fire Control Systems; General Specification for

MIL-N-18307 Nomenclature and Nameplates Airborne Electronic and Associated Equipment

MIL-P-17555 Preparation for Delivery of Electronic Equipment, Miscellaneous Electrical Equipment (Except Rotating Electrical Equipment) and Associated Repair Parts.

Source: https://assist.dla.mil -- Downloaded: 20261O-19T14:01Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS (Con't.)

Military

MIL-T-18303 Test Procedures; Preproduction and Inspection, for Aircraft Electronic Equipment, Format For

2.2 Availability of Documents

(1) When requesting applicable documents give both the title and number. All requests shall be made via the cognizant inspector of Naval Material or Bureau of Weapons representative.

(2) Copies of applicable documents may be obtained upon application to the Commanding Officer, Naval Aviation Supply Depot (AD), Philadelphia 11, Pennsylvania.

2.3 Precedence of Documents - When the requirements of the contract, this specification or applicable subsidiary specifications are in conflict, the following precedence shall apply.

(1) Contract - The contract shall have precedence over all referenced documents.

(2) This Specification - This specification shall have precedence over all applicable subsidiary documents. Deviations from this specification, or from subsidiary documents where applicable, may be made only upon written approval.

(3) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified herein.

3. REQUIREMENTS

3.1 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing the following shall govern:

(1) Parts and materials as approved by Specification MIL-T-21200 shall be given first consideration.

(2) When the characteristics of standard MIL parts and materials are such that their use will not fulfill the requirements because of size, weight, performance or other reasons, material and parts shall be used which most nearly meet or exceed the requirements of the respective standard parts and material specifications.

(3) When a non-standard part is used, the meeting of general material requirements such as non-inflammability, fungus resistance, non-toxicity, etc., and the meeting of environmental conditions as required by Specification MIL-T-21200 shall be of prime consideration.

Source: https://assist.dla.mil -- Downloaded: 20260-19T14:01Z
Check the source to verify that this is the current version before use.

(4) In the selection of parts, the above considerations shall apply if the assembly is to be built for detail part maintenance. In the event the entire assembly is built to be expended, the assembly shall be constructed and the quality of the individual parts shall be such that the unit as a whole will pass material, electrical and environmental tests. Any assembly built to be expended shall be approved first by the Bureau of Weapons.

3.1.1 Non-Standard Parts and Material Approval - Approval for the use of non-standard parts and materials shall be obtained as outlined in Specification MIL-T-21200 except as follows:

(1) Mechanical parts shall be submitted as non-standard parts only when the material requirements of Specification MIL-T-21200 are not met.

(2) Non-Standard parts of an electrical nature as defined in Specification MIL-T-21200, shall be approved before the preproduction model of the equipment is submitted for tests. The request for approval must be forwarded to the Bureau of Weapons before the part is purchased or fabricated. In addition to or in lieu of the Non-Standard Part Data Sheet, the contractor shall submit an itemized list of the parts, their sources, and the contractor's drawing or purchase specification covering the parts.

3.2 Design and Construction

3.2.1 General - The equipment shall conform to all the applicable requirements of MIL-T-21200 for design, construction, and workmanship, unless otherwise specified herein.

3.2.2 Total Weight - The total weight of the equipment, including the transit case, shall be a minimum consistent with good design and shall not exceed 24 pounds.

3.2.3 Operating Life

3.2.3.1 Reliable Operating Life - The equipment shall have a reliable operating life of 200 hours without removal for bench servicing. Parts requiring servicing or replacement at the end of this interval to renew this service shall be specified by the manufacturer.

3.2.3.2 Total Operating Life - The equipment shall have a minimum total operating life of 2000 hours with reasonable servicing and replacement of parts. Parts requiring replacement within this interval and the life of such parts shall be specified by the manufacturer.

3.2.4 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval of equipment identification shall be in accordance with Specification MIL-N-18307.

3.2.5 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T14:01Z
Check the source to verify that this is the current version before use.

Temperature	Room ambient ($30^{\circ}C \pm 10^{\circ}C$)
Altitude	Normal ground
Vibration	None
Humidity	Room ambient up to 90% relative humidity

3.2.6 Service Conditions - The equipment shall operate under any of the environmental service conditions or reasonable combination of these conditions as specified in Specification MIL-T-21200 for Class 2B equipment.

3.3 Detail Requirements - The Maintenance Kit shall have the following components:

3.3.1 Transition Seal - The transition seal shall provide a pressure seal at the transition (WEC Dwg. 503R413) of the Antenna AS-940/APQ-72, with the feedhorn removed, when performing a 30 psig pressure test of the antenna waveguide. The seal shall utilize the sealing components available in the transition assembly insofar as is possible.

3.3.2 Pressure Plate Assembly - The pressure plate shall seal the input waveguide (WEC Dwg. 503R420) on the Antenna AS-940/APQ-72. It shall provide an air check valve to permit pressure to be applied to the waveguide through the use of a MK 20A/UP pressure kit and to maintain 30 psig pressures when the MK 20A/UP pressure pump has been removed. The pressure plate shall be equipped with a pressure gauge which is capable of measuring pressures of 0-30 psig of air. The check valve shall be a standard Schraeder Fitting.

3.3.3 Wrench Set - The set shall consist of nine (9) standard, Allen type wrenches, size .035, 1/16, 5/64, 3/32, 1/8, 5/32, 3/16, 7/32, and 1/4. In addition there will be provided eight special Allen type wrenches. Sizes 5/64, 3/32, 1/8, 5/32, 3/16 with respective lengths of 8 inches, 14", 12", 15" and 15" and sizes 5/32, 1/8, 3/16 with respective short arm length of 9/16", 5/8" and 1/2".

3.3.4 Plier Set - This set of six (6) pliers is to facilitate the removal and replacement of retaining rings. They are covered by NavOrd Nos. 41-P-1992-27, 41-P-1992-28, 41-P-1992-29, 41-P-1992-34, 41-P-1992-35 and 41-P-1992-36.

3.3.5 Screws (Special) - There shall be six (6) screws, included in the kit. The screws shall provide means for displacing the spin motor stator (WEC Dwg. 575R578H01) to facilitate disassembly of the Antenna, AS-940/APQ-72.

3.3.6 Pinion Wrench - The pinion wrench, used for zeroing the antenna resolvers shall be per BuOrd Dwg. No. 677036.

3.3.7 Magnetron Maintenance Wrench - The magnetron maintenance wrench shall be made of a non-magnetic material and shall be capable of readily removing the four nuts holding the magnetron to the modulator chassis.

3.3.8 Indicator Face Plate Protector - The Indicator Face Plate Protector shall provide means, in conjunction with the Indicator handles, to support Indicator, IP447/APQ-72 when it is placed on its face.

Source: https://assist.dla.mil -- Downloaded: 202640-19T14:01Z
Check the source to verify that this is the currentversion before use.

3.3.9 Spin Generator Adjust Tool - The spin generator adjust tool shall provide the means to readily adjust the phase of the Spin Generator Stator (Dwg. 575R578H03) with respect to the Spin Motor Stator (WEC Dwg. 575R578H01) on the antenna AN-940/APQ-72.

3.3.10 Wrench, Special - For removal and installation of the external-internal wrenching nuts in the Indicators IP-447/APQ-72 and IP-513/APQ-72.

3.3.11 Flushing Block - Two Required - These flushing blocks are to be used to replace the azimuth and elevation servo valves during flushing of the Antenna AS-940/APQ-72.

3.3.12 Actuator Jacking Screws - There shall be four each, Allen head type 10-32 by 1/2 inch long and 1/4-28 by 2 inches long, to be used for removing and installing the azimuth and elevation actuators on the Antenna, AS-940/APQ-72.

3.3.13 Rotor Jacking Screws - Four Required - There shall be four Allen head type screws, 6-32 by 2 inches long, for removing the rotor sub-assembly of the Antenna, AS-940/APQ-72.

3.3.14 Socket Wrench, Special - One Required - This wrench is to be used to disconnect wires to the magnetic stop on the Antenna, AS-940/APQ-72.

3.3.15 Connector Alignment Fixtures - One fixture is required for the Pilot's Indicator IP-513/APQ-72 and one for the RO Indicator IP-447/APQ-72. These fixtures are used to mechanically align the connector and guide pins on the above assemblies.

3.3.16 Transit Case - The transit case shall be designed to hold securely, all the items included in the kit (Par. 3.3.1 thru 3.3.15).

4. QUALITY ASSURANCE PROVISIONS

4.1 General - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements:

(1) Preproduction Tests

(2) Production Sample Tests

(3) Acceptance Tests

(4) Life Tests

4.1.1 Inspection - The supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examination and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 20260-19T14:01Z
Check the source to verify that this is the current version before use.

4.2 Preproduction Tests - Preproduction tests shall be made on one or more equipments representative of the production equipments to be supplied under the contract. Preproduction tests shall consist of the following:

(1) Contractor's Demonstration Tests

(2) Service Approval Tests

4.2.1 Contractor's Demonstration Tests - Contractor's demonstration tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of 4.6. Data obtained by the contractor in conducting these tests shall be submitted to the procuring activity for review and approval prior to shipping the equipment to the specified destination for service approval tests. The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the service of a commercial testing laboratory satisfactory to the procuring activity.

4.2.2 Service Approval Tests - At the completion of the contractor's demonstration tests and when requested by the procuring activity, the equipment shall be delivered to a specified government laboratory for additional testing. This additional testing may consist of duplicating tests previously conducted and such other tests as are deemed necessary to determine compliance with all applicable design and performance requirements.

4.2.2.1 Accessory Material - In addition to the complete equipment submitted for service approval tests, the contractor shall also submit the accessory material and design and test data specified in Specification MIL-T-21200. This information shall indicate the physical and electrical characteristics of the equipment and establish the equipment's compliance with applicable requirements.

4.2.3 Scope of Tests - Preproduction tests shall include all tests deemed necessary to determine that the equipment meets all the requirements of this specification and the contract. Pre-production tests shall include environmental tests in accordance with Specification MIL-T-21200 and interference tests in accordance with Specification MIL-I-6181.

4.2.4 Preproduction Approval - Approval of the preproduction model shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction model. Prefabrication of production equipment prior to the approval of the preproduction model is at the contractor's own risk. The approved preproduction model will be returned to the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction model shall not be considered as one of the equipments under the contract; however, it may be reworked by the contractor and submitted for acceptance as a production equipment.

Source: https://assist.dla.mil -- Downloaded: 202640-19T14:01Z
Check the source to verify that this is the current version before use.

4.3 Production Sample Tests - When requested by the procuring activity, one equipment shall be selected from the first 10 production equipments submitted for acceptance and sent to a designated government laboratory for tests. The equipment shall be selected by the government inspector after the equipment has successfully passed all individual tests.

4.3.1 Scope of Tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved preproduction sample in design, construction and performance and that it meets all applicable requirements.

4.3.2 Production Sample Approval - Approval of the production sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Upon failure of the production sample to pass any of the tests, delivery of equipment under the contract shall cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

4.3.3 Reconditioning of Production Test Sample - On completion of the production sample test the equipment shall be reworked by the contractor by replacing all wear or damaged items. After reworking the contractor shall resubmit the equipment for acceptance.

4.4 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

(1) Individual Tests

(2) Sampling Tests

(3) Special Tests

4.4.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests:

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T14:01Z
Check the source to verify that this is the current version before use.

(1) Examination of Product

(2) Operational Test

(3) Manufacturing Reliability Test

4.4.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.4.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.4.1.3 Manufacturing Reliability Test - Each equipment shall be operated under the conditions specified herein for a period of 6 hours without failure. A failure shall be defined as anything which causes malfunctioning of the equipment. Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of the equipment.

Temperature	Ambient room
Humidity	Ambient room
Vibration (10 minutes)	Any selected frequency within the range of 20 to 30 cps (excluding resonant points) and a minimum double amplitude of .06 inches

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 6-hour period of operation. Where feasible, the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes and lateral to that plane for 5 minutes. Where it is not feasible to vibrate the equipment in 2 directions the vertical direction shall be used. During the 6-hour period of operation following the 10-minute vibration period, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, it should be repaired and the test started over, except that the 10-minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be composed of two 3-hour periods to conform with standard working hours.

4.4.2 Sampling Tests - Sampling tests shall be conducted on equipments which have successfully passed the individual tests. The following equipments shall be selected by the Government Inspector for sampling tests:

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T14:01Z
Check the source to verify that this is the current version before use.

Quantity of Equipments Offered for Acceptance	Quantity to be tested
First 10	1
Next 50	1
Next 75	1
Next 100	1 for each additional 200 or fraction thereof

4.4.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests:

(1) Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

(2) Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the preproduction and special tests.

(3) Manufacturing reliability test specified in 4.4.1.3, except that the test duration shall be 30 hours.

4.4.3 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling tests.

4.4.3.1 Special Tests Schedule - Selection of equipments for special tests shall be made as follows:

(1) On an early production equipment.

(2) On an equipment midway of the production run.

(3) On an early equipment after an engineering change.

(4) Whenever failure reports or other information indicate additional equipments should be tested. (This will be determined by the procuring activity.)

Exceptions from the above may be necessary when the number of equipments procured under contract or other factors affecting performance may require a variation to assure satisfactory control.

4.4.3.2 Scope of Tests - Special tests shall consist of such tests as are approved by the procuring activity. Test procedures previously approved for the preproduction and sampling tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests. As a

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T14:01Z
Check the source to verify that this is the current version before use.

minimum, the following tests shall be made, except that for those equipments selected as a result of design changes and failure reports, only those tests required to check the characteristics in question need be conducted.

(1) Temperature - Altitude Tests

(2) Vibration Test (60 minutes cycling in each of 3 planes)

(3) Humidity Tests

4.4.4 Equipment Failure - Should a failure occur during either the sampling or special tests, the following action shall be taken:

(1) Determine the cause of failure.

(2) Determine if the failure is an isolated case or design defect.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occuring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement to assure that the defect has been satisfactorily corrected.

(5) Whenever a failure occurs, shift to one (1) sample unit out of ten (10) and proceed with testing as indicated in paragraph 4.4.2.

4.5 Life Test - A 300-hour life test shall be conducted at the contractor's plant on an early equipment representative of the current production. The life test shall be performed under the conditions specified in 4.5.1. The life test sample shall be selected by the government inspector in accordance with the following: When a production sample equipment is submitted to the procuring activity for test then the first equipment specified below need not be selected or subjected to this test. (Equipments which have successfully passed the sampling tests or special tests may be selected for life tests.)

Quantity of Equipments Offered for Acceptance	Quantity to be Tested
First 25	1
Next 175	1
Next 300	1 for each additional 500 or fraction thereof

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T14:01Z
Check the source to verify that this is the current version before use.

4.5.1 Test Conditions - The life test shall be conducted under the following simulated service conditions.

Temperature	Normal room
Altitude	Normal ground (0 - 5000 ft.)
Humidity	Room Ambient

4.5.2 Test Periods - The test may be run continuously or intermittently. Any period of operation shall be of sufficient duration to permit the equipment temperature to stabilize. Periodically, the equipment shall be turned on and off several times and put through its various phases of operation.

4.5.3 Performance Check - At approximately 8-hour intervals during the test, a limited performance check shall be made. The performance check proposed by the contractor shall be subject to approval by the procuring activity.

4.5.4 Test Data - The contractor shall keep a daily record of the performance of the equipment, making particular note of any deficiencies or failures. In the event of part failures, the defective part shall be replaced and the operation resumed for the balance of the test period. A record shall be kept of all failures throughout the test, including all tube failures. This record shall indicate the following:

(1) Part type number

(2) The circuit reference symbol number

(3) The part function

(4) Name of the manufacturer

(5) Nature of the failure

(6) The number of hours which the part operated prior to failure

4.5.4.1 Failure Report - In the event of a failure, the government inspector shall be notified immediately. A report shall be submitted to the procuring activity upon completion of the test. In this report, the contractor shall propose suitable and adequate design or material corrections for all failures which occurred. The procuring activity will review such proposals and determine whether they are acceptable.

4.5.5 Reconditioning of Life Test Samples - An equipment which has been subjected to the life test shall be reconditioned as follows:

(1) On completion of the life test, the equipment shall be reworked by the contractor by replacing all tubes and "wear" items. The "wear" items shall be determined by agreement between the contractor and the procuring activity.

(2) After reworking, the contractor may resubmit the equipment for acceptance.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T14:01Z
Check the source to verify that this is the current version before use.

4.6 Test Procedures - The procedures used for conducting preproduction tests, acceptance tests and life tests shall be prepared by the contractor. The right is reserved by the procuring activity or the government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification or the contract. Specification MIL-T-18303 shall be used as a guide for preparation of test procedures. When test procedures are available from previous contracts such procedures may be used when approved by the procuring activity.

4.7 Presubmission Testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.8 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the government inspector. Units rejected after retest shall not be resubmitted without the specific approval of the procuring activity.

4.9 Equipment Changes - After approval of the preproduction model, no changes which affect weight, installation interchangeability and interchangeability of maintenance parts or assemblies shall be incorporated in the equipment unless approved by the procuring activity. To obtain procuring activity approval, the contractor shall submit an Engineering Change Proposal (ECP) giving the necessary information concerning the change. This shall apply for either a procuring activity's recommended change or a contractor's proposed change. When required, the contractor shall also prepare a Material Change (MC) and a Material Bulletin (MB) to cover the approved change. Engineering Change Proposals, Material Changes and Material Bulletins shall be prepared in accordance with SAR-300.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with Specification MIL-P-17555.

6. NOTES

6.1 Intended Use - The Kit covered by this specification is intended to provide the special tools necessary to perform maintenance on the APQ-72 Radar Set.

NOTICE - When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation or conveying any rights or permission to manufacture, use, or sell any patented invention that may be in any way related thereto.

Source: https://assist.dla.mil -- Downloaded: 20261019T14:01Z
Check the source to verify that this is the current version before use.