MIL-G-49141(EL)
29 September 1977

MILITARY SPECIFICATION
GENERATOR, SWEEP SG-677( )/U

This specification is approved for use by the Electronics Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers Generator, Sweep SG-677( )/U, a solid state, UHF/VHF Generator with a frequency range from 1 MHz to 1.2 GHz.

1.2 Classification. The equipment will be as defined in MIL-T-28800 and herein for Type III, Class 5, Style E, and Color R.

2. APPLICABLE DOCUMENTS

2.1 Issue of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Electronics Command, ATTN: DRSEL-RD-TS-S, Fort Monmouth, New Jersey 07703 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 6625

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:50Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-T-28800	Test Equipment for use with Electrical and Electronic Equipment General Specification for

STANDARDS

MILITARY

MIL-STD-109	Quality Assurance Terms and Definitions
MIL-STD-461A	Electromagnetic Interference Characteristics Requirements for Equipment
MIL-STD-462	Electromagnetic Interference Characteristics, Measurements of
MIL-STD-781	Reliability Tests, Exponential Distribution
MIL-STD-810	Environmental Test Methods

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Configuration. Equipment covered by this specification shall meet the requirements as defined in MIL-T-28800 for Type III, Class 5, Style E and as specified herein.

3.1.1 First Article. When specified (See 6.2) the contractor will furnished five sample equipments for first article inspection and approval (See 4.4 and 6.2)

3.2 Safety. The equipment shall comply with the Type III safety requirements of MIL-T-28800.

3.3 Parts, Materials and processes. Unless otherwise specified herein, the equipment shall comply with the Type III parts, materials and processes requirement as defined in MIL-T-28800.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:50Z
Check the source to verify that this is the currentversion before use.

3.3.1 Restricted materials. The equipment shall comply with the restricted material requirements of MIL-T-28800 including the requirements covering use of mercury or radio-active materials; and shall contain no combination of materials which could cause deterioration of any material contained in the equipment due to the effects of outgassing.

3.3.2 Signal input and output connectors. Unless otherwise specified herein all signal input and output connectors shall be series "BNC" except for the RF output(s) which shall be series "N" connector.

3.4 Design and construction. Unless specified herein the equipment shall comply with Type III design and construction of MIL-T-28800.

3.4.1 Controls. Unless otherwise specified herein, built-in adjustments and compensating devices shall not be externally accessible.

3.4.1.1 Front panel controls. All controls which are required to operate the equipment throughout its specified performance characteristics, shall be located on the front panel.

3.4.2 Solid state construction. The equipment shall be of solid-state modular miniaturized construction. Electron tubes shall not be used.

3.4.3 Encapsulation and embedment. Encapsulation and embedment (potting) of subassemblies may be used only for high voltage circuits.

3.5 Electrical power sources and connections. The equipment shall comply with the Type III electrical power sources and connections requirements of MIL-T-28800. The equipment shall operate from a nominal 115/230 volts single phase 50, 60 and 400 Hz source.

3.5.1 Power selection switch. A switch shall be provided to select the desired operating voltage. The switch shall be configured to guard against accidental switching.

3.5.2 Input power switch. A front panel mounted power switch shall be provided. The ON position shall have panel identification. The switch shall break both sides of the power source.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:50Z
Check the source to verify that this is the current version before use.

3.5.3 Input power cable. The equipment shall meet the requirements of MIL-T-28800.

3.5.4 Indicators. The equipment shall meet the provisions of MIL-T-28800 Type III.

3.6 Dimensions, weight, mechanical stability.

3.6.1 Dimensions. The maximum dimensions of the equipment shall not exceed 483 mm (19 inches) in width, 254 mm (10 inches) in height and 533 mm (21 inches) in depth.

3.6.2 Weight. The maximum weight of the equipment shall not exceed 16 Kg (35 pounds).

3.7 Enclosure. The equipment enclosure shall be as specified for Style E. The enclosure shall have the capability of being rack mountable with additional hardware not furnished with the equipment but available on request from the contractor The rack mount conversion kit shall meet the requirements of MIL-T-28800.

3.8 Marking and identification. The equipment shall comply with the Type III marking and identification requirements of MIL-T-28800 except that the supplemental identification plate need only contain the following marking data:

a. Nomenclature
b. Contract number
c. Serial number
d. Manufacturer's name
e. US

3.9 Environmental requirements. Except for electromagnetic interference and humidity equipment shall comply with the Class 5, Style E requirements of MIL-T-28800.

3.9.1 Humidity. The equipment shall meet the requirements of paragraph 3.9 when tested in accordance with Procedure II, Method 507 of MIL-STD-810.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:50Z
Check the source to verify that this is the current version before use.

3.9.2 Electromagnetic interference. The signal generator shall comply with the following emission and susceptibility requirements of Notice 4, MIL-STD-461A.

CE02	CS02	RE02.1	RS03
CE04	CS06	RE02	

RE02.1 and RS03 shall be performed from 14 KHz to 10 GHz with RS03 at a susceptibility level of one volt per meter (1 V/m).

3.10 Reliability requirements.

3.10.1 Reliability burn-in. Each equipment delivered against this specification shall be subjected to a minimum 96 hours on-time burn-in procedure as specified in para. 4.5.6.5. The last 24 hours shall be failure free.

3.10.2 Reliability. Reliability shall comply with the requirements as specified herein. The specified MTBF shall be 1000 hours when tested as specified in para. 4.5.6. A failure shall be as defined in para. 3.1 of MIL-STD-781 and as any departure from the required performance as operation outside of the required accuracies (not correctable by normal use of the operating control(s)) after the test is initiated. Test Level B, MIL-STD-781, shall be the required test level.

3.11 Maintainability. The equipment shall comply with the Type III maintainability requirements of MIL-T-28800 and as specified herein.

3.11.1 Certification time. Certification time shall not exceed 2.0 hours and it shall include all time required to check operating characteristics.

3.11.2 Maintenance provisions. The equipment shall meet the Type III, maintenance provisions of MIL-T-28800 except that "Accessibility of Accessories" does not apply.

3.11.3 Indicator lights. Unless approved by the procuring activity upon presentation of acceptable reliability data, indicator lights other than light emitting diodes (LED's) shall be accessible from the operators side of the front panel.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:50Z
Check the source to verify that this is the current version before use.

3.11.4 Maintenance and calibration aids. When required in the contract or order, any circuit board extendees, special adaptors, special tools, and patch cables required for maintenance or calibration of equipment shall be stowed in a suitable reusable pouch or container which shall be marked "MAINTENANCE AIDS FOR USE WITH (equipment nomenclature)".

3.12 Performance requirements.

3.12.1 Frequency range. The output range of the equipment shall be variable from 1 MHz to 1.2 GHz.

3.12.1.1 Frequency range accuracy. The accuracy of the output frequency shall be ±1 percent of the indicated frequency or ±10 MHz (whichever is greater).

3.12.1.2 Frequency response. The output frequency response shall be less than ±0.5 db over any frequency range.

3.12.1.3 Harmonic distortion. The harmonic distortion shall be more than 20 db from 1 to 10 MHz and 25 db from 11 to 1200 MHz.

3.12.1.4 Standing wave ratio. The standing wave ratio shall be less than 1.5:1 when properly terminated within the tuning range of the equipment.

3.12.2 Output voltage. The minimum of voltage shall be 0.5 rms across a 50 load.

3.12.2.1 Output meter accuracy. The rf meter accuracy shall be ±3%.

3.12.3 Output attenuation. The output attenuation range shall be more than 80 dB, calibrated in 1 dB increments.

3.12.3.1 Output attenuation accuracy. The output attenuation accuracy shall be 2% ± .3 dB from 0 to 10 dB 3% ± .1 dB from 11 to 80 dB.

3.12.4 Output impedance. The output impedance of the equipment shall be 50 ohms.

3.12.5 Sweep width. The sweep width shall be at a minimum from 100 KHz to 400 MHz and shall be continuously variable.

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:50Z
Check the source to verify that this is the currentversion before use.

3.12.5.1 Sweep rate. The sweep rate shall be variable from at least 10 millisecond to 30 seconds plus line rate position of 50/60 Hz.

3.12.5.2 Sweep linearity. The sweep linearity shall be ±3 percent of the sweep width.

3.12.6 Sweep mode. The sweep mode shall be selectable between automatic manual, CW, ΔF and start/stop.

3.12.7 Sweep output. The sweep output voltage corresponding to the rf output frequency shall be a sawtooth voltage from 0 to 10 volts.

3.12.8 Residual FM. Shall be less than 15 KHz P.

3.12.9 Crystal marker capability. Harmonic markers of 1, 10, and 50 MH shall be provided. Provision for up to three additional single or fixed frequency markers shall also be provided. Crystal marker accuracy shall be 0.005%.

3.12.10 Marker amplitude. The equipment shall be provided with a front panel marker amplitude control adjustment.

3.12.11 Marker tilt. A marker tilt must be provided, adjustable from vertical to approximately 90°.

3.12.12 External detector. An rf detector shall be supplied with each instrument. The detector shall be operable from .5 to 1200 MHz, with input impedence of 50 ohms, a VSWR less than 1.2:1, and a efficiency of 75% for .5 rms level.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facility suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:50Z
Check the source to verify that this is the current version before use.

4.1.1 Quality assurance terms and definitions. Quality assurance terms used herein shall be in accordance with MIL-STD-109.

4.2 Classification of inspections. The inspections required herein are classified as in a through c.

a. Bid sample inspection (See 4.3).
b. First Article inspection (See 4.4).
c. Quality conformance inspection (See 4.5).

4.3 Bid sample inspection. When required in the solicitation, bid samples shall be submitted to the procuring activity for bid sample evaluation. Unless otherwise required in the solicitation the bid sample shall consist of two equipments, including accessories, instruction manuals and clear and concise rationale showing how the reliability and maintainability characteristics of the equipment comply with the requirements of the solicitation (See 6.5 & 6.6). In the event an equipment under test becomes unacceptable during the Group C or Group D testing, the other equipment will be subjected to the Group C or Group D tests which were not satisfactorily completed.

4.3.1 Bid sample inspection, Group A. The two equipments will be subjected to the Group A inspection specified in Tables I and II.

4.3.2 Bid sample tests, Group B. The two equipments that have satisfactorily passed the Group A inspection will be subjected to the Group B tests specified in Tables I and III.

4.3.3 Bid sample tests, Group C. One equipment that has satisfactorily passed the Group B tests will be subjected to the Group C tests as specified in Table I.

4.3.4 Bid sample tests, Group D. One equipment that has satisfactorily passed the Group B tests will be subjected to the Group D tests as specified in Table I.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:50Z
Check the source to verify that this is the current version before use.

TABLE I - EXAMINATION AND TEST GROUPS

Description	Requirement	Inspection Method: Bid Sample	First Article	Quality Conformance
Group A				
Preoperational inspection	3.	4.6	4.6	4.6
Level A performance	3.12	4.6	4.6	4.6
Leakage current	3.2	4.6	4.6	4.6
Group B				
Level B performance	3.12	4.6	4.6	4.6
Group C				
Temperature and humidity	3.9	4.6	4.6	4.6
Humidity	3.9	4.6.2	4.6.2	4.6.2
Low temperature	3.9	4.6	4.6	4.6
High temperature	3.9	4.6	4.6	4.6
Altitude	3.9	4.6	4.6	4.6
Vibration	3.9	4.6	4.6	4.6
Shock				
Shock pulse	3.9	4.6	4.6	4.6
Bench handling	3.9	4.6	4.6	4.6
Electrical power				
Input power consumption	3.5	4.6	4.6	4.6
Voltage and frequency variation	3.5	4.6	4.6	4.6
Voltage transient	3.5	4.6	4.6	4.6
Frequency transient	3.5	4.6	4.6	4.6
Verification, Group C	3.12	4.6	4.6	4.6
Group D				
Electromagnetic interference	3.9.2	4.6.1	4.6.1	4.6.1

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:50Z
Check the source to verify that this is the current version before use.

TABLE I - EXAMINATION AND TEST GROUPS (Contd)

Description	Requirement	Inspection Method		
		Bid Sample	First Article	Quality Conformance
Group E				
Maintainability	3.11	N/A	4.6	4.6
Acoustic noise	3.9	4.6	4.6	4.6
Dimensions	3.6	4.6	4.6	4.6
Weight	3.6	4.6	4.6	4.6
Mechanical stability	3.6	4.6	4.6	4.6
Group F				
Reliability	3.10	N/A	4.5.6	4.5.6

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:50Z
Check the source to verify that this is the current version before use.

TABLE II - LEVEL A PERFORMANCE TESTS

DESCRIPTION	Requirement
Frequency range	3.12.1
Output voltage	3.12.2
Output attenuation	3.12.3
Sweep width	3.12.5
Sweep rate	3.12.5.1
Sweep output	3.12.7
Crystal marker capability	3.12.9

NOTE: (See 6.4)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:50Z
Check the source to verify that this is the current version before use.

TABLE III - LEVEL B PERFORMANCE TESTS

DESCRIPTION	Requirement
Frequency range	3.12.1
Frequency range accuracy	3.12.1.1
Frequency response	3.12.1.2
Harmonic distortion	3.12.1.3
Standing wave ratio	3.12.1.4
Output voltage	3.12.2
Output meter accuracy	3.12.2.1
Output attenuation	3.12.3
Output attenuation accuracy	3.12.3.1
Output impedance	3.12.4
Sweep width	3.12.5
Sweep rate	3.12.5.1
Sweep linearity	3.12.5.2
Sweep mode	3.12.6
Sweep output	3.12.7
Residual FM	3.12.8
Crystal marker capability	3.12.9
Marker amplitude	3.12.10
Marker tilt	3.12.11
External detector	3.12.12

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:50Z
Check the source to verify that this is the current version before use.

4.3.5 Bid sample tests, Group E. Equipments that have satisfactorily passed the Group B tests will be subjected to the Group E tests as specified in Table I. The number of equipments to be tested will be as in a through d.

a. Maintainability. No equipment will be tested.
b. Acoustical noise test. One equipment will be tested if forced air cooling is used.
c. Dimensions and weight tests. One equipment will be tested.
d. Mechanical Stability. One equipment will be tested.

4.3.6 Bid sample tests, Group F. Unless otherwise specified in the solicitation, Group F reliability testing will not be performed on bid samples.

4.4 First Article. Unless otherwise specified in the contract or purchase order, the First Article inspection shall be performed by the contractor.

4.4.1 First Article inspection.

4.4.1.1 First Article inspection Group A. The five equipments shall be subjected to the Group A inspection specified in Table I.

4.4.1.2 First Article inspection Group B. The five equipments that satisfactorily passed the Group A inspection shall be subjected to the Group B tests of Table I.

4.4.1.3 First Article inspection Group C. The five equipments that satisfactorily passed the Group B inspection shall be subjected to the Group C tests of Table I.

4.4.1.4 First Article inspection Group D. Two equipments that satisfactorily passed the Group A and Group B tests shall be subjected to the Group D test of Table I.

4.4.1.5 First Article inspection Group E. Equipments that have satisfactorily passed the Group D tests shall be subjected to the Group E tests as specified in Table I. The number of equipments tested will be as in a through d.

a. Maintainability. One equipment shall be tested.
b. Acoustic noise. One equipment shall be tested if forced air cooling is used.
c. Dimensions and weight. Two equipments shall be tested.
d. Mechanical stability. Two equipments shall be tested.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:50Z
Check the source to verify that this is the current version before use.

4.4.1.6 First Article inspection Group F. The Group F reliability demonstration shall be conducted in accordance with paragraph 4.5.6 and its associated subparagraphs. The demonstration shall be performed on at least five (5) equipments that have satisfactorily passed the Group A and Group B tests. The use of ten (10) samples is encouraged, but not more than ten samples shall be used.

4.5 Quality conformance inspection. Unless otherwise required herein, the test methods, procedures and conditions used for quality conformance inspection shall be as specified in 4.6 and MIL-T-28800.

4.5.1 Production inspection. Each equipment shall be subjected to the Group A inspection as specified in Tables I and II to ensure qualitatively the proper functioning of the equipment, including all operating controls, and conformance with safety requirements.

4.5.2 Production control tests. The Group B tests of Tables I and III shall be performed on equipment that have passed Group A inspection.

4.5.2.1 Production control sampling plan. From each lot which has passed production inspection (See 4.5.1) a random sample shall be selected and subjected to the Group B tests. Minimum sampling shall be in accordance with MIL-T-28800.

4.5.3 Environmental and electrical power tests. The Group C tests of Table I shall be performed on equipment which have passed the required tests in accordance with 4.5.2.

4.5.3.1 Environmental and electrical power sampling plan. From the First Production lot, which has passed the required tests in accordance with 4.5.2 a random sample shall be selected and subjected to the Group C tests. The sampling shall be in accordance with MIL-T-28800.

4.5.4 EMI tests. The Group D test of Table I shall be performed on equipment which have passed the required tests in accordance with 4.5.2.

4.5.4.1 EMI sampling plan. From the First Production lot, which has passed the required tests in accordance with 4.5.2, a random sample shall be selected and subjected to the Group D tests. The sampling shall be in accordance with MIL-T-28800.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:50Z
Check the source to verify that this is the current version before use.

4.5.5 Other tests. The Group E tests of Table I shall be performed on equipment which have passed the required tests in accordance with 4.5.2.

4.5.5.1 Other tests sampling plan. From the First Production Lot, which has passed the required tests in accordance with 4.5.2, a random sample shall be selected and subjected to the Group E tests. The sampling shall be in accordance with a through d.

a. Acoustic noise. One equipment shall be randomly selected from the First Production Lot and tested if forced air cooling is used.

b. Maintainability. One equipment shall be randomly selected from the First Production Lot and tested.

c. Dimensions and weight. Two equipment shall be randomly selected from the First Production Lot and tested.

d. Mechanical stability. Two equipments shall be randomly selected from the First Production Lot and tested.

4.5.6 Reliability tests. The Group F tests shall be conducted in accordance with the following test plan:

TOTAL TEST TIME *

Number of Failures	Accept ** (Equal or More)	Reject *** (Equal or Less)
0	800	- - -
1	1500	223
2	2150	825
3	2750	1540
4	3350	2290
5	3950	3090
6	4550	4550 ****

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:50Z
Check the source to verify that this is the currentversion before use.

Θ_o = 1000

* Total test time is total unit hours of "equipment on" time.

** Accept if test time is greater than or equal to that listed.

*** Reject if test time is less than or equal to that listed.

**** Reject if time is strictly less than 4550 with 6 failures.

4.5.6.1 Reliability demonstration phase. The reliability demonstration shall be performed on a random sample of ten equipments selected from the First Production Lot.

4.5.6.2 Reliability sampling phase. Unless the reliability has been demonstrated in accordance with paragraphs 4.3.6 and 4.4.1.6 during Bid Sample, the demonstration shall be run on the First Production Lot only.

4.5.6.3 Duty cycle. The equipment shall be operated and examined weekly in the satisfactory operation test, para. 4.6.b. The equipment shall be performing continuously and measured daily in the satisfactory operation check, para. 4.6.a during the power-on time. Input voltage cycling para. 5.2.4 of MIL-STD-781 is required.

4.5.6.3.1 Test length. Testing will continue until the total unit hours together with the total count of relevant equipment failures permit either an accept or reject decision in accordance with the specified test plan. Only equipment "on" time may be used in MTBF or longevity determinations. Testing shall be monitored in such a manner that the times to failure may be determined with reasonable accuracy. No single equipment "on" time shall be less than one half the average operating time of all equipments on test.

4.5.6.4 Reliability examination and test method. Paragraph 4.6 Examination and Test Methods of this specification shall be used to verify equipment operation on a continuous basis. Satisfactory operation check, para. 4.6 subpara. a., shall be used to monitor the proper operation of the Rf output frequency on the low, middle and top ranges daily. Satisfactory operation test, para. 4.6.b shall be used to confirm specified operation prior to reliability demonstration and at completion. Weekly satisfactory operation test, para. 4.6.b specified shall confirm all parameters found in Level A performance test (See Table II).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:50Z
Check the source to verify that this is the current version before use.

4.5.6.5 Reliability burn-in. Each deliverable equipment shall be subjected to a minimum 96 hour on-time burn-in period prior to Group A testing as follows:

4.5.6.5.1 Each equipment will be allowed to accumulate failures during the first 72 hours of burn-in time.

4.5.6.5.2 During the last 24 hours of burn-in, each equipment must operate failure free. Each equipment which fails during this period shall be repaired and returned to test until it successfully survives a 24 hour period without failure.

4.5.6.5.3 Failures which occur during the burn-in test shall be noted and reported but shall not be counted toward the establishment of equipment MTBF.

4.5.6.5.4 Duty cycle. Prior to the burn-in a satisfactory operation test shall be conducted. Daily satisfactory operation checks (para. 4.6.a) shall be conducted. For the last 24 hour failure free period a complete satisfactory operation test (para 4.6.b) shall be conducted prior to and after the period.

4.5.6.6 Reliability failure actions, Group F. In the event of failure(s) during reliability testing, failure action shall be taken as required in MIL-STD-781, para. 5.5.

4.5.6.7 Corrective action, Group F. In the event the reliability test reaches a reject decision, corrective action shall be taken as required in MIL-STD-781, para. 5.7.

4.6 Examination and test methods. Examination and test methods shall be in accordance with MIL-T-28800 and as specified herein:

a. The satisfactory operation check shall confirm the proper operation of the Rf output frequency, when monitored on the low, middle and top ranges.

b. The satisfactory operation test shall confirm the specified operation of the equipment for all parameters of the Level A performance test (See Table II).

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:50Z
Check the source to verify that this is the current version before use.

4.6.1 Electromagnetic interference. The signal generator shall be tested for compliance with requirements of para. 3.9.2. Test setups and procedures shall comply with the measurement techniques of Notice 3, MIL-STD-462. Emission and susceptibility tests shall be performed with the supplied output cable connected to and extended parallel with the front of the signal generator. The output cable shall be terminated to simulate a normal loading configuration.

4.6.2 Humidity. The equipment shall meet the requirements of para. 3.9 when tested in accordance with Procedure II, Method 507 of MIL-STD-810.

4.7 Optional quality assurance testing. The procuring activity may substitute a Department of Defense (DoD) approved supplier's quality assurance system for any or all tests in Table 1.

5. PACKAGING

5.1 Preservation-packaging. Packaging shall be in accordance with MIL-T-28800 and as specified by the procuring activity.

6. NOTES

6.1 Intended use. Equipment described by this specification is intended for use in testing equipment and systems in laboratory, shop, repair and depot activities. This specification will be used to procure quality, commercial test equipment modified for or possessing specific military requirements.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number and data of this specification.
b. Levels of packing and packaging (See Section 5).
c. Quantity of bid sample required.
d. Place of final inspection.
e. Technical literature required.
f. Quantity of tools and running spare parts required.

6.3 Contract data requirements.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:50Z
Check the source to verify that this is the current version before use.

a. Nomenclature assignment.
b. National stock number.
c. Bid sample test plans.
d. Test equipment approval requests.
e. Quality assurance test plans.
f. Quality assurance test reports.

6.4 Definitions.

6.4.1 Level A performance tests. Level A testing (Table II) is a reduced amount of testing which is performed on each equipment produced. Its purpose is to insure that all functions and modes of operation of the equipment are evaluated without extensively checking each parameter as required in the Level B test (Table III). The approved equipment test procedure shall specify the actual amount of testing to be performed.

6.5 Reliability rationale. Reliability rationale submitted with the bid sample should provided clear and concise rationale showing how the reliability of the equipment complies with minimum requirements of the solicitation. The rationale must include quantitative data. The sources of the data may be from previous reliability tests, reliability predictions or any other quantitative data available to the offeror. Reliability data should include conditions under which data was generated and the failure definitions used. This may include data from previous reliability tests, reliability predictions and other data available to the offeror. In the absence of such data on the equipment being offered, such data on similar equipment of equal or greater complexity produced by the offeror may be submitted. However, such data must be clearly identified as comparative data, and accomplished with specifications and technical literature on the similar equipment. The acceptance of the submitted rationale does not relieve the successful bidder of performing and successfully completing the production reliability testing.

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:50Z
Check the source to verify that this is the currentversion before use.

6.6 Maintainability rationale. Maintainability rationale submitted with the bid sample should provided clear and concise rationale showing how the maintainability of the equipment complies with requirements of the solicitation. This may include data from previous maintainability tests, records of repair and calibration data, and other data on the equipment available to the offeror. Data on selection of module size and other design (See 3.4) features relevant to maintainability may also be submitted. The acceptance of the submitted rationale does not relieve the successful bidder of performing and successfully completing the production maintainability testing.

Custodian
Army-EL

Preparing Activity
Army-EL

Project No. 6625-A694

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:50Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.
NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER (Number) AND TITLE MIL-G-49141(EL) GENERATOR, SWEEP SG-577( )/U

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY (Printed or typed name and address — Optional)

TELEPHONE NO.

DATE

DD FORM 1 OCT 78 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:50Z
Check the source to verify that this is the current version before use.