INCH POUND

MIL-S-64055(AL)
31 August 1994

MILITARY SPECIFICATION

SHOP EQUIPMENT, MECHANICAL MAINTENANCE,

SHELTER MOUNTED, EXPANDABLE

This specification is approved for use by the Armament Research, Development and Engineering Center (Tool and Equipment Engineering Division, Standardization and Specification Engineering Branch), Department of the Army and is available for usage by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the installation of tools and equipment into a portable, expandable shelter mounted mechanical maintenance repair shop.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and drawings. The following specifications, standards, and drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto, cited in the solicitation (see 6.2.1).

SPECIFICATIONS

FEDERAL

A-A-1898	-	Cushioning Material, Cellulosic, Packaging
PPP-B-636	-	Box, Shipping, Fiberboard
PPP-T-60	-	Tape, Packaging, Waterproof

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Armament Research, Development and Engineering Center, ATTN: SMCAR-EST-P, Rock Island, IL 61299-7300 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 4940

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:18Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-P-116	-	Preservation, Methods of
MIL-F-14072	-	Finishes for Ground Based Electronic Equipment
MIL-C-83286	-	Coating Urethane, Aliphatic Isocyanate, for Aerospace Applications

STANDARDS

FEDERAL

FED-STD-595	-	Colors

MILITARY

MIL-STD-129	-	Marking for Shipment and Storage
MIL-STD-130	-	Identification Marking of US Military Property
MIL-STD-889	-	Dissimilar Metals
MIL-STD-1190	-	Minimum Guidelines for Level C Preservation, Packing and Marking

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the DoDSSP, Standardization Document Order Desk, 700 Robbins Avenue, Philadelphia, PA 19120-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues shall be those cited in the solicitation.

DEPARTMENT OF THE ARMY

DRAWINGS

11A520000	- List of Components, S/E,Mechanical Maintenance, Shelter Mounted
11A521000	- Shop Equipment, Mechanical Maintenance Shelter Mounted
13226E7441	- US/GE Standardized Camouflage Pattern Painting

SUPPLY CATALOG

SC 4940-95-A52 -List of Components

DEPARTMENT OF COMMERCE

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY

(Copies of specifications, standards, handbooks, drawings, and publications required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:18Z
Check the source to verify that this is the current version before use.

the DoDISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS are the issues of the document cited in the solicitation (see 6.2.1).

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 - National Electric Code

(Application for copies should be addressed to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269-9101.)

(Nongovernment standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, (except for related associated detail specifications, specification sheets or MS standards) the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified (see 6.2.1), a sample shall be subject to first article inspection in accordance with 4.3. The approved first article and the production items shall be identical and in accordance with the terms of the contract. Approval of the first article shall not relieve the supplier of the responsibility to furnish equipment in accordance with the requirements of this specification.

3.2 Description. Tools and equipment installed in the shelter and other modification shall be in accordance with drawing 11A521000 and as specified herein. The shelter shall include all tools and equipment specified in set components list 11A520000 as compiled from Set Components (SC) 4940-95-A52.

3.2.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer or his or her designated representative. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to ensure correct fit, assembly, and operation of the shelter shop equipment. Any data, such as shop drawings, layouts, flow sheets, processing procedures, prepared by the supplier or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Materials shall be free from defects which would adversely affect performance or maintainability of the individual components or overall assembly. When dissimilar metals are used in contact with each other, suitable protection against galvanic corrosion shall be applied in accordance with MIL-STD-889.

3.4 Installation, expanded and closed configurations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:18Z
Check the source to verify that this is the current version before use.

3.4.1 Tools and equipment. The tools and equipment shall be installed inside the shelter in the expanded configuration and in the closed configuration in accordance with the applicable drawings (see 3.2).

3.4.2 Major components. The contractor shall install tables, shelves, cabinets and heavy items in the shelter in accordance with the applicable drawings (see 3.2). The contractor shall furnish all fastenings, brackets, bolts, nuts, screws, straps, and adhesives for major and auxiliary units mounted on the floor, tables, shelves and walls in accordance with applicable drawings (see 3.2).

3.4.3 Other items. Unless otherwise specified (see 6.2.1), the contractor shall stow items within designated compartments of cabinet drawers and shelves in accordance with applicable drawings (see 3.2).

3.4.4 Overflow items. Overflow items shall be stowed in boxes as specified in drawings (see 3.2). The box shall conform to PPP-B-636 domestic, fiberboard box. The void space shall be filled with cushioning conforming to A-A-1898, grade II. The box shall be closed in accordance with the appendix of the box specification.

3.5 Floor stability. The shelter floor shall show no evidence of crack, fracture or any kind of damage except peeling of paint due to installation of items as specified in 3.4.1 through 3.4.4. Remove peeling paint from installation areas and touch-up in accordance with 3.12.

3.6 Securing of parts. Bolt holes shall be accurately formed and shall have burrs removed. Washers shall be provided where necessary. All fasteners shall be correctly installed with means for preventing loss of tightness and shall have full thread engagement. Brackets, lugs, straps, inserts, bolts and other mounting arrangement shall be such as to retain items securely when subjected to specified service conditions. Parts shall be so mounted that loosening, wear or mounting arrangements, or permanent separation of parts will not occur when the items in which they are used are subjected to service conditions.

3.7 Weight. The gross shelter weight with all tools and equipment shall be not more than 15,000 pounds in closed configuration.

3.8 Cleaning. After equipment installation the shelter shall be cleaned throughly and shall be free from loose hardware and other foreign material.

3.9 Transportability. In the transport mode (closed configuration), the shelter with installed items (see 3.2) and mounted on a M1022 Dolly Set (see 3.15.1) shall be towed by a truck (see 3.15.2) over the following courses.

3.9.1 Perryman course. The shelter shall be towed over the Perryman cross-country course (see 6.9) for a distance of 1,000 miles at speeds up to 15 miles per hour (mph) maximum with no damage to the installed and stowed items.

3.9.2 Munson courses. The shelter shall be towed five times over each of the below listed road courses (see 6.9) with no damage to the installed and stowed items. The speed over each course shall range from 5 mph minimum to 15 mph maximum.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:18Z
Check the source to verify that this is the current version before use.

Munson road courses

1. Six-inch washboard
2. Belgian block
3. Radial washboard
4. Space bump
5. Two-inch washboard

3.10 Environmental conditions.

3.10.1 Environmental control unit (ECU). ECU units (two) as specified in 3.15.3 shall be installed on the expandable part of the shelter in accordance with drawing 11A521000. The cutout on the shelter wall shall show proper fit and assembly for the ECU unit. The ECU unit shall be operated for 15 minutes to check its electrical installation.

3.10.2 Water tightness. All joints and edges of ECU unit framing and cutouts shall be sealed to prevent entrance of moisture to the core material of the shelter panels and to the interior of the shelter. The shelter in its expanded configuration shall show no evidence of water leakage, penetration, or absortion through ECU cutout panels when subjected to a simulated rainfall, using garden type hose at a pressure of 25 pounds per square inch gage (PSIG) for a period of five minutes.

3.11 Electrical system. Electrical system shall be in accordance with the applicable drawings and comply with NFPA 70.

3.12 Shelter interior. Shelter interior touch-up paint, where required, shall be in accordance with MIL-F-14072, finish No. as specified below:

a. Floor: Finish No. P515 plus walkway compound, gray, color 26251 of FED-STD-595.
b. Ceiling and wall: Finish No. P510.3 plus MIL-C-83286, color 17925 of FED-STD-595.

3.13 Shelter exterior. Unless otherwise specified (see 6.2.1), the shelter exterior shall be painted with camouflage pattern standard in accordance with drawing 13226E7441.

3.14 Government furnished property (GFP). Unless otherwise specified (see 6.2.1), the following property in the quantities indicated shall be provided by the Government (see 6.6).

Item No.	Description	Identification	Quantity
1.	Sets, kits and outfits (SKO) per list 11A520000	NSN 4940-00-209-6227	1

3.15 Government loaned property (GLP).

3.15.1 Dolly set, lift type. The transportable shelter lift type dolly set National Stock Number (NSN) 2330-01-167-7262 will be loaned by the Government (see 6.5).

Source: https://assist.dla.mil -- Downloaded: 202610-23T03:18Z
Check the source to verify that this is the current version before use.

3.15.2 Truck. The truck required for use in towing the shelter mounted on the dolly set during the roadability test shall be a standard 5 ton truck and will be loaned by the Government (see 6.5).

3.15.3 ECU unit. The ECU unit required for the shelter for proper fit and assembly will be loaned by the Government (see 6.5). The NSN of the ECU unit will be 4120-01-268-4451 or related NSN.

3.16 Aircraft loading data plate. The shelter completely loaded and in the closed configuration shall be provided with data plates imprinted with the dimensions which locate the center-of-gravity of the shelter facility and assemblage in the three reference planes; and the gross weight of the shelter.

3.17 Technical literature. Technical literature which comes with the sets, kits, and outfits shall be assembled in a ring binder and located with the technical manual of the shelter.

3.18 Padlocks and keys. The shelter for delivery shall be padlocked. Padlock keys shall be concealed by attaching to the underside of the door cover with tape conforming to PPP-T-60. The shipping document shall be so annoted.

3.19 Identification marking. The shelter shop shall be identified in accordance with MIL-STD-130.

3.20 Workmanship. Standards of workmanship shall be such that the shelter shop shall have the safety, stability, and operating characteristics specified herein and shall be free of defects that could adversely affect its intended use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of Sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

Source: https://assist.dla.mil -- Downloaded: 202640-23T03:18Z
Check the source to verify that this is the current version before use.

4.1.2 Component and material inspection. The contractor shall be responsible for ensuring that components and materials used are manufactured, tested, and inspected in accordance with referenced specifications and standards.

4.1.3 Disassembly inspection. A first article shop failing a performance test shall be disassembled in the presence of a Government representative to the extent necessary to determine the cause of the failure. Each disassembled part shall be inspected in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, and tolerances. Parts not complying with such requirements shall be rejected. Reassembled with accepted parts and retesting shall be the responsibility of the contractor.

4.1.4 Examination or test of GFP or GLP items. Failure of GFP (see 3.14) or GLP (see 3.15) during examinations or tests does not constitute failure of the examination or test. This includes failure of GFP or GLP engines to start during the tests. Failure of GFP and GLP items are to be reported through normal channels.

4.2 Classification of inspection. The inspection requirements specified herein are:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Comparison test (see 4.6).
d. Packaging inspection (see 4.7).

4.3 First article inspection.

4.3.1 Examination. The first article shall be examined for defects marked X in column 3 of table II. Presence of one or more defects shall be cause for rejection or for performing the disassembly inspection specified in 4.1.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:18Z
Check the source to verify that this is the current version before use.

TABLE II. Examination schedule

Defect	Requirement Paragraph	First Article	Quality Conformance
1	2	3	4
Assembly incomplete or incorrect	3.2	X	X
Material not as specified	3.3	X	X
Installation not as specified	3.4	X	X
Floor stability not as specified	3.5	X	X
Parts not stowed and secured as specified	3.6	X	X
Shelter not cleaned as specified	3.8	X	X
Electrical not as specified	3.11	X	X
Interior touch-up paint not as specified	3.12	X	X
Exterior camouflage pattern not as specified	3.13	X	X
SKO per 11A520000 not as specified	3.14	X	X
Aircraft loading data plate not as specified	3.16	X	X
Technical literature not assembled as specified	3.17	X	X
Padlocks and keys not as as specified	3.18	X	X
Idenification marking not as specified	3.19	X	X
Workmanship not as specified	3.20	X	X

4.3.2 Tests. The shelter shop shall be subjected to all the tests in 4.5.

4.4 Quality conformance inspection.

4.4.1 Examination. Each shelter shop shall be examined for the defects marked X in column 4 of table II. Presence of one or more defects shall be cause for rejection.

4.5 Tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:18Z
Check the source to verify that this is the current version before use.

4.5.1 Weight test. Weigh the shelter in the closed configuration loaded with tools and equipment as specified in 3.4. The shelter with installed equipment shall not exceed 15,000 pounds (see 3.7). The weighing scale shall be accurate to ±1% with calibration traceable to the National Institute of Standards and Technology.

4.5.2 Transportability. The shelter in the closed configuration loaded with tools and equipment (see 3.4) and mounted on a dolly set (see 3.15.1) shall be towed by a Government furnished military cargo truck (see 3.15.2) over the following road courses (see 3.9).

4.5.2.1 Perryman cross-country course (see 6.9). The shelter with installed tools and equipment in the transport mode shall be towed over the Perryman cross-country course for a distance of 1,000 miles at speeds up to 15 mph maximum (see 3.9.1). During the course of the test, there shall be at least ten abrupt stops from speeds of 10 mph.

4.5.2.2 Munson road course (see 6.9). The shelter with installed tools and equipment in the transport mode shall shall be towed five times over each of the below listed road courses (see 3.9.2). The speed over each course shall range from 5 mph minimum to 15 mph maximum.

Munson road courses

1. Six-inch washboard
2. Belgian block
3. Radial washboard
4. Space bump
5. Two-inch washboad

Examine the shelter after completion of each phase of the road tests. Damage to, or displacement (see 6.7) of any component, part, or tool; evidence of defective welded, bolted connections excluding the Government furnished equipment shall constitute failure of these road tests.

4.5.3 Environmental.

4.5.3.1 Rain test. The shelter shop in its expanded configuration shall be exposed to simulated rain using a garden type hose with a spray nozzle, and water line pressure not less than 25 PSIG for a period of five minutes. Each ECU cutout panel shall be subjected to a five minute rain test. Spray shall simulate rain with normal wind conditions which requires spraying around all sides of cutout panel without forcing water under any protective water shed device. Spraying will be done from a distance of no less than four feet from each ECU cutout panel. Thereafter, with time allowed for drainage of all water from panels, open door and examine internally for any signs of leakage. Water leakage into the internal area shall be cause for rejection (see 3.10.2).

4.5.3.2 Environmental control unit. Operate the environmental control unit continuously for not less than 15 minutes to check the electrical installation of the environmental control unit (see 3.10.1).

4.6 Comparison test. The Government may select shelter shops at any time during the contract production period and subject these shelter shops to the tests in 4.5.1, 4.5.2 and 4.5.3 to determine conformance to the requirements of this specification. The inspection will be performed by the

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:18Z
Check the source to verify that this is the current version before use.

Government at a site selected by the Government. Shelter shops will be selected at random from those which have been accepted by the Government and shelter shops will not include the previously inspected first article model. In addition to any test specified as part of the comparison test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the comparison test and failure of such additional tests shall have the same effect as failure of those tests specified as comparison tests.

4.6.1 Inspection failure. Failure of an comparison test shelter shop to meet any requirement specified herein during and as a result of the examination and test specified (see 4.6) shall be cause for rejection of the comparison test shop and shall be cause for refusal by the Government to continue acceptance of production shops until evidence has been provided by the supplier that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the supplier at no cost to the Government on shelter shops previously produced and accepted under the contract. Any deficiencies found as a result of comparison test inspection will be considered prima facie evidence that all shops accepted after approval of the initial production shelter shop are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.7 Packaging inspection. Packaging inspection shall be conducted to determine compliance with the requirements of Section 5.

5. PACKAGING

5.1 Preservation. Preservation shall be Level A or Level C as specified (see 6.2.1).

5.1.1 Level A.

5.1.1.1 Cleaning. Cleaning shall be in accordance with method C-1 of MIL-P-116, except that no class 1 ozone depleting substance such as 1.1.1 trichloroethane, halons, chlorofluorocarbons or carbon tetrachloride shall be used.

5.1.1.2 Drying. Drying shall be accomplished by any applicable means stated in MIL-P-116.

5.1.1.3 Preservative application. Immediately after cleaning and drying surfaces of any item in the shop set that is subject to corrosion shall be treated with a P-type preservative in accordance with MIL-P-116, except that preservative P-6 shall not be used. Excessive use of preservative compounds shall be avoided. Petroleum (P-type) preservative compounds shall not be applied to non-metallic parts, corrosion resistant metal or metal that is treated or painted to resist corrosion.

5.1.1.4 Handtools, soldering equipment, sets and kits. Items furnished with carrying cases; handtools, soldering equipment, sets and kits shall be preserved as specified in 5.1.1.3, replaced in their case and placed in the proper storage compartment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T03:18Z
Check the source to verify that this is the current version before use.

5.1.1.5 Items having mounting brackets or holders. Items furnished with mounting brackets or holders shall be preserved as specified in 5.1.1.3 and replaced in the bracket or holder and secured to prevent movement.

5.1.1.6 Environmental control unit. The environmental control unit shall be completely drained. Exterior body openings shall be sealed with tape conforming to PPP-T-60.

5.1.1.7 Items furnished in commercial containers. Items and materials such as lubricating oil, silicone compound, grease, commercially furnished in sealed cans, pails, jars, or tubes shall not require additional preservation or packing, and shall be placed in their proper storage compartment.

5.1.1.8 Electrical wire. The ends of electrical wire shall be sealed with tape to prevent moisture from contacting wire. Loose wire shall be coiled to a safe minimum diameter and secured in three equidistant places with cotton twine or tape.

5.1.1.9 Locks and keys. The interior of locks shall be coated a with dry lubricant and the locks operated to assure penetration of the lubricant.

5.1.1.10 Miscellaneous supplies and equipment. Items, equipment, and components not specifically identified herein shall be preserved as specified for supplies and equipment of similar design, construction, and characteristics.

5.1.2 Level C.

5.1.2.1 Preservation and packing. Level C preservation and packing shall be accordance with MIL-STD-1190.

5.2 Packing (see 6.8). The shelter, with equipment enclosed, shall be prepared for shipment in a manner to assure carrier acceptance and safe delivery to destination at lowest ratings. Items and equipment installed in the shelter shop, and other movable equipment or items, shall be cushioned, blocked, braced, and anchored to prevent damage to the equipment or to the shelter. All doors and drawers shall be secured to prevent accidental opening and to prevent pilferage of contents.

5.3 Marking. All marking requirements shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature, that may be helpful, but is not mandatory.)

6.1 Intended use. The mechanical maintence repair shelter shop is intended to be used as a portable shop with a set of hand and machine tools, and work space for mechanical repairmen repairing military equipment in the field.

6.2 Ordering data.

6.2.1 Acquisition requirements. Acquisition documents should specify the following:

Source: https://assist.dla.mil -- Downloaded: 202610-23T03:18Z
Check the source to verify that this is the currentversion before use.

(a) Title, number, and date of this specification.
(b) Issue of DoDISS to be cited in the solicitation, and if required, the specific issue of the individual documents referenced (see 2.1.1 and 2.2).
(c) First article when required (see 3.1).
(d) Other items stowed if different (see 3.4.3).
(e) Exterior finish if different (see 3.13).
(f) Government-furnished property if different (see 3.14).
(g) Preservation as required (see 5.1).

6.3 Set components list. The contracting officer should arrange to furnish information concerning items specified in drawing 11A520000 (see 3.2).

6.4 Technical interface data. The contracting officer should arrange to provide information concerning technical interface for the Government furnished items specified in 3.14.

6.5 Government-loaned property. The contracting officer should arrange to loan the contractor the property specified in 3.15.

6.6 Government-furnished property. The contracting officer should arrange to furnish the supplier the property specified in 3.14.

6.7 Displacement. Displacement is defined as dislodgment of any tool or equipment from its designated position. Movement of a tool or equipment within its designated position without any dislodgment is permitted (see 4.5.2.2).

6.8 Packing (see 5.2). Levels of packing have not been included for shelter as the nature of the item is such that only mobile packing is appropriate. For purposes of packing markings, the level of packing should be considered level A and should be marked A/A.

6.9 Road tests. For information on the Perryman cross-country course and Munson course road tests, contact the Director; Development and Proof Services, Aberdeen Proving Grounds, Aberdeen, Maryland (see 3.9.1 and 3.9.2).

6.10 Contract data requirements. Required technical data such as operator's manuals, parts lists, and other instructions for operation and maintenance, as identified on a numbered DD Form 1664, should be specified on a DD Form 1423 incorporated in the contract.

6.11 Provisions. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment of shops.

6.12 Subject term (key word) listing.

Environmental	Expandable	Tools and equipment
Mobility	Portable	Shelter

Custodian:
Army - AL

Preparing activity:
Army - AL

Project No. 4940-A663

Source: https://assist.dla.mil -- Downloaded: 202610-23T03:18Z
Check the source to verify that this is the current version before use.