MIL-M-60059 (MU)
1 October 1964

MILITARY SPECIFICATION

MINE, ANTI-PERSONNEL NM, M25 PARTS FOR

1. SCOPE

1.1 This specification covers quality assurance provisions, and special requirements not covered by the drawings, for the fabrication of the inert parts for one type of mine designated as Mine, Anti-Personnel, NM, M25.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification the the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550	- Ammunition and Special Weapons; General Specification for.
MIL-P-10025	- Packaging, Packing and Marking for Interplant Shipment of Inert Ammunition Components; General Specification for.
MIL-I-45208	- Inspection Requirements; General Specifications for.
MIL-I-45607	- Inspection Equipment, Supply and Maintenance of.
MIL-D-45608	- Designs and Drawings, Ordnance Inspection Equipment.

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-109 - Quality Assurance Terms and Definitions.
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8864070 - Mine, Anti-Personnel, NM, M25, Parts Arrangement.

PUBLICATIONS

ORDNANCE CORPS

IEL 8864070 - Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with applicable drawings and specifications.

3.2 Inert parts.-The inert parts shall comply with all requirements specified on Drawing (dwg.) 8864070, and with all requirements specified in applicable specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

3.3 Workmanship.

3.3.1 Molded parts.-The molded parts shall be free of flash, tool marks, blisters or porosity, cracks, chipped edges, warpage and scratches which would affect their serviceability.

3.3.2 Metal parts.-The metal parts shall be free of cracks, chips, dirt, grease, rust and other foreign material. The cleaning method shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agents. Surface coatings shall be continuous except for scratches not exposing base metal.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-The supplier's responsibilities will be as specified in the contract or purchase order. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Contractor quality assurance system.-The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL-I-45208.

4.1.2 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

b. Number of units of product inspected.

c. Results obtained for all inspection performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Statement of findings on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL-I-45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial production inspection.

4.2.1 Process specification (plastic parts).-Prior to the start of manufacture of the pre-production lot, the contractor shall submit to a Government approved facility designated by the contracting officer (see 6.4) for approval, a process specification which shall specify the time, temperature, and pressure ranges which shall be maintained during production of molded parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

Periodically, during the operation of the approved process, the Government inspector shall observe the process to ascertain that the approved limits are being adhered to. No deviation from these limits without approval from the procuring activity shall be allowed. In the event of an approved deviation, the contractor shall submit a new initial production sample.

4.2.2 Submission.-Prior to regular production, the contractor shall submit an initial production sample to a Government approved facility, as designated by the contracting officer (see 6.5), for evaluation in accordance with the provisions of 4.2.3. The sample shall consist of 4 complete sets of parts, from each mold cavity (i.e., 4 each of every component, and 4 each of every subassembly) which have been produced by the contractor or furnished by a supplier, and which have been manufactured using the same production process, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by statements of findings for all materials or tests. An initial production sample, or portions thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity, as determined by the Government. Prior to submission the contractor shall inspect the sample to the degree necessary to assure it conforms to the requirements of the contract and submit a record of this inspection with the sample.

4.2.3 Inspections to be performed.-Each component and subassembly shall be examined by the Government for all requirements and dimensions of applicable drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

4.2.4 Rejection.-If any component or subassembly fails to comply with the applicable requirement, the initial production sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of a component or subassembly in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample, or portion thereof. Until an initial production sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

4.3 Inspection provisions.

4.3.1 Lot formation.-A lot shall consist of inert parts produced by one manufacturer in one unchanged process, in accordance with the sample drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance or fit, as determined by the Government, shall not necessitate changing the lot interfix number.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

4.3.2.1 Safety clip assembly (see dwg. 8864063 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Symmetry of clip with handle	Gage	01001
102.	Width of clip opening, maximum (max)	Gage	01002
103.	Length inside clip, minimum (min)	Gage	01003
104.	Width of clip, min	Gage	01004
105.	Protective finish improper	Visual	01005
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.3.2)	Visual	01006

4.3.2.2 Plug (see dwg. 8863727 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Body upper mating diameter	Gage	02001
Minor:	AQL 1.0 percent		
201.	Radius at junction of body upper mating surfaces, max	Gage	02002
202.	Evidence of poor workmanship (see 3.3.1)	Visual	02003

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

4.3.2.3 Ring, detector (see dwg. 8864059 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Tab missing or bent	Visual	03001
Minor:	AQL 1.5 percent		
201.	Large inside diameter	Gage	03002
202.	Small inside diameter	Gage	03003
203.	Protective finish improper	Visual	03004
204.	Evidence of poor workmanship (see 3.3.2)	Visual	03005

4.3.2.4 Body, upper (see dwg. 8862732 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.5 percent		
101.	Charge container cavity open end diameter	Gage	04001
102.	Charge container cavity spline diameter	Gage	04002
103.	Depth of charge container cavity	Gage	04003
104.	Ball retaining diameter	Gage	04004
105.	Support detonator housing mating diameter	Gage	04005

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

106.	Detonator housing clearance diameter.	Gage	04006
107.	Depth to ball retaining shoulder, min.	Gage	04007
108.	Concentricity of support detonator housing mating surfact with detonator housing clearance surface	Gage	04008
109.	Concentricity of ball retaining diameter with detonator housing clearance surface	Gage	04009
110.	Diameter of body lower mating diameter	Gage	04010
111.	Depth to housing detonator shoulder, min	Gage	04011
112.	Depth to body lower shoulder, min	Gage	04012
113.	Length across ring detector slots, max	Gage	04013
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.1.1)	Visual	04014

4.3.2.5 Housing detonator (see dwg. 8864061 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Large outside diameter, max	Gage	05001
102.	Thickness of retaining lip, max	Gage	05002
103.	Thickness of flange, max	Gage	05003
104.	Thickness of cavity bottom, max	Gage	05004
105.	Diameter of detonator cavity	Gage	05005
106.	Length of detonator cavity	Gage	05006
107.	Support detonator housing mating diameter	Gage	05007
108.	Overall length, max	Gage	05008
109.	Length to flange, max	Gage	05009

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.1.1).....	Visual	05010

4.3.2.6 Support, detonator housing (see dwg. 8864072 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Outside diameter.....	Gage	06001
102.	Inside diameter.....	Gage	06002
103.	Width of ball slot.....	Gage	06003
104.	Length to ball slot.....	Gage	06004
Minor:	AQL 1.0 percent		
201.	Length, max.....	Gage	06005
202.	Evidence of poor workmanship (see 3.3.1).....	Visual	06006

4.3.2.7 Firing pin assembly (see dwg. 8863729 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Outside diameter.....	Gage	07001
102.	Concentricity of firing pin with outside collar diameter.....	Gage	07002
103.	Flat on firing pin, max.....	Gage	07003
104.	Angle of firing pin point.....	Gage	07004
105.	Length from front of collar to rear of pin, max.....	Gage	07005
106.	Flat on collar missing.....	Visual	07006

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.5 percent		
201.	Width between ball indents	Gage	07007
202.	Firing pin diameter, max	Gage	07008
203.	Evidence of poor workmanship (see 3.3.1)	Visual	07009

4.3.2.8 Spring, firing (see dwg. 8863728 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Inside diameter, min	Gage	08001
102.	Outside diameter, max	Gage	08002
103.	Solid length, max	Gage	08003
104.	Load at compressed length	Gage	08004
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.3.2)	Visual	08005

4.3.2.9 Body, lower (see dwg. 8863730 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Diameter of spring hole	Gage	09001
102.	Depth to bottom of spring hole, min	Gage	09002
103.	Body upper mating diameter	Gage	09003
104.	Concentricity of spring hole with body upper mating diameter	Gage	09004

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.5 percent		
201.	Outside diameter, max.	Gage	09005
202.	Overall length, max.	Gage	09006
203.	Evidence of poor workmanship (see 3.3.1)	Visual	09007

4.3.2.10 Charge container (see dwg. 8864063 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Cap, charge container mating diameter	Gage	10001
102.	Charge mating diameter	Gage	10002
103.	Body upper, mating diameter, max.	Gage	10002
104.	Overall length, max.	Gage	10004
105.	Inside depth, min.	Gage	10005
106.	Perpendicularity of body upper mating diameter with bottom	Gage	10006
107.	Concentricity of body upper mating diameter with cap charge container diameter	Gage	10007
Minor:	AQL 1.0 percent		
201.	Length to lip, min.	Gage	10008
202.	Evidence of poor workmanship (see 3.3.1)	Visual	10009

4.3.2.11 Cap, charge, container (see dwg. 8864068 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

Major:	AQL 1.0 percent		
101.	Body upper clearance diameter	Gage	11001
102.	Cone clearance diameter	Gage	11002
103.	Charge container mating diameter	Gage	11003
104.	Small inside diameter, min	Gage	11004
105.	Depth of charge container seating surface, min	Gage	11005
106.	Depth to cone seating shoulder, min	Gage	11006
Minor:	AQL 1.5 percent		
201.	Overall length, max	Gage	11007
202.	Length to flange, min	Gage	11008
203.	Evidence of poor workmanship (see 3.3.1)	Visual	11009

4.3.2.12 Cone (see dwg. 8864066 covering a detail of dwg. 8864070).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Outside diameter	Gage	12001
102.	Height	Gage	12002
103.	Diameter	Gage	12003
104.	Perpendicularity of outside diameter with open end face	Gage	12004
105.	Concentricity of cone with outside diameter	Gage	12005
Minor:	AQL 1.0 percent		
201.	Thickness of flange	Gage	12006
202.	Evidence of poor workmanship (see 3.3.1)	Gage	12007

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

4.3.3 Testing

4.3.3.1 Molded components (see dwgs. 8863725, 8863727, 8863729, 8863730, 8863732, 8864060, 8864061, 8864066, 8864068 and 8864072).-At the start of production from a new mold or after adjustment or repair to a mold, consecutively produced units from each mold shall be dimensionally examined until 4 consecutive units meet all applicable drawing requirements. After adjustment or repair, those dimensions affected by the adjustment or repair shall be examined. During production, the molding procedures shall be monitored for uniformity of molding practices. Suspected deviations in mold product shall be examined to determine if corrective action or mold repair is required.

4.3.4 Inspection Equipment.-Index of Inspection Equipment Number IEL 8864070 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists procided and revised in accordance with the requirements of the IEL may be used by DOD activities, for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement of parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and wherever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection and test equipment.-The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Packaging.

5.1.1 Level C.-Mine parts shall be packaged in accordance with the requirements of Specification MIL-P-10025.

5.2 Packing.

5.2.1 Level C.-Packing shall conform to the requirements of MIL-P-10025.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify title, number and date of this specification.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 Inspection equipment lists.-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (OO Form 1242-3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designed in the IEL by the following codes:

CDAF - Contractor's design responsibility on Army format in accordance with MIL-D-45608.
CDCF - Contractor's design responsibility on contractor format.
AD - Army design.
ADMU - Army design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

6.3.4 Specification control drawing.-Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagramatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above.

6.3.7 Submission of contractor designs.-Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normlly be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Submission of process specification.-Instructions as to facility for the evaluation of the process specification shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries shall be forwarded to: Commanding Officer, Picatinny Arsena., ATTN: SMUPA-DC, Dover, New Jersey.

6.5 Submission of initial production sample.-Instructions as to the location for the evaluation of Initial Production qualification shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries should be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-NI, Dover, New Jersey.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1345-A149

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.